ELOP RELOCATABLE CLASSROOM







W LINCOLN RD

AREA MAP

VICINITY MAP

DEFERRED SUBMITTALS

W BENJAMIN HOLT DR

IRIS AVE

PRADO WAY

PRESIDIO WAY

E LINCOLN RD

FILE NO.: 39-69

230 PRESIDIO WAY

PROJECT ADDRESS

STOCKTON, CA 95207

CLASSROOM BUILDING "M"

INCLUDE BUT NOT NECESSARILY LIMITED TO:

- (1) NEW 36'X40' STOCKPILE #04-123793 APPROVED RELOCATABLE CLASSROOM BUILDING 'P' PURCHASED UNDER A SEPARATE CONTRACT BETWEEN THE DISTRICT AND CLASS LEASING.
- SEE SPECIFICATION SECTION "MULTIPLE CONTRACT SUMMARY" FOR ADDITIONAL INFORMATION ALTERATIONS TO BUILDING ADMINISTRATION BUILDING "A" AND

MODULAR MANUFACTURER SHALL BE RESPONSIBLE FOR:

WELD PLATES WILL BE PROVIDED BY CLASS LEASING AND DELIVERED TO SITE CONTRACTOR PRIOR TO DELIVERY OF

PREPARATION OF EXISTING SITE INCLUDING EXCAVATION AND REMOVAL OF SOIL IN PREPARATION FOR PIT-SET BUILDING WITH

- CONCRETE FOOTINGS AND REINFORCEMENT AS INDICATED ON TH RELOCATABLE DRAWINGS.
- DELIVERY VEHICLES, INSTALLING ON CONCRETE FOUNDATION AND ALL REQUIRED CONNECTIONS AS INDICATED ON THE RELOCATABLE
- SIGNAGE AND EXTERIOR AND INTERIOR FINISHES AS INDICATED IN THE CONSTRUCTION DOCUMENTS
- CONNECTION AND START UP OF UTILITIES INCLUDING FIRE ALARM AND NEW SWITCHGEAR. NEW PUBLIC HYDRANT.

PRIOR TO INSTALLATION OF MODULAR BUILDINGS AT THE SITE PER STOCKPILE APPLICATION 04-123793, THE TEAM MUST SUBMIT TO DSA THE IN-PLANT INSPECTOR INSPECTION CARD / VERIFIED REPORT FROM DSA 152-IPL FOR THE STOCKPILE APPLICATION UPLOADED TO DSABOX.

PROJECT DESCRIPTION

ENFORCING AGENCY

DIVISION OF THE STATE ARCHITECT (DSA), SACRAMENTO OFFICE

FLOOD ZONE INFORMATION

FLOOD ZONE DESIGNATION: ZONE X AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE OF FLOOD. FLOOD INSURANCE RATE MAP (FIRM) PANEL DESIGNATION: 06077C0320F PANEL EFFECTIVE DATE OF (FIRM): OCTOBER 16, 2009

BASE FLOOD ELEVATION (BFE): NOT REQUIRED APPLICABLE COMMUNITY ORDINANCE SECTION: NOT REQUIRED

AGENCY & FLOOD ZONE INFORMATION

THE CALIFORNIA ENERGY CODE SECTION 10-103 REQUIRES ACCEPTANCE TESTING ON ALL NEWLY INSTALLED LIGHTING CONTROLS, MECHANICAL SYSTEMS, ENVELOPES, AND PROCESS EQUIPMENT AFTER INSTALLATION AND BEFORE PROJECT COMPLETION. AN ACCEPTANCE TEST IS A FUNCTIONAL PERFORMANCE TEST TO HELP ENSURE THAT NEWLY INSTALLED EQUIPMENT IS OPERATING AND IN COMPLIANCE WITH THE ENERGY CODE.

LIGHTING CONTROLS ACCEPTANCE TESTS MUST BE PERFORMED BY A CERTIFIED LIGHTING CONTROLS ACCEPTANCE TEST TECHNICIAN (ATT)

MECHANICAL SYSTEM ACCEPTANCE TESTS MUST BE PERFORMED BY A CERTIFIED MECHANICAL

ATT FOR PROJECTS SUBMITTED ON OR AFTER OCTOBER 1, 2021.

ENVELOPE AND PROCESS EQUIPMENT ACCEPTANCE TESTS SHALL BE PERFORMED BY INSTALLING CONTRACTOR, ENGINEER/ARCHITECT OF RECORD OR THE OWNER'S AGENT.

A LISTING OF CERTIFIED ATT'S CAN BE FOUND AT HTTPS: WWW.ENERGY.CA.GOV./PROGRAMS-AND-TOPICS/PROGRAMS/ACCEPTANCE-TEST-TECHNICIAN-CERTIFICATION-PROVIDER-

THE ACCEPTANCE TESTING PROCEDURES MUST BE REPEATED, AND DEFICIENCIES MUST BE CORRECTED BY THE BUILDER OR INSTALLING CONTRACTOR UNTIL THE CONSTRUCTION/INSTALLATION OF THE SPECIFIED SYSTEMS CONFORM AND PASS THE REQUIRED

PROJECT INSPECTORS WILL COLLECT THE FORMS TO CONFIRM THAT THE REQUIRED ACCEPTANCE TESTS HAVE BEEN COMPLETED.

FIRST TIME RELOCATION DIRECTLY FROM THE STOCKPILE (C-24-3164 A/B/C)

THE FOLLOWING DOCUMENTS SHALL BE ON THE JOBSITE PRIOR TO INSTALLATION OF THE

- A. IN-PLANT VERIFIED REPORT
- **B. LABORATORY VERIFIED REPORT**
- THE SITE INSPECTOR SHALL VERIFY THE ABOVE DOCUMENTS AND SERIAL NUMBERS ARE

IR16-1 AND INCLUDE THE FOLLOWING INFORMATION ON ID TAG OF SHOP FABRICATED

- THE DSA APPLICATION NUMBER AND CBC EDITION UNDER WHICH THE BUILDING
- CONSTRUCTION WAS AUTHORIZED: THE MANUFACTURER OR BUILDER'S NAME;
- THE SERIAL NUMBER: 4. THE DESIGN CLIMATE ZONES;
- 5. THE DESIGN LIVE LOADS FOR THE ROOF AND FLOOR;
- 6. THE DESIGN WIND SPEED AND EXPOSURE CATEGORY; THE SEISMIC DESIGN PARAMETER Ss.

(CCD) OR A SEPARATE SET OF PLANS AND SPECIFICATIONS DETAILING AND SPECIFYING THE REQUIRED REPAIR WORK SHALL BE SUBMITTED TO AND APPROVED BY DSA BEFORE

MODULAR MANUFACTURER BUILDING

- 2022 CALIFORNIA ADMINISTRATIVE CODE (CAC), PART 1, TITLE 24 C.C.R. 2022 CALIFORNIA BUILDING CODE (CBC), PART 2, TITLE 24 C.C.R.
- 2022 CALIFORNIA ELECTRICAL CODE (CEC), PART 3, TITLE 24, C.C.R 2022 CALIFORNIA MECHANICAL CODE (CMC), PART 4, TITLE 24 C.C.R 2022 CALIFORNIA PLUMBING CODE (CPC), PART 5, TITLE 24 C.C.R.
- 2022 CALIFORNIA ENERGY CODE, PART 6, TITLE 24 C.C.R. 2022 CALIFORNIA FIRE CODE (CFC), PART 9, TITLE 24 C.C.R.
- 2022 CALIFORNIA EXISTING BUILDING CODE (CEBC), PART 10, TITLE 24 C.C.R. 2022 CALIFORNIA GREEN BUILDING STANDARDS CODE (CALGREEN), PART 11, TITLE 24 C.C.R. 2022 CALIFORNIA REFERENCED STANDARDS CODE. PART 12. TITLE 24.
- TITLE 19 C.C.R., PUBLIC SAFETY, STATE FIRE MARSHAL REGULATIONS NFPA 14 STANDARD FOR THE INSTALLATION OF STANDPIPE AND HOSE SYSTEM (CA AMENDED 2019 EDITION
- STANDARD FOR DRY CHEMICAL EXTINGUISHING SYSTEMS 2021 EDITION NFPA 17A STANDARD FOR WET CHEMICAL EXTINGUISHING SYSTEMS
- STANDARD FOR THE INSTALLATION OF STATIONARY PUMPS FOR FIRE PROTECTION 2019 EDITION STANDARD WATER TANKS FOR PRIVATE FIRE PROTECTION
- STANDARD FOR THE INSTALLATION OF PRIVATE FIRE SERVICE MAINS AND THEIR APPURTENANCES (CA AMENDED) 2022 EDITION
- NATIONAL FIRE ALARM AND SIGNALING CODE (CA AMENDED) STANDARD FOR FIRE DOORS AND OTHER OPENING PROTECTIVES 2019 EDITION NFPA 2001 STANDARD ON CLEAN AGENT FIRE EXTINGUISHING SYSTEM
- (CA AMENDED) 2018 EDITION STANDARD FOR FIRE TESTING OF FIRE EXTINGUISHING SYSTEM FOR
- PROTECTION OF COMMERCIAL COOKING EQUIPMENT 2005 (R2014) AUDIBLE SIGNALING DEVICES FOR FIRE ALARM AND SIGNALING SYSTEMS, INCLUDING ACCESSORIES 2003 EDITION
- UL 521 STANDARD FOR HEAT DETECTORS FOR FIRE PROTECTIVE SIGNALING SYSTEMS 1999 EDITION (R2005) STANDARD FOR SIGNALING DEVICES FOR THE HEARING IMPAIRED 2002 (R2012)

GOVERNING CODES

56 SOUTH LINCOLN ST.

CONTACT: VICKIE BRUM

EMAIL: vbrum@stocktonusd.net

STOCKTON, CA 95203

(209) 933-7045

STOCKTON UNIFIED SCHOOL DISTRICT

FOR A COMPLETE LIST OF APPLICABLE NFPA STANDARDS REFER TO 2022 CBC (SFM) CHAPTER 35 AND CALIFORNIA FIRE CODE (CFC) CHAPTER 80.

SEE CALIFORNIA BUILDING CODE, CHAPTER 35, FOR STATE OF CALIFORNIA AMENDMENTS 2022 CALIFORNIA FIRE CODE (CFC) - CHAPTER 33 - FIRE SAFETY DURING CONSTRUCTION

1. A COPY TITLE 24 C.C.R. PARTS 1 AND 2 SHALL BE KEPT ON THE JOB SITE AT ALL

PORTIONS OF THE APPROVED PLANS AND SPECIFICATIONS AFTER THE WORK

- PART 1, AND APPROVED T & I SHEET.
- 4. TESTS OF MATERIALS AND TESTING LABORATORY SHALL BE IN ACCORDANCE WITH TITLE 24 SECTION 4-335, PART I, AND THE DISTRICT SHALL EMPLOY AND PAY THE LABORATORY. COSTS OF RETEST MAY BE BACK CHARGED TO THE
- A CLASS 3 "DSA CERTIFIED" INSPECTOR REQUIRED FOR THIS PROJECT SHALL B EMPLOYED BY OWNER AND APPROVED BY ARCHITECT. STRUCTURAL ENGINEER AND DSA. INSPECTOR SHALL BE IN ACCORDANCE WITH SECTION 4-333(c). THE DUTY OF THE INSPECTOR SHALL BE IN ACCORDANCE WITH TITLE 24 SECTION
- SUPERVISION OF CONSTRUCTION BY DSA SHALL BE IN ACCORDANCE WITH TITLI 24 SECTION 4-334, PART 1.
- CONTRACTOR, INSPECTOR, ARCHITECT, AND ENGINEERS SHALL SUBMIT VERIFIED REPORTS (FORM SSS-6) IN ACCORDANCE WITH TITLE 24 SECTION 4-336
- THE ARCHITECT AND THE STRUCTURAL ENGINEER SHALL PERFORM THEIR DUTIES IN ACCORDANCE WITH TITLE 24 SECTION 4-333(a) AND 4-341, PART I.
- 10. THE CONTRACTOR SHALL PERFORM HIS DUTIES IN ACCORDANCE WITH TITLE 24
- 11. THE INTENT OF THE DRAWINGS AND SPECIFICATIONS IS TO CONSTRUCT THE SCHOOL BUILDING IN ACCORDANCE WITH TITLE 24 C.C.R. SHOULD ANY CONDITIONS DEVELOP NOT COVERED BY THE CONTRACT DOCUMENTS WHEREIN THE FINISHED WORK WILL NOT COMPLY WITH SAID TITLE 24, C.C.R., A CHANGE ORDER DETAILING AND SPECIFYING THE REQUIRED WORK SHALL BE SUBMITTED TO AND APPROVED BY DSA BEFORE PROCEEDING WITH THE WORK.
- 12. SUBSTITUTIONS AND REQUESTS FOR INFORMATION AFFECTING STRUCTURAL SAFETY, FIRE AND LIFE SAFETY OR ACCESS COMPLIANCE SHALL BE APPROVED BY DSA PRIOR TO FABRICATION OR USE.
- 13. ADDENDA MUST BE SIGNED BY ARCHITECT AND APPROVED BY DSA.
- 14. NO CHANGES OR REVISIONS SHALL BE MADE FOLLOWING WRITTEN APPROVAL WHICH AFFECTS ACCESS COMPLIANCE ITEMS UNLESS SUCH CHANGES OR REVISIONS ARE SUBMITTED TO THE DSA FOR APPROVAL
- 15. CONSTRUCTION CHANGE DOCUMENTS MUST BE SIGNED BY THE FOLLOWING: ARCHITECT OR ENGINEER OF RECORD
 - STRUCTURAL ENGINEER (WHEN APPLICABLE)
- DELEGATED PROFESSIONAL ENGINEER 16. MATERIALS AND THEIR INSTALLATION SHALL COMPLY WITH APPLICABLE CODES, STANDARDS AND MANUFACTURER'S RECOMMENDATIONS.
- 17. THESE PLANS AND SPECIFICATIONS WILL COMPLY WITH CFC CHAPTER 33 FIRE SAFETY DURING CONSTRUCTION AND DEMOLITION.
- 18. GRADING PLANS, DRAINAGE IMPROVEMENTS, ROAD AND ACCESS REQUIREMENTS AND ENVIRONMENTAL HEALTH CONSIDERATIONS SHALL COMPLY WITH ALL LOCAL ORDINANCES.
- 19. DSA IS NOT SUBJECT TO ARBITRATION


STATEMENT OF GENERAL CONFORMANCE

FOR ARCHITECTS/ENGINEERS WHO UTILIZE PLANS, INCLUDING BUT NOT LIMITED TO SHOP DRAWINGS, PREPARED BY OTHER LICENSED DESIGN PROFESSIONALS AND/OR

APPLICATION NO:. <u>02-122764</u> FILE NO:. <u>39-69</u> THE DRAWINGS OR SHEETS LISTED ON THE COVER OR INDEX SHEET

CONSULTANTS WHO ARE LICENSED AND/OR AUTHORIZED TO PREPARE

- . DESIGN INTENT AND APPEARS TO MEET THE APPROPRIATE REQUIREMENTS OF TITLE 24, CALIFORNIA CODE OF REGULATIONS AND THE PROJECT SPECIFICATIONS PREPARED BY ME. AND
- 2. COORDINATION WITH MY PLANS AND SPECIFICATIONS AND IS ACCEPTABLE FOR INCORPORATION INTO THE CONSTRUCTION OF THIS PROJECT.
- THE STATEMENT OF GENERAL CONFORMANCE "SHALL NOT BE CONSTRUED AS RELIEVING ME OF MY RIGHTS, DUTIES, AND RESPONSIBILITIES UNDER SECTIONS 17302 AND 81138 OF THE EDUCATION CODE AND SECTIONS 4-336, 4-341, AND 4-344" OF TITLE 24, PART I.
- ALL DRAWINGS OR SHEETS LISTED ON THE COVER OR INDEX THIS DRAWING OR PAGE
- IS/ARE IN GENERAL CONFORMANCE AND HAVE BEEN COORDINATED WITH THE PROJECT PLANS AND SPECIFICATIONS



07-31-25 LICENSE NUMBER EXPIRATION DATE

ARCHITECT'S STATEMENT

WIND DESIGN DATA [2022 CBC 1603A.1.4]

1. ULTIMATE DESIGN WIND SPEED

3. WIND EXPOSURE CATEGORY EARTHQUAKE DESIGN DATA [2022 CBC 1603A.1.5]

SITE COORDINATES: 38.0191842° N, -121.3103933° W 1. RISK CATEGORY

2. SEISMIC IMPORTANCE FACTOR le = 1 3.MAPPED SPECTRAL RESPONSE ACCELERATION PARAMETERS

 $S_1 = 0.279g$ 4. SITE CLASS 5. DESIGN SPECTRAL RESPONSE ACCELERATION PARAMETERS

 $S_{DS} = 0.581g$ 6. SITE AMPLIFICATION Fa = 1.236

WIND / SEISMIC DESIGN DATA

PROJECT ARCHITECT CIVIL ENGINEER

GENERAL NOTES

7535 N. PALM AVE., SUITE 201 **FRESNO, CA 93711** (559) 437-0887

CONTACT: JAMIE HICKMAN

E-MAIL: jamie.hickman@teterae.com

NORTHSTAR ENGINEERING GROUP

MODESTO, CA 95354 (209) 524-3525 **CONTACT: CHRISTIAN GRAJEDA**

EMAIL: cgrajeda@nseng.net

LANDSCAPE ARCHITECT SAM HARNED LANDSCAPE ARCHITECT

Oakdale, CA 95361 c:(209) 380-7376 **CONTACT: SAM HARNED** EMAIL: sam@harnedla.com **ELECTRICAL ENGINEER 7535 N. PALM AVE., SUITE 201**

FRESNO, CA 93711 (559) 437-0887 CONTACT: JASON MARCH E-MAIL: jason.march@teterae.com

APP: 02-122764 MOSHER CREEK

HAMMER LN

GOYA DR

MURILLO DR

ESPERANZA WAY

N.T.S.

IDENTIFICATION STAM DIV. OF THE STATE ARCHITEC

REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹

APP: 02-122764 INC:








8 > CLASSR NTAR

ACCEPTANCE TESTING

PROJECT DIRECTORY

IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT APP: 02-122764 INC: REVIEWED FOR

SS 🗹 FLS 🗹 ACS 🗸 DATE: 12/18/2024





23-12901

G001

EXECUTE KEYNOTES

2.04 EXISTING KNOX BOX, EMERGENCY KEY STORAGE TO REMAIN

2.05 EXISTING PAIR OF 10'-0" WIDE CHAIN LINK FIRE ACCESS GATES TO REMAIN (A# 02-110702)

2.07 EXISTING 'ENTRY WARNING / TOW AWAY' SIGN TO BE REMOVED AND A NEW TOW AWAY SIGN IS TO BE INSTALLED, SEE DETAIL 16 / A110

2.08 EXISTING 'LOADING ZONE ONLY' SIGN TO REMAIN (02-110702)

2.12 EXISTING DECORATIVE METAL GATE WITH PANIC HARDWARE TO REMAIN (A#

2.14 EXISTING 15'-0" WIDE SLIDING CHAIN LINK FIRE ACCESS GATE

2.18 EXISTING ACCESSIBLE GATE WITH PANIC HARDWARE TO REMAIN (A# 02-109993)

32.72 EXISTING GATE TO BE REPLACED, SITE CONTRACTOR TO INSTALL NEW GATE AND HARDWARE AS INDICATED IN THE GATE SCHEDULE

33.02 NEW PUBLIC HYDRANT, SEE CIVIL

LEGEND

EXISTING BUILDING NO SCOPE OF WORK UNDER THIS PROJECT

EXISTING CONCRETE NO SCOPE OF WORK UNDER THIS PROJECT

PROPOSED MODULAR BUILDING



OF WORK, SEE MFR DWGS. PROPOSED CONCRETE PAVING, SEE CIVIL FOR GRADING, CONSTRUCTION, ISOLATION, AND CONTRACTION JOINTS.

MODULAR BUILDING UNDER THIS SCOPE



PROPOSED TURF AREA
SEE LANDSCAPE DRAWINGS (TREES AND PLATING NOT SHOWN FOR CLARITY)



PROPOSED DECOMPOSED GRANITE SEE LANDSCAPE DRAWINGS (TREES AND PLATING NOT SHOWN FOR CLARITY)

SITE INFORMATION

7071-07071-07071-0707

EXISTING 20'-0" FIRE ACCESS LANE PER A# 02-110702

ASSUMED BUILDING PROPERTY LINE

EXISTING CHAIN LINK FENCING, TYP NEW 6'-0"H CHAIN LINK FENCE/GATE

> **EXISTING ACCESSIBLE ROUTE** (2022 C.B.C. SECTION 11B-206)

PROPOSED ACCESSIBLE ROUTE

(2022 C.B.C. SECTION 11B-206)

EXIT DISCHARGE TO AREA OF _ _ SAFE DISPERSAL

FIRE DEPARTMENT PEDESTRIAN ACCESS FROM FIRE DEPARTMENT ROADWAY TO PROPOSED BUILDING

(E) FIRE HYDRANT PROPOSED FIRE HYDRANT

KNOX BOX @ CENTER 5'-0" ABV. GRADE

| BUILDING SUMMARY | | | | | | |
|------------------|-----------|---------|------|---------------------------|--|--|
| BUILDING | SIZE | SQ. FT. | TYPE | OCC. LOAD (20 SF/OCC.) | | |
| BUILDING 'P' | 36'X40' | 1,440 | V-B | 54 | | |
| FRONT OVERHANG | 5'X36' | 180 | | | | |
| REAR OVERHANG | 2'-6"X36' | 90 | | | | |
| TOTAL | | 1,710 | | 54 OCCUPANTS | | |

BUILDING ANALYSIS:

BASIC ALLOWABLE AREA FOR TYPE V-B. NON-SPRINKLERED E OCCUPANCY = 9,500 SF TOTAL BUILDING AREA 1,710 SF < 9,500 SF

OFFICE 139 SQ.FT. BUILDING 1,440 SQ.FT.

139/1,440=0.96 = 9.6% < 10% = OKAY NO SEPARATION REQUIRED


| AREA OF SAFE DISPERSAL CALCULATION | | | |
|------------------------------------|-----------------|----------|--|
| APPLICATION NO. | TOTAL OCC. LOAD | REQ.D SF | |
| UNDER THIS APP. | 54 X 3 SF | 162 | |
| MIN. TOTAL AREA RE | QUIRED | 162 | |
| TOTAL AREA PROVID | DED | 168 | |


DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024

IDENTIFICATION STAME




ELEMENTARY SCHOOL STOCKTON, CALIFORNIA












VICINITY MAP

BENCHMARK



BRASS DISK MARKING COS MONUMENT STAMPED "2N-2"
RCE 60 IN MONUMENT WELL LOCATED A THE NE CORNER
OF HAMMER LN AND EL DORADO ST +/- 23.5 FT SOUTH OF
CENTERLINE WHEELCHAIR RAMP



CONTACTS

| A. REGULATORY AGENCY: | DIVISION OF THE STATE ARCHITECT-SACRAMENTO 1102 Q STREET, SUITE 5200 SACRAMENTO, CA 95811 T: (916) 445-8730 |
|-----------------------|--|
| B. OWNER/DEVELOPER: | STOCKTON UNIFIED SCHOOL DISTRICT 56 S LINCOLN ST, STOCKTON, CA. 95203 T: (209) 933-7000 |
| C. PROJECT LOCATION: | PULLIAM ELEMENTARY SCHOOL 230 PRESIDIO WAY, STOCKTON, CA. 95207 |
| D. ENGINEER: | NORTHSTAR ENGINEERING GROUP, INC 620 12TH STREET MODESTO, CA. 95354 T: (209) 524-3525 F: (209) 524-3526 CONTACT: JOHN ELLIS |
| E. ARCHITECT: | TETER, INC. 7535 N PALM AVENUE, SUITE 201 FRESNO, CA, 93711 T: (559) 437-0887 CONTACT: JAMIE HICKMAN |

SHEET INDEX

| <u>SH</u> | EEI | INDEX |
|-------------------------------------|--|--|
| 1. 2. 3. 4. 5. 6. | C1.1 C1.2 | GENERAL NOTES AND SPECIFICATIONS DETAILS AND CROSS SECTIONS CITY DETAILS |
| 7. 8. 9. 10. 11. 12. | SITE C2.1 C2.2 C3.1 C3.2 C4.1 C4.2 C5.1 | TOPOGRAPHIC AND DEMOLITION PLAN DIMENSION AND PAVING PLAN DIMENSION AND PAVING PLAN GRADING AND DRAINAGE PLAN |
| 14. 15. | ERO C6.1 C6.2 | |


COPYRIGHT © $\underline{2024}$ NORTHSTAR ENGINEERING GROUP, INC

IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT

APP: 02-122764 INC:


REVIEWED FOR

SS FLS ACS





FRESNO HEADQUARTERS
ALIA I BAKERSFIELD I MODESTO I SAN LUIS OBISPO



SOVEMENT PLANS FOR

M ELEMENTARY

L


PULLIAM ELE SCHOOL STOCKTON,

PROJECT NO. 23-12901

DRAWING

C1.1

| ABBREV | ATIONS |
|--------|--------|
| | |
| | |





GAS, OIL, STEAM (YELLOW)

VERTICAL CURVE VITRIFIED CLAY PIPE VERTICAL

WEST, WATER
WITH
WALL

WATER BOX WATER METER WATER METER BOX WASHOUT AREA WATER SERVICE WATER VALVE WATER WELL

WAY YARD

WELDED WIRE FABRIC



UNLESS OTHERWISE SPECIFIED WATER (BLUE) SEWER/STORM DRAIN (GREEN)
TEMPORARY SURVEY MARKINGS (MAGENTA)
COMMUNICATION CATV (ORANGE) RECLAIMED WATER IRR. SLURRY (PURPLE) ELECTRICAL (RED)
PROPOSED EXCAVATION (WHITE)



IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT

REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹

APP: 02-122764 INC:

DATE: 12/18/2024

Z

PROJECT NO.

23-12901

DRAWING C1.2

COPYRIGHT © 2024 NORTHSTAR ENGINEERING GROUP, INC

| SINGLE LINE DOUBLE LINE STOP BARKCROSSWALK DASHED LINE DOUBLE DASHED LINE MANHOLE MAILBOX UTILITY STRUCTURE WATER VALVE WATER VALVE BACKFLOW PREVENTER DOUBLE CHECK DETECTOR ASSEMBLY FIRE HYDRANT SWALE STORM DRAIN (LANDSCAPE SERVICES) N/A ROCK TRENCH FRENCH DRAIN CULVERT SWALE STORM DRAIN (LANDSCAPE SERVICES) N/A ROCK TRENCH ROCK TRENCH ROCK TRENCH WA WW WW WW WW WW WW WW WM BO DODA DODA | LEGEND | | | | | |
|--|--------------------------------|--|---|----------------------------------|--|---------------|
| March | | EXISTING | PROPOSED | T | EXISTING | PROPOSED |
| ## A TABLE | BOUNDARY LINE | | | AIR RELEASE VALVE | 1 | 1 |
| Section Sect | CENTERLINE | | | | | _ |
| Section 1 | | | | | | |
| SATURE OF SALES AND SALES | | | | | | |
| Marie Mari | | | | WATER (NON-POTABLE WATER) | | |
| Procedure | SECTION LINE | | N/A | WATER (FIRE SERVICE) | — — w — [Ēx8"FS] — | 8"FS |
| A | EASEMENT | | | WATER STRUCTURE ID | · · | |
| ### PRODUCTOR AND PRODUCTOR AN | RIGHT-OF-WAY EASEMENT | | | IRRIGATION MANHOLE | (f- ²) \L' | |
| A PROTECTION OF THE PROTECTION | SETBACK LINE | N/A | | IRRIGATION METER | ÌḾ () | M |
| A SECTION OF THE PROPERTY OF T | RESTRICTED ACCESS | | 111111111111111111111111111111111111111 | | BFP | BFP |
| Second | CENTERI INE STATION POINT | ^ /o\ | A | | ICB | ICB |
| ### Company | | | | | | <u> </u> |
| ## 20 | | | | IRRIGATION CONTROL VALVE | 10v | ICV ⊗ |
| Second | PROPERTY CORNER | | | IRRIGATION LINE | | |
| ### APPLE 1 1 1 1 1 1 1 1 1 | BENCHMARK | • | • | GAS VALVE | | _ |
| Section Sect | TREE | ** | ** | GAS METER | GM '' | GM |
| ### CONTROL OF CONTROL | BOULDER | (| N/A | GAS LINE | — <u> </u> | — GAS — 4"G — |
| STATE STAT | STUMP | A | N/A | | | |
| CASE OLDS CASE O | | | | | 5 | I |
| Application | | | | SITE LIGHTING | | |
| TEST ON A STATE OF THE STATE OF | CURB + GUTTER | | | TRAFFIC SIGNAL | | N/A |
| March Marc | ACCESSIBLE RAMP | / 1 1 1 1 | / \ | TRAFFIC SIGNAL WITH STREET LIGHT | [p] = = = = = = = = = = = = = = = = = = = | N/A |
| MAILTOCATE MAI | DETECTABLE WARNING SURFACE | | | UTILITY POLE | `~' | |
| ###################################### | EDGE OF PAVEMENT | | | UTILITY POLE WITH LIGHT | UP | <u> </u> |
| ### PARTICLE | BUILDING OVERHEAD | | | | אַר באַ | |
| ### ### ### ### ### ### ### ### ### ## | | | | | - | |
| MARTIN CONTRIBUTION | | | | | | |
| December | | | | TELEPHONE MAINTENANCE HOLE | l . | |
| Control | WHEEL STOP | PRINCE EXCEPTED | - | ELECTRIC MAINTENANCE HOLE | l . | |
| | HANDRAIL | :======== | | CABLE MAINTENANCE HOLE | (5) | |
| MILY VALUE | BOLLARD | N/A | • | TRANSFORMER | | |
| CLID Y-SECTION CLID | DOOR | | | OUTLET | / | N/A |
| SATE | VALLEY GUTTER | | | | | |
| ### AMANG WALL ### AMANG WALL | | | | UTILITY VALVE | ₩ | |
| CAMBRO SOL | WALL | | | JOINT TRENCH | | |
| ### CAMERIA MONTH PART 10 10 10 10 10 10 10 1 | WALL | | | OVERHEAD ELECTRICAL | — — OHE — — — | ОНЕ |
| TREPROVE | RETAINING WALL | | | TELEVISION/CABLE | TV | |
| FORTION | FENCE - CHAINLINK/VINYL/CABLE | | | UNDERGROUND ELECTRICAL | UG | |
| ELECTRICAL PRICE PROPERT PRICE - PROPERT PRICE | FENCE - WOOD/METAL/STEEL | | | TELEPHONE | | |
| FERCE - TRICK FROM - PLANNING FROM - PLANNING AMERICAN AM | FENCE - BARBED WIRE | xxx | xx | | _ | |
| PARK 1980 | | | | | | |
| FEACURE (1909/10) FEACURATE (| | | | MISCELLANEOUS UTILITY | | <u> </u> |
| FEACE (100/MIC) OLLY PROMITE OLLY PROMITE ON OUT | FENCE - SPLIT RAIL | | N/A | SEWER MANHOLE | (§); | S |
| APPRIATE A | FENCE - HOGWIRE | | | ECCENTRIC SEWER MANHOLE | | () |
| ORACHOL CORE ORANG GOTT ORAN | BARRICADE | _ 0 0 0 0 0 0 | | SEWER CLEAN OUT | (m) | ● |
| SOURCE AND SOURCE SOURCE AND SOURCE | GUARDRAIL | | N/A | SEPTIC TANK | - <u>SEPIC</u> - ¬ | SEPTIC |
| Service (ARAN) IMA SERVICE (ARAN) SERVICE (ARAN | ROLLING GATE | <i>□</i> | <i></i> | | L3 | |
| PRENCH SAME SEMER LATERAL SAME PLOTES WAND SOUTH PROTECT NA SIDAN DARING CLEAN OUI STORM DARING STRUCTURE D PART TO THE CONTROLL STRUCTURE D STORM DARING STRUCTURE D SAME PLOTES WAND SOUTH DARING STRUCTURE D NA STORM DARING STRUCTURE D NA STORM DARING STRUCTURE D SAME SAME STORM DARING STRUCTURE D SAME SAM | | <i>></i> < | \ <u>\</u> | | · · | |
| SWACUT DAY SERVED FORDER MANO STORM DRAIN MANIELE DEWATERING MANHOLE DEWATERING M | | i vo | | SEWER (MAIN) | — ss — (<u>Ex12"SS</u> ! — | 12"SS |
| UTILITY FEMOVAL CONTOUR - MACOR CONTOUR - MACO | TRENCH | | N/A | SEWER (LATERAL) | N/A | |
| DAYLIGHT FILL ANA CHIRINET CHIRILET CHIRIL | SAWCUT | <u> ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,</u> | N/A | SEWER (FORCE MAIN) | — — ss — (<u>Ex12"FM</u> ! — | 12"SSFM |
| DAYLIGHT FILL ANA CHIRINET CHIRILET CHIRIL | UTILITY REMOVAL | ////////////////////////////////////// | N/A | STORM DRAIN MANHOLE | (ŚĎ) | (SD) |
| DAMBET CUT NA DAMBET FILE NA CURRAN RET CURRAN RE | CONTOUR - MAJOR | 32 | 32 | DEWATERING MANHOLE | (M) | |
| DAVIGHT FILL ANA CUPRA NET CHENATION FIG.00 FIRMANATER LEADER FIRMANATER LEAD | CONTOUR - MINOR | 32 | 32 | | Enn. | |
| DAYLIGHT FILL NA CLIFR NIET CHAIN NILET CHAIN NILET CON MANHOLE CHAIN NI | | Ν/Δ | | | | |
| GRAND ESPECIALS PADE LEVATION 10.0 SLOPE | | | | | (a) | |
| PAD ELEVATION JO.05 SLOPE Q.007 Q.0007 STORM DRAIN STRUCTURE ID NA PRIAL RELEVATION TAG TOE OF SLOPE HICH POINT SIGN SINGLE LINE DOUBLE LINE STORM DRAIN STORM DRAIN THENCH DRAIN TOE OF SLOPE HICH POINT SIGN SINGLE LINE SWALE STORM DRAIN (LANDSCAPE SERWICES) NA TOE DASHED LINE DOUBLE DASHED LINE THE PRIAL TOE MANHOLE THE PRIAL THE PRI | | N/A | | CURB INLET | | |
| PAD ELEVATION JO.05 SLOPE Q.007 Q.0007 STORM DRAIN STRUCTURE ID NA PRIAL RELEVATION TAG TOE OF SLOPE HICH POINT SIGN SINGLE LINE DOUBLE LINE STORM DRAIN STORM DRAIN THENCH DRAIN TOE OF SLOPE HICH POINT SIGN SINGLE LINE SWALE STORM DRAIN (LANDSCAPE SERWICES) NA TOE DASHED LINE DOUBLE DASHED LINE THE PRIAL TOE MANHOLE THE PRIAL THE PRI | GRADE BREAK | | | DRAIN INLET | | |
| SLOPE LEEVATON TAG .00.00 CC. RAINWATER LEADER RIPPAR (ROCK DISCHARGE PAD) STORM DRAIN TRENCH DRAIN SINGLE LINE DOUBLE LINE STORM DRAIN (LANDSCAPE SERVICES) ROCK THENCH COLLIVERT WATER MALE WATER MALE BLOW OFF VALVE BACKFLOW PREVENTER DOUBLE CHECK DETECTOR ASSEMBLY FIRST PAGE OF SUPPLY DOUBLE CHECK DETECTOR ASSEMBLY DOUBLE CHECK D | PAD ELEVATION | 10.0 | 10.0 | DRAIN INLET ON MANHOLE | | (<u>e</u>) |
| ELEVATION TAG TOE OF SLOPE HIGH POINT SIGN STORM DRAIN TRENCH DISCHARGE PAD) STORM DRAIN TRENCH DISCHARGE PAD) STORM DRAIN TRENCH DRAIN STORM DRAIN (LANDSCAPE SERVICES) NA STOP BAR/CROSSWALK DASHED LINE MAILEOX UTILITY STRUCTURE WATER MAILE BLOW OFF VALIVE WATER MAILE DODA DOD | SLOPE | 0.00% | 0,00% | STORM DRAIN STRUCTURE ID | _ | |
| TOE OF SLOPE HIGH POINT SIGN SINGLE LINE DOUBLE LINE STOP BAR/CROSSWALK DASHED LINE DOUBLE DASHED LINE MANHOLE MALBOX UTILITY STRUCTURE WATER MATER BLOW OFF VALVE BACKFLOW PREVENTER DOUBLE CHECK DETECTOR ASSEMBLY FIRE HYDRANT | ELEVATION TAG | 00.00 CC | 00.00 CC | | · · | |
| STORM DRAIN SIGNALE SIGNALE SIGNALE SIGNALE SIGNALE STORM DRAIN TRENCH DRAIN STORM DRAIN (LANDSCAPE SERVICES) N/A PRINCH DRAIN N/A CULVERT CULVERT STORM DRAIN CULVERT STORM DRAIN CULVERT STORM DRAIN CULVERT STORM DRAIN CULVERT CULVERT STORM DRAIN CULVERT CULVERT STORM DRAIN CULVERT STORM DRAIN CULVERT CULVERT STORM DRAIN CULVERT CULVERT STORM DRAIN CULVERT CULV | TOE OF SLOPE | | | | | |
| SIGN SINGLE LINE DOUBLE LINE STORM DRAIN TRENCH DRAIN SWALE STORM DRAIN (LANDSCAPE SERVICES) NA ROCK TRENCH FRENCH DRAIN NA CULVERT CULVE | | | | | | |
| SINGLE LINE DOUBLE LINE SYALE STORM DRAIN (LANDSCAPE SERVICES) N/A ROCK TRENCH ROCK TRENCH | | - | | | | 12"SD |
| DOUBLE LINE STORM DRAIN (LANDSCAPE SERVICES) N/A ROCK TRENCH ROCK TRENCH RENCH DRAIN N/A CULVERT CULVERT CULVERT STORM DRAIN (LANDSCAPE SERVICES) N/A ROCK TRENCH ROCK TRENCH ROCK TRENCH RENCH DRAIN N/A CULVERT CULVERT CULVERT CULVERT CULVERT CULVERT CULVERT CULVERT CULVERT | | | -0 | STORM DRAIN TRENCH DRAIN | הערונה עם | |
| STOP BAR/CROSSWALK DASHED LINE DOUBLE DASHED LINE MANHOLE MAIL WITHIN STRUCTURE WATER VALVE WATER METER BLOW OFF VALVE BACKFLOW PREVENTER DOUBLE CHECK DETECTOR ASSEMBLY DCDA | SINGLE LINE | | | SWALE | | ————— |
| DASHED LINE DOUBLE DASHED LINE MANHOLE MAIL WILL WILLITY STRUCTURE WATER VALVE WATER METER BLOW OFF VALVE BACKFLOW PREVENTER DOUBLE CHECK DETECTOR ASSEMBLY FIRE HYDRANT FRENCH DRAIN N/A CULVERT CULVERT FRENCH DRAIN N/A CULVERT FRENCH DRAIN N/A CULVERT DOUBLE CHECK DETECTOR ASSEMBLY FRENCH DRAIN N/A CULVERT | DOUBLE LINE | | | STORM DRAIN (LANDSCAPE SERVICES) | N/A | |
| DASHED LINE DOUBLE DASHED LINE MANHOLE MALBOX UTILITY STRUCTURE WATER VALVE WATER METER BLOW OFF VALVE BACKFLOW PREVENTER DOUBLE CHECK DETECTOR ASSEMBLY FRENCH DRAIN NA CULVERT FRENCH DRAIN NA CULVERT CULVERT | STOP BAR/CROSSWALK | | | ROCK TRENCH | | |
| DOUBLE DASHED LINE MANHOLE MAIL MAIL UTILITY STRUCTURE WATER VALVE WATER METER BLOW OFF VALVE BACKFLOW PREVENTER DOUBLE CHECK DETECTOR ASSEMBLY FIRE HYDRANT CULVERT CULVERT CULVERT CULVERT | DASHED LINE | | | | | |
| MANHOLE MAILBOX UTILITY STRUCTURE WATER VALVE WATER METER BLOW OFF VALVE BACKFLOW PREVENTER DOUBLE CHECK DETECTOR ASSEMBLY FIRE HYDRANT DOUBLE CHECK DETECTOR ASSEMBLY FIRE HYDRANT DOUBLE CHECK DETECTOR ASSEMBLY DOUBLE C | | | | | | |
| UTILITY STRUCTURE WATER VALVE WATER METER BLOW OFF VALVE BACKFLOW PREVENTER DOUBLE CHECK DETECTOR ASSEMBLY FIRE HYDRANT US US US US US US US US US U | | | | CULVERI | | |
| UTILITY STRUCTURE WATER VALVE WATER METER BLOW OFF VALVE BACKFLOW PREVENTER DOUBLE CHECK DETECTOR ASSEMBLY FIRE HYDRANT US US US US US US US US US U | | | | | | |
| UTILITY STRUCTURE WATER VALVE WATER METER BLOW OFF VALVE BACKFLOW PREVENTER DOUBLE CHECK DETECTOR ASSEMBLY FIRE HYDRANT US US US US US US US US US U | MAILBOX | IVIAIL | | | | |
| WATER METER BLOW OFF VALVE BACKFLOW PREVENTER DOUBLE CHECK DETECTOR ASSEMBLY FIRE HYDRANT WM BBO BO BO BO BO BC BFP BFP BFP BFP BCDA DCDA | UTILITY STRUCTURE | US * | | | | |
| WATER METER BLOW OFF VALVE BACKFLOW PREVENTER DOUBLE CHECK DETECTOR ASSEMBLY FIRE HYDRANT WM BBO BO BO BO BO BO BO BC BFP BFP BFP BFP BCDA DCDA DCDA | WATER VALVE | WV * | WV ⊗ | | | |
| DCDA DCDA DCDA DCDA DCDA DCDA DCDA DCDA | WATER METER | WM (50000) | WM (50000) | | | |
| DOUBLE CHECK DETECTOR ASSEMBLY DCDA DCDA | | <u>"</u> BO | | | | |
| DOUBLE CHECK DETECTOR ASSEMBLY DCDA DCDA | | BFP | BFP | | | |
| FIRE HYDRANT FIRE HYDRANT THE CHECK DETECTOR ASSEMBLY THE CHECK DETECTO | | | | | | |
| | DOUBLE CHECK DETECTOR ASSEMBLY | | a B□DB o a B□DB o% | | | |
| | FIRE HYDRANT | | \bigcap | | | |
| TTT \MWD | MONITORING WELL | | | | | |

| ABBREVI | ATIONS | | | |
|-----------------------------|---|-----------------------|---|-------------------------|
| <u>+</u> @ | PLUS OR MINUS (NOT EXACT) AT | IV JB | IRRIGATION VALVE JUNCTION BOX | |
| Ø AB | DIAMETER AGGREGATE BASE | JP JT | JUNCTION POLE JOINT TRENCH | |
| ABDN AC | ABANDONED ACRE, ASPHALT CONCRETE | JP L, LT | JOINT POLE LEFT | |
| A/C ACP ACM | AIR CONDITIONING ASBESTOS CEMENT PIPE ASBESTOS CONTAINING MATERIAL | L= LF | LENGTH (CURVE) LINEAL/LINEAR FEET LATERAL | |
| AD ADA | ASBESTOS CONTAINING MATERIAL AREA DRAIN AMERICANS W/ DISABILITIES ACT | LAT LIP LN | LIP OF GUTTER LANE | |
| AG AGG | ATRIUM GRATE AGGREGATE | LP FH | LIGHT POLE, LOW POINT FIRE HYDRANT | |
| ALGN ALT | ALIGNMENT ALTERNATE | LS LSA | LANDSCAPE LANDSCAPE ARCHITECT | UOS USA-B |
| APN ARV | ASSESSORS PARCEL NUMBER AIR RELEASE VALVE | MA MAX | MEDICAL AIR MAXIMUM | USA-G USA-M |
| ASB ASPH ASR | AGGREGATE SUBBASE ASPHALT AUTOMATIC SPRINKLER RISER | MEP MH MIN | MECHANICAL/ELECTRICAL/PLUMBING MAN/MAINTENANCE HOLE MINIMUM | USA-O USA-P |
| BC BDRY | BEGIN CURVE BOUNDARY | MIPT MJ | MALE IRON PIPE THREAD MECHANICAL JOINT | USA-R USA-W USA-Y |
| BFP BK | BACK FLOW PREVENTOR BOOK | MPVC MON | MIDPOINT OF VERTICAL CURVE MONUMENT | VC VCP |
| BLDC BLDG | BUILDING CORNER BUILDING BEST MANAGEMENT PRACTICES | MS MW | MOW STRIP MONITORING WELL | VERT W |
| BMP BM BO | BEST MANAGEMENT PRACTICES BENCHMARK BLOW OFF | N (N) NDS | NORTH, NORTHING COORDINATE NEW NDS INC. (MANUFACTURER) | W/ WA |
| BOD BOL | BOTTOM OF DOCK BOLLARD | NIC NO | NOT INCLUDED/IN CONTRACT NUMBER | WB WM WMB |
| BOW BSW | BACK OF WALK BACK OF SIDEWALK | NSE NTS | NORTHSTAR ENGINEERING NOT TO SCALE | WOA WS |
| BS BSL BVC | BEGIN STRIPING BUILDING SETBACK LINE BEGIN VERTICAL CURVE | OC OG OHE | ON CENTER ORIGINAL GROUND / GRADE OVERHEAD ELECTRICAL | WV WW |
| BW C | FINISHED GRADE AT BOTTOM OF WALL CIVIL | O.R. (P) | OFFICIAL RECORDS PROPOSED | WWF WY |
| CC CB | CONCRETE CATCH BASIN | P, PAV PB | PAVEMENT PULL BOX | YD |
| CBL CDS | CABLE CONTINUOUS DEFLECTION | PCC PCC | POINT OF COMPOUND/CONVERSE CURVATURE PORTLAND CEMENT CONCRETE | |
| CG/C&G CG&S | CURB AND GUTTER CURB, GUTTER & SIDEWALK | PE PED | PLAIN END PEDESTRIAN PEDESTRIAN | |
| CI CIP • OR CL | CAST IRON/CURB INLET CAST IRON PIPE CENTER LINE | PERF PG PG&E | PERFORATED PAGE PACIFIC GAS AND ELECTRIC | |
| CLR CMH | CLEAR CABLE MAINTENANCE HOLE | PH PID | POTHOLE POINT ID | |
| CMN CMP | COMMUNICATION CORRUGATED METAL PIPE | PIV PL | POST/PRESSURE INDICATOR VALVE PROPERTY LINE | |
| CO COMP. | CLEAN OUT COMPACTION | PM PMH | PARKING METER, PARCEL MAP POWER MANHOLE | |
| CONC OR CC CONST CONF | CONCRETE CONSTRUCTION OR CONSTRUCT CONFORM TO EXISTING | PO POC POI | PUSH-ON POINT ON CURVE/POINT OF CONNECTION POINT OF INTERSECTION | |
| COS OR C.O.S CR | CITY OF STOCKTON CURB/CROWN | PP PRC | POWER POLE POINT OF REVERSE CURVATURE | |
| CT. CU | COURT/CUBIC CULVERT | PROF PRV | PROFILE PRESSURE REDUCING VALVE | |
| CV CV | CHECK VALVE CUBIC YARD | PRUE PT | PRIVATE UTILITY EASEMENT POINT PAGISTRE TO FOLIONE & TELEGRAPH | |
| D= DCDA DEMO | DELTA (CURVE) DOUBLE CHECK DETECTOR ASSEMBLY DEMOLISH | PT&T PUE PVC | PACIFIC TELEPHONE & TELEGRAPH PUBLIC UTILITY EASEMENT POLYVINYL CHLORIDE PIPE | |
| DEPT DI | DEPARTMENT DROP/DRAIN INLET/DUCTILE IRON | R R= | RIGHT RADIUS | |
| DIA DIP | DIAMETER DUCTILE IRON PIPE | RC RCP | RELATIVE COMPACTION REINFORCED CONCRETE PIPE | |
| DOM, (DOM) DR DS | DOMESTIC DRIVE DOWNSPOUT | RD RJ RP | ROAD, RELATIVE DENSITY RESTRAINED JOINT RADIUS POINT | |
| DTL DW | DETAIL DOMESTIC WATER/DRYWELL/DEWATERING | RPPA RSC | REDUCED PRESSURE PRINCIPLE ASSEMBLY RECEIVING AND SUPPORT CENTER | |
| DWG DWY | DRAWING DRIVEWAY | RV RW | RESISTANCE VALUE RECYCLED WATER | |
| DYL E | DOUBLE YELLOW LINE EAST/EASTING COORDINATE/ELECTRIC | RW, R/W, ROW RWL | RIGHT-OF-WAY RAINWATER LEADER | |
| (E) EC EG | EXISTING END CURVE EXISTING GRADE | S.A.D. SBL | SOUTH, SLOPE SEE ARCHITECTURAL DRAWINGS SETBACK LINE, SOLID BLACK LINE | |
| EL, ELEV ELB | ELEVATION ELECTRIC BOX | SJC SCO | SAN JOAQUIN COUNTY SEWER CLEANOUT | |
| ELC/ELEC ELV | ELECTRICAL ELECTRIC VAULT | SD SDB | STORM DRAIN STORM DRAIN BASIN | |
| EM EMH | ELECTRIC METER ELECTRIC MAINTENANCE HOLE | SDCB SDCO SDDW | STORM DRAIN CATCH BASIN STORM DRAIN CLEAN OUT STORM DRAIN DEWATERING | |
| EP ES ESMT OR EASE | EDGE OF PAVEMENT END STRIPING EASEMENT | SDI SDFM | STORM DRAIN DEWATERING STORM DRAIN INLET STORM DRAIN FORCE MAIN | |
| EVC EX OR EXIST | END OF VERTICAL CURVE EXISTING | SDMH S.E.D. | STORM DRAIN MAINTENANCE HOLE SEE ELECTRICAL DRAWINGS | |
| EVA (F) | EMERGENCY VEHICLE ACCESS FUTURE | SG SF | SUB-GRADE SILT FENCE SG SUBGRADE | |
| FA FAB FC, F/C | FIRE ALARM FIRE ALARM BOX FACE OF CURB | SHT SIM SL | SHEET SIMILAR STREET LIGHT | |
| FD FDC | FOUND/FRENCH DRAIN FIRE DEPARTMENT CONNECTION | S.L.D. SLB | SEE LANDSCAPE DRAWINGS STREET LIGHT BOX | |
| FE FES | FENCE FLARED END SECTION | SMH S.M.D. | SIGNAL MANHOLE SEE MECHANICAL DRAWINGS | |
| FF FFE | FINISH FLOOR FINISH FLOOR ELEVATION | SNS SP | STREET NAME SIGN SERVICE POLE | |
| FG FH FIPT | FINISH GRADE FIRE HYDRANT FEMALE IRON PIPE THREAD | S.P.D SRL SS | SEE PLUMBING DRAWINGS SOLID RED LINE SANITARY SEWER | |
| FL FLG | FLOW LINE/FLANGE FLANGE | SSCO SSFM | SANITARY SEWER CLEAN OUT SANITARY SEWER FORCE MAIN | |
| FM FOUND | FLOWMETER/FORCE MAIN FOUNDATION | SSMH SSPS | SANITARY SEWER MAN/MAINTENANCE HOLE SANITARY SEWER PUMP STATION | |
| FS FSR FT | FINISHED SURFACE, FIRE SERVICE FIRE SPRINKLER RISER FOOT, FEET | ST STA STD | STREET, SEPTIC TANK STATION STANDARD | |
| FW G | FIRE WATER GAS, GROUND | STL S/W, SW | STEEL SIDEWALK | |
| GB GE | GRADE BREAK GROUND ELEVATION | SWL T | SOLID WHITE LINE, SWALE TELEPHONE | |
| GI GM | GALVANIZED IRON GAS METER | TC TBC | TOP OF CURB TOP BACK OF CURB | |
| GR GRD GS | GRATE GROUND GROUND SHOT ELEVATION | TCP TD TEL | TEMPORARY CONTROL POINT TRENCH DRAIN TELEPHONE | |
| GUY GV | GUY/GUIDE LINE GAS VALVE | TELB TELV | TELEPHONE BOX TELEPHONE VAULT | |
| H2O HB | WATER HOSE BIB | TEMP TFC | TEMPORARY TOP FACE OF GRATE | |
| HMA HORIZ | HOT MIX ASPHALT HORIZONTAL | TG TH | TOP OF GRATE THRESHOLD | |
| HT HP HPS | HEIGHT HIGH POINT HIGH PRESSURE SODILIM/SYSTEM | THK TI | THICK TRAFFIC INDEX TELEPHONE MAINTENANCE HOLE | |
| HPS HT HWY | HIGH PRESSURE SODIUM/SYSTEM HEIGHT HIGHWAY | TMH TOD TOW | TELEPHONE MAINTENANCE HOLE TOP OF DOCK TOP OF WALL | |
| HWL IBX | HIGH WATER LINE IRRIGATION BOX | TP TPE | TELEPHONE POLE, TEST PIT TREE PLANTING EASEMENT | |
| ICB ICV | IRRIGATION CONTROL BOX IRRIGATION CONTROL VALVE | TS TSB | TRAFFIC SIGNAL TRAFFIC SIGNAL BOX | |
| IHW IM | IRRIGATION HEADWALL IRRIGATION METER | TSCE TSP | TEMPORARY STABILIZED CONSTRUCTION ENTRANCE TRAFFIC SIGNAL POLE | |
| IMH ID INV | IRRIGATION MAINTENANCE HOLE INSIDE DIAMETER INVERT | TV TVR TYP | TELEVISION CABLE TV RISER TYPICAL | |
| INST IRR | INSTALL IRRIGATION | U/UTIL/UTL UG, U/G | UTILITY UNDERGROUND | |
| ISP | IRRIGATION STAND PIPE | UON | UNLESS OTHERWISE NOTED | |

ENGINEERING GROUP'S TYPICAL GENERAL NOTES AND SOME NOTES MAY NOT BE APPLICABLE TO THIS

PRIOR TO ANY WORK BEING PERFORMED. THE CONTRACTOR SHALL CONTACT THE APPROPRIATE REGULATORY AGENCIES FOR A PRE-CONSTRUCTION CONFERENCE. CONTRACTOR SHALL ALSO NOTIFY THE PROJECT CONTACTS LISTED ON THIS SHEET FORTY-EIGHT (48) HOURS IN ADVANCE OF SAID

CALIFORNIA BUILDING CODE STANDARDS, THE CITY AND/OR CALIFORNIA BUILDING CODE STANDARDS SHALL PREVAIL. ALL WORK SHALL BE SUBJECT TO THE INSPECTION OF THE CITY OF STOCKTON.

- IT IS INTENDED THAT THESE PLANS AND SPECIFICATIONS REQUIRE ALL LABOR AND MATERIALS NECESSARY AND PROPER FOR THE WORK CONTEMPLATED AND THAT THE WORK BE COMPLETED IN ACCORDANCE WITH THEIR TRUE INTENT AND PURPOSE. THE CONTRACTOR SHALL NOTIFY NORTHSTAR FNGINEFRING GROUP, INC. ("FNGINEFR") IMMEDIATELY REGARDING ANY DISCREPANCIES AND AMBIGUITIES WHICH MAY EXIST IN THE PLANS AND SPECIFICATIONS. IF THE PLANS OR SPECIFICATIONS DESCRIBE PORTIONS OF THE WORK IN GENERAL TERMS BUT NOT IN COMPLETE DETAIL, IT IS UNDERSTOOD THAT ONLY THE BEST GENERAL PRACTICE IS TO PREVAIL AND THAT ONLY MATERIALS AND WORKMANSHIP OF THE FIRST QUALITY ARE TO BE USED.
- IF NORTHSTAR ENGINEERING GROUP. INC. IS TO PERFORM ANY SURVEY STAKING. THEN CONSTRUCTION STAKING FOR GRADING. CURB. GUTTER. SIDEWALK. SANITARY SEWER. STORM DRAIN AND WATER SHALL BE DONE UNDER THE DIRECTION OF THE ENGINEER. THE CONTRACTOR SHALL NOTIFY THE ENGINEER SEVENTY-TWO (72) HOURS IN ADVANCE OF THIS NEED FOR STAKING. ANY STAKING REQUESTED BY THE CONTRACTOR OR HIS SUBCONTRACTORS THAT IS ABOVE AND BEYOND NORMAL STANDARD STAKING NEEDS AS OUTLINED IN THE CONTRACT, WILL BE SUBJECT TO AN EXTR BACK CHARGE TO THE CONTRACTOR.
- THE CONTRACTOR SHALL EXERCISE DUE CAUTION AND SHALL CAREFULLY PRESERVE BENCH MARKS REFERENCE POINTS AND ALL SURVEY STAKES, AND SHALL BEAR ALL EXPENSE FOR REPLACEMENT AND/OR ERRORS CAUSED BY THEIR UNNECESSARY LOSS OR DISTURBANCE.
- CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SIT CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY A HOLD THE OWNER, ENGINEER AND THE CITY HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR THE ENGINEER.
- THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY FIELD CHANGES MADE WITHOUT WRITTEN AUTHORIZATION FROM THE CITY ENGINEER.
- THE CONTRACTOR SHALL PROVIDE ALL LIGHTS, SIGNS, BARRICADES, FLAGMEN, OR OTHER DEVICES NECESSARY FOR PUBLIC SAFETY IN ACCORDANCE WITH THE CURRENT ISSUE OF "MANUAL OF TRAFFI CONTROLS. WARNING SIGNS. LIGHTS. AND DEVICES FOR USE IN PERFORMANCE OF WORK UPON HIGHWAY" PUBLISHED BY THE STATE OF CALIFORNIA BUSINESS AND TRANSPORTATION AGENCY. CONTRACTOR SHALL COORDINATE WITH THE GOVERNING LOCAL AGENCY TO DETERMINE IF ANY CHANGES TO THE CLASSIFICATION OR OPERATION OF A ROADWAY ARE REQUIRED DUE TO THE IMPROVEMENTS SHOWN ON THESE PLANS (SUCH AS SPEED LIMITS INTERSECTION TYPE, ETC.) ANI SHALL BE RESPONSIBLE FOR PROVIDING ALL NECESSARY INTERIM TRAFFIC MANAGEMENT MEASUR REQUIRED BY THE GOVERNING AGENCY, INCLUDING TRANSITIONAL SIGNAGE AND STRIPING IN PREPARATION OF AND TO BE INSTALLED PRIOR TO COMPLETION AND ACCEPTANCE OF ULTIMATE SIGNAGE AND STRIPING. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH IMPLEMENTING THESE MEASURES.
- THE OFFICE OF THE CITY OF STOCKTON PUBLIC WORKS SHALL BE NOTIFIED AT LEAST 48 HOURS IN ADVANCE OF ANY WORK.
- CABLE TV, ELECTRICAL, GAS, AND TELEPHONE UNDERGROUND WORK SHALL BE COMPLETED PRIOR TO CONSTRUCTION OF THE CURB. GUTTER, SIDEWALK AND PAVING.
- THE CONTRACTOR SHALL OBTAIN AN ENCROACHMENT PERMIT FROM THE CITY OF STOCKTON. DEPARTMENT OF PUBLIC WORKS OR ANY OTHER APPLICABLE AGENCY PRIOR TO COMMENCEMENT WORK WITHIN EXISTING CITY RIGHT-OF-WAY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PERMITS AND LICENSES REQUIRED FOR THE CONSTRUCTION AND COMPLETION OF THE PROJECT.
- THE CITY OF STOCKTON OR ASSOCIATED UTILITY COMPANY AND RESIDENCES TO BE AFFECTED SHALL BE NOTIFIED IMMEDIATELY UPON ANY UTILITY SERVICE DISRUPTION OTHER THAN SPECIFIED ON THESE IMPROVEMENT PLANS AND A TWENTY-FOUR (24) HOUR NOTICE SHALL BE GIVEN FOR ANY PLANNED
- STREET SIGNS, TRAFFIC CONTROL SIGNS, AND PAVEMENT MARKINGS SHALL BE PROVIDED AND INSTALLED BY THE CONTRACTOR AT LOCATIONS ESTABLISHED BY THE ENGINEER.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING EXISTING IMPROVEMENTS FROM DAMAGE. COST OF REPLACING DAMAGED EXISTING IMPROVEMENTS SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEMS REQUIRING REMOVAL AND REPLACEMENT.
- CONTRACTOR IS RESPONSIBLE FOR COORDINATION OF THE REMOVAL OR RELOCATION OF ALL EXISTING UTILITIES WITH RESPECTIVE UTILITY COMPANIES.
- ASPHALT CONCRETE SHALL BE PLACED ONLY WHEN THE ATMOSPHERIC TEMPERATURE IS ABOVE 50°F
- DRAWING NUMBERS SHOWN ON THE PLANS REFER TO DRAWINGS CONTAINED IN THE CITY OF STOCKTON STANDARD SPECIFICATIONS (I.E. DWG. 30).
- ALL TRENCHES IN PAVED AREAS SHALL BE PAVED WITH TEMPORARY PAVING, OR COVERED WITH A STEEL PLATE OF APPROPRIATE SIZE AND STRENGTH, THE SAME DAY THE PAVEMENT CUT IS MADE.
- WHENEVER PAVEMENT IS BROKEN OR CUT IN THE INSTALLATION OF THE WORK COVERED BY THESE SPECIFICATIONS AND PLANS, THE PAVEMENT SHALL BE REPLACED, AFTER PROPER BACK FILLING, WITH PAVEMENT MATERIALS EQUAL TO OR BETTER THAN THE MATERIALS USED IN THE ORIGINAL PAVING. THE FINISHED PAVEMENT SHALL BE SUBJECT TO THE APPROVAL OF THE CITY ENGINEER.
- PRIOR TO COMMENCING ANY WORK, IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO HAVE EACH UTILITY COMPANY LOCATED, IN THE FIELD, THEIR MAIN AND SERVICE LINES. THE CONTRACTOR SHALL NOTIFY MEMBERS OF THE UNDERGROUND SERVICE ALERT (U.S.A.) FORTY-EIGHT (48) HOURS IN ADVANCE OF PERFORMING ANY EXCAVATION WORK BY CALLING THE TOLL-FREE NUMBER (800) 227-2600. THE CONTRACTOR SHALL RECORD THE U.S.A. ORDER NUMBER. IT SHALL BE THE CONTRACTOR'S SOLE RESPONSIBILITY TO PROTECT ALL EXISTING UTILITIES SO THAT NO DAMAGE RESULTS TO THEM DURING THE PERFORMANCE OF THIS CONTRACT. ANY REPAIRS NECESSARY TO DAMAGED UTILITIES SHALL BE PAID FOR BY THE CONTRACTOR. THE CONTRACTOR SHALL BE REQUIRED TO COOPERATE WITH OTHER CONTRACTORS AND UTILITY COMPANIES INSTALLING NEW STRUCTURES, UTILITIES AND SERVICE TO THE DEVELOPMENT.
- PAYMENT FOR PAVEMENT WILL BE MADE ONLY FOR AREAS SHOWN ON THE PLANS. REPLACEMENT OF PAVEMENT WHICH IS BROKEN OR CUT DURING THE INSTALLATION OF THE WORK COVERED BY THESE SPECIFICATIONS AND PLANS, AND WHICH LIES OUTSIDE OF SAID AREAS, SHALL BE INDICATED IN THE CONTRACTOR'S UNIT PRICE FOR PAVEMENT, AND NO ADDITIONAL PAYMENT SHALL BE MADE FOR SUCH WORK.
- EXCAVATIONS OF 5 FEET OR MORE IN DEPTH WILL REQUIRE AN EXCAVATION PERMIT FROM THE STATE OF CALIFORNIA DEPARTMENT OF INDUSTRIAL SAFETY. FOR TRENCHES 5 FEET OR MORE IN DEPTH, THE CONTRACTOR SHALL COMPLY WITH SECTION 5-1.02A OF THE CALTRANS STANDARDS, CHAPTER 9 OF THE STATE OF CALIFORNIA LABOR CODE, AND ANY LOCAL CODES OR ORDINANCES.
- WE CALL YOUR ATTENTION TO TITLE 8 CALIFORNIA ADMINISTRATION CODE SECTION 1540 (A) (1) OF THE CONSTRUCTION SAFETY ORDERS ISSUED BY THE OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD PURSUANT TO THE CALIFORNIA OCCUPATIONS SAFETY AND HEALTH ACT OF 1973 AS AMENDED WHICH STATES: (1) PRIOR TO OPENING AN EXCAVATION EFFORT SHALL BE MADE TO DETERMINE WHETHER UNDERGROUND INSTALLATIONS; I.E. SEWER, WATER, FUEL, ELECTRICAL LINES ETC., WILL BE ENCOUNTERED AND IF SO, WHERE SUCH UNDERGROUND INSTALLATIONS ARE LOCATED WHEN THE EXCAVATION APPROACHES THE APPROXIMATE LOCATION OF SUCH INSTALLATION, THE EXACT LOCATION SHALL BE DETERMINED BY CAREFUL PROBING OR HAND DIGGING; AND, WHEN IT IS UNCOVERED, ADEQUATE PROTECTION SHALL BE PROVIDED FOR THE EXISTING INSTALLATION. ALL KNOWN OWNERS OF UNDERGROUND FACILITIES IN THE AREA CONCERNED SHALL BE ADVISED OF PROPOSED WORK AT LEAST FORTY-EIGHT (48) HOURS PRIOR TO THE START OF ACTUAL EXCAVATION
- THE CONTRACTOR SHALL MAINTAIN A NEATLY MARKED SET OF FULL-SIZE AS-BUILT RECORD DRAWINGS SHOWING THE FINAL LOCATION AND LAYOUT OF ALL MECHANICAL. ELECTRICAL AND INSTRUMENTATION EQUIPMENT, PIPING AND CONDUITS, STRUCTURES AND OTHER FACILITIES. AS-BUILT RECORD DRAWINGS SHALL REFLECT CHANGE ORDERS, ACCOMMODATIONS, AND ADJUSTMENTS TO ALL IMPROVEMENTS CONSTRUCTED. WHERE NECESSARY, SUPPLEMENTAL DRAWINGS SHALL BE PREPARED AND SUBMITTED BY THE CONTRACTOR TO THE DEVELOPER AND APPROVAL AGENCY
- SIGNING, STRIPING AND PAVEMENT MARKINGS SHALL BE IN STRICT CONFORMANCE WITH THE CITY OF STOCKTON STANDARDS AND SPECIFICATIONS.

GENERAL NOTES (CONT)

- PRIOR TO ACCEPTANCE OF THE PROJECT, THE CONTRACTOR SHALL DELIVER TO THE ENGINEER, ONE SET OF NEATLY MARKED AS-BUILT RECORD DRAWINGS SHOWING THE INFORMATION REQUIRED ABOVE. AS-BUILT RECORD DRAWINGS SHALL BE REVIEWED AND THE COMPLETE AS-BUILT RECORD DRAWING SET SHALL BE CURRENT WITH ALL CHANGES AND DEVIATIONS REDLINED AS A PRECONDITION TO THE FINAL PROGRESS PAYMENT APPROVAL AND/OR FINAL ACCEPTANCE.
- AFTER CONSTRUCTION OF ALL IMPROVEMENTS, THE CONTRACTOR SHALL SUBMIT ONE SET OF REPRODUCIBLE PLANS. FINAL INVERT ELEVATIONS FOR SEWER AND STORM DRAIN LINES THAT ARE TO BE EXTENDED FOR FUTURE CONSTRUCTION SHALL ALSO BE SHOWN ON THE "AS-BUILT" PLANS ALL AS PROVIDED BY THE CONTRACTOR.
- THE CONTRACTOR SHALL NOTIFY NORTHSTAR ENGINEERING AT LEAST 48 HOURS PRIOR TO BACK FILLING OF ANY PIPE WHICH STUBS TO A FUTURE PHASE OF CONSTRUCTION FOR INVERT VERIFICATION. TOLERANCE SHALL BE IN ACCORDANCE WITH THE CITY OF STOCKTON STANDARD
- WHENEVER EXISTING FACILITIES ARE REMOVED, DAMAGED, BROKEN, OR CUT IN THE INSTALLATION OF THE WORK COVERED BY THESE PLANS OR SPECIFICATIONS, SAID FACILITIES SHALL BE REPLACED AT THE CONTRACTORS EXPENSE, AFTER PROPER BACKFILLING AND/OR CONSTRUCTION, WITH MATERIALS EQUAL TO OR BETTER THAN THE MATERIALS USED IN THE ORIGINAL EXISTING FACILITIES. THE FINISHED PRODUCT SHALL BE SUBJECT TO THE APPROVAL OF THE OWNER, THE ENGINEER, AND THE RESPECTIVE REGULATORY AGENCY.
- DUST CONTROL SHALL BE PROVIDED AT ALL TIMES, AT THE CONTRACTOR'S EXPENSE TO MINIMIZE ANY DUST NUISANCE AND SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE CITY OF STOCKTON. CONTRACTOR SHALL OBTAIN A PERMIT FROM CAL WATER FOR USE OF WATER FROM FIRE HYDRANTS FOR CONSTRUCTION PURPOSES. THE PERMIT SHALL BE APPROVED BY THE CITY OF STOCKTON FIRE DEPARTMENT.
- CONTRACTOR SHALL PROVIDE CITY WITH A CERTIFICATE SIGNED BY A REGISTERED CIVIL ENGINEER OF LAND SURVEYOR STATING THAT ALL BUILDING PAD ELEVATIONS ARE IN ACCORDANCE WITH THE APPROVED GRADING PLAN.
- UNLESS OTHERWISE STATED. ALL STATIONS INDICATED ON THE IMPROVEMENT PLANS ARE REFERENCED TO THE CENTERLINE OF THE STREET. ALL STATIONS OFF CENTER ARE PERPENDICULAR TO OR RADIALLY OPPOSITE CENTERLINE STATIONS, UNLESS OTHERWISE NOTED.
- DRIVEWAYS ON STREETS TO BE LOCATED IN THE FIELD BY THE ENGINEER AT THE TIME OF CONSTRUCTION. DRIVEWAYS SHALL NOT COINCIDE WITH WHEELCHAIR RAMPS.
- IF THE PROJECT IS SUBJECT TO THE INDIRECT SOURCE REVIEW (ISR) REQUIREMENT, THE CONTRACTOR IS REQUIRED TO KEEP DAILY RECORDS OF THE TOTAL HOURS OF OPERATION FOR EACH PIECE OF EQUIPMENT GREATER THAN 50-HORSEPOWER BEING USED ON THE PROJECT SITE DURING CONSTRUCTION. WITHIN 30 DAYS OF COMPLETING CONSTRUCTION OF EACH PROJECT PHASE, A REPORT SUMMARIZING TOTAL HOURS OF OPERATION BY EQUIPMENT TYPE, MODEL, YEAR, AND HORSEPOWER FOR EACH PIECE OF CONSTRUCTION EQUIPMENT GREATER THAN 50-HORSEPOWER MUST BE SUBMITTED TO THE AIR DISTRICT. TO ASSIST IN THIS RECORDKEEPING, THE "DETAILED FLEET TEMPLATE" IS AVAILABLE ON THE DISTRICT'S WEBSITE AT HTTP://WWW.VALLEYAIR.ORG/ISR/ISRFORMSANDAPPLICATIONS.HTM. FOR EACH PROJECT PHASE, TH DISTRICT WILL VERIFY THAT THE FLEET DETAILS ACHIEVED THE REQUIRED EMISSION REDUCTIONS. IF THE CONTRACTOR IS NOT GOING TO MEET THE STANDARDS AND/OR RECORD KEEPING REQUIRED BY THE AIR DISTRICT, THE CONTRACTOR SHALL NOTIFY THE AIR BOARD PRIOR TO CONSTRUCTION SO THE
- PRIOR TO FINALIZING IMPROVEMENTS AND OPENING ROADS THE CONTRACTOR SHALL COORDINATE WITH THE GOVERNING LOCAL AGENCY FOR POTENTIAL TRAFFIC SIGNAGE AND STRIPING MODIFICATIONS (FOR EXAMPLE, SPEED LIMIT CHANGES OR REDUCTIONS) BEYOND THE PROJECT LIMITS THAT ARE NECESSITATED BY THE CONSTRUCTION OF THE IMPROVEMENTS SHOWN ON THESE PLANS. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH SIGNAGE AND STRIPING MODIFICATIONS REQUIRED BY THE GOVERNING AGENCY.

NECESSARY MITIGATION FEE SHALL BE PAID. IF THE AIR BOARD IS NOT NOTIFIED PRIOR TO

CONSTRUCTION, THE CONTRACTOR SHALL BE REQUIRED TO PAY THE PENALTY TO THE AIR BOARD.

ANY ASSUMPTION MADE BY THE CONTRACTOR IS NOT THE RESPONSIBILITY OF THE ENGINEER OR DESIGN CONSULTANT. CONTRACTOR SHALL SUBMIT A PRE-BID REQUEST FOR INFORMATION (RFI) FOR ANY CLARIFICATION NEEDED AND SHALL BE RESPONSIBLE FOR COMPLETING THE PROJECT AT THE CONTRACTOR'S EXPENSE FOR ANY WRONG ASSUMPTIONS MADE.

GRADING NOTES

GRADING NOTES (CONT)

- THE VALUES SHOWN ON THE GRADING PLAN ARE FOR REFERENCE AND FEE PURPOSES ONLY. SINCE THE ENGINEER CANNOT CONTROL THE EXACT METHOD OR MEANS USED BY THE CONTRACTOR DURIN GRADING OPERATIONS. NOR CAN THE ENGINEER GUARANTEE THE EXACT SOIL CONDITION OVER THE ENTIRE SITE. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR FINAL EARTHWORK QUANTITIES.
- THE VALUES SHOWN ON THE GRADING PLAN ARE TO AID THE CONTRACTOR IN DETERMINING THE QUANTITIES OF DIRT TO BE MOVED. THE CUT AND FILL QUANTITIES SHOWN INDICATE A THEORETICAL YARDAGE FIGURE AND ARE GIVEN ONLY AS A CONVENIENCE TO THE CONTRACTOR. THE QUANTITIES SHOWN SHALL NOT BE USED AS THE BASIS OF BID COSTS.
- EARTHWORK QUANTITY VALUES SHOWN ON PAVING PLAN REPRESENT THE DIFFERENCE BETWEEN TH ESTIMATED EXISTING GRADES FROM ASBUILT DOCUMENTS COMPARED WITH THE SUBGRADE STRUCTURAL SECTIONS OF THE PROPOSED GRADING DESIGN. SEE STRUCTURAL SECTIONS IN HATCH LEGEND ON PAVING PLAN.
- EARTHWORK QUANTITY CALCULATIONS DO NOT INCLUDE STRIPPING, SHRINKAGE, SWELL FACTORS OF MATERIAL FROM UTILITY TRENCH SPOILS.

NPDES NOTES

STORM DRAIN NPDES PERMIT TO COMPLY WITH THE STATE OF CALIFORNIA'S STATEWIDE GENERAL NPDES PERMIT, REGULATING DISCHARGES OF STORM WATER ASSOCIATED WITH CONSTRUCTION ACTIVITY FROM SOIL DISTURBANCES OF ONE (1) ACRE OR MORE, A NOTICE OF INTENT (NOI) TO COMPLY WITH THE TERMS OF THE GENERAL PERMIT TO DISCHARGE STORM WATER ASSOCIATED WITH CONSTRUCTION ACTIVITY MUST BE FILED AND THE APPROPRIATE FEE PAID PRIOR TO COMMENCEMENT OF CONSTRUCTION. IN ADDITION, AT THE CONCLUSION OF THE PROJECT A NOTICE OF TERMINATION (NOT) MUST ALSO BE FILED. SUBMIT THE FEE, NOI, AND NOT TO THE STATE WATER RESOURCES CONTROL BOARD UTILIZING THE STORM WATER MULTIPLE APPLICATION AND REPORT TRACKING SYSTEM (SMARTS) AT THE FOLLOWING ADDRESS:

WWW.SMARTS.WATERBOARDS.CA.GOV

FEES AND PAYMENTS CAN BE MADE TO THE FOLLOWING ADDRESS

STATE WATER RESOURCES CONTROL BOARD DIVISION OF WATER QUALITY

ATTN: STORM WATER PERMIT UNIT SACRAMENTO, CA 95812-1977

IF YOU HAVE ANY QUESTIONS CALL JOSEPH HENAO, WATER QUALITY CONTROL ENGINEER, CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD, AT (916) 255-3028.

HE FOLLOWING MUST BE SUBMITTED TO THE CITY PRIOR TO BEGINNING WORK AND PRIOR TO THE SUANCE OF AN ENCROACHMENT PERMIT

- TRANSMITTAL MEMO THAT INCLUDES: st the name and phone number of the Person responsible for swppp implementation, and * IF APPLICABLE, A LISTING OF THE POST-CONSTRUCTION BEST MANAGEMENT PRACTICES THAT WIL BE INSTALLED TO SATISFY THE REQUIREMENTS OF THE CITY OF STOCKTON MUNICIPAL CODE CHAPTER TITLES 13 AND 15.
- * COPY OF SWPPP MUST REMAIN ON SITE DURING CONSTRUCTION AT ALL TIMES
- COPY OF A SIGNED NOTICE OF INTENT FORM OR A WASTE DISCHARGE IDENTIFICATION NUMBER. WDID#: CONTRACTOR TO PROVIDE PRIOR TO CONSTRUCTION; IF REQUIRED

FOR SITES THAT HAVE SOIL DISTURBANCES OF 1 ACRE OR MORE AND ARE REQUIRED TO OBTAIN

THE CONTRACTOR SHALL FURNISH, INSTALL, OPERATE AND MAINTAIN ALL MACHINERY APPLIANCES,

AND EQUIPMENT TO MAINTAIN ALL EXCAVATIONS FREE FROM WATER DURING CONSTRUCTION. THE

CONTRACTOR SHALL DISPOSE OF THE WATER SO AS NOT TO CAUSE DAMAGE TO PUBLIC OR PRIVATE

PROPERTY, OR TO CAUSE A NUISANCE OR MENACE TO THE PUBLIC OR VIOLATE THE LAW. THE

DEWATERING SYSTEM SHALL BE INSTALLED AND OPERATED SO THAT THE GROUNDWATER LEVEL

ENDANGERED ADJACENT STRUCTURES OR PROPERTY. ALL COST FOR DEWATERING SHALL BE

OUTSIDE THE EXCAVATION IS NOT REDUCED TO THE EXTENT WHICH WOULD CAUSE DAMAGE OR

DRAWN DOWN A MINIMUM OF 1 FOOT BELOW THE BOTTOM OF EXCAVATIONS TO MAINTAIN THE

WORKING CONDITION FOR EMERGENCIES AND SHALL HAVE WORKMEN AVAILABLE FOR IT'S

THE CONTROL OF GROUNDWATER SHALL BE SUCH THAT SOFTENING OF THE BOTTOM OF

TO MAINTAIN THE UNDISTURBED STATE OF THE NATURAL FOUNDATIONS SOILS, PREVENT

SHALL BE OBTAINED BY THE CONTRACTOR PRIOR TO ANY DEWATERING ACTIVITIES.

COMPLETED TO 1 FOOT ABOVE THE NORMAL STATIC GROUNDWATER LEVEL.

THE GROUNDWATER LEVEL SHALL BE PROVIDED.

OR DURING WORK STOPPAGES.

NECESSARY FOR PUBLIC SAFETY.

MAINTENANCE HOLES.

THE CITY OF STOCKTON.

EXCAVATION SHALL BE GRADED TO DRAIN TO THE SUMPS.

STORM DRAIN NOTES

INCLUDED IN THE UNIT PRICE BID FOR ALL PIPE CONSTRUCTION. THE STATIC WATER LEVEL SHALL BE

UNDISTURBED STATE OF NATURAL SOILS AND ALLOW THE PLACEMENT OF ANY FILL TO THE SPECIFIE

DENSITY. THE CONTRACTOR SHALL HAVE ON HAND, PUMPING EQUIPMENT AND MACHINERY IN GOOD

THE CONTRACTOR SHALL CONTROL SURFACE WATER TO PREVENT ENTRY INTO EXCAVATIONS. AT EACH

EXCAVATIONS, OR FORMATION OF "QUICK" CONDITIONS OR "BOILS", DOES NOT OCCUR. DEWATERING

SYSTEMS SHALL BE DESIGNED AND OPERATED SO AS TO PREVENT REMOVAL OF THE NATURAL SOILS.

DISTURBANCE OF COMPACTED BACK FILL, AND PREVENT FLOTATION OR MOVEMENT OF STRUCTURES

ONE HUNDRED PERCENT STANDBY PUMPING CAPACITY SHALL BE AVAILABLE ON SITE AT ALL TIMES

ADDITION, STANDBY AUXILIARY EQUIPMENT AND APPLIANCES FOR ALL ORDINARY EMERGENCIES, AND

COMPETENT WORKMEN FOR OPERATION AND MAINTENANCE OF ALL DEWATERING EQUIPMENT SHALL

BE ON SITE AT ALL TIMES. STANDBY EQUIPMENT SHALL INCLUDE EMERGENCY POWER GENERATION

DEWATERING SYSTEMS SHALL NOT BE SHUT DOWN BETWEEN SHIFTS, ON HOLIDAYS, ON WEEKENDS,

ALL STORM DRAIN CONSTRUCTION, MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH

THE CONTRACTOR SHALL PROVIDE ALL LIGHTS, SIGNS, BARRICADES, FLAGMEN OR OTHER DEVICES

THE CONTRACTOR SHALL PROVIDE ALL SHORING, BRACING, SLOPING OR OTHER PROVISIONS

NECESSARY TO PROTECT WORKMEN FOR ALL AREAS TO BE EXCAVATED TO A DEPTH OF 5 FEET OR

MORE. SAID PROTECTION TO BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF THE CITY OF

ALL MAINTENANCE HOLE RIMS TO BE ADJUSTED TO PROPOSED FINISH GRADE AFTER STREET PAVING

UNLESS OTHERWISE NOTED. COST FOR RAISING FACILITIES TO BE INCLUDED IN UNIT PRICES FOR

ALL STORM DRAIN LINES SHALL BE CLEANED OF ALL SAND AND DEBRIS PRIOR TO ACCEPTANCE BY

THE CONTRACTOR SHALL EXPOSE ALL EXISTING STORM DRAIN PIPES, WHERE A CONNECTION IS TO B

MADE, AND NOTIFY THE ENGINEER IF THERE IS A DISCREPANCY BETWEEN THE SIGNED PLANS AND THE

STORM DRAIN CONTRACTOR SHALL VERIFY LOCATION OF ALL EXISTING UNDERGROUND UTILITIES AND

CONTRACTOR TO BE RESPONSIBLE FOR ALL TESTING OF STORM DRAIN FACILITIES IN ACCORDANCE

THE REQUIREMENTS OF THE LATEST EDITION OF THE CALIFORNIA PLUMBING CODE.

STOCKTON DEPARTMENT OF PUBLIC WORKS, AND STATE REGULATIONS.

EXISTING FIELD CONDITION PRIOR TO THE START OF CONSTRUCTION.

WITH THE CITY OF STOCKTON STANDARD SPECIFICATIONS AND PLANS.

STORM DRAINAGE SYSTEM WILL BE PRIVATELY OWNED AND MAINTAINED.

WILL BE RESPONSIBLE FOR PROTECTION OF THE SAME.

AND AUTOMATIC SWITCH OVER TO THE EMERGENCY GENERATOR WHEN NORMAL POWER FAILS.

SUMPS SHALL BE NO DEEPER THAN 5 FEET AND SHALL BE AT THE LOW POINT OF EXCAVATION.

AND SHALL BE CONNECTED TO THE DEWATERING SYSTEM PIPING TO PERMIT IMMEDIATE USE. IN

PIPELINES AND SEWERS. IF AN NPDES (NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM)

PERMIT IS REQUIRED FOR DISPOSAL OF WATER FROM CONSTRUCTION DEWATERING ACTIVITIES, IT

THE RELEASE OF GROUNDWATER AT ITS STATIC LEVEL SHALL BE PERFORMED IN SUCH A MANNER AS

EXCAVATION, A SUFFICIENT NUMBER OF TEMPORARY OBSERVATION WELLS TO CONTINUOUSLY CHECK

OPERATION. DEWATERING SYSTEMS SHALL OPERATE CONTINUOUSLY UNTIL BACK FILL HAS BEEN

COVERAGE UNDER THE STATE'S CONSTRUCTION GENERAL PERMIT (CGP): THE CONTRACTOR SHALL COORDINATE WITH THE OWNER AND ENSURE THAT A QUALIFIED SWPPP PRACTITIONER (QSP) IS CONTRACTED TO PROVIDE QSP SERVICES THROUGHOUT THE COURSE OF CONSTRUCTION (FROM THE START OF CONSTRUCTION TO THE DATE AT WHICH THE NOTICE OF TERMINATION - NOT - IS FILED). THE QSP SHALL BE RESPONSIBLE FOR ALL APPLICABLE INSPECTION TRAINING, SAMPLING, TESTING, REPORTING, CHANGES OF INFORMATION (COI), SWPPP REVISIONS, NOTICE OF TERMINATION (NOT), AND OTHER QSP-RELATED RESPONSIBILITIES AS IDENTIFIED IN THE

DEWATERING NOTES

- EARTHWORK SHALL BE PERFORMED IN ACCORDANCE WITH THE CITY OF STOCKTON STANDARDS AND THE PROJECT SOILS REPORT. ALL FILL AREAS SHALL BE TESTED AS REQUIRED BY THE CITY OF STOCKTON AND SHALL BE PAID FOR BY THE CONTRACTOR.
- THE DEVELOPER SHALL BE RESPONSIBLE FOR COST OF INITIAL TEST FOR MOISTURE DENSITY CURVE. IF THE FIRST TEST FAILS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR COST OF ALL SUBSEQUENT
- MATERIALS SHALL BE REMOVED FROM THE SITE AT THE EXPENSE OF THE CONTRACTOR AND SHALL BE INCLUDED IN THE LUMP SUM CLEARING COST. THE CONTRACTOR SHALL PRESERVE ALL STAKES AND POINTS SET FOR LINES, GRADES OR

THE CONTRACTOR SHALL REVIEW SITE PRIOR TO BIDDING. ALL VEGETATION AND DELETERIOUS

- MEASUREMENT OF THE WORK IN THEIR PROPER PLACES UNTIL AUTHORIZED TO REMOVE THEM BY THE ENGINEER. ALL EXPENSES INCURRED IN REPLACING STAKES THAT HAVE BEEN REMOVED WITHOUT PROPER AUTHORITY SHALL BE PAID FOR BY THE CONTRACTOR.
- CONTRACTOR'S PRICE SHALL INCLUDE COST TO ACHIEVE A BALANCED SITE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO IMPORT AND EXPORT MATERIAL AS REQUIRED TO BALANCE SITE.
- CONTRACTOR SHALL GRADE ALL LANDSCAPE AREAS TO WITHIN 0.10 FEET OF FINAL GRADE ELEVATIONS WITH APPROPRIATE LANDSCAPE SECTIONS INCLUDED.
- ALL A.C. PAVING SHALL BE FOG SEALED PER SECTION 37 OF CALTRANS STANDARD SPECIFICATIONS, THE LATEST EDITION.
- GRADE TAGS LOCATED ON CURBS REFERENCE TOP OF CURB ELEVATION UNLESS OTHERWISE NOTED. ADDITIONAL DESCRIPTIONS ARE PROVIDED TO DENOTE HORIZONTAL AND VERTICAL CHANGES IN ACCORDANCE WITH ABBREVIATIONS DEFINED ON COVER SHEET. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING HIS OWN EARTHWORK QUANTITIES FOR
- BIDDING, CONTRACT AND CONSTRUCTION PURPOSE. IF IT APPEARS THERE WILL BE AN EXCESS OR SHORTAGE OF MATERIAL, THE CONTRACTOR SHALL NOTIFY THE ENGINEER TO DETERMINE IF POSSIBLE GRADE ADJUSTMENTS CAN BE MADE.
- SITE CONTRACTOR SHALL COORDINATE WITH BUILDING CONTRACTOR TO ACCOMMODATE THE PROPER CLEARANCE BETWEEN THE BOTTOM OF THE STUCCO AND THE TOP OF THE GRADE TREATMENT ALONG THE BUILDING AS APPLICABLE, IN ACCORDANCE WITH SECTION 2512.1.2. OF THE MOST CURRENT CALIFORNIA BUILDING CODE, IF THE SUBJECT BUILDING SIDING TREATMENT IS STUCCO. CONTRACTOR SHALL NOTIFY ENGINEER IF ANY GRADES ARE ADJUSTED. CONTRACTOR SHALL ALSO APPLY FLASHING WHERE APPLICABLE WITHIN AREAS OF GRADE TRANSITION.
- ALL LANDSCAPE AREAS THAT ABUT ANY PORTION OF THE BUILDING SHALL BE GRADED SUCH THAT THE FINISHED GRADE IN LANDSCAPE AREAS SHALL BE A MINIMUM OF EIGHT INCHES (8") BELOW FINISHED FLOOR OF THE ABUTTING BUILDING AND IN NO CASE SHALL THE LANDSCAPE AREA BE GRADED OR LANDSCAPED SUCH THAT WATER DRAINS TOWARD THE BUILDING.
- SINCE THE ENGINEER CANNOT CONTROL THE EXACT METHOD OR MEANS USED BY THE CONTRACTOR DURING GRADING OPERATIONS, NOR CAN THE ENGINEER GUARANTEE THE EXACT SOIL CONDITION OVER THE ENTIRE SITE, THE ENGINEER ASSUMES NO RESPONSIBILITY FOR FINAL EARTHWORK
- CONTRACTOR IS RESPONSIBLE FOR THE OFF HAUL AND DISPOSAL OF ANY AND ALL EXCESS DIRT FROM CONSTRUCTION SITE.
- CONTRACTOR SHALL COORDINATE WITH THE EXISTING ADJOINING PROPERTY OWNERS PRIOR TO ANY WORK BEING STARTED THAT MAY AFFECT THEIR PROPERTY.
- CONTRACTOR SHALL PROVIDE A SMOOTH TRANSITION FROM THE PROPOSED GRADING TO THE EXISTING FLOWLINE, CURB, CONCRETE, AND OR PAVEMENT ELEVATIONS.
- ALL EXISTING WELLS AND SEPTIC TANKS SHALL BE REMOVED AND/OR ABANDONED PER THE REQUIREMENTS OF THE COUNTY HEALTH DEPARTMENT AND THE CITY OF STOCKTON. THIS WORK SHALL BE INCLUDED IN THE LUMP SUM CLEARING COST.
- CONTRACTOR SHALL VERIFY BUILDING SUBGRADE SECTIONS WITH ARCHITECT PLANS BEFORE CONSTRUCTION. IF A DISCREPANCY EXISTS, CONTRACTOR TO NOTIFY THE ENGINEER IMMEDIATELY.
- PRIOR TO CONSTRUCTING ANY FLATWORK THE CONTRACTOR SHALL VERIFY THE FINISH FLOOR ELEVATIONS AT ALL DOORS. NOTE THAT FINISH FLOOR ELEVATIONS MAY HAVE BEEN CHANGED DUE TO FOUNDATION ADJUSTMENTS IN FIELD. CONTRACTOR SHALL HOLD ADJUSTED FINISH FLOOR GRADES. ACCOUNT FOR DOOR THRESHOLDS. AND ADJUST GRADES AS NECESSARY TO STAY IN COMPLIANCE WITH CURRENT ADA STANDARDS. CONTRACTOR SHALL NOTIFY NORTHSTAR ENGINEERING IMMEDIATELY IF ANY GRADE ADJUSTMENTS WILL CREATE ADA ACCESSIBILITY ISSUES.

STORM DRAIN NOTES (CONT)

ALL STORM DRAIN PIPE MATERIALS SHALL BE IN ACCORDANCE WITH TABLE 701.2 OF THE 2022 CALIFORNIA PLUMBING CODE. CONTRACTOR SHALL HAVE PIPE MANUFACTURER PERFORM CALCULATIONS TO DETERMINE PIPE CLASS PRIOR TO CONSTRUCTION DUE TO EXCESSIVE DEPTH

THE TELEVISING OF ALL SEWER LINES.

ALL STORM DRAIN MAINTENANCE HOLES AND BASES SHALL BE PRECAST AND CONSTRUCTED IN ACCORDANCE WITH CITY OF STOCKTON STANDARDS, CONTRACTOR SHALL SET MAINTENANCE HOLE CASTING AND COVERS TO FINISH GRADE AFTER STREET IMPROVEMENTS ARE COMPLETE, AND SHALL BE RESPONSIBLE FOR LOCATION OF MAINTENANCE HOLES BENEATH THE FINISH PAVEMENT.

SANITARY SEWER NOTES

- ALL SANITARY SEWER CONSTRUCTION, MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE CITY OF STOCKTON OR APPROPRIATE AGENCY STANDARD SPECIFICATIONS AND PLANS.
- THE CONTRACTOR SHALL EXPOSE EXISTING SANITARY SEWER WHERE CONNECTION IS TO BE MADE, SO THAT THE ENGINEER CAN VERIFY EXISTING FLOW LINES AND LOCATIONS BEFORE START OF
- SEWER MAINS SHALL BE INSTALLED FROM THE EXISTING FACILITIES UPSTREAM TO THE END OF THE
- ALL SANITARY SEWER CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS THE CITY OF STOCKTON. MAIN LINES AND LATERAL SHALL BE AIR TESTED FOR LEAKAGE IN CONFORMANCE WITH THE CITY OF STOCKTON STANDARDS.
- ALL TESTING REQUIRED BY THE CITY SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, INCLUDING
- THE CONTRACTOR SHALL PROVIDE ALL SHORING, BRACING, SLOPING OR OTHER PROVISIONS NECESSARY TO PROTECT WORKMEN FOR ALL AREAS TO BE EXCAVATED TO A DEPTH OF 5 FEET OR MORE. SAID PROTECTION TO BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE CITY OF STOCKTON DEPARTMENT OF PUBLIC WORKS, AND STATE REGULATIONS.
- SEWER PIPE SHALL BE IN ACCORDANCE WITH TABLE 701.2 OF THE 2022 CALIFORNIA BUILDING CODE CONTRACTOR SHALL HAVE PIPE MANUFACTURER PERFORM CALCULATIONS TO DETERMINE PIPE CLASS PRIOR TO CONSTRUCTION DUE TO EXCESSIVE DEPTH.
- THE CONTRACTOR SHALL PROVIDE ALL LIGHTS, SIGNS, BARRICADES, FLAGMEN, OR OTHER DEVICES NECESSARY FOR PUBLIC SAFETY.
- ALL SANITARY SEWER CONSTRUCTION SHALL COMPLY WITH THE REQUIREMENTS OF THE STATE HEALTH DEPARTMENT. WHERE SANITARY SEWER SERVICES AND LATERALS CROSS ABOVE WATER MAINS, A 20 FEET MINIMUM JOINT OF PVC C-900, CLASS 200, OR AN 18 FEET JOINT OF CLASS 50 D.I.P., SHALL BE CENTERED ON THE SEWER MAIN. CONTRACTOR SHALL CONSTRUCT ALL CROSSING IN ACCORDANCE WITH THE CALIFORNIA HEALTH DEPARTMENT REQUIREMENTS.
- SEWER CONTRACTOR SHALL VERIFY LOCATION OF ALL EXISTING UNDERGROUND UTILITIES, AND WIL BE RESPONSIBLE FOR THE PROTECTION OF SAME
- MAINTENANCE HOLE CASTINGS AND COVERS SHALL BE ADJUSTED TO FINISH GRADES BY THE PAVIN CONTRACTOR AFTER STREET IMPROVEMENTS ARE COMPLETED. COST FOR ADJUSTING FACILITIES TO BE INCLUDED IN THE UNIT PRICE FOR MAINTENANCE HOLES AND CLEANOUTS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADEQUATELY MARKING INSTALLED LOCATION OF SERVICE LATERALS. THE CONTRACTOR SHALL STAMP AN "S" AT THE CURB FACE DIRECTLY OVER THE
- SANITARY SEWER SYSTEM WILL BE PRIVATELY OWNED AND MAINTAINED.

DOMESTIC AND FIRE WATER NOTES

APPROPRIATE SHORING SYSTEM STANDARDS.

(AWWA) STANDARDS, SECTION C-651.

- ALL WATER CONSTRUCTION, MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE CITY OF STOCKTON, CALIFORNIA PLUMBING CODE, CALIFORNIA FIRE CODE, O APPROPRIATE AGENCY STANDARD SPECIFICATIONS PLANS.
- CONTRACTOR SHALL EXPOSE EXISTING WATER LINES WHERE CONNECTIONS ARE TO BE MADE TO VERIFY EXISTING ELEVATION AND LOCATION PRIOR TO START OF CONSTRUCTION. ALL CONNECTIONS TO EXISTING CITY OF STOCKTON FACILITIES SHALL BE MADE IN THE PRESENCE O
- THE CITY OF STOCKTON ENGINEER, OR HIS APPOINTED REPRESENTATIVE. FOR EXCAVATIONS OF FIVE FEET OR MORE, TRENCHES SHALL BE MADE IN CONFORMANCE WITH
- PAVING REPLACEMENT TO MATCH EXISTING PAVEMENT SECTION. OR IN ACCORDANCE WITH STREET DETAILS ON THESE PLANS.
- WATER LINE TESTING SHALL BE AS FOLLOWS: A) ALL WATER LINES SHALL BE TESTED AND DISINFECTED IN CONFORMANCE WITH THE REQUIREMENTS OF THE CITY OF STOCKTON AND THE AMERICAN WATER WORKS ASSOCIATION
- B) WATER LINE TESTING SHALL INCLUDE: HYDROSTATIC PRESSURE TESTING PER CITY OF STOCKTOI STANDARDS & SPECIFICATIONS; BACTERIOLOGICAL TESTING PER OF CITY OF STOCKTON STANDARDS AND SPECIFICATIONS.
- C) AFTER THE FINAL FLUSHING AND BEFORE THE NEW WATER MAIN IS CONNECTED TO THE DISTRIBUTION SYSTEM, TWO CONSECUTIVE SETS OF ACCEPTABLE SAMPLES, TAKEN 24 HOURS APART, SHALL BE COLLECTED AT SITES SHOWN ON THE PLANS. (AT LEAST ONE SET OF SAMPLES SHALL BE COLLECTED EVERY 1200 FEET OF THE NEW WATER MAIN, PLUS ONE SET AT EACH END OF THE LINE AND AT LEAST ONE SET FROM EACH BRANCH). ALL SAMPLES SHALL BE TESTED FOR BACTERIOLOGICAL QUALITY, AND SHALL SHOW THE ABSENCE OF COLIFORM ORGANISMS. A STANDARD HETEROPHIC PLATE COUNT MAY BE REQUIRED AT THE OPTION OF THE ENGINEER.
- D) SAMPLES SHALL BE TAKEN FROM WATER THAT HAS STOOD IN THE NEW MAIN FOR AT LEAST 16 HOURS AFTER FINAL FLUSHING HAS BEEN COMPLETED.
- E) IF THE INITIAL DISINFECTION FAILS TO PRODUCE SATISFACTORY BACTERIOLOGICAL SAMPLES, THE MAIN SHALL BE REFLUSHED AND RESAMPLED DAILY FROM THE SAME POINT(S) UNTIL TWO CONSECUTIVE SAMPLES ARE NEGATIVE FOR COLIFORM ORGANISMS.
- F) THE DEVELOPER SHALL PAY FOR THE INITIAL BACTERIOLOGICAL TESTS. THE CONTRACTOR SHALL PAY FOR ALL TESTING NECESSITATED BY FAILURE OF THE INITIAL TEST(S).
- G) IF TRENCH WATER HAS ENTERED THE NEW MAIN DURING CONSTRUCTION, OR, IF IN THE OPINION OF THE CITY OF STOCKTON, EXCESSIVE QUANTITIES OF DIRT AND DEBRIS HAVE ENTERED THE NEW MAIN, BACTERIOLOGICAL SAMPLES SHALL BE TAKEN AT INTERVALS OF APPROXIMATELY 200 FEET AND SHALL BE IDENTIFIED BY LOCATION. THE CONTRACTOR SHALL INSTALL ADDITIONAL WATER SERVICE TAPS AND SAMPLING STATIONS AS REQUIRED. THE CONTRACTOR SHALL ALSO REMOVE SAMPLING STATIONS AND SERVICES UPON SATISFACTORY COMPLETION OF TESTING. THE CONTRACTOR SHALL PAY FOR TESTING OF THE CONTAMINATED AREAS.
- H) CONTRACT PRICE SHALL INCLUDE FULL COMPENSATION FOR FURNISHING ALL LABOR, MATERIALS, TOOLS, EQUIPMENT, AND INCIDENTALS, AND FOR DOING ALL OF THE WORK INVOLVED IN TESTING AND DISINFECTION OF THE WATER MAINS.
- CONTRACTOR SHALL PROVIDE ALL LIGHTS, SIGNS, BARRICADES, FLAGMEN, OR OTHER DEVICES NECESSARY FOR PUBLIC SAFETY.
- WATER PIPE MATERIALS SHALL BE IN ACCORDANCE WITH TABLE 604.1 OF THE 2022 CALIFORNIA PLUMBING CODE.
- OF PIPE TO PROPOSED FINISH GRADE AS SPECIFIED BY THE CITY OF STOCKTON. . ALL WATER IMPROVEMENTS MUST BE REVIEWED AND APPROVED BY THE CITY OF STOCKTON.

COVERAGE ON THE WATER LINE SHALL BE 30 INCHES MINIMUM AND 36 INCHES MAXIMUM FROM TOP

- WATER LINES SHALL BE A MINIMUM OF 10 FEET OUTSIDE OF PIPE TO OUTSIDE OF PIPE FROM SEWER AND STORM DRAIN MAINS. CROSSINGS SHALL MEET STATE HEALTH STANDARDS.
- ALL FIRE SERVICE LINES SHALL BE C900 CL200.
- WHERE WATER LINE CROSSES UNDER STORM DRAIN, A 20 FEET MIN JOINT OF PVC C-900 CLASS 200, OR AN 18 FEET JOINT OF CLASS 50 D.I.P. SHALL BE CENTERED ON STORM DRAIN OR IN ACCORDANCE WITH CITY OF STOCKTON STANDARDS AND SPECIFICATIONS.
- WATER SYSTEM WILL BE PRIVATELY OWNED AND MAINTAINED.
- CONTRACTOR SHALL PAINT FIRE HYDRANTS WITH ENAMEL SAFETY YELLOW PAINT.

DOMESTIC AND FIRE WATER NOTES (CONT) TOPOGRAPHY NOTES (CONT)

CONTRACTOR IS ADVISED THAT ANY FIELD CHANGES DUE TO EXISTING CONDITIONS MUST COMPLY

PROVIDE THRUST BLOCKS AT FIRE HYDRANTS, BLOW-OFFS, TEES, AND AT CHANGES IN SIZE AND

DIRECTION, AND AT CAPS, BENDS, AND ENDS, INSTALL THRUST BLOCKS, AS REQUIRED. IN

ALL VALVES TWELVE (12) INCHES AND LARGER SHALL BE BUTTERFLY VALVES AND OPERATORS

COMPLETION OF STERILIZATION AND TESTING OF NEW WATER MAINS. ALL EXISTING WATER VALVES TO

REDUCED PRESSURE BACKFLOW PREVENTION DEVICE MUST BE INSPECTED AND APPROVED BY AN

THE WATER METER AND METER BOX SHALL BE PROVIDED AND INSTALLED BY THE CITY OF STOCKTON,

SPRINKLER MAINS, ON THE SYSTEM SIDE OF THE FDC, SHALL BE HYDROSTATICALLY TESTED AT 200

DEPARTMENT BY THE CONTRACTOR. THEY SHALL BE PROVIDED AT A RATIO OF ONE REFLECTOR PER

HYDRANT, UNLESS THE FIRE HYDRANT FACES TWO STREETS THEN TWO REFLECTORS SHALL BE

REQUIRED. CONTRACTOR SHALL REFER TO THE MUTCD, CALIFORNIA SUPPLEMENT, SECTION 3B.11

A LOCATING "TRACE WIRE" IS REQUIRED ON ALL MAINS AND SERVICE LINES. THE "TRACE WIRE" SHALL

BE FIRMLY ATTACHED TO THE TOP CENTER OF THE PIPE AT INTERVALS NOT EXCEEDING FIVE (5) FEET.

ALL MAIN LINE "TRACE WIRES" SHALL BE INTERCONNECTED TO FORM A GRID. ALL SPLICES SHALL BE

COMPOUND. INSTALLATION OF THE "TRACE WIRE" SYSTEM SHALL BE INSPECTED AND APPROVED BY

TESTING PERSONNEL AFTER THE TRENCHES HAVE BEEN BACKFILLED AND HYDROSTATIC TESTS HAVE

BEEN PERFORMED, BUT BEFORE ANY PAVEMENT HAS BEEN PLACED. THE CITY SHALL PAY THE COST

THE DISCHARGE OF CHLORINATED AND DE-CHLORINATED WATER INTO THE STORM DRAIN SYSTEM IS

PROHIBITED. THE DISCHARGE OF CHLORINATED AND DE-CHLORINATED WATER INTO THE SANITARY

ALL VALVE BOXES TO BE ADJUSTED TO FINISH GRADE AFTER PAVING. COST FOR RAISING FACILITIES

PRIOR TO COMMENCEMENT OF CONSTRUCTION, THE FIRE DEPARTMENT REQUIRES ALL ACCESS

PLAN SET DESIGN BASED OFF OF TOPOGRAPHIC SURVEY PERFORMED ON MAR 11, 2024.

ACTUAL LOCATIONS MAY VARY AND ADDITIONAL CROSSINGS MAY EXIST IN THE FIELD.

CONFLICTS EXIST BETWEEN PROPOSED AND EXISTING IMPROVEMENTS.

AGENCY TO DO ANY WORK WITHIN RIGHT-OF-WAY PRIOR TO CONSTRUCTION.

ALL EXISTING UTILITIES WERE PLOTTED FROM RECORD INFORMATION AND FIELD TOPOGRAPHY.

THE CONTRACTOR SHALL USE EXTREME CAUTION WHEN EXPOSING EXISTING UTILITY CROSSINGS AND

PRIOR TO BEGINNING CONSTRUCTION THE CONTRACTOR SHALL CALL U.S.A. (800) 227-2600 TO HAVE

THE SITE MARKED. THE CONTRACTOR SHALL POTHOLE ALL EXISTING UTILITIES TO VERIFY THAT NO

CONTRACTOR/DEVELOPER SHALL OBTAIN AN ENCROACHMENT PERMIT FROM THE APPROPRIATE

IN CONJUNCTION WITH CONTACTING USA TO LOCATE UNDERGROUND UTILITIES WITHIN THE PUBLIC

RIGHT-OF-WAY IT IS HIGHLY RECOMMENDED THAT THE CONTRACTOR UTILIZE (GPR) GROUND

PENETRATING RADAR UNDERGROUND SERVICES TO IDENTIFY ONSITE UTILITIES THAT MAY NOT BE

CONTRACTOR SHALL REVIEW ALL OF THE CONSULTANT'S PLAN SETS FOR ADDITIONAL DEMOLITION,

REPLACEMENT AND IMPROVEMENTS PRIOR TO BEGINNING OF ANY WORK. IF A CONFLICT IS FOUND

A) MONUMENTS SET SHALL BE SUFFICIENT IN NUMBER AND DURABILITY AND EFFICIENTLY PLACED

SO AS NOT TO BE READILY DISTURBED, TO ASSURE, TOGETHER WITH MONUMENTS ALREADY

EXISTING, THE PERPETUATION OR FACILE REESTABLISHMENT OF ANY POINT OR LINE OF THE

BOUNDARIES, ROADS, STREETS, OR HIGHWAYS, OR PROVIDE HORIZONTAL OR VERTICAL SURVEY

CONTROL, THE MONUMENTS SHALL BE LOCATED AND REFERENCED BY OR UNDER THE DIRECTION

OF A LICENSED LAND SURVEYOR OR REGISTERED CIVIL ENGINEER PRIOR TO THE TIME WHEN ANY

STREETS, HIGHWAYS, OTHER RIGHTS-OF-WAY, OR EASEMENTS ARE IMPROVED, CONSTRUCTED,

RECONSTRUCTED, MAINTAINED, RESURFACED, OR RELOCATED, AND A CORNER RECORD OR

RECORD OF SURVEY OF THE REFERENCES SHALL BE FILED WITH THE COUNTY SURVEYOR. THEY

SHALL BE RESET IN THE SURFACE OF THE NEW CONSTRUCTION, A SUITABLE MONUMENT BOX

PLACED THEREON, OR PERMANENT WITNESS MONUMENTS SET TO PERPETUATE THEIR LOCATION

IF ANY MONUMENT COULD BE DESTROYED, DAMAGED, COVERED, OR OTHERWISE OBLITERATED,

AND A CORNER RECORD OR RECORD OF SURVEY FILED WITH THE COUNTY SURVEYOR PRIOR TO

PROPERTY, RIGHT-OF-WAY AND EASEMENT LINES, PROPERTY CORNERS, AND SUBDIVISION AND

ORIGINATING ON MONUMENTS DIFFERING FROM THOSE THAT CURRENTLY CONTROL THE AREA. IT

MONUMENTS SHALL BE RETAINED OR REPLACED IN THEIR ORIGINAL POSITIONS TO ENABLE

TRACT BOUNDARIES TO BE REESTABLISHED WITHOUT PREVIOUS SURVEYS NECESSARILY

SHALL BE THE RESPONSIBILITY OF THE GOVERNMENTAL AGENCY OR OTHERS PERFORMING

CONSTRUCTION WORK TO PROVIDE FOR THE MONUMENTATION REQUIRED BY THIS SECTION. IT

SHALL BE THE DUTY OF EVERY LAND SURVEYOR OR CIVIL ENGINEER TO COOPERATE WITH THE GOVERNMENTAL AGENCY IN MATTERS OF MAPS, FIELD NOTES, AND OTHER PERTINENT RECORDS.

RIGHT-OF-WAY OR EASEMENT LINES SHALL NOT BE DEEMED ADEQUATE FOR THIS PURPOSE

IMPROVEMENT WORKS WITH DIRECT TIES IN BEARING OR AZIMUTH AND DISTANCE BETWEEN

CONTRACTOR SHALL COORDINATE WITH THE LAND SURVEYOR OF RECORD, PRIOR TO STARTING

CONSTRUCTION, TO IDENTIFY ALL SURVEY MONUMENTS THAT MAY BE SUBJECT TO DISTURBANCE

AND SHALL INCLUDE COSTS FOR MONUMENT PRESERVATION, REPLACEMENT, AND PREPARATION

PURSUANT TO SUBDIVISION (B) SHALL BE AT THE ELECTION OF THE LICENSED LAND SURVEYOR OR

SURVEY MONUMENTS SHALL BE PRESERVED, REFERENCED, OR REPLACED PURSUANT TO SECTION

D) THE DECISION TO FILE EITHER THE REQUIRED CORNER RECORD OR A RECORD OF SURVEY

REGISTERED CIVIL ENGINEER SUBMITTING THE DOCUMENT, AT CONTRACTOR'S EXPENSE.

§732.5, §1492.5, §1810.5 OF THE CALIFORNIA STREETS AND HIGHWAYS CODES STATE:

UNLESS SPECIFICALLY NOTED ON THE CORNER RECORD OR RECORD OF SURVEY OF THE

MONUMENTS SET TO MARK THE LIMITING LINES OF HIGHWAYS, ROADS, STREETS OR

OF CORNER RECORDS OR RECORD OF SURVEY IN CONTRACTOR'S BID.

THESE AND OTHER MONUMENTS OF RECORD.

8771 OF THE BUSINESS AND PROFESSIONS CODE.

THE RECORDING OF A CERTIFICATE OF COMPLETION FOR THE PROJECT. SUFFICIENT CONTROLLING

THEN THE CONTRACTOR SHALL NOTIFY THE ARCHITECT AND ENGINEER IMMEDIATELY.

IN ACCORDANCE WITH SECTION 8771 OF THE PROFESSIONAL LAND SURVEYORS ACT

B) WHEN MONUMENTS EXIST THAT CONTROL THE LOCATION OF SUBDIVISIONS, TRACTS,

ANY DAMAGE TO EXISTING UTILITIES WILL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

ROADS AND WATER SUPPLIES TO BE SUFFICIENTLY PROVIDED FOR THE PROPOSED DEVELOPMENT

SITE. IF THERE IS ANY ALTERATION TO THIS REQUIREMENT, THE PROPOSED DEVELOPMENT WILL BE

SUBJECT TO A FINE AND CONSTRUCTION MAY BE SHUTDOWN FOR AN INDEFINITE PERIOD OF TIME, OF

THE ENGINEER PRIOR TO BACKFILL. THE "TRACE WIRE" SYSTEM SHALL BE TESTED BY APPROVED

OF THE INITIAL TEST. ANY SUBSEQUENT TESTING COSTS SHALL BE THE RESPONSIBILITY OF THE

MECHANICALLY AND ELECTRONICALLY SOUND AND MADE WATERPROOF WITH AN APPROVED

FIRE HYDRANT MAINS SHALL BE HYDROSTATICALLY TESTED AT 50 PSI FOR ONE HOUR AND FIRE

PSI FOR TWO HOURS. CALL THE FIRE PREVENTION BUREAU 48 HOURS PRIOR TO DESIRED TEST.

SELF ADHESIVE BLUE REFLECTIVE FIRE HYDRANT MARKERS ARE TO BE PROVIDED TO THE FIRE

ACTUAL CONNECTIONS TO EXISTING WATER LINES WILL NOT BE PERMITTED PRIOR TO THE

BE OPERATED UNDER THE DIRECTION OF THE WATER DIVISION OF THE REGULATORY AGENCY

ACCORDANCE WITH CITY OF STOCKTON STANDARDS AND SPECIFICATIONS.

APPROVED TESTING FIRM PRIOR TO THE FINAL APPROVAL OF THE BUILDING.

24. FIRE HYDRANT STEM BREAKAWAY MUST COINCIDE WITH BREAKAWAY SPOOL.

SEWER SYSTEM REQUIRES PRIOR APPROVAL FROM MUD.

TO BE INCLUDED IN UNIT PRICES FOR VALVES.

TOPOGRAPHY NOTES

UNTIL COMPLIANCE HAS BEEN MET.

VISIBLE FROM THE SURFACE.

INTENDED FOR BURIED SERVICE IN A DOMESTIC WATER SYSTEM.

WITH STATE HEALTH DEPARTMENT CRITERIA.

PERSONNEL ONLY.

PAID BY THE DEVELOPER.

AND FIGURE 3B-102.

CONTRACTOR



620 12th Street Modesto, CA 95354 (209) 524-3525 Phone (209) 524-3526 Fax

CONTRACTOR TO BE CAUTIOUS OF UNDERGROUND STUBS AND LINES. CONTRACTOR SHALL USE EXTREME CAUTION AS TO OTHER LINES MAY EXIST ON THE SITE THAT ARE NOT CLEARLY MARKED. AN ATTEMPT HAS BEEN MADE TO SHOW ALL EXISTING STRUCTURES, UTILITIES, DRIVES, PAVEMENTS CURBS, WALKS, ETC. IN THEIR APPROXIMATE LOCATION ON THE SURVEY AND/OR WORKING DRAWINGS. HOWEVER, OTHERS THAT ARE NOT SHOWN MAY EXIST AND MAY BE FOUND UPON VISITING THE SITE OR DURING THE CLEARING AND REMOVAL WORK. IT WILL BE THE RESPONSIBILITY OF THIS CONTRACTOR TO ACCURATELY LOCATE ALL EXISTING FACILITIES AND TO DETERMINE THEIR EXTENT. I SUCH FACILITIES OBSTRUCT THE PROGRESS OF THE WORK AND ARE NOT INDICATED TO BE REMOVED OR RELOCATED, THEY SHALL BE REMOVED OR RELOCATED ONLY AS DIRECTED BY THE OWNER. THE CONTRACTOR SHALL REPORT ANY EXISTING SITE ELEMENT NOT SHOWN ON THE WORKING DRAWINGS TO THE ARCHITECT OF RECORD SO THAT THE PROPER DISPENSATION OF THAT ELEMENT **SITE LAYOUT NOTES**

- SEE ELECTRICAL PLANS FOR DRY UTILITY LAYOUT, DRY UTILITY DETAILS AND SPECIFICATIONS, MODIFICATIONS TO EXISTING DRY UTILITIES, SITE LIGHTING LOCATIONS AND DETAILS, POINTS OF CONNECTION, AND SLEEVE CROSSINGS. ANY AND ALL ELECTRICAL REMOVAL OR RELOCATION.
- STRIPING SHALL BE APPLIED PER CITY STANDARDS AS SHOWN ON THIS PLAN SET. ADDITIONALLY STRIPING AND SIGNAGE INFORMATION SHALL FOLLOW MANUAL OF UNIFORM TRAFFIC CONTROL
- FLATWORK SHALL BE INSTALLED WITH CRACK CONTROL JOINTS AT APPROPRIATE SPACING.
- CONSTRUCT CONTROL AND CONSTRUCTION JOINTS IN ACCORDANCE WITH CURRENT PORTLAND CEMENT ASSOCIATION GUIDELINES AND CITY STANDARDS; USE WHICH EVER IS MORE STRINGENT.
- ANY UNSUITABLE MATERIAL ENCOUNTERED AT OR BELOW GRADE SHALL BE COMPLETELY REMOVED TO THE FULL DEPTH AND REPLACED WITH COMPACTED ENGINEERED FILL OR APPROVED IMPORT
- GEOTECHNICAL ENGINEER SHALL VERIFY MOISTURE CONTENT AND CONDITIONING PRIOR TO POURING
- PRIOR TO CONSTRUCTION CONTRACTOR SHALL REVIEW EXISTING GRADES ALONG SAWCUT LINE AND TRANSITIONS TO MATCH EXISTING IMPROVEMENTS TO ENSURE BOTH DRAINAGE FLOW IS CONTINUOUS AND UNINTERRUPTED AND ACCESSIBILITY REQUIREMENTS ARE BEING MET.
- ARCHITECT PLANS.

- SEE ARCHITECTURAL PLANS FOR ALL BUILDING DETAILS, STRUCTURAL DETAILS, FOOTING DETAILS, UTILITY POINTS OF CONNECTION, ROOF DRAIN LOCATIONS, ADA PATH OF TRAVEL, ADA SIGNAGE, ADA ACCESSIBILITY DETAILS. TRUNCATED DOME LOCATIONS. ENTRY MONUMENTS. GENERAL SIGNAGE. PARKING LOT STRIPING AND SITE PLAN CONSTRAINTS.
- SEE PLUMBING PLANS FOR CONTINUATION OF UTILITIES WITHIN 5 FEET OF THE BUILDING.
- SEE LANDSCAPE PLANS FOR ALL LANDSCAPE IMPROVEMENTS INCLUDING LANDSCAPE IRRIGATION, LANDSCAPE AREA GRADING, LANDSCAPE SLEEVE CROSSINGS AND LANDSCAPE SLOPE TREATMENT ANY AND ALL LANDSCAPE REMOVAL OR RELOCATION.
- OFOVER-EXCAVATION AND SUBGRADE REQUIREMENTS PER THE GEOTECHNICAL RECOMMENDATIONS DOCUMENT FOUND IN THE APPENDIX OF THE PROJECT SPECIFICATIONS

GEGEOTECHNICAL ENGINEER SHALL BE PRESENT TO PROVIDE RECOMMENDATIONS AS TO THE EXTENT

- DEVICES (MUTCD) LATEST EDITION, MUTCD CALIFORNIA SUPPLEMENTS
- ANY CONCRETE OR ASPHALT
- CONTRACTOR SHALL ADJUST ANY AND ALL BOXES, STRUCTURES, ETC. TO FINISH GRADE WITH

TRAFFIC RATED LID FOR VEHICULAR AREAS AND ACCESSIBLE LID FOR PEDESTRIAN AREAS BASED ON

PROPOSED GRADING DESIGN SHOWN IN THIS PLAN SET. SEE ARCHITECTURAL PLANS. SEE LANDSCAPE

COPYRIGHT © 2024 NORTHSTAR ENGINEERING GROUP, INC

3. CONTRACTOR SHALL MAINTAIN EROSION RESISTANT VEGETATION ON FACE OF ALL SLOPES.

PROJECT NO.

DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹

IDENTIFICATION STAM

 $\geq \supset \bigcirc$ \Box \Box \Diamond

CITY OF STOCKTON STANDARD DETAILS

DTL No. W-11

DTL No. W-12

PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL OBTAIN THE MOST UP TO DATE CITY STANDARDS FOR REFERENCE PRIOR TO AND DURING CONSTRUCTION. THE LATEST COPY OF THE CITY OF STOCKTON STANDARDS SHALL BE CONSIDERED PART OF THIS PLAN SET. IN THE EVENT OF A DISCREPANCY BETWEEN THIS PLAN SET AND CITY STANDARDS; THE CITY STANDARDS SHALL PREVAIL. STANDARD PLAN DRAWINGS REFERENCED WITHIN THIS PLAN SET INCLUDE, BUT ARE NOT LIMITED TO THE FOLLOWING CITY OF STOCKTON: DTL No. R-36 EXISTING STREET TRENCH SECTION FOR TRENCHES LARGER THAN 8" DTL No. R-50 SIDEWALK DETAILS CONCRETE CURB, GUTTER & SIDEWALKS CONSCTURCTION STANDARDS DTL No. R-55 DTL No. S-4 CALIFORNIA HEALTH DEPARTMENT REQUIREMENTS DTL No. S-15 PROTECTION OF STORM DRAINS AND SANITARY SEWER LINES DTL No. S-18 WATER SERVICE INSTALLATION 1",1.5" AND 2" SERVICE DTL No. W-3 DTL No. W-4 FITTINGS FOR WATER SERVICE


VALVE BOX DETAILS

THRUST BLOCK DETAILS


- ½" DIAMETER, 24" LONG --SEE EXPANSION JOINT DETAIL FOR SEALANT SMOOTH STEEL DOWEL AND ADDITIONAL INFORMATION SEE CONC/AC PAVING TRANSITION-FOR THICKENED CONCRETE EDGE -DRILL EXISTING SIDEWALK -FINISH GRADE 0.10' BELOW FLATWORK COMPACTED AB CLASS II -*SCARIFIED AND RE-COMPACTED SUBGRADE PER GEOTECHNICAL RECOMMENDATIONS
 - *NOTE:

 1. *SUBGRADE PREPARATION REQUIREMENTS PER GEOTECHNICAL RECOMMENDATIONS, CITY OF STOCKTON STANDARDS AND SPECIFICATIONS, AND PROJECT SPECIFICATIONS.
 - 2. AT EXPANSION JOINT USE ½"x24" SMOOTH STEEL DOWELS, 18" OC GREASE 1/2 THE LENGTH BEFORE CONCRETE PLACEMENT. SEE EXPANSION JOINT DETAIL THIS SHEET.
 - 3. EXPANSION JOINTS SHALL BE PROVIDED AT A MAXIMUM SPACING OF 60D=20 FEET ON CENTER BOTH WAYS. CONTROL JOINTS SHALL BE PLACED AT A MAXIMUM SPACING OF 5 FEET.
 - 4. CONSTRUCT CONTROL AND CONSTRUCTION JOINTS IN ACCORDANCE WITH CURRENT PORTLAND CEMENT ASSOCIATION GUIDELINES.
 - 5. SEE STRUCTURAL SECTIONS ON DIMENSIONS AND PAVING PLANS: SHEETS C3.1-C3.2


CONCRETE FLATWORK AT EXISTING FLATWORK



TYPICAL DOOR THRESHOLD AT CONCRETE LANDING




- 1. CLEAN-OUT RISER SHALL BE THE SAME SIZE AS THE LATERAL.
- 2. CLEAN-OUT RIM SHALL BE FLUSH WITH GRADE, ADA COMPLIANT AND "HEEL PROOF."
- 3. *SUBGRADE PREPARATION REQUIREMENTS PER GEOTECHNICAL RECOMMENDATIONS, CITY OF STOCKTON STANDARDS AND SPECIFICATIONS, AND PROJECT SPECIFICATIONS.
- TYPICAL STORM DRAIN OR SANITARY SEWER CLEAN OUT RISER




EXPANSION JOINT

└-1/2" MAX. THICK EXPANSION JOINT




4' CONCRETE WHEEL STOP



CONC / AC PAVING TRANSITION AND THICKENED EDGE

- 1. *SUBGRADE PREPARATION REQUIREMENTS PER GEOTECHNICAL RECOMMENDATIONS, CITY OF STOCKTON STANDARDS AND SPECIFICATIONS, AND PROJECT SPECIFICATIONS.
- 2. AT EXPANSION JOINT USE 1/2"x24" SMOOTH DOWELS, 18" OC. GREASE 1/2 THE LENGTH BEFORE CONCRETE PLACEMENT. SEE EXPANSION JOINT DETAIL 4 THIS SHEET.
- 3. CONSTRUCT CONTROL AND CONSTRUCTION JOINTS IN ACCORDANCE WITH CURRENT PORTLAND CEMENT ASSOCIATION GUIDELINES.
- 4. SEE STRUCTURAL SECTIONS ON DIMENSIONS AND PAVING PLANS: SHEETS C3.1-C3.2

SEE DIMENSION AND PAVING PLAN SEE CONC/AC PAVING TRANSITION-FOR REINFORCEMENT \ FOR THICKENED CONCRETE EDGE FINISH GRADE 0.1' BELOW FLATWORK COMPACTED AB CLASS II -*SCARIFIED AND RE-COMPACTED SUBGRADE PER GEOTECHNICAL RECOMMENDATIONS



*NOTE:


1. *SUBGRADE PREPARATION REQUIREMENTS PER GEOTECHNICAL RECOMMENDATIONS, CITY OF STOCKTON STANDARDS AND SPECIFICATIONS, AND PROJECT SPECIFICATIONS.

2. LAP JOINT SHALL APPLY AT ALL SAWCUT LOCATIONS ALONG ALL PAVEMENT UNLESS OTHERWISE NOTED.


LAP JOINT DETAIL







LANDSCAPE CONCRETE MOW STRIP



IDENTIFICATION STAMP

DIV. OF THE STATE ARCHITEC

REVIEWED FOR

SS 🗹 FLS 🗹 ACS 🗹

APP: 02-122764 INC:





S P S


PROJECT NO. 23-12901

COPYRIGHT © 2024 NORTHSTAR ENGINEERING GROUP, INC











 \triangleleft \vdash μЩ

O D O

DRAWING



| CONCRETE CURB, GUTTER & SIDEWALKS CONSTRUCTION STANDARDS | REVISION NO. | APPROVED N | Horasa |
|---|-----------------|--------------------------|------------|
| CITY OF STOCKTON DEPARTMENT OF PUBLIC WORKS | SCALE | SUPERSEDES DWG. DATED | DRAWING NO |



- 1" IPS DIA. MINIMUM LINE TO EACH LOT. 1.5" AND 2" SERVICE LINES TO BE CTS SIZE ACCORDINGLY. PLASTIC SERVICE PIPE TO BE CONTINUOUS WITH NO SPLICING ALLOWED. SEE DWG. NO. W-4 FOR FITTINGS AND BOX ASSEMBLY.
- METERS SHALL BE FURNISHED AND INSTALLED BY CITY OF STOCKTOP SERVICE CONNECTION AT THE METER SHALL BE A DEPTH OF 8" MIN. TO 12" MAX. 5. THE LOCATION OF THE TAP SHALL BE A MIN. OF 24" FROM ANOTHER TAP, BELL, SPIGOT, OR OTHER FITTING.
- METER BOX MAY BE PLACED ADJACENT TO PROPERTY OR EASEMENT LINE WITH PRIOR APPROVAL OF THE CITY ENGINEER. USE CHRISTY B-12 METER BOX WITH B12 TR/PL COVER OR EQUIVALENT. ALL BOXES LOCATED IN DRIVEWAY AREAS TO HAVE TRAFFIC COVERS MEET HS20 44 LOADING WITH
- Touch read hole 1-3/4" dia. Hole for t/r meter in upper right or lower left CORNER OF LID. INSTALLATION OF A BACKFLOW PREVENTION DEVICE SHALL BE REQUIRED FOR ALL
- CONNECTIONS TO THE CITY WATER SYSTEM, EXCEPT FOR SINGLE FAMILY RESIDENCES. . SERVICE LINES FROM ALL METERS TO PROPERTY LINES SHALL HAVE A MINIMUM OF 8" OF COVER FROM TOP OF SIDEWALK OR GROUND LINE:

| TO MULTIPLE METER MANIEULDS SUBJECT TO APPROVAL BY | MUNICIPAL UTILITIES DEPARTMENT. |
|--|-------------------------------------|
| | |
| WATER SERVICE INSTALLATION | REVISION APPROVED BY CITY ENGINEER: |

THRUST BLOCK AREA IS BASED ON THE SIZE OF THE BRANCH LINE.

THRUST BLOCK AREA REQUIRED

"A"

1'-6"

2'-0"

3'-0"

2'-6"

2'-6"

2'-0"

3'-0"

4'-0"

3'-0"

3'-0"

3'-0"

3'-6''

4'-0"

4'-0"

3'-0''

4'-0"

7'-0"

5'-0"

5'-0'

TYPICAL THRUST BLOCK

TEE OUTLET

22 🚽

LINE

22

45

90°

22 5

22 5

45"

90.

TEE OUTLET

TEE OUTLET

DEAD END

TEE OUTLET

DEAD END

TEE OUTLET

DEAD END

DEAD END

1", 1.5", AND 2" SERVICE

CITY OF STOCKTON

B DATE: 09/27/2016

SCALE SUPERSEDES DRAWING NO. 11/25/03 W-3

TYPICAL THRUSE BLOCK

ALLOWABLE SOIL BEARING VALUE

1000 LBS. PER SQ. FT.

DEAD END

"B"

1'-6''

2'-0"

2'-6"

2'-0"

2'-0"

2'-0"

2'-6"

3'-0''

3'-0"

3'-0"

2'-0"

3'-0"

4'-0"

3'-6"

3'-6"


3'-0"

4'-0"


4'-0"


4'-0"


4'-0"





| OF ENGLING HOLL EXTENSION REGULED IN DEEL CH. THANK | 9 1 661. | | |
|---|-----------------|--------------------------------------|-------------------|
| VALVE BOX DETAILS | REVISION NO. | APPROVED BY | 7/1280 |
| CITY OF STOCKTON DEPARTMENT OF PUBLIC WORKS | SCALE NONE | SUPERSEDES DWG. DATED 01/09/02 | DRAWING N W-11 |
| | 333604 | Vijvejez | 1 57 |











Page 1 of 2 REVISION APPROVED BY CITY ENGIN **FITTINGS FOR WATER SERVICE** DATE: 09/27/2016 SCALE SUPERSEDES DWG, DATED DRAWING NO. CITY OF STOCKTON W-4 DEPARTMENT OF PUBLIC WORKS NONE 01/09/02

- NEW PAVEMENT TO BE 1/8" HIGHER THAN

NOTE NO. 2

THE ENGINEER.

: D+16" MIN.

"-D+24" MAX."

INVENIONAL TERMINORS SIGNATURE IN INVESTIGATION INTERPORTED INTERPORT

BOTTOM OF THE PIPE AND REPLACE WITH SAND OR AGGREGATE SUBBASE IN LIEU OF SHAPING BOTTOM OF TRENCH TO FIT PIPE BARREL JOINTS SHALL BE SHAPED IN

DEVIATION FROM ABOVE MAY BE ALLOWED WHEN APPROVED BY THE CITY ENGINEER. TRENCH — WHERE THE TRENCH SECTION PARALLELS THE EXISTING CURB AND GUTTER, THE EDGE OF THE TRENCH SHALL BE A MIN. OF 1 -0 FROM LIP OF THE EXISTING

GUTTER. THE PAVEMENT SHALL BE REMOVED AND REPLACED TO THE LIP OF THE GUTTER.

CONTROLLED DENSITY FILL (CDF) MAY BE USED IN LIEU OF SPECIFIED BACKFILL METHOD.

MINIMUM TRENCH WIDTH MAY BE REDUCED TO 2-1/2" CLEAR OF EACH SIDE OF PIPE.

FLEXIBLE PIPE SHALL HAVE A 6" BEDDING OF GRANULAR MATERIAL AS DESCRIBED IN

PLASTIC SERVICE PIPE SHALL BE ULTRA HIGH MOLECULAR WEIGHT (UHMW) P.E. 3406 CS

255-63, POLYETHYLENE (STANDARD SPECIFICATIONS 78-1.02J) AS MANUFACTURED BY

1" X 1" CORPORATION STOPS AS MANUFACTURED BY FORD OR EQUIVALENT

1" DIAMETER CORPORATION STOPS AS MANUFACTURED BY FORD OR EQUIVALENT

(2) 1" X 1" CORPORATION STOP. FORD NO. 800 PLUS A C-16-44 COMPRESSION

1" I.D. ANGLE METER STOP AS MANUFACTURED BY FORD OR EQUIVALENT COMPLETE

. 1-1/2 AND 2 INCH DIAMETER ANGLE METER STOPS
ANGLE METER STOPS AS MANUFACTURED BY FORD OR EQUIVALENT SHALL BE USED

WITH LOCK WING AND STAINLESS STEEL INSERT FOR 1" I.D. PLASTIC PIPE.

(1) 1" ANGLE METER STOP. FORD NO. KV63-444 WITH SS INSERT.

(3) 2" ANGLE METER STOP. FORD FV 43-777 WITH SS INSERT.

FITTING WITH STAINLESS STEEL RESTRAINING CLAMP WITH NUT

(2) 1-1/2" ANGLE METER STOP. FORD FV 43-666 WITH SS INSERT.

D. ALL 1", AND 1.5", AND 2" ANGLE METER STOPS SHALL HAVE A COMPRESSION

COMPLETE WITH STAINLESS STEEL INSERTS FOR 1" I.D. PLASTIC PIPE.

COMPLETE WITH STAINLESS STEEL INSERTS FOR 1" I.D. PLASTIC PIPE.

(1) 1" CORPORATION STOP. FORD NO. 1001 WITH SS INSERTS.

(3) 1-1/2" AND 2" CORPORATION STOPS. FORD NO. FB-1000.

ADS OR APPROVED EQUAL WITH MINIMUM PRESSURE RATING OF 160 P.S.I.

ALL VERTICAL EDGES OF EXISTING ASPHALT CONCRETE SHALL BE TACK COATED.

EXISTING STREET TRENCH SECTION

FOR TRENCHES LARGER THAN 8"

CITY OF STOCKTON

NOTE: SEE DWG. NO. W-3 FOR DETAILS.

CONNECTION SHALL BE AS FOLLOWS:

B. 8 AND 12 INCH DIAMETER LINES

C. ALTERNATE PRODUCT SUPPLIER

ADAPTER WITH SS INSERTS.

A. 1 INCH DIAMETER ANGLE METER STOPS

WITH STAINLESS STEEL INSERTS.

C. ALTERNATE PRODUCT SUPPLIER

A. 6 INCH DIAMETER LINES

1. CORPORATION STOPS

2. ANGLE METER STOPS

DEPARTMENT OF PUBLIC WORKS

PAVING SHALL CONFORM TO SECTION 100-1.06 OF THE STANDARD SPECIFICATIONS. ALL JOINT PIPE REPAIRS SHALL BE BEDDED WITH A MINIMUM OF 6 INCHES OF 3*

WHEN EXCAVATION IS IN EXISTING PAVED STREETS, REPLACE PAVEMENT 12" ON EACH SIDE

OF EXCAVATION, TRENCH, BELL HOLE OR POT HOLES, TO BE REMOVED AFTER COMPACTION

NOTES
1. FOR RIGID PIPE, CONTRACTOR MAY, AT THEIR EXPENSE, EXCAVATE 6" BELOW THE

DIAMOND SAW CUTTING, MILLING, OR

OTHER APPROVED DEVICE SHALL BE

USED, REPAVE TO A CLEAN - N

COMPACT IN 12" MAX.

LAYERS TO A MIN. RELATIVE

COMPACTION OF 95% UNDER THE PAVEMENT

COMPACT IN 12" MAX.

LAYERS TO A MIN. RELATIVE COMPACTION OF 90% AT VARYING DEPTH. MATERIAL TO BE APPROVED

MPORT OR SUITABLE SITE

EXCAVATED MATERIAL

SHAPE BOTTOM OF TRENCH

PIPE JOINTS, PIPE SHALL BE

EITHER CASE.

& REFORE PAVING

CRUSHED ROCK.

PLASTIC PIPE:

TO FIT PIPE BARREL AND

CENTERED IN TRENCH.

SEE NOTE #1 AND #6.

STRAIGHT EDGE (TYP).

ADJACENT PAVEMENT, APPLY FOG SEAL COAT

OF CSS-1 OR SS-1 ASPHALT EMULSION.

TO BE REMOVED AFTER

COMPACTION & BEFORE PAVING

PAVEMENT SECTION SHALL BE EQUIVALENT TO EXISTING PAVEMENT

BUT IN NO CASE LESS THAN 8"

STREET AND 13" FOR ARTERIALS

UNLESS OTHERWISE DIRECTED BY

COMPACT IN 6" MAX. LAYERS TO MIN. RELATIVE COMPACTION 85%.

MATERIAL TO BE IMPORTED SAND OR AN APPROVED CLEAN GRANULAF

DEBRIS, ETC., HAVING THE

FOLLOWING GRADING: 100%

NO. 200 MINIMUM SAND

MECHANICAL MEANS.

MATERIAL FREE OF ALL LUMPS AND

PASSING 3/4", 5%-20% PASSING

EQUIVALENT = 20, COMPACTION BY

REVISION APPROVED BY CITY ENGINEER

SCALE SUPERSEDES DRAWING NO.

NONE 11/25/03

R-36

FOR LOCAL AND COLLECTOR

PROPERTY LINE

SEE NOTE NO .-

8, DWG R-55

— 5'-0" M⊪N. -—

PREFORMED FIBER EXPANSION —

SIDEWALK DETAILS

S CITY OF STOCKTON DEPARTMENT OF PUBLIC WORKS

1" METER BOXES SHALL BE CHRISTY B-12 BOX.

1-1/2" AND 2" METER BOXES SHALL BE CHRISTY

LOADING WITH TOUCH READ HOLE 1-3/4" DIA.

FITTINGS FOR WATER SERVICE

CITY OF STOCKTON

DEPARTMENT OF PUBLIC WORKS

NO. 7, DWG R-55

FIGURE 2 EXPANSION JOINT

JOINT FILLER CONFORMING TO

FIGURE 1 WEAKENED PLANE JOINT

3. SERVICE SADDLES

MANUFACTURED BY FORD.

FOR LIDS, SEE NOTE NO. 5.

WATER METER BOX COVER

READ HOLE 1-3/4" DIA.

4. WATER METER BOXES

SECTION A-A

OR PARKWAY STRIP

EAKENED PLANE

JOINT, SEE FIG. 1 AND NOTE NO. 6, DWG R-55

FIGURE 3 SCORE MARK

REVISION APPROVED BY CITY ENGINEE

NONE

SCALE

-see note no. 7 dwg r-55

SCALE SUPERSEDES DRAWING NO. COPYRIGHT © 2024 NORTHSTAR ENGINEERING GROUP, INC

REVISION APPROVED BY CITY ENGINEER

DATE: 09/27/2015

ŻΞ ⋚Ш IVIL IMPROUL SCHOOL

> PROJECT NO. 23-12901

STATE OF CALIFORNIA DEPARTMENT OF HEALTH CRITERIA FOR THE SEPARATION OF WATER MAINS WITH SANITARY SEWERS AND STORM SEWERS

A. BASIC STANDARDS

- THE "CALIFORNIA WATERWORKS STANDARDS" SETS FORTH THE MINIMUM SEPARATION REQUIREMENT FOR WATER MAINS WITH SANITARY AND STORM SEWER LINES. THESE STANDARDS, CONTAINED IN SECTION 64630, TITLE 22, CALIFORNIA ADMINISTRATIVE CODE, SPECIFY: 1) PARALLEL CONSTRUCTION: THE HORIZONTAL DISTANCE BETWEEN PRESSURE WATER
- MAINS AND SEWER LINES SHALL BE AT LEAST 10 FEET. 2) PERPENDICULAR CONSTRUCTION (CROSSING): PRESSURE WATER MAINS SHALL BE AT
- LEAST ONE FOOT ABOVE SANITARY SEWER LINES WHERE THESE LINES MUST CROSS. 3) SEPARATION DISTANCES SPECIFIED ABOVE SHALL BE MEASURED FROM THE NEAREST EDGES OF THE FACILITIES.
- 4) WATER MAINS AND SEWER LINES MUST NOT BE INSTALLED IN THE SAME TRENCH. 5) WATER MAINS AND SEWERS OF 24 INCHES DIAMETER OR GREATER MAY CREATE SPECIAL HAZARDS BECAUSE OF THE LARGE VOLUMES OF FLOW. INSTALLATIONS OF WATER MAINS AND SEWER LINES 24 INCHES DIAMETER OR LARGER MUST BE REVIEWED AND APPROVED BY THE HEALTH AGENCY AND CITY ENGINEER PRIOR TO CONSTRUCTION.
- 6) WHEREVER THE WORD "SEWER" IS USED IN CONNECTION WITH ANY REQUIREMENTS AS SHOWN ON DRAWINGS S-4, PAGE 4 & 5 THE WORD SHALL APPLY EQUALLY TO SANITARY OR STORM SEWER INSTALLATIONS.

B. EXCEPTIONS TO BASIC SEPARATION STANDARDS

REFER TO STD DWG S-4, PAGE 4 & 5 FOR SEPARATION DETAILS.

LOCAL CONDITIONS, SUCH AS AVAILABLE SPACE, LIMITED SLOPE, EXISTING STRUCTURES, ETC., MAY CREATE A SITUATION WHERE THERE IS NO ALTERNATIVE BUT TO INSTALL WATER MAINS OR SEWER LINES AT A DISTANCE LESS THAN THAT REQUIRED BY THE BASIC SEPARATION STANDARDS. IN SUCH CASES, ALTERNATIVE CONSTRUCTION CRITERIA AS SPECIFIED IN SECTION C SHALL BE FOLLOWED, SUBJECT TO THE SPECIAL PROVISIONS IN SECTION D.

C. ALTERNATE CRITERIA FOR CONSTRUCTION

THE CONSTRUCTION CRITERIA FOR SEWER LINES OR WATER MAINS WHERE THE BASIC SEPARATION STANDARDS CANNOT BE ATTAINED ARE SHOWN ON DRAWINGS S-4, PAGE 4 & 5. THERE ARE TWO SITUATIONS ENCOUNTERED:

CASE 1 -- NEW SEWER LINE - NEW OR EXISTING WATER MAIN.

CASE 2 -- NEW WATER MAIN - EXISTING SEWER LINE.

FOR CASE 1, THE ALTERNATE CONSTRUCTION CRITERIA APPLY TO THE SEWER LINE.

FOR CASE 2, THE ALTERNATE CONSTRUCTION CRITERIA MAY APPLY TO EITHER OR BOTH WATER MAIN AND SEWER LINE.

THE CONSTRUCTION CRITERIA APPLY TO THE HOUSE LATERALS THAT CROSS ABOVE A PRESSURE WATER MAIN BUT NOT TO THOSE HOUSE LATERALS THAT CROSS BELOW A PRESSURE WATER MAIN.

| CALIFORNIA HEALTH DEPARTMENT REQUIREMENTS | REVISION NO. | DATE: 09/27/ | CITY ENGINEER |
|--|-----------------|--------------------------|---------------|
| CITY OF STOCKTON DEPARTMENT OF PUBLIC WORKS | SCALE | SUPERSEDES DWG. DATED | DRAWING NO. |
| DEFAITIVILITY OF PUBLIC WORKS | NONE | 01/09/02 | J-7 |

SPECIAL CONSTRUCTION REQUIREMENTS

(TO BE USED ONLY WHERE REQUIRED SEPARATION CANNOT BE OBTAINDED)

CASE 1 - NEW SEWER BEING INSTALLED

ZONES A.B.C. AND D INDICATE RESTRICTED AREAS.

ZONES P INDICATE PROHIBITED USE AREAS.

ZONE "P" ├ZONE "A"

PERMISSION)

(PROHIBITED)

SCALE

SUPERSEDES DWG. DATED

01/09/02

DRAWING NO.

(PROHIBITED) (SPECIAL

WATER PIPE

PARALLEL CONSTRUCTION

(SPECIAL NO

JOINT PIPES)

PERPENDICULAR CONSTRUCTION

NO JOINT:

CALIFORNIA HEALTH

DEPARTMENT REQUIREMENTS

CITY OF STOCKTON

DEPARTMENT OF PUBLIC WORKS

-ZONE "A"

(SPECIAL


 \sum PERMISSION).


(SPECIAL

SPECIAL CONSTRUCTION REQUIREMENTS ZONE "B" (SPECIAL PIPE) ZONE "D"(SPECIAL NO -JOINT PIPES) 4" ZONE "P" (PROHIBITED) Page 4 of 5 REVISION APPROVED BY CITY ENGINEER

CASE 1: NEW SEWER BEING INSTALLED (DRAWING NO. S-4, PAGE 4) ZONE SPECIAL CONSTRUCTION REQUIRED FOR SEWER SEWER LINES PARALLEL TO WATER MAINS SHALL NOT BE PERMITTED IN THIS ZONE WITHOUT APPROVAL FROM THE RESPONSIBLE HEALTH AGENCY AND WATER SUPPLIER. A SEWER LINE PLACED PARALLEL TO A WATER LINE SHALL BE CONSTRUCTED OF: 1. EXTRA STRENGTH VITRIFIED CLAY PIPE WITH COMPRESSION JOINTS. 2. PLASTIC SEWER PIPE WITH RUBBER RING JOINTS (PER ASTM D3034) OR EQUIVALENT. 3. CAST OR DUCTILE IRON PIPE WITH COMPRESSION JOINTS. CASE 2

| С | A SEWER LINE CROSSING A WATER MAIN SHALL | BE CON | ISTRUCTED | OF: |
|--------|--|---------------|----------------------------|------------------------|
| | 1. DUCTILE IRON PIPE WITH HOT DIP BITUM | INOUS C | COATING ANI | |
| | MECHANICAL JOINTS. 2. A CONTINUOUS SECTION OF CLASS 200 | | | |
| | PLASTIC PIPE OR EQUIVALENT, CENTERED CROSSED. | | | EING |
| | 3. ANY SEWER PIPE WITHIN A CONTINUOUS | SLEEVE. | • | |
| | | | | |
| 2: NEW | WATER MAINS BEING INSTALLED (DRAWING N | 0. S-4, | PAGE 5) | |
| ZONE | SPECIAL CONSTRUCTION REQUIRED FOR SEWER | | • | |
| Α | NO WATER MAINS PARALLEL TO SEWERS WITHIN CONSTRUCTED WITHOUT APPROVAL FROM THE HE | | | |
| В | IF THE SEWER PARALLELING THE WATER MAIN DO ZONE B, REQUIREMENTS, THE WATER MAIN SHALL | | | |
| | CEMENT LINED DUCTILE IRON PIPE WITH COATING. | HOT DIF | BITUMINO | JS |
| | DIPPED AND WRAPPED ONE—FOURTH—INC PIPE. | H-THICK | K WELDED S | STEEL |
| | 3. CLASS 200 PRESSURE RATED PLASTIC W | ATER PI | PE (DR 14 | PER |
| | AWWA C900) OR EQUIVALENT. 4. REINFORCED CONCRETE PRESSURE PIPE, PER AWWA (C300-74 OR C301-79 OR | | | YPE, |
| С | IF THE SEWER CROSSING THE WATER MAIN DOES ZONE C, REQUIREMENTS, THE WATER MAIN SHAL C AND BE CONSTRUCTED OF: | | | |
| | | | | |
| | | | | |
| | | DE1/101011 | 45550155 | Page 2 of 5 |
| | CALIFORNIA HEALTH | NO. | APPROVED BY | CITY ENGINEER: |
| DEF | PARTMENT REQUIREMENTS | 4 | DATE: 09/27/ SUPERSEDES | |
| 2 | S CITY OF STOCKTON DEPARTMENT OF PUBLIC WORKS | SCALE NONE | 01/09/02 | DRAWING NO. S-4 |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | CDECIAL CONCEDUCTION DECLID | | 10 | |





Page 3 of 5

revery

S-4

REVISION APPROVED BY CITY INGINEER


SCALE SUPERSEDES DRAWING NO.

NONE 01/09/02






IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: **REVIEWED FOR** SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024



S P S

PROJECT NO. 23-12901

DRAWING



AWWA C900) OR EQUIVALENT.

AWWA C900) OR EQUIVALENT.

POSSIBLE USE.

POSSIBLE USE.

BE CONSTRUCTED OF:

EXISTING LINE.

6. SEWER FORCE MAINS

CALIFORNIA HEALTH

CITY OF STOCKTON

DEPARTMENT OF PUBLIC WORKS

DEPARTMENT REQUIREMENTS

D SPECIAL PROVISIONS

COATING.

3. REINFORCED CONCRETE PRESSURE PIPE, STEEL CYLINDER TYPE,

PER AWWA (C300-74 OR C301-79 OR C303-70). REQUIRES

SPECIFIC DESIGN APPROVAL OF PIPE AND FITTING PRIOR TO

REQUIREMENTS FOR ZONE D. CASE 1. THE WATER MAIN SHALL HAVE NO JOINTS WITHIN FOUR FEET FROM EITHER SIDE OF THE SEWER AND SHALL

1. CEMENT LINED DUCTILE IRON PIPE WITH HOT DIP BITUMINOUS

2. CLASS 200 PRESSURE RATED PLASTIC WATER PIPE (DR 14 PER

3. REINFORCED CONCRETE PRESSURE PIPE, STEEL CYLINDER TYPE,

1. THE BASIC SEPARATION STANDARDS ARE APPLICABLE UNDER NORMAL

CONDITIONS, SUCH AS HIGH GROUND WATER EXIST.

CONDITIONS FOR SEWAGE COLLECTION LINES AND WATER DISTRIBUTION MAINS. MORE STRINGENT REQUIREMENTS MAY BE NECESSARY IF

2. SEWER LINES SHALL NOT BE INSTALLED WITHIN 25 FEET HORIZONTALLY

3. NEW WATER MAINS AND SEWER SHALL BE PRESSURE TESTED WHERE

4. IN THE INSTALLATION OF WATER MAINS OR SEWER LINES, MEASURES

SHOULD BE TAKEN TO PREVENT OR MINIMIZE DISTURBANCES OF THE

a. SEWER FORCE MAINS SHALL NOT BE INSTALLED WITHIN TEN

b. WHEN A SEWER FORCE MAIN MUST CROSS A WATER LINE, THE

FORCE MAIN SHOULD BE AS CLOSE TO PERPENDICULAR AS PRACTICAL. THE SEWER FORCE MAIN SHOULD BE AT LEAST

EXISTING WATER MAIN, ALL PORTIONS OF THE SEWER FORCE MAIN WITHIN TEN FEET (HORIZONTALLY) OF THE WATER MAIN

d. WHEN A NEW WATER MAIN CROSSES OVER AN EXISTING SEWER FORCE MAIN, THE WATER MAIN SHALL BE CONSTRUCTED OF

PIPE MATERIALS WITH A MINIMUM RATED WORKING PRESSURE

TEMPORARY

5. SPECIAL CONSIDERATION SHALL BE GIVEN TO THE SELECTION OF PIPE

c. WHEN A NEW SEWER FORCE MAIN CROSSES UNDER AN

SHALL BE ENCLOSED IN A CONTINUOUS SLEEVE.

OF 200 PSI OR EQUIVALENT PRESSURE RATING.

OF A LOW HEAD (5 PSI OR LESS PRESSURED) WATER MAIN.

MATERIALS IF CORROSIVE CONDITIONS ARE LIKELY TO EXIST.

FEET (HORIZONTALLY) OF A WATER MAIN.

ONE FOOT BELOW THE WATER LINE.

THE CONDUITS ARE LOCATED TEN FEET APART OR LESS.


PER AWWA (C300-74 OR C301-79 OR C303-70). REQUIRES SPECIFIC DESIGN APPROVAL OF PIPE AND FITTING PRIOR TO


IF THE SEWER CROSSING THE WATER MAIN DOES NOT MEET THE

PLA NT MENT F









LEGEND

| EXISTING CONCRETE | EXISTING PAVEMENT |
|----------------------------|------------------------------------|
| EXISTING BUILDING OVERHANG | EXISTING CONCRETE TO BE REMOVED |

KEY NOTES

- A SAWCUT AND REMOVE EXISTING PAVEMENT, CONCRETE, AND OR CURB AS REQUIRED PER THESE PLANS. CONTRACTOR MAY NEED TO FIELD ADJUST SAWCUT LINE TO REMOVE THE PAVEMENT OR CONCRETE SECTION AT A CLEAN EDGE OR NEAREST JOINT BASED ON FIELD CONDITIONS WHILE MAINTAINING ACCESSIBLE TRANSITION TO PROVIDE COMPLIANCE WITH ACCESSIBILITY STANDARDS, WHERE APPLICABLE.
- B CONTRACTOR SHALL *USE EXTREME CAUTION* THROUGHOUT THE COURSE OF CONSTRUCTION AS ADDITIONAL UNDERGROUND LINES AND STRUCTURES NOT SHOWN ON THIS PLAN MAY EXIST AND ARE NOT CLEARLY MARKED OR VISIBLE FROM THE SURFACE. ADDITIONALLY CONTRACTOR SHALL USE EXTREME CAUTION WHILE WORKING BY LOW HANGING POWER LINES. IN CONJUNCTION WITH CONTACTING USA TO LOCATE UNDERGROUND UTILITIES WITHIN THE PUBLIC RIGHT-OF-WAY IT IS HIGHLY RECOMMENDED THAT THE CONTRACTOR UTILIZE (GPR) GROUND PENETRATING RADAR UNDERGROUND SERVICES TO IDENTIFY UTILITIES THAT MAY NOT BE VISIBLE FROM THE SURFACE.
- *USE EXTREME CAUTION* CONTRACTOR SHALL PROTECT EXISTING STRUCTURES, OVERHEAD LINES AND UNDERGROUND UTILITIES THROUGHOUT THE COURSE OF CONSTRUCTION AND REPAIR/REPLACE IF DAMAGED DURING CONSTRUCTION, AT CONTRACTOR'S EXPENSE. COORDINATE WITH APPROPRIATE CONSULTANT AND/OR AGENCY FOR ANY RELOCATION OR REMOVAL. CONTRACTOR SHALL ADJUST TO PROPOSED GRADE AS NECESSARY.
- CONTRACTOR SHALL PROTECT EXISTING CONCRETE, CURB AND/OR PAVEMENT THROUGHOUT THE COURSE OF CONSTRUCTION AND REPAIR/REPLACE IF DAMAGED DURING CONSTRUCTION, AT CONTRACTOR'S EXPENSE. SEE KEYNOTE "A" ABOVE.
- © CONTRACTOR SHALL PROTECT EXISTING BUILDING, RAMPS, AND ASSOCIATED STRUCTURES THROUGHOUT THE COURSE OF CONSTRUCTION AND REPAIR/REPLACE IF DAMAGED DURING CONSTRUCTION, AT CONTRACTOR'S EXPENSE.
- © CONTRACTOR SHALL PROTECT EXISTING FENCE, GATE AND/OR MOWSTRIP THROUGHOUT THE COURSE OF CONSTRUCTION AND REPAIR/REPLACE IF DAMAGED DURING CONSTRUCTION, AT CONTRACTOR'S
- G CONTRACTOR SHALL PROTECT EXISTING STRIPING AND SIGNAGE THROUGHOUT THE COURSE OF CONSTRUCTION AND REPAIR/REPLACE IF DAMAGED DURING CONSTRUCTION, AT CONTRACTOR'S
- H CONTRACTOR SHALL PROTECT EXISTING OVERHEAD STRUCTURES AND COLUMNS THROUGHOUT THE COURSE OF CONSTRUCTION AND REPAIR/REPLACE IF DAMAGED DURING CONSTRUCTION, AT CONTRACTOR'S EXPENSE.
- CONTRACTOR SHALL PROTECT EXISTING TREE, SHRUB, AND ROOTS THROUGHOUT THE COURSE OF CONSTRUCTION. EXCAVATION AND GRADING SHOULD BE KEPT TO A MINIMUM AND NOTIFY THE OWNER IMMEDIATELY SHOULD THE TREE NEED TO BE REMOVED TO COMPLETE IMPROVEMENTS.
- CONTRACTOR SHALL REMOVE EXISTING CONCRETE, CURB, AND/OR PAVEMENT AS SHOWN AND DISPOSE OF OFF-SITE AT THE CONTRACTOR'S EXPENSE. SEE KEYNOTE "A" ABOVE FOR ADDITIONAL INFORMATION.
- CONTRACTOR SHALL REMOVE EXISTING OUTDOOR BENCH AND TABLE. CONTRACTOR SHALL COORDINATE WITH PROPERTY OWNER FOR ANY SALVAGING OF MATERIALS; OTHERWISE, CONTRACTOR SHALL DISPOSE OF OFFSITE AT THE CONTRACTOR'S EXPENSE.
- M CONTRACTOR SHALL RELOCATE EXISTING SIGN. CONTRACTOR SHALL SALVAGE EXISTING SIGNS AND POSTS AND RE-INSTALL AT THE LOCATION SHOWN ON THESE PLANS.
- N CONTRACTOR SHALL REMOVE FENCE/GATE AND DISPOSE OF OFF-SITE AT THE CONTRACTOR'S

COPYRIGHT © 2024 NORTHSTAR ENGINEERING GROUP, INC

IDENTIFICATION STAME DIV. OF THE STATE ARCHITEC

REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹

APP: 02-122764 INC:

DATE: 12/18/2024







MENT F

CIVIL IMPROV PULLIAM E SCHOOL STOCKTON,

PROJECT NO. 23-12901

DRAWING





IDENTIFICATION STAN DIV. OF THE STATE ARCH APP: 02-122764 INC:

REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹





VEMENT PLANS FILEMENTARY

CIVIL IMPRO PULLIAM SCHOOL


PROJECT NO.


23-12901

COPYRIGHT © 2024 NORTHSTAR ENGINEERING GROUP, INC










LEGEND



PCC/6" CLASS II AB (95% RC) W/ #4 REBAR @ 18" O.C., BOTH WAYS SEE DETAIL 7 ON SHEET C1.4 *CONCRETE SECTION - PEDESTRIAN 4"PCC/4" CLASS II AB (95% RC) W/ #4 REBAR @ 18" O.C., BOTH WAYS

SEE DETAIL 7 ON SHEET C1.4

*CONTRACTOR SHALL REFER TO GEOTECHNICAL RECOMMENDATIONS DOCUMENT FOR ADDITIONAL NFORMATION, INCLUDING SUBGRADE AND AGGREGATE BASE PREPARATION AND COMPACTION AND TO CONFIRM STRUCTURAL SECTIONS SHOWN ABOVE. **SEE ARCHITECTURAL PLANS FOR SCORING, CONTROL JOINTS, PATTERN, COLOR AND ADDITIONAL

KEY NOTES

CONCRETE DETAILS AND SPECIFICATIONS.

SEE TOPOGRAPHIC AND DEMOLITION SHEETS C2.1-C2.2 FOR ADDITIONAL REMOVAL, REPLACEMENT AND PROTECTION NOTES.

A SAWCUT AND REMOVE EXISTING PAVEMENT, CONCRETE, AND OR CURB AS REQUIRED PER THESE PLANS. CONTRACTOR MAY NEED TO FIELD ADJUST SAWCUT LINE TO REMOVE THE PAVEMENT OR CONCRETE SECTION AT A CLEAN EDGE OR NEAREST JOINT BASED ON FIELD CONDITIONS. WHILE MAINTAINING ACCESSIBLE TRANSITION TO PROVIDE COMPLIANCE WITH ACCESSIBILITY STANDARDS, WHERE APPLICABLE. LAP JOINT PER DETAIL 8 ON SHEET C1.4 SHALL APPLY TO ALL SAWCUT LOCATIONS ALONG AC PAVEMENT, UNLESS OTHERWISE NOTED. CONTRACTOR SHALL INSTALL DOWELS AT ALL CONNECTIONS BETWEEN EXISTING AND PROPOSED CONCRETE PER DETAIL 1 ON SHEET C1.4. CONTRACTOR SHALL INSTALL THICKENED EDGE AT ALL CONNECTIONS BETWEEN PAVEMENT AND PROPOSED CONCRETE PER DETAIL 6 ON SHEET C1.4.

B ACCESSIBLE PATH OF TRAVEL NOT TO EXCEED 5.0% MAX RUNNING SLOPE AND 2.0% MAX CROSS SLOPE. ACCESSIBLE PATH OF TRAVEL DETERMINATION, ACCESSIBILITY AND SIGNAGE SHALL BE DETERMINED BY ARCHITECTURAL AND LANDSCAPE PLANS. SEE ARCHITECTURAL AND LANDSCAPE PLANS FOR DIMENSIONS AND DETAILS, INCLUDING HANDRAILS, WHERE APPLICABLE.

- C CONTRACTOR SHALL INSTALL CONCRETE WHEEL STOPS PER DETAIL 5 ON SHEET C1.4.
- ONTRACTOR SHALL INSTALL TRUNCATED DOMES PER ARCHITECTURAL PLANS AND SPECIFICATIONS
- © CONTRACTOR SHALL INSTALL FENCE AND/OR GATE PER ARCHITECTURAL PLANS.
- F CONTRACTOR SHALL CONSTRUCT BUILDING PER ARCHITECTURAL PLANS AND SPECIFICATIONS.
- G CONTRACTOR SHALL INSTALL 6" LANDSCAPE MOW STRIP PER DETAIL 9 ON SHEET C1.4. H CONTRACTOR SHALL INSTALL STRIPING INCLUDING CROSSWALKS AS INDICATED BY THE ARCHITECT AND THE LATEST EDITIONS OF THE CALIFORNIA BUILDING CODE STANDARDS. SEE

ARCHITECTURAL PLANS FOR ADDITIONAL DETAILS AND SPECIFICATIONS.

- ONTRACTOR SHALL RE-INSTALL ACCESSIBLE SIGNAGE AND STRIPING. SEE ARCHITECTURAL PLANS FOR ADDITIONAL DETAILS AND SPECIFICATIONS. USE EXTREME CAUTION WHEN INSTALLING SIGN FOOTINGS AS UNDERGROUND UTILITIES MAY EXIST.
- CONTRACTOR SHALL RE-INSTALL PRINCIPAL PARKING SIGN.

COPYRIGHT © 2024 NORTHSTAR ENGINEERING GROUP, INC

IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC

REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹

APP: 02-122764 INC:

DATE: 12/18/2024



/EMENT PLANS F ELEMENTAR


CIVIL IMPROVPULLIAM ESCHOOL STOCKTON,


PROJECT NO.

23-12901

DRAWING

⋛Ш





IDENTIFICATION STAM DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR

Modesto, CA 95354

EXISTING PAVEMENT

SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024





OVEMENT PLANS FELEMENTARY

CIVIL IMPROVPULLIAM ESCHOOL STOCKTON,


PROJECT NO.

23-12901

DRAWING







IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC

REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹

APP: 02-122764 INC:

DATE: 12/18/2024


VEMENT PLANS FELEMENTARY

CIVIL IMPROVPULLIAM ESCHOOL STOCKTON,

PROJECT NO.

23-12901

DRAWING




KEY NOTES

SEE TOPOGRAPHIC AND DEMOLITION SHEETS C2.1-C2.2 FOR ADDITIONAL REMOVAL, REPLACEMENT AND PROTECTION NOTES.

A SAWCUT AND REMOVE EXISTING PAVEMENT, CONCRETE, AND OR CURB AS REQUIRED PER THESE PLANS. CONTRACTOR MAY NEED TO FIELD ADJUST SAWCUT LINE TO REMOVE THE PAVEMENT OR CONCRETE SECTION AT A CLEAN EDGE OR NEAREST JOINT BASED ON FIELD CONDITIONS. WHILE MAINTAINING ACCESSIBLE TRANSITION TO PROVIDE COMPLIANCE WITH ACCESSIBILITY STANDARDS, WHERE APPLICABLE. LAP JOINT PER DETAIL 8 ON SHEET C1.4 SHALL APPLY TO ALL SAWCUT LOCATIONS ALONG AC PAVEMENT, UNLESS OTHERWISE NOTED. CONTRACTOR SHALL INSTALL DOWELS AT ALL CONNECTIONS BETWEEN EXISTING AND PROPOSED CONCRETE PER DETAIL 1 ON SHEET C1.4. CONTRACTOR SHALL INSTALL THICKENED EDGE AT ALL CONNECTIONS BETWEEN PAVEMENT AND PROPOSED CONCRETE PER DETAIL 6 ON SHEET C1.4.


- B ACCESSIBLE PATH OF TRAVEL NOT TO EXCEED 5.0% MAX RUNNING SLOPE AND 2.0% MAX CROSS SLOPE. ACCESSIBLE PATH OF TRAVEL DETERMINATION, ACCESSIBILITY AND SIGNAGE SHALL BE DETERMINED BY ARCHITECTURAL AND LANDSCAPE PLANS. SEE ARCHITECTURAL AND LANDSCAPE PLANS FOR DIMENSIONS AND DETAILS, INCLUDING HANDRAILS, WHERE APPLICABLE.
- CONTRACTOR SHALL INSTALL CONCRETE WHEEL STOPS PER DETAIL 5 ON SHEET C1.4.
- D CONTRACTOR SHALL INSTALL TRUNCATED DOMES PER ARCHITECTURAL PLANS AND SPECIFICATIONS
- © CONTRACTOR SHALL INSTALL FENCE AND/OR GATE PER ARCHITECTURAL PLANS.
- © CONTRACTOR SHALL CONSTRUCT BUILDING PER ARCHITECTURAL PLANS AND SPECIFICATIONS.
- G CONTRACTOR SHALL INSTALL 6" LANDSCAPE MOW STRIP PER DETAIL 9 ON SHEET C1.4.
- (H) CONTRACTOR SHALL CONSTRUCT ACCESSIBLE PARKING STALLS AND UNLOADING AREAS WITH A MAXIMUM 2% SLOPE IN ALL DIRECTIONS.
- ONTRACTOR SHALL SWALE AND GRADE LANDSCAPE AREA IN SUCH A WAY THAT NO PONDING WILL OCCUR. CONTRACTOR SHALL GRADE LANDSCAPE AREAS SO THAT ALL RUNOFF IS COLLECTED IN THE STORM DRAIN SYSTEM. ALL LANDSCAPE AREAS THAT ABUT ANY PORTION OF THE BUILDING SHALL BE A MINIMUM OF EIGHT INCHES (8") BELOW FINISHED FLOOR OF THE ABUTTING BUILDING AND IN NO CASE SHALL THE LANDSCAPE AREA BE GRADED OR LANDSCAPED SUCH THAT WATER DRAINS TOWARD THE BUILDING.
- RIOR TO CONSTRUCTING ANY CONCRETE OR PAVEMENT THE CONTRACTOR SHALL VERIFY THE FINISH FLOOR ELEVATIONS AT ALL DOORS. CONTRACTOR SHALL HOLD FIELD VERIFIED FINISH FLOOR GRADES, ACCOUNT FOR DOOR THRESHOLDS, AND ADJUST GRADES AS NECESSARY TO STAY IN COMPLIANCE WITH CURRENT ACCESSIBLE STANDARDS. CONTRACTOR SHALL NOTIFY NORTHSTAR ENGINEERING IMMEDIATELY IF ANY GRADE ADJUSTMENTS WILL CREATE ANY ACCESSIBILITY ISSUES. SEE DETAIL 2 ON SHEET C1.4.
- LIMITS OF 6:1 FILL SLOPE. CONTRACTOR SHALL REFER TO LANDSCAPE ARCHITECTURAL PLANS FOR PLANTING AND IRRIGATION.

COPYRIGHT © 2024 NORTHSTAR ENGINEERING GROUP, INC









KEY NOTES

SEE TOPOGRAPHIC AND DEMOLITION SHEETS C2.1-C2.2 FOR ADDITIONAL REMOVAL, REPLACEMENT AND PROTECTION NOTES.

SAWCUT AND REMOVE EXISTING PAVEMENT, CONCRETE, AND OR CURB AS REQUIRED PER THESE PLANS. CONTRACTOR MAY NEED TO FIELD ADJUST SAWCUT LINE TO REMOVE THE PAVEMENT OR CONCRETE SECTION AT A CLEAN EDGE OR NEAREST JOINT BASED ON FIELD CONDITIONS. WHILE MAINTAINING ACCESSIBLE TRANSITION TO PROVIDE COMPLIANCE WITH ACCESSIBILITY STANDARDS, WHERE APPLICABLE. LAP JOINT PER DETAIL 8 ON SHEET C1.4 SHALL APPLY TO ALL SAWCUT LOCATIONS ALONG AC PAVEMENT, UNLESS OTHERWISE NOTED. CONTRACTOR SHALL INSTALL DOWELS AT ALL CONNECTIONS BETWEEN EXISTING AND PROPOSED CONCRETE PER DETAIL 1 ON SHEET C1.4. CONTRACTOR SHALL INSTALL THICKENED EDGE AT ALL CONNECTIONS BETWEEN PAVEMENT AND PROPOSED CONCRETE PER DETAIL 6 ON SHEET C1.4.

- B ACCESSIBLE PATH OF TRAVEL NOT TO EXCEED 5.0% MAX RUNNING SLOPE AND 2.0% MAX CROSS SLOPE. ACCESSIBLE PATH OF TRAVEL DETERMINATION, ACCESSIBILITY AND SIGNAGE SHALL BE DETERMINED BY ARCHITECTURAL AND LANDSCAPE PLANS. SEE ARCHITECTURAL AND LANDSCAPE PLANS FOR DIMENSIONS AND DETAILS, INCLUDING HANDRAILS, WHERE APPLICABLE.
- CONTRACTOR SHALL INSTALL CONCRETE WHEEL STOPS PER DETAIL 5 ON SHEET C1.4.
- © CONTRACTOR SHALL INSTALL TRUNCATED DOMES PER ARCHITECTURAL PLANS AND
- © CONTRACTOR SHALL INSTALL FENCE AND/OR GATE PER ARCHITECTURAL PLANS.
- $\begin{tabular}{ll} \hline \textbf{CONTRACTOR SHALL CONSTRUCT BUILDING PER ARCHITECTURAL PLANS AND SPECIFICATIONS.} \\ \hline \end{tabular}$
- G CONTRACTOR SHALL INSTALL 6" LANDSCAPE MOW STRIP PER DETAIL 9 ON SHEET C1.4.
- CONTRACTOR SHALL CONSTRUCT ACCESSIBLE PARKING STALLS AND UNLOADING AREAS WITH A MAXIMUM 2% SLOPE IN ALL DIRECTIONS.
- CONTRACTOR SHALL SWALE AND GRADE LANDSCAPE AREA IN SUCH A WAY THAT NO PONDING WILL OCCUR. CONTRACTOR SHALL GRADE LANDSCAPE AREAS SO THAT ALL RUNOFF IS COLLECTED IN THE STORM DRAIN SYSTEM. ALL LANDSCAPE AREAS THAT ABUT ANY PORTION OF THE BUILDING SHALL BE A MINIMUM OF EIGHT INCHES (8") BELOW FINISHED FLOOR OF THE ABUTTING BUILDING AND IN NO CASE SHALL THE LANDSCAPE AREA BE GRADED OR LANDSCAPED SUCH THAT WATER DRAINS TOWARD THE BUILDING.
- PRIOR TO CONSTRUCTING ANY CONCRETE OR PAVEMENT THE CONTRACTOR SHALL VERIFY THE FINISH FLOOR ELEVATIONS AT ALL DOORS. CONTRACTOR SHALL HOLD FIELD VERIFIED FINISH FLOOR GRADES, ACCOUNT FOR DOOR THRESHOLDS, AND ADJUST GRADES AS NECESSARY TO STAY IN COMPLIANCE WITH CURRENT ACCESSIBLE STANDARDS. CONTRACTOR SHALL NOTIFY NORTHSTAR ENGINEERING IMMEDIATELY IF ANY GRADE ADJUSTMENTS WILL CREATE ANY ACCESSIBILITY ISSUES. SEE DETAIL 2 ON SHEET C1.4.
- LIMITS OF 6:1 FILL SLOPE. CONTRACTOR SHALL REFER TO LANDSCAPE ARCHITECTURAL PLANS FOR PLANTING AND IRRIGATION.

COPYRIGHT © $\underline{2024}$ NORTHSTAR ENGINEERING GROUP, INC

IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT APP: 02-122764 INC:

REVIEWED FOR

DATE: 12/18/2024

SS 🗹 FLS 🗹 ACS 🗹

Teter, Inc. expressly reserves its common law copyright and other property rights in these plans. This document, the ideas and designs in corporated herein, as an instrument of professional service, is not to be used in whole or in part, for any other project without



FRESNO HEADQUARTERS
VISALIA | BAKERSFIELD | MODESTO | SAN LUIS OBISPO



CALIFORNIA


MENIAK.

CIVIL IMPROVEME PULLIAM ELE SCHOOL STOCKTON,

PROJECT NO.

23-12901

DRAWING







SEE TOPOGRAPHIC AND DEMOLITION SHEETS C2.1-C2.2 FOR ADDITIONAL REMOVAL, REPLACEMENT AND PROTECTION NOTES.

A CONTRACTOR SHALL *USE EXTREME CAUTION* THROUGHOUT THE COURSE OF CONSTRUCTION AS TO AVOID EXISTING UNDERGROUND LINES AND STRUCTURES THAT MAY CONFLICT WITH PROPOSED

B CONTRACTOR SHALL EXCAVATE EXISTING SEWER LINE TO VERIFY THE HORIZONTAL AND VERTICAL ALIGNMENT PRIOR TO THE INSTALLATION OF THE SEWER SYSTEM. CONTRACTOR SHALL INFORM THE ENGINEER IF THE ALIGNMENTS ARE DIFFERENT THAN SHOWN. CONTRACTOR SHALL CONNECT TO EXISTING SEWER SYSTEM PER CITY OF STOCKTON STANDARDS AND SPECIFICATIONS WITH APPROPRIATE FITTINGS. CONTRACTOR SHOULD BE AWARE THAT IN THE CASE OF A DISCREPANCY BETWEEN THE DESIGN SHOWN ON THESE PLANS AND THE LOCATION AND DEPTH OF THE EXISTING SYSTEM A LIFT STATION WITH ASSOCIATED STRUCTURES, PUMPING EQUIPMENT, AND ELECTRICAL WORK MAY BE REQUIRED.

USE EXTREME CAUTION TO AVOID UNDERGROUND UTILITIES WHEN INSTALLING FOOTINGS FOR WALLS, FENCES OR ARCHITECTURAL AMENITIES AT ALL UTILITY WALL/FENCE/AMENITY CROSSINGS.

ONTRACTOR SHALL INSTALL DRINKING FOUNTAIN PER ARCHITECTURAL PLANS AND

SPECIFICATIONS.

© CONTRACTOR SHALL INSTALL SEWER CLEANOUT PER DETAIL 3 ON SHEET C1.4.

PROPOSED DOMESTIC WATER WITH SHUT OFF VALVE TO BE STUBBED 5 FEET FROM THE FACE OF THE BUILDING. CONTRACTOR SHALL VERIFY THE LOCATIONS OF THE UTILITY CONNECTIONS WITH THE PLUMBING PLANS PRIOR TO CONSTRUCTION OF PROPOSED STUBS.

G CONTRACTOR SHALL INSTALL SEWER CLEANOUT PER DETAIL 3 ON SHEET C1.4 WITH APPROPRIATE FITTINGS AND REDUCER. CONTRACTOR SHALL VERIFY THE LOCATIONS OF THE UTILITY CONNECTIONS WITH THE PLUMBING PLANS PRIOR TO CONSTRUCTION OF PROPOSED STUBS AND STUB 5 FEET FROM THE FACE OF THE BUILDING.

HO CONTRACTOR SHALL CONNECT TO EXISTING DOMESTIC WATER LINE PER CITY OF STOCKTON DETAIL W-3 STANDARDS AND SPECIFICATIONS. CONTRACTOR SHALL EXCAVATE EXISTING WATER LINE TO VERIFY THE HORIZONTAL AND VERTICAL ALIGNMENT PRIOR TO THE INSTALLATION OF THE PROPOSED WATER PIPE. CONTRACTOR SHALL INFORM THE ENGINEER IF THE ALIGNMENTS ARE DIFFERENT THAN SHOWN.

ONTRACTOR SHALL INSTALL WATER PIPES WITH SUFFICIENT ENOUGH DEPTH TO MAINTAIN 1' MINIMUM VERTICAL CLEARANCE FORM OUTSIDE DIAMETER OF PIPES AND COMPLY WITH THE MOST CURRENT STATE HEALTH CODE AND THE CALIFORNIA BUILDING AND PLUMBING CODE STANDARDS. CONTRACTOR SHALL DEEPEN WATER PIPES AS NECESSARY AND USE EXTREME CAUTION WHEN PLACING THRUST BLOCKS AS TO AVOID CONFLICTS WITH OTHER UTILITY PIPES. CONTRACTOR SHALL INSTALL REDUCERS AS REQUIRED. WATER VALVES SHALL BE INSTALLED ON 4" WATER PIPES OR LARGER AND BALL VALVES/CORP STOPS SHOULD BE INSTALLED ON 3" WATER PIPES OR SMALLER. THRUST BLOCKS SHALL BE INSTALLED AT FIRE HYDRANTS, BLOW-OFFS, TEES, CAPS, BENDS, ENDS, AND CHANGES IN SIZE AND/OR DIRECTION. WATER SEPARATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION 720.0 AND TABLE 7-7 OF THE CALIFORNIA PLUMBING CODE. SEE CITY OF STOCKTON STANDARD DETAIL S-4 FOR CALIFORNIA HEALTH DEPARTMENT REQUIREMENTS, DETAIL W-12 FOR THRUST BLOCK DETAILS AND SPECIFICATIONS.

CONTRACTOR SHALL INSTALL STORM DRAIN INLET PER ARCHITECTURAL PLANS AND SPECIFICATIONS.

CONTRACTOR SHALL INSTALL STORM DRAIN DRYWELL PER ARCHITECTURAL PLANS AND

COPYRIGHT © 2024 NORTHSTAR ENGINEERING GROUP, INC

IDENTIFICATION STAM DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR

SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024






OVEMENT PLANS FELEMENTARY

CIVIL IMPROV PULLIAM E SCHOOL STOCKTON,

PROJECT NO.

23-12901

DRAWING







LEGEND




-XXXXXXXXXX


INLET PROTECTION (SEE DETAILS "A", "B", C, AND "D") SHALL BE PLACED AROUND ALL CATCH BASINS WITHIN THE PROJECT DRAINAGE LIMITS; INCLUDING BUT NOT LIMITED TO ALL LANDSCAPE DRAINAGE. ALSO, INLET PROTECTION SHALL BE PLACED AT THE FIRST INLET DOWNSTREAM FROM THE PROJECT SITE (ON EITHER

CONCRETE WASHOUT AREA (SEE DETAIL "F")

STRAW WATTLE (SEE DETAIL "E") TO BE PLACED AT ALL LOCATIONS SHOWN. STRAW WATTLES SHALL ALSO BE PLACED AT THE FRONT OF ANY LOT WHERE AN UNDERCUT IS NOT PRESENT.

TEMPORARY STABILIZED CONSTRUCTION ENTRANCE (SEE DETAIL "G") TO BE DETERMINED BY CONTRACTOR IN FIELD.





IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT

REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹

APP: 02-122764 INC:

DATE: 12/18/2024





23-12901

PROJECT NO.

DRAWING

COPYRIGHT © 2024 NORTHSTAR ENGINEERING GROUP, INC





EROSION CONTROL NOTES

THESE PLANS DEPICT APPROPRIATE MEASURES TO CONTROL EROSION ON THE SITE TO BE GRADED AS SHOWN ON THE PLANS THE NATIVE VEGETATION WILL BE REMOVED ONLY FROM THOSE AREAS TO BE GRADED. AREAS OUTSIDE OF AND DOWNSLOPE OF THE LIMITS OF GRADING WILL BE PROTECTED FROM SILT LADEN RUNOFF BY PERIMETER SILT FENCES AS DEPICTED ON THIS PLAN. SLOPED AREAS WHICH HAVE BEEN STRIPPED OF VEGETATION AND NEW SLOPES OVER FOUR FEET HIGH CREATED DURING THE GRADING OPERATION WILL BE TRACKWALKED & HYDROSEEDED.

- ALL EROSION SEDIMENT STRUCTURES SHALL BE INSPECTED AFTER EACH RAINSTORM AND SHALL BE CLEANED OUT AS
- A STABILIZED CONSTRUCTION ENTRANCE SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF GRADING. THE LOCATION IS SHOWN ON THESE PLANS. ALL CONSTRUCTION TRAFFIC ENTERING THE PAVED ROAD MUST CROSS THE ENTRANCE.

THE CONTRACTOR IS RESPONSIBLE FOR ALL ASPECTS OF EROSION CONTROL FOR THE LIFE OF THE PROJECT AND SHALL INSTALL AND MAINTAIN ANY DEVICES AND MEASURES NECESSARY TO THE SATISFACTION OF THE CITY ENGINEER, DURING CONSTRUCTION ACTIVITIES.

- TO MINIMIZE EROSION OF GRADED BANKS, ALL GRADED BANKS AND STOCKPILE AREAS SHALL BE HYDROSEEDED, LANDSCAPED
- STRAW BALES, PIECES OF WOOD, FABRIC OR OTHER SUITABLE MATERIALS SHALL BE USED TO PREVENT SEDIMENT LADEN RUNOFF FROM ENTERING ANY COMPLETED STORM DRAIN INLETS. THESE PROTECTION MEASURES SHALL BE MAINTAINED UNTIL

WHEN TEMPORARY STRUCTURES HAVE SERVED THEIR INTENDED PURPOSE AND THE CONTRIBUTING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED. THE EMBANKMENT AND RESULTING SEDIMENT DEPOSITS ARE TO BE LEVELED OR OTHERWISE DISPOSED OF BY THE CONTRACTOR AS RECOMMENDED BY THE SOILS ENGINEER.


- GRADED AREAS MUST DRAIN AWAY FROM THE FACE OF SLOPES AT THE CONCLUSION OF EACH WORKING DAY. DRAINAGE SHALL BE DIRECTED TOWARDS DRAINAGE INLETS.
- TEMPORARY EROSION CONTROL DEVICES SHOWN ON THIS PLAN WHICH INTERFERE WITH THE WORK SHALL BE RELOCATED OR MODIFIED AS AND WHEN THE INSPECTOR SO DIRECTS AS THE WORK PROGRESSES.
- ALL LOOSE SOIL AND DEBRIS SHALL BE REMOVED FROM THE STREET AREAS UPON STARTING OPERATIONS AND PERIODICALLY THEREAFTER AS DIRECTED BY THE INSPECTOR.
- HYDROMULCHING OF SLOPES OVER 5' IN HEIGHT SHALL BE COMPLETED BETWEEN SEPTEMBER 1 AND OCTOBER 1 OF THE YEAR IN WHICH THEY ARE CONSTRUCTED OR IMMEDIATELY AFTER THEIR CONSTRUCTION IF THEY ARE COMPLETED AFTER OCTOBER 1ST. APPLICATION RATES SHALL BE AS FOLLOWS AS REQUIRED BY CITY OF STOCKTON:

| HYDROSEED MIX: | | | | |
|--|---------------------------|---------------|--------------------|-------------|
| BOTANICAL NAME | (COMMON NAME) | MIN. % PURITY | MIN. % GERMINATION | LB/ACRE |
| ARISTIDA TERNIPES VAR. HAMULOSA | (THREE-AWN) | 90% | 85% | 2 |
| BROMUS CARINATUS | (CALIFORNIA BROME) | 90% | 85% | 2 |
| ELYMUS GLAUCUS | (BLUE WILD RYE) | 90% | 85% | 4 |
| ELYMUS TRACHYCAULUS SSP. TRACHYCAULUS | (SLENDER WHEATGRASS) | 90% | 85% | 3 |
| MELICA CALIFORNICA | (CALIFORNIA ONION GRASS) | 90% | 85% | 2 |
| MUHLENBERGIA RIGENS | (DEER GRASS) | 90% | 85% | 4 |
| NASSELLA LEPIDA | (FOOTHILL NEEDLEGRASS) | 90% | 85% | 6 |
| TRIFOLIUM HIRTUM | ('HYKON' ROSE CLOVER) | 90% | 85% | 10 |
| CELLULOSE FIBER MULCH | | | | 2000 |
| ORGANIC BINDER WITH HYDROSEED SLUF | RRY | | | 50 |
| 16-20-O-S FERTILIZER | | | | 300 |
| WHEN DIDECTED BY THE INCRECTOR A 40 L | NOU DEDM OUALL DE MAINITA | | | 1005 511 10 |


- WHEN DIRECTED BY THE INSPECTOR, A 12-INCH BERM SHALL BE MAINTAINED ALONG THE TOP OF THE SLOPE OF THOSE FILLS ON WHICH GRADING IS NOT IN PROGRESS.
- 13. STAND-BY CREWS SHALL BE ALERTED BY THE PERMITTEE OR CONTRACTOR FOR EMERGENCY WORK DURING RAINSTORMS.
- SEWER OR STORM DRAIN TRENCHES THAT DRAIN THROUGH BASIN DIKES SHALL BE PLUGGED WITH SANDBAGS FROM TOP OF
- ALL UTILITY TRENCHES SHALL BE BLOCKED WHEN DIRECTED BY THE DESIGN ENGINEER AT THE PRESCRIBED INTERVALS FROM THE BOTTOM TO TOP WITH DOUBLE ROW OF SANDBAGS PRIOR TO BACKFILL. SANDBAGS ARE TO BE PLACED WITH ALTERNATE HEADER AND STRETCHER COURSES. THE INTERVALS PRESCRIBED BETWEEN SANDBAG BLOCKING SHALL DEPEND ON THE SLOPE OF THE GROUND SURFACE, BUT NOT TO EXCEED THE FOLLOWING:

| GRADE OF GROUND SURFACE OR STREET LESS THAN 2% 2% TO 4% 4% TO 10% | INTERVAL AS REQUIRE 100 FEET 50 FEET |
|--|---|
| OVER 10% | 25 FEET |
| | |

- PROVIDE VELOCITY CHECK DAMS IN ALL UNPAVED STREET AREAS AT THE INTERVALS INDICATED ABOVE. VELOCITY CHECK DAMS MAY BE CONSTRUCTED OF SANDBAGS, TIMBER, OR OTHER EROSION RESISTANT MATERIALS APPROVED BY THE INSPECTOR, AND SHALL EXTEND COMPLETELY ACROSS THE STREET OR CHANNEL AT RIGHT ANGLES TO THE CENTERLINE. EARTH DIKES MAY NOT
- AFTER SEWER AND UTILITY TRENCHES ARE BACKFILLED AND COMPACTED, THE SURFACES OVER SUCH TRENCHES SHALL BE MOUNDED SLIGHTLY TO PREVENT CHANNELING OF WATER IN THE TRENCH AREA. CARE SHOULD BE EXERCISED TO PROVIDE FOR CROSS-FLOW AT FREQUENT INTERVALS WHERE TRENCHES ARE NOT ON THE CENTERLINE OF A CROWNED STREET. REMOVE ALL CHECK DAMS PRIOR TO BACKFILL
- TO CONTROL SEDIMENT ENTERING FIELD INLETS, PLACE TWO STRAW BALES IN THE CONCRETE V-DITCH AT THE SIDE OPENING OF THE FIELD INLET AT THE LOCATIONS SHOWN ON THIS PLAN.
- EXCEPT AS OTHERWISE DIRECTED BY THE INSPECTOR, ALL DEVICES SHOWN SHALL BE IN PLACE AT THE END OF EACH WORKING DAY OR WHEN DIRECTED BY THE INSPECTOR.
- 20. ALL BASINS AND CHECK DAMS SHALL HAVE BEEN PUMPED DRY, AND ALL DEBRIS AND SILT REMOVED WITHIN 24 HOURS AFTER
- SANDBAGS SHALL BE STOCKPILED ON-SITE, READY TO BE PLACED IN POSITION WHEN RAIN FORECAST IS 40% CHANCE OR
- 2. EXPOSED SLOPES SHALL BE PROTECTED BY VEGETATION COVER OR FABRIC COVER AS APPROVED BY THE CITY ENGINEER.
- $_{
 m IS}$. WHEN PAD ELEVATION OF ADJACENT LOTS OR ELEVATION BETWEEN STREET AND LOT ARE SEPARATED BY MORE THAN 6 FEET, A MINIMUM 12" BERM SHALL BE MAINTAINED ALONG THE PROPERTY LINE SEPARATING THE LOTS, AND THE BERM SHALL DIRECT THE WATER TO THE OUTLET. VELOCITY CHECK DAMS SHALL BE INSTALLED BETWEEN THE OUTLET ON THE LOT AND THE STREET.
- 4. ALL EROSION CONTROL MEASURES SHALL BE IN COMPLIANCE WITH THE LATEST EDITION OF THE CASQA STORMWATER MANAGEMENT HANDBOOK.
- 25. ALL FINISHED PADS SHALL BE PROTECTED.
- 26. THE FOLLOWING PLANS ARE ACCURATE FOR EROSION CONTROL PURPOSES ONLY.
- THE INFORMATION ON THIS PLAN IS INTENDED TO BE USED AS A GUIDELINE FOR THE CONTRACTOR AND SUBCONTRACTORS TO COMPLY WITH THE REQUIREMENTS OF THE STATE WATER RESOURCES CONTROL BOARD. FIELD CONDITIONS MAY NECESSITATE MODIFICATIONS TO THIS PLAN.
- 28. NO ONSITE FUELING SHALL TAKE PLACE.
- 29. SEAL OR SKIRT BETWEEN TRAILER & GRADING TO PREVENT EXPOSURE TO DRAIN.
- STRAW WATTLES INSTALLED ON A SLOPE SHALL CONFORM TO THE GUIDELINES SPECIFIED BY THE UNITED STATES ENVIRONMENTAL PROTECTION AGENCY NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM BEST MANAGEMENT
- . EROSION RESISTANT VEGETATION SHOULD BE MAINTAINED ON THE FACE OF ALL SLOPES.
- CONTRACTOR SHALL REFER TO THE PROJECT STORM WATER POLLUTION PLAN (SWPPP) FOR ALL PRE AND POST CONSTRUCTION EROSION CONTROL MEASURES AND BEST MANAGEMENT PRACTICES (BMPs).
- 33. ALL BASINS SHALL BE HYDROSEEDED IN ACCORDANCE TO THE PROJECT SWPPP.
- 34. CONTRACTOR SHALL INSTALL DRAIN INLET PROTECTION FOR ALL CATCH BASINS LOCATED IN THE VICINITY OF WORK. THIS INCLUDES ANY CATCH BASINS LOCATED IN THE PUBLIC RIGHT-OF-WAY, AS WELL AS ANY ONSITE CATCH BASINS.
- i. CONTRACTOR SHALL ENSURE THAT CONSTRUCTION ACTIVITIES DO NOT DEPOSIT SEDIMENT ON TO THE PUBLIC ROADWAY, SIDEWALKS AND GUTTERS.
- i. CONTRACTOR SHALL USE STREET SWEEPING OR OTHER DRY SWEEPING METHODS, AS NECESSARY, TO REMOVE CONSTRUCTION RELATED SEDIMENT FROM PAVEMENT IN THE PROJECT AREA AND PROJECT ROADWAY.
- CONTRACTOR SHALL SCHEDULE WORK FOR DRY WEATHER DAYS WHEN NO RAIN IS IN THE IMMEDIATE FORECAST.



TYPICAL PROTECTION FOR INLET ON SUMP



- 1. INTENDED FOR SHORT-TERM USE.
- 2. USE TO INHIBIT NON-STORM WATER FLOW.
- 3. ALLOW FOR PROPER MAINTENANCE AND CLEAN UP.
- 4. BAGS MUST BE REMOVED AFTER ADJACENT OPERATION IS COMPLETED. 5. NOT APPLICABLE IN AREAS WITH HIGH SILTS AND CLAYS WITHOUT FILTER FABRIC.


DI PROTECTION TYPE 3 - GRAVEL BAG

THE GRAVEL BAG BARRIER (TYPE 3) IS SHOWN IN THE FIGURES. FLOW FROM A SEVERE STORM SHOULD NOT OVERTOP THE CURB. IN AREAS OF HIGH CLAY AND SILTS, USE FILTER FABRIC AND GRAVEL AS ADDITIONAL FILTER MEDIA. GRAVEL BAGS SHOULD BE USED DUE TO THEIR HIGH PERMEABILITY.


- 1. USE SAND BAG MADE OF GEOTEXTILE FABRIC (NOT BURLAP) AND FILL WITH 0.75 IN.
- CONSTRUCT ON GENTLY SLOPING STREET.
- 3. LEAVE ROOM UPSTREAM OF BARRIER FOR WATER TO POND AND SEDIMENT TO
- 4. PLACE SEVERAL LAYERS OF SAND BAGS OVERLAPPING THE BAGS AND PACKING
- THEM TIGHTLY TOGETHER. 5. LEAVE GAP OF ONE BAG ON THE TOP ROW TO SERVE AS A SPILLWAY. FLOW FROM A
- SEVERE STORM (E.G., 10 YEAR STORM) SHOULD NOT OVERTOP THE CURB. 6. THIS DETAIL IS TO BE USED ON EXISTING STREETS WHERE SILTED FLOW IS TO BE INTERCEPTED (CAUGHT) PRIOR TO ENTERING THE STORM DRAIN SYSTEM. SANDBAGS CAN ALSO BE USED WHEN THE ROUGH GRADED STREETS HAVE POURED INPLACE CONCRETE SURROUNDING THE INLET TO CREATE A "FLOW LINE"

WHERE A DAM CAN BE ACHIEVED TO PROTECT THE STORM SYSTEM FROM THE

INFLOW OF SEDIMENT. C DI PROTECTION - TYPE 3








STRAW WATTLE DIKE CONSTRUCTION SPECIFICATIONS

WATTLES SHALL BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING

EACH WATTLE SHALL BE EMBEDDED IN THE SOIL A MINIMUM OF 4 INCHES. WATTLES SHALL BE SECURELY ANCHORED IN PLACE BY TWO STAKES OR REBARS DRIVEN THROUGH THE WATTLES. THE FIRST STAKE IN EACH WATTLE SHALL BE DRIVEN TOWARD THE

THEIR PURPOSE SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

PREVIOUSLY LAID WATTLE TO FORCE THE WATTLES TOGETHER. THE DIKE SHALL BE INSPECTED AFTER EACH STORM, AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED. THE WATTLES SHALL BE REMOVED ONCE THEY HAVE SERVED





- 1. FACE SIGN TOWARD NEAREST STREET OR ACCESS POINT. 2. CONCRETE WASHOUT SHALL BE LOCATED BEHIND THE CURB AND
- 50 FEET MINIMUM FROM DRAINAGE INLETS OR WATERCOURSES.
- 3. CONTRACTOR SHALL CONDUCT ALL CONCRETE WASHOUT OFF-SITE











CORRUGATED


STEEL PANELS

WIDTH AS REQUIRED

TO ACCOMMODATE

ANTICIPATED TRAFFIC

CONCRETE WASHOUT



- CRUSHED AGGREGATE GREATER THAN 3" BUT SMALLER TAPER EDGES-3% OR FLATTER AT 1:1 SLOPE 12" MIN, UNLESS OTHERWISE. - ORIGINAL GRADE SPECIFIED BY A SOILS ENGINEER

 CORRUGATED STEEL PANELS CRUSHED AGGREGATE-GREATER THAN 3" BUT SMALLER FABRIC FILTER 12" MIN, UNLESS OTHERWISE SPECIFIED BY A SOILS ENGINEER **SECTION B-B**

AND CHANNELIZE RUNOFF TO SEDIMENT TRAPPING DEVICE

SECTION A-A

TEMPORARY STABILIZED CONSTRUCTION ENTRANCE

DESIGN AND CONSTRUCTION SPECIFICATIONS:

- 1. THE TEMPORARY STABILIZED CONSTRUCTION ENTRANCE SHALL BE CONSTRUCTED IN STRICT ACCORDANCE WITH THE PLANS AND SPECIFICATIONS OF LATEST EDITION OF THE CALIFORNIA STORMWATER HANDBOOK, DETAIL TC-1. WHERE THERE IS A DISCREPANCY BETWEEN THIS DETAIL AND THE CALIFORNIA STORMWATER HANDBOOK, THE HANDBOOK SHALL GOVERN.
- 2. CONTRACTOR SHALL CONSTRUCT A STABILIZED CONSTRUCTION ENTRANCE AT EACH ENTRANCE TO THE PROJECT SITE AND SHALL BE CONSTRUCTED ON
- THE MATERIAL FOR CONSTRUCTION OF THE PAD SHALL BE 3 TO 6 INCH DIA. STONE. THE THICKNESS FOR THE PAD SHALL NOT BE LESS THAN 12 INCHES OR AS RECOMMENDED BY SOILS ENGINEER.

AND CHANNELIZE RUNOFF TO


SEDIMENT TRAPPING DEVICE


- THE WIDTH OF THE PAD SHALL NOT BE LESS THAN 30' OR THE FULL WIDTH OF ALL POINTS OF INGRESS OR EGRESS, WHICHEVER IS GREATER.
- THE LENGTH OF THE PAD SHALL BE AS REQUIRED, BUT NOT LESS THAN 50 FEET. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAY. THIS MAY
- REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND, AND REPAIR AND/OR CLEAN OUT ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHT-OF-WAY SHALL BE REMOVED IMMEDIATELY. 8. WHEN NECESSARY, WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY. WHEN WASHING IS REQUIRED, IT
- SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP, SEDIMENT BASIN, OR SEDIMENT SWALE. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH, OR WATERCOURSE THROUGH USE OF GRAVEL BAGS, GRAVEL, BOARDS, OR OTHER APPROVED METHODS
- 9. CONTRACTOR TO REMOVE AND DISPOSE OF STABILIZED CONSTRUCTION ENTRANCE UPON COMPLETION OF CONSTRUCTION. 10. CONSTRUCTION AND MAINTENANCE SHALL BE IN ACCORDANCE WITH THE 2003 CALIFORNIA STORMWATER BMP HANDBOOK.

G3 TEMPORARY STABILIZED CONSTRUCTION ENTRANCE

COPYRIGHT © 2024 NORTHSTAR ENGINEERING GROUP, INC

IDENTIFICATION STAME DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹







PROJECT NO.

23-12901

S P S



Sam Harned Landscape Architect PO Box 2275 Oakdale, CA 95361 209-380-7376 www.harnedla.com

IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024


LANDSCAPE DEMOLITION LEGEND

Existing turf and landscape areas to remain. Preserve and protect in place. Do not not store materials, and do not park or drive vehicles in this area. Maintain existing irrigation in operable condition throughout duration of the Work of this project.

Restore or replace planting and turf areas that are damaged as part of the Work of this project. All areas of repair shall be repaired to the same level as turf area renovation (see Planting Plan), and to the satisfaction of the District. This includes utility trenches or other similar distrubances that may occur on the campus as part of the course of Work for this Project, but that may not be shown on these landscape plans.

In areas needing repair, Contractor shall grade damaged areas as needed to return to existing conditions and to coordinate with any proposed grading associated with this project. Any fill required shall be of a suitable quality for the purpose. Planting shall be restored with existing species. Plant maintenance for repaired areas shall be included with the plant maintenance component of the proposed work. Irrigation that is damaged shall be replaced in kind for model and manufacturer.

Area of turf renovation. See Planting Plan for work in this area.




Existing landscape to be removed.


Turf Areas: Provide min. (3) applications of approved herbicide to kill turf; applications to be minimum (1) week apart. Once turf is dead, remove turf down through root zone at a minimum. Coordinate with the work of other consultant's plans associated with this project for other Work that may be required in this area. Verify limit of demolition with District and Architect prior to start of work.

Landscape Areas: Remove all shrubs, ground cover and trees. Remove root balls and roots to a minimum 24" below grade. Fill holes or depressed areas with suitable fill and return to uniform graded level.

Contractor to remove and dispose of all debris associated with this demolition, unless otherwise approved by







0.45

4,684 sf

4,684 sf

142,590 gal/yr

49.1 in/yr 0.62



Sam Harned Landscape Architect PO Box 2275 Oakdale, CA 95361 209-380-7376 www.harnedla.com

IDENTIFICATION STAME DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024

IRRIGATION SCHEDULE

| SYMBOL | MANUFACTURER/MODEL/DESCRIPTION | <u>PSI</u> | <u>GPM</u> | RADIUS | DETAIL |
|------------|--|------------|------------|--------|---------------|
| 2 5 | Rain Bird 5006-PL-PC-SAM-R-SS-MPR 25 Turf Rotor, 6in. Pop-Up, Stainless Steel Riser, with Flow Shut-Off Device. Matched Precipitation Rotor (MPR Nozzle), Arc and Radius as per Symbol. 25 ft=red, 30 ft=green, 35ft=beige. With Seal-A-Matic Check Valve, and In-Stem Pressure Regulator. | 25 | | 21' | 8/L4 |
| 30) | Rain Bird 5006-PL-PC-SAM-R-SS-MPR 30 Turf Rotor, 6in. Pop-Up, Stainless Steel Riser, with Flow Shut-Off Device. Matched Precipitation Rotor (MPR Nozzle), Arc and Radius as per Symbol. 25 ft=red, 30 ft=green, 35ft=beige. With Seal-A-Matic Check Valve, and In-Stem Pressure Regulator. | 25 | | 26' | 8/L4 |
| 35) | Rain Bird 5006-PL-PC-SAM-R-SS-MPR 35 Turf Rotor, 6in. Pop-Up, Stainless Steel Riser, with Flow Shut-Off Device. Matched Precipitation Rotor (MPR Nozzle), Arc and Radius as per Symbol. 25 ft=red, 30 ft=green, 35ft=beige. With Seal-A-Matic Check Valve, and In-Stem Pressure Regulator. | 25 | | 29' | 8/L4 |
| SYMBOL | MANUFACTURER/MODEL/DESCRIPTION | | | | <u>DETAIL</u> |
| | Rain Bird PESB-PRS-D Plastic Industrial Remote Control Valve. Low Flow Operating Capability, Globe Configuration. With Pressure Regulating Module, and Scrubber Technology, size per plan. | | | | 7/L4 |
| × | Nibco T-113 Class 125 bronze gate shut off valve with wheel handle, same size as mainline pipe diameter at valve location. | | | | 6/L4 |
| С | Rain Bird ESP4ME3 Controller, outdoor model, provide expansion modules for required number of stations. Include options to work with remote control. Provide and connect to electrical supply. Final location determined in field with Owner's representative or Architect. | | | | 5/L4 |
| (L) | Rain Bird LNK2WIFI Upgrades controllers (ESP-M, ESP-RZXe, ST8) to Have Weather Data for ET-Based Adjustments (WaterSense Approved) & WiFi Capabilities - | | | | |
| POC T | Point of Connection 3" Existing main line. Connect at existing valve box. Install new gate valve and extend 3" main line to new valve bank. | | | | |
| | Irrigation Lateral Line: PVC Schedule 40 | | | | 1/L5 |
| | Irrigation Mainline: 3" PVC Schedule 40 | | | | 1/L5 |
| ======= | Pipe Sleeve: PVC Class 200 SDR 21 Install dbl. 3" (min.) sleeves at each location on the plan. For pipes 2" and greater install sleeves at twice the diameter of the pipe. | | | | 2/L5 |
| | /alve Callout Valve Number | | | | |
| # • # • | Valve Flow | | | | |
| #" • | Valve Size | | | | |
| TION NOTES | | | | | |

EXISTING IRRIGATION NOTES

- 1. The existing irrigation for this part of the turf area is performed manually. The irrigation design proposed as part of this project is to provide automated irrigation for the new planter areas and directly adjacent to the building. The area outside of this new automated area will continue to be irrigated manually.
- 2. The new irrigation system for this project connects to an existing system. Contractor shall investigate the existing system and verify that it can support the design as shown; contact the landscape architect if found otherwise.
- 3. Modifications may be necessary to the existing system as part of the Work of this project. Contractor shall modify and reconnect all existing zones as required to provide continued water supply to the existing zones and to provide a coordinated and functional irrigation system for the overall site at completion of work.
- 4. The design of these plans is based on the following parameters of the existing system. Confirm and report any discrepancies to landscape architect for further clarification or direction as may be

Pressure: 70 psi

Available Flow: 100 gpm Contractor shall investigate the existing controller to determine if it is functional and feasible for connection of new valves. Report findings to Owner's Representative and landscape architect for final determination and additional direction. Use of existing controller in place of new proposed controller may be an option pending approval by Owner.

IRRIGATION NOTES

- 1. Contractor shall become familiar with the drawings, specifications, and site conditions prior to beginning work. Should conflicting information be found in these documents or between these documents and site conditions, notify the Landscape Architect before proceeding with the work in question.
- 2. All existing utilities, water lines, and fire hydrants shall remain connected and in full continuous operation unless specifically directed otherwise. 2.1. Irrigation backflow prevention device and meter are existing on this project. Verify both are in proper operation, meet current code requirements, and are sufficient for the work of these plans.
- 3. Irrigation plan is diagrammatic. Actual routing of pipe and location of equipment shall be determined based on field conditions and as directed by the Landscape Architect. Install pipe and equipment in landscape areas wherever possible unless specifically noted otherwise. Stake layout of mainline and primary laterals for field review and approval prior to trenching. Field adjust existing irrigation system as necessary.
- 4. Pipe Sizing:
- 4.1. Minimum pipe size shall be 3/4".
- 4.2. Unlabeled pipe segments shall be equal to the size of the segment immediately upstream.
- 4.3. In making adjustments to irrigation zone layouts Contractor shall be responsible to determine pipe sizes as required to deliver water pressure required for each outlet device considering flow rate, elevation changes, length of run, and other factors affecting pressure loss. Maximum flows in various pipe sizes shall not exceed the following guidelines. Flows may may need to be significantly less than the maximums stated below to off-set other
- factors affecting pressure loss: 4.3.1. 3/4": up to 8 gpm. 4.3.2. 1": 8-12 gpm.
- 4.3.3. 1-1/4": 12-22 gpm.
- 4.3.4. 1-1/2": 22-30 gpm. 4.3.5. 2": 30-50 gpm.

- 4.4. Mainline pipe sizes shall not be changed without written approval of the Landscape Architect.
- 4.5. Lateral line pipe runs of lengths greater than the typical distance between outlet devices shall not be made without written approval of the Landscape Architect.
- 5. Do not install the irrigation system as shown on the drawings when it is obvious in the field that obstructions, grade differences or differences in the area dimensions exist that might not have been considered in the engineering. Notify the Landscape Architect of all such conditions immediately upon discovery. In the event this notification is not provided, the Contractor shall assume full responsibility for all revisions necessary in response to field conditions with no additional compensation. 6. Controller(s):
- 6.1. Locate as directed. Extend electrical service to controllers and dedicate one breaker of proper size for each controller. Provide
- one additional duplex outlet at each controller location. 6.2. Electrical service to controllers shall be completed by a licensed electrical contractor in accordance with all applicable codes.

- 7.1. All pipe under existing and proposed paving shall be installed in
- 7.2. Sleeves are shown for contractor's convenience. Contractor shall be responsible to coordinate irrigation sleeve locations and installation with other trades.
- 7.3. Extend all sleeves 18 inches beyond paving, cap and clearly mark by
- approved means to facilitate recovery. 7.4. Install sleeves to accommodate future paving where indicated or as
- may be needed.

completion.

8. Spray Heads and Rotors: 8.1. Install perpendicular to grade unless otherwise noted in plans. 9. Contractor to flush entire system and adjust all delivery devices and

assemblies for complete coverage and reduced over-spray, prior to project

| 1 | Ĕ — | res | Cob | <u> </u> | plan | ide | ince | inst | ser | <u>ء</u> ۔ | any | |
|---|--------|-----|-----|----------|------|-----|------|---------|-------------|---------------|---------------|--|
| | | | | | | | | | DESCRIPTION | | DSA BACKCHECK | |
| | | | | | | | | | DATE | | 11/13/24 | |
| | | | | | | | | | MARK | | | |
| | | | | | AN | DS | CAP | <i></i> | | | | |





PROJECT NO. 23-12901

(SHLA 24-20)

Rehabilitated Landscape Area: 3,500 sf Area of Irrigation Removed: 1,215 sf. Existing Shade Tree in Project Area: Building Roof Shade/Overhang:

PARKING AREA SHADE

The project is not providing any new parking spaces; rather, existing parking stalls will be re-striped. No new parking spaces or parking areas landscape required or provided with this

PROJECT SHADE CALCULATIONS

Calculations provided to show compliance with CBC Section 5.106.12. Tree diameters per species is based on published local municipality documentation or the Sunset Western Garden Book.

| Tree Type | Area at 100% | 100% | | 75% | | 50% | | 25% | | Subtota | l |
|-------------------------------------|-----------------|-------------|--------|------------|----------|--------------|---------|----------------------|------------------|---------|---|
| | (sf) | sf | qty. | sf | qty. | sf | qty. | sf | qty. | | |
| Pistacia chinensis 'Keith Davey' | 962 | 962 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 962 | |
| Existing Shade Tree | 1215 | 1,215 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1,215 | |
| | | | | | | Total s | hade p | provided by | trees: | 2,177 | |
| | | | | | | Sha | ade pro | ovided by bu over | uilding hang: | 268 | |
| | | | | | | | Total | shading pro | vided: | 2,445 | : |
| | | | | Total P | roject A | Area for Lar | ndscap | e and Hard | scape | 8,184 | |
| | | Shading Pro | ovided | at Landsca | pe and | Hardscape | Areas | (min. 20% | req'd) | 30 | |



COMMON NAME SIZE QUANTITY SPACING

Chinese

Pistache

Existing turf and landscape areas to remain. See Landscape Demolition Plan for notes.

Area of turf renovation. Fill low or depressed areas with suitable fill and grade area to drain min. 2% away from buildings and to flow with existing and proposed grading and drainage patterns. Grade to be 1-1/2" below finish

Install new sod turf. Tahoma 31 Bermudagrass by West Coast Turf, or as

Install decomposed granite paving (3/8" max.), minimum 3" depth, compacted.

otherwise approved by District. See Detail 3 /Sheet L4.

LANDSCAPE PLANTING LEGEND

DESCRIPTION

surface at paved areas.

Color: Gray. See Detail 2 / Sheet L4.

SYMBOL

 \vee \vee

Examine site conditions and locate utilities prior to start of work.

2. Confirm all plant quantities. The quantity of symbols on the plan

expense to the Owner.

contractor expense.

Agriculture Code.

the project site. All plant material shall:

Be vigorous and of normal habit of growth.

7.3. Be free of girdling roots, sun scald, abrasions, disease 8. Plants shall equal or exceed the standards as outlined by the

documents.

shall have priority over the quantity provided in the legend. Contractor is responsible for maintaining current condition of

Report any conflicts to Owner or Landscape Architect prior to

starting work. Start of work implies acceptance of site conditions.

existing landscape to remain. Any damage that occurs to landscape

The contractor shall be responsible for the purchasing of all material

after start of work shall be repaired or replaced at no additional

to provide a complete installation per the intent of the contract

to planting. Plant material may be rejected at any time due to

then rejected material shall be replaced by the contractor at

the project has been completely turned over to the owner.

The contractor is responsible for the protection of all material until

Landscape Architect reserves the right to review plant material prior

condition, form, or damage, before or after planting. Installed and

All plant material to be nursery grown in a climate similar to that of

Be pest and disease free, including insects, insect eggs and

American Standards for Nursery Stock and to applicable California

The landscape contractor shall, prior to installation of any plant

material, provide for a Soil Agronomy Report (per WELO) from an

approved soils laboratory that shall include recommendations for

for review and further direction regarding soil amendments and

soil pH, total soluble salts, sodium, and percent organic matter.

10. Prepare the soil by removing all rock and debris larger than 1" from planting areas; legally dispose of materials removed from this

Report, including any additional amendments specified by the

Provided below is a list of minimum amendments that shall be

incorporated into all planting pits and broadcast into soil to depth of

12", by means of a roto-tiller or equal, per 1000 square feet. This

landscape architect, prior to the installation of plant material.

list is provided for Bid purposes and shall be augmented as

recommended by the Soils Agronomy Report.

bark humus

15 lbs. soil sulfur

15 lbs. 15-15-15 fertilizer

4 cyds organic amendment. Cow manure

or nitrogen-treated sawdust or ground

11. Amend the soil per the recommendations of the Soil Agronomy

amending and preparing soil. Provide report to landscape architect

preparation. Soil analysis shall include: soil texture, infiltration rate,

BOTANICAL NAME

'Keith Davey'

PIS CHI Pistacia chinensis

Sam Harned Landscape Architect PO Box 2275 Oakdale, CA 95361 2 0 9 - 3 8 0 - 7 3 7 6 www.harnedla.com

RATING DETAIL

As shown Low 4 / L4

IDENTIFICATION STAME DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024

| DSA BACKCH | 11/13/24 | |
|-------------|---------------------------|------|
| | | |
| NESCEIDTION | DATE | MADK |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | DESCRIPTION DSA BACKCHECK | |



CLASSROC NTARY

PROJECT NO.

DRAWING

23-12901 (SHLA 24-20)

Planting pits for trees shall be excavated per the details provided in these plans. Planting pit backfill mix for all trees and shrubs shall consist of the following: 6 parts 'on-site' soil

4 parts organic amendment (same as described above) 1 lb./yd. of mix 12-12-12 commercial fertilizer

2 lbs./cu. yd. of mix Iron Sulfate 10 lbs./cu. yd. of mix Agricultural Gypsum 15. Fertilizer tablets (20-10-5) to be placed in all planting pits in the

12. Notify landscape architect if site soil has been lime treated.

Additional testing may be required to determine extent of lime

13. Provide weed control prior to planting. Thoroughly irrigate the site to

(Round-Up or equal) at the rate specified by the manufacturer.

treatment, compaction, or other condition that may be deleterious to

promote germination of weed seeds that may be in the soil. Once

germination has taken place spray the site with approved herbicide,

following quantities per plant container size:

5 gallon 3 tablets 15 gallon 9 tablets

24" box

healthy plant growth.

Reapply as needed.

36" box 15 tablets 16. Plant establishment period of ninety (90) days shall commence upon notice of Substantial Completion. Maintain all plant material throughout duration of plant establishment period to a point accepted by the Landscape Architect or Owner's Representative. See Planting Specifications for additional information.

9 tablets

17. Trees to be planted a min. of 5'-0" from edge of paving or walls, U.O.N.

17.1. Tree planting shall conform to minimum distances away from lights or other utilities, as published in the local jurisdictions standards or guidelines.

18. Groundcover shall be installed continuous under all shrub masses,


19. Install vines with runners securely attached to the adjacent wall or trellis. Remove nursery stakes prior to completion of plant establishment period, unless otherwise directed by owner or


landscape architect. 20. Prior to placing mulch, apply pre-emergent weed control, (Ronstar, or approved equal) in the amounts specified by the manufacturer. 21. Uniformly place a minimum 3" depth of recycled, organic mulch


turf areas. Color: Brown (un-dyed). 21.1. "Gorilla Hair" is not acceptable unless specifically noted.


Do not install bark mulch in areas of inundation (e.g. bio-swale or basin). Place min. 3" layer of crushed aggregate mulch $\binom{3}{4}$ ") in these areas in place of the bark mulch. Transition back to bark mulch at top of slope, U.O.N. Submit sample for approval.

(3/4" - 1-1/2" chip size) over all shrub areas. Do not install mulch at









4,684 sf.

IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 DATE: __ 12/18/2024

 \Box

AND

PROJECT NO. 23-12901 (SHLA 24-20)

DRAWING

Sam Harned Landscape Architect PO Box 2275 Oakdale, CA 95361 2 0 9 - 3 8 0 - 7 3 7 6 www.harnedla.com

329413.19-13

- Finish surface to

be appx. $\frac{1}{4}$ " below

adjacent paving

FS of header or

Header,per

callout, see


separate detail


Per plans,


3" min.

321516-04

329301-18








Width per plans

Decomposed granite,

compact to 90%, see





Waterproof wire connectors, per specs

Water-proof tag,

provide station

number based on





STAKING DETAIL

TREE PLANTING

DECOMPOSED GRANITE (DG) PAVING 329301-13

Subgrade, 90% —

1. Decomposed granite to be $\frac{3}{8}$ " - $\frac{1}{4}$ ". Color: per plans.

Compaction rates provided are per ASTM D1557.

Conform to compaction specified in soils report, if

compaction, U.O.N

Submit sample for approval.

one is prepared for this project.


MOW CURB - 12"


Paving or other built —

element, where

occurs, per plans

Finish grade Install rotor body perpendicular to slope Backfill excavated INSTALLED ON SLOPE hole with clean soil, compact to match adjacent soil density Sch. 80 PVC Rotor, per legend nipple, length as 3/4" PVC SCH. 80 required, set at 45-degree angle nipple (4" min.) Marlex street ells, 3 ea. Sch. 40 PVC ell or tee (SxSxT) Lateral line -





CONTROLLER - WALL MOUNT

8 GEAR ROTOR
NTS

Set top of box 1" above -FG in turf, 2" above FG

Control wires, provide

24"-30" separated coil of

in planter

ea. wire

union

1. Control wire shall be direct burial 14 AWG

2. All wire runs shall be continuous without any

splices unless approved by the Owner's

made using DBR/Y-6 connectors or

3. All Sch. 80 PVC to Sch. 40 PVC threaded

4. Valve boxes shall be located in planting

Representative. Wire connections shall be

connections shall be made using teflon tape.

REMOTE CONTROL VALVE

Sch. 80 PVC

PVC lateral pipe -

or larger.

approved equal.

328401-15

Rectangular plastic

valve box, per specs.

Remote control valve,

PVC true union ball

Sch. 80 PVC nipples at

union valves, 3" min, typ.

- Sch. 80 PVC 90 ell (TxT)

Brick supports at

Sch. 80 PVC nipple

(length as required)

Sch. 40 or 80 PVC tee or ell (SxT)

PVC main line

3/4" dia. drain rock,

min. 6" depth

4 corners


for info


see Irrigation Schedule

DISTRICT PLANTING AND IRRIGATION NOTES

THESE NOTES ARE PROVIDED AS SUPPLEMENTAL TO PLANTING AND IRRIGATION NOTES THAT ARE INCLUDED ON OTHER SHEETS. IN THE EVEN OF A DISCREPANCY BETWEEN THESE NOTES AND OTHERS ON THESE PLANS, THESE NOTES BELOW SHALL SUPERSEDE.

- PRODUCT "OR APPROVED EQUAL" SPECIFICATION NOTE: ALL SPECIFIED MATERIALS, PRODUCTS AND MANUFACTURERS ARE RELEVANT TO DESCRIBE THE REQUIRED QUALITY AND FEATURES OF A PARTICULAR COMPONENT OF THE PROJECT, HOWEVER, THE SPECIFIC PRODUCT OR MANUFACTURER NOTED IS TO BE CONSTRUED TO BE FOLLOWED BY THE WORDS, "OR APPROVED EQUAL".
- GENERAL NOTE: THE CONTRACTOR IS TO SUPPLY ALL EQUIPMENT, MATERIALS AND LABOR TO PROVIDE A COMPLETE AND OPERATIONAL SYSTEM. ADDITIONAL EQUIPMENT AND MATERIALS IN ADDITION TO THE SYSTEM COMPONENTS LISTED IN THE LEGEND MAY BE REQUIRED TO PROVIDE A COMPLETE AND OPERATIONAL SYSTEM.
- 3. SPRINKLER ADJUSTMENT NOTE: CONTRACTOR SHALL MAKE ANY ADJUSTMENTS OR CHANGES TO SPRINKLERS, NOZZLES, RADIUS AND ARCS AS REQUIRED TO PROVIDE 100% COVERAGE TO ALL LANDSCAPE AREAS AND PREVENT OVER SPRAY ONTO BUILDINGS OR HARDSCAPED SURFACES.
- 4. EXISTING IRRIGATION SYSTEM AND WATERING NOTE: THE CONTRACTOR IS RESPONSIBLE TO KEEP THE EXISTING IRRIGATION SYSTEM TO REMAIN OPERATIONAL TO IRRIGATE ALL LANDSCAPED AREAS. WHERE AUTOMATIC OPERATION OF EXISTING IRRIGATION SYSTEMS IS INTERRUPTED DUE TO CONSTRUCTION ACTIVITIES, THE CONTRACTOR IS RESPONSIBLE TO SUPPLY TEMPORARY IRRIGATION TO NEW AND/OR EXISTING AREAS THAT ARE AFFECTED BY THE SERVICE INTERRUPTION AS REQUIRED DUE TO PREVAILING WEATHER CONDITIONS. THE CONTRACTOR SHALL MAKE REPAIRS TO THE EXISTING SYSTEM AS NEEDED. THE CONTRACTOR IS TO ASSIST CAMPUS MAINTENANCE PERSONNEL AS NEEDED TO KEEP THE EXISTING LANDSCAPED AREAS IRRIGATED. AREAS AFFECTED BY NEW CONSTRUCTION ARE TO BE IRRIGATED BY THE CONTRACTOR. CONTRACTOR IS TO REPLACE ANY DEAD OR STRESSED PLANT MATERIALS (TO MATCH EXISTING) THAT WERE TO REMAIN THAT WERE DAMAGED OR NEGLECTED DUE TO CONSTRUCTION ACTIVITIES.
- 5. EXISTING IRRIGATION SYSTEM TO BE REPLACED BY NEW IRRIGATION SYSTEM NOTE: THE CONTRACTOR IS TO REMOVE EXISTING SPRINKLERS, VALVES AND OTHER IRRIGATION IMPROVEMENTS VISIBLE AT THE SURFACE IN AREAS TO RECEIVE NEW IRRIGATION AND DELIVER SALVAGED PARTS, INCLUDING, BUT NOT LIMITED TO SPRINKLERS, VALVES, VALVE BOXES ETC., TO THE CAMPUS MAINTENANCE DEPARTMENT. PIPING IS TO BE REMOVED WHERE IT INTERFERES WITH CONSTRUCTION ACTIVITIES, OTHERWISE PIPING MAY BE ABANDONED BELOW GRADE. WHERE PIPING IS BROUGHT TO THE SURFACE, THE CONTRACTOR SHALL CUT IT OFF A MINIMUM OF 12" BELOW GRADE. DEPRESSIONS AND HOLES THAT ARE CREATED FROM REMOVING EXISTING IRRIGATION IMPROVEMENTS BEING REPLACED ARE TO BE FILLED WITH CLEAN TOPSOIL LEVEL WITH SURROUNDING GRADE AND COMPACTED. IRRIGATION SYSTEM AND BUILDING WATER ARE TO REMAIN INTACT AND OPERATIONAL.
- 6. CAMPUS IRRIGATION WATER AVAILABILITY NOTE: THE CONTRACTOR IS TO INSTALL ALL REROUTED MAINLINE PIPES WHILE LEAVING THE EXISTING IRRIGATION SYSTEM IN SERVICE DURING THE PROJECT. WHEN ALL PIPING AND WIRE REROUTING WORK IS COMPLETE THE CONTRACTOR MAY ARRANGE TO SHUT OFF THE WATER TO MAKE FINAL CONNECTIONS FOR A PERIOD OF TIME NOT TO EXCEED TWO DAYS. THE CAMPUS MAINTENANCE SUPERVISOR IS TO BE GIVEN A MINIMUM OF ONE WEEK WRITTEN NOTICE TO OVERWATER THE CAMPUS AREAS IN QUESTION PRIOR TO SHUTTING OFF THE WATER TO MAKE FINAL CONNECTIONS. IF PREVAILING WEATHER CONDITIONS ARE OVER 95 DEGREES DAYTIME HIGH TEMPERATURES, THEN THE SHUT DOWN DURATION MAY BE LIMITED TO NO MORE THAN ONE DAY AS DECIDED BY CAMPUS MAINTENANCE SUPERVISOR.
- 7. EXISTING TURF, PLANT & TREE TO REMAIN & PROTECT NOTE: THE CONTRACTOR IS RESPONSIBLE TO REPLACE ANY EXISTING TURF, PLANT MATERIALS OR TREES THAT ARE DAMAGED DUE TO CONSTRUCTION ACTIVITIES, VEHICLE DAMAGE, AND STRESS DUE TO LACK OF WATER OR OTHER DETERIORATION OF THE EXISTING AREAS TO REMAIN ARE TO BE RESTORED BY THE CONTRACTOR TO THE EXISTING CONDITION PRIOR TO THE PROJECT AT NO ADDITIONAL COST TO THE DISTRICT. THIS INCLUDES DAMAGE THAT MAY OCCUR AT ANY AREA OF THE CAMPUS.
- 8. CONTRACTOR IS RESPONSIBLE FOR REMOVAL AND DISPOSAL OF ANY VEGETATION WITHIN THE PROJECT AREA THAT IS NOT CALLED TO REMAIN AND PROTECT. ANY ADJACENT LANDSCAPE AREAS OUTSIDE THE PROJECT AREA THAT ARE TO REMAIN AND PROTECT THAT ARE DAMAGED ARE TO BE REPAIRED AND RESTORED AT NO ADDITIONAL COST TO THE DISTRICT. CONTRACTOR IS TO VISIT THE SITE PRIOR TO BID TO VERIFY EXISTING CONDITIONS AND IMPROVEMENTS.
- EXISTING IRRIGATION REMOTE CONTROL VALVES TO BE REMOVED NOTE: PRIOR TO ANY DEMOLITION WORK, CONTRACTOR IS TO FIELD VERIFY THAT ANY IRRIGATION SYSTEMS CONNECTED TO REMOTE CONTROL VALVES NOTED TO BE REMOVED HAVE NEW IRRIGATION PLANNED FOR THOSE AREAS. IF ANY IRRIGATION SYSTEM, OR PART THERE OF, IS LOCATED IN AN EXISTING AREA TO REMAIN & PROTECT, THE CONTRACTOR IS TO LEAVE THAT VALVE, OR A PORTION OF IT, IN SERVICE AS REQUIRED. NOTIFY THE LANDSCAPE ARCHITECT FOR DIRECTION. CONTRACTOR TO FIELD VERIFY.
- 10. ALL AREAS ADJACENT TO THE PROJECT AREA HAVE EXISTING IRRIGATION IMPROVEMENTS TO REMAIN & PROTECT. CONTRACTOR IS TO REPAIR ALL DAMAGE TO EXISTING IMPROVEMENTS THAT ARE INTENDED TO REMAIN & PROTECT TO MATCH EXISTING IMPROVEMENTS. DAMAGE MAY BE A DIRECT, INDIRECT RESULT OF THEIR WORK OR MAY BE CAUSED BY NEGLECT. CONTRACTOR TO FIELD VERIFY.
- 11. SEE LANDSCAPE IRRIGATION PLAN FOR WORK RELATING TO EXISTING SPRINKLERS AND LATERAL PIPING. CONTRACTOR TO FIELD VERIFY.
- 12. MANUAL IRRIGATION NOTE: THE CONTRACTOR IS RESPONSIBLE TO MANUALLY IRRIGATE ANY EXISTING IRRIGATION SYSTEM AREAS ON THE SITE WHERE THE EXISTING AUTOMATIC OPERATION OF THE EXISTING SYSTEMS TO REMAIN AND PROTECT ARE INTERRUPTED DUE TO CONSTRUCTION ACTIVITIES. DEPENDING UPON PREVAILING WEATHER CONDITIONS, DAILY WATERING MAY BE REQUIRED AS REQUESTED BY THE CAMPUS MAINTENANCE SUPERVISOR. THIS MAY INCLUDE A LARGE AREA WITH MANY REMOTE CONTROL VALVES. THE CONTRACTOR IS TO CAREFULLY FIELD VERIFY AND COORDINATE WORK TO AVOID DAMAGING THE EXISTING PIPING OR WIRING THAT MAY REQUIRE MANUAL IRRIGATION OF THE SITE BY THE CONTRACTOR FOR EXTENDED PERIODS OF TIME.
- 13. THE CONTRACTOR IS RESPONSIBLE TO CAREFULLY EXAMINE THE SITE AND PLANS TO FIELD VERIFY ALL EXISTING CONCRETE, PATIOS, SIDEWALKS, PAVING AND OTHER HARDSCAPING TO REMAIN AND PROTECT TO DETERMINE THE SCOPE OF WORK REGARDING THE REQUIRED HORIZONTAL DIRECTIONAL BORING THAT WILL BE NECESSARY TO COMPLETE THE PROJECT. ALL EXISTING CONCRETE, PATIOS, SIDEWALKS, PAVING AND OTHER HARDSCAPED SURFACES MAY NOT BE SHOWN ON THE PLANS. IT IS THE CONTRACTORS RESPONSIBILITY TO FIELD VERIFY ALL LOCATIONS THAT MAY REQUIRE BORING, OR CUTTING AND PATCHING OF EXISTING HARDSCAPED SURFACES PRIOR TO BIDDING. GENERALLY, ALL HARDSCAPED SURFACE CROSSINGS ARE TO BE BY HORIZONTAL DIRECTIONAL BORING. THE CONTRACTOR MUST RECEIVE WRITTEN PERMISSION FROM THE DISTRICT PROJECT MANAGER TO SAW CUT AND PATCH ANY EXISTING HARDSCAPED SURFACES.
- 14. EXISTING REMOTE CONTROL VALVES AND IRRIGATION IMPROVEMENTS SHOWN ON THE PLAN ARE DIAGRAMMATIC. CONTRACTOR IS RESPONSIBLE TO FIELD LOCATE ALL IMPROVEMENTS AND PERFORM THE WORK OUTLINED AS SHOWN ON THE PLANS. CONTRACTOR IS TO TRACE EXISTING WIRING, POT HOLE AND USE ALL REASONABLE MEANS TO FIELD LOCATE EXISTING IMPROVEMENTS.







TRENCHING









FRESNO HEADQUARTERS

LIA | BAKERSFIELD | MODESTO | SAN



NTARY

30 PRESIDIO WA
OCKTON, CA
AWING TITLE

DJECT NO.

23-12901 (SHLA 24-20)

RAWING L5


IDENTIFICATION STAMP APP: 02-122764 INC: REVIEWED FOR

DIV. OF THE STATE ARCHITEC SS 🗹 FLS 🗹 ACS 🗹 12/18/2024

ELOP RELOCATABLE CLAPULLIAM ELEMENT
230 PRESIDIO WAY
STOCKTON, CA
DRAWING TITLE

ABBREVIATIONS

AND



IDENTIFICATION STAME DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹

DATE: __ 12/18/2024

CLASSR: NTAR ELOP RELOCATABLE CL.
PULLIAM ELEMENT
230 PRESIDIO WAY

PROJECT NO.

EXECUTE KEYNOTES

- 2.13 EXISTING TREE TO REMAIN, PROTECT DURING CONSTRUCTION
- 2.37 EXISTING AC PAVING TO REMAIN
- 2.51 REMOVE EXISTING LANDSCAPE FOR NEW RELOCATABLE CLASSROOM BUILDING AND SITE PAVING. SEE CIVIL AND LANDSCAPE
- 2.52 REMOVE EXISTING CHAIN LINK FENCING, CUT POST TO BE FLUSH WITH SURROUNDING SURFACE AND FILL WITH GROUT
- 2.53 REMOVE EXISTING CHAIN LINK GATE, CUT POST AND FILL WITH
- 2.55 REMOVE AND SALVAGE EXISTING BENCH AND TABLES AND RETURN
- 2.57 FOR LIMITS OF DEMOLITION, SEE LANDSCAPE, CIVIL AND ELECTRICAL DRAWINGS
- 5.12 LINE OF ROOF OVERHANG, SEE NEW RELOCATABLE CLASSROOM BUILDING DRAWINGS
- 5.41 STEEL GRATE FOR BELOW FLOOR VENTILATION, SEE DETAIL 4 / A112
- 5.42 STEEL GRATE FOR BELOW FLOOR ACCESS, SEE DETAIL 4 / A112
- 7.54 SHEET METAL DOWNSPOUT (SPILL AT GRADE), SEE NEW

RELOCATABLE CLASSROOM BUILDING DRAWINGS

- 22.03 HIGH-LOW PEDESTAL DRINKING FOUNTAIN WITH BOTTLE FILLER, SEE
- 23.01 HVAC UNIT, SEE NEW RELOCATABLE CLASSROOM BUILDING
- 26.05 ELECTRICAL PULL BOX, SEE ELECTRICAL

CIVIL, AND 10 / A802

DRAWINGS

- 32.03 DECOMPOSED GRANITE, SEE LANDSCAPE
- 32.61 CHAIN LINK FENCING, SEE DETAIL 5/A111
- 33.01 UTILITIES POINT OF CONNECTIONS, SEE CIVIL DRAWINGS AND DETAIL 3 / A112

LEGEND

EXISTING BUILDING
NO SCOPE OF WORK UNDER THIS PROJECT

EXISTING CONCRETE
NO SCOPE OF WORK UNDER THIS PROJECT

PROPOSED MODULAR BUILDING

MODULAR BUILDING UNDER THIS SCOPE OF WORK, SEE MFR DWGS.

SEE CIVIL FOR GRADING, CONSTRUCTION, ISOLATION, CONTRACTION JOINTS

DEMOLITION OF TURF AREA SEE LANDSCAPE DRAWINGS

> PROPOSED TURF AREA
> SEE LANDSCAPE DRAWINGS (TREES AND PLATING NOT SHOWN FOR CLARITY)

SITE INFORMATION

EXISTING CHAIN LINK FENCING, TYP

-0, 0 0 -,

NEW 6'-0"H CHAIN LINK FENCE/GATE

EXISTING ACCESSIBLE ROUTE (2022 C.B.C. SECTION 11B-206)

PROPOSED ACCESSIBLE ROUTE (2022 C.B.C. SECTION 11B-206) EXIT DISCHARGE TO AREA OF

ACCESSIBLE ROUTE (2022 C.B.C. SECTION 11B-206)

SAFE DISPERSAL

DEMOLITION NOTES

- A. REFER TO CIVIL, LANDSCAPE, ELECTRICAL AND RELOCATABLE DRAWINGS FOR UTILITY INFORMATION. CONTRACTOR TO COORDINATE ALL TRADES TO MAINTAIN
- BRUSH, ROOTS, DEBRIS, ORGANIC MATTER AND ALL OTHER MATTER DETERMINED BY THE INSPECTOR TO BE DELETERIOUS. SUCH MATERIAL SHALL BE REMOVED BY THE SITE CONTRACTOR.
- EXCAVATION SHALL BE ADEQUATELY SHORED, BRACED & SHEETED SO THAT THE EARTH WILL NOT SETTLE OR SLIDE AND SO THAT ALL EXISTING IMPROVEMENTS OF
- D. PROPERTY DIMENSIONS ARE SHOWN BASED ON RECORD INFORMATION AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.

SITE PLAN NOTES


- . ALL UTILITY TRANSITIONS SHALL BE CONCEALED WITHIN IN THE WALL CAVITIES AND SHALL TRANSITION BELOW GRADE TO POINT OF CONNECTION BELOW THE
- B. SEE CIVIL, LANDSCAPE, ELECTRICAL AND RELOCATABLE DRAWINGS FOR
- C. EXTERIOR CONCRETE LANDING AT DOORS SHALL NOT BE MORE THAN 1/2 INCH LOWER THAN THE TOP OF THE DOORWAY THRESHOLD, LANDING SHALL SLOPE 1/4 INCH PER FOOT MAX.

IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR

SS 🗹 FLS 🗹 ACS 🗹

DATE: 12/18/2024





IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT APP: 02-122764 INC:
REVIEWED FOR

APP: 02-122764 INC:

REVIEWED FOR

SS ☑ FLS ☑ ACS ☑

DATE: 12/18/2024

Teserves its common law copyright and other property rights in these plans. This document, the ideas and designs incorporated herein, as an instrument of professional service, is not to be used in whole or in part, for any other project without



FRESNO HEADQUARTERS
| BAKERSFIELD | MODESTO | SAN LUIS OBISPO

VISA


30 PRESIDIO WAY

OCKTON, CA
AWING TITLE
ROPOSED PARKING PLAN AN


ROJECT NO.

23-12901

A110




IDENTIFICATION STAME DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024



ELOP RELOCATABLE CLASSROO PULLIAM ELEMENTARY 230 PRESIDIO WAY STOCKTON, CA SITE DETAILS


23-12901


DRAWING



IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹

DATE: 12/18/2024





ELOP RELOCATABLE CLASSROOM
PULLIAM ELEMENTARY
230 PRESIDIO WAY
STOCKTON, CA
SITE DETAILS

23-12901

DRAWING

MIN. REQ'D EXIT WIDTH: MIN. REQ'D EXIT WIDTH: DOORS: 0.2 X 27 = 5.4" < 34" | OK DOORS: 0.2 X 27 = 5.4" < 34" | OK (PER CBC 1005.3.2) (PER CBC 1005.3.2) 36 X 40 MODULAR RC-1 BUILDING PC # 04-123793 **CLASSROOM** 948 SF / 20 TRD-U RN-1 TRW-U TRD-U (STUDENT) TRW-U (STAFF) WORKROOM 126 SF / 50 3 Occ. OFFICE 102 GENDER NEUTRAL STAFF RESTROOM GENDER NEUTRAL 1 Occ.

1/4" = 1'-0" 2

1/4" = 1'-0" | 11 | EXIT ANALYSIS AND SIGNAGE PLAN

DOOR HARDWARE SCHEDULE ROOM **ROOM NAME** HARDWARE REMARKS DOOR# CLASSROOM A, B 101A 01 A, B 101B CLASSROOM 01 02 A, B 102A OFFICE 104A GENDER NEUTRAL RR 03 A, B GENDER NEUTRAL RR 03 A, B 105A

- SITE CONTRACTOR SHALL SALVAGE AND REMOVE HARDWARE FROM DOORS AND RETURN TO DISTRICT.
- THE SPECIFICATIONS

SIGNAGE LEGEND FOR TYPICAL IDENTIFICATION AND TACTILE SIGNAGE, SEE DETAIL 4 / A800

(RN - 1) PROVIDE ROOM IDENTIFICATION SIGN

(TE - 1) PROVIDE EXIT SIGNAGE AT INTERIOR SIDE OF DOOR

(ALS - 1) PROVIDE ASSISTED LISTENING SIGNAGE AT INTERIOR SIDE

OF DOOR

(TRW-U) PROVIDE WALL MOUNTED TOILET ROOM SIGNAGE AT EXTERIOR SIDE OF DOOR, LABELED "STAFF RESTROOM"

(TRW-U) PROVIDE WALL MOUNTED TOILET ROOM SIGNAGE AT EXTERIOR SIDE OF DOOR, LABELED "STUDENT RESTROOM"

(TRD - U) PROVIDE DOOR MOUNTED TOILET ROOM SIGNAGE

(RC - 1) ROOM CAPACITY SIGN

EXIT ANALYSIS LEGEND

XX

PATH OF EGRESS TRAVEL ____

NUMBER OF OCCUPANTS EXITING

ROOM NAME & NUMBER ROOM AREA 150 SF / 50 OCCUPANT LOAD FACTOR CALCULATED LOAD FACTOR

> ILLUMINATED EXIT SIGNS, SEE ELECTRICAL FOR ADDITIONAL INFORMATION

GENERAL NOTES

- OWNER TO PROVIDE EMERGENCY EVACUATION SIGNAGE PER CFC 403.2, 403.4 AND 403.5, AS APPLICABLE, PRIOR TO OCCUPANCY OF THE BUILDINGS OR CAMPUS.
- EGRESS WIDTH COMPONENT (CBC SECTION 1005.3.2): 0.2"/OCC.; A 36" WIDE DOOR HAS A CLEAR WIDTH OF 33" MIN. AND WILL ACCOMMODATE 165 OCCUPANTS.

ASSISTIVE LISTENING: CLASSROOM 48 OCC

 $48 \times 4\% = 2 \text{ RECEIVERS MIN.}$

OWNER TO PROVIDE 2 RECEIVERS, 2 TO BE HEARING AID COMPATIBLE

TOTAL OCCUPANTS: 54

IDENTIFICATION STAME DIV. OF THE STATE ARCHITEC

REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹

APP: 02-122764 INC:

DATE: 12/18/2024

ELOP RELOCATABLE CLASSROO PULLIAM ELEMENTARY 230 PRESIDIO WAY STOCKTON, CA FLOOR PLANS

23-12901

EXECUTE KEYNOTES

9.51

EXTERIOR THRESHOLD AT DOOR BY SITE CONTRACTOR, SEE 1/A112


RUBBER TOP SET BASE ON ALL WALLS - BY SITE CONTRACTOR,

FLUSH TRANSITION BETWEEN CARPETS, SEE 14 / A800

FLOORING TRANSITION STRIP BY SITE CONTRACTOR, SEE 13 / A800


SITE CONTRACTOR SHALL PROVIDE NEW HARDWARE AS INDICATED IN

DOOR HARDWARE SCHEDULE



- OR THE ORDERING OF ANY EQUIPMENT.
- 4. ALL DRAWINGS AND SPECIFICATIONS ARE TO BE CONSIDERED PART OF THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REVIEW AND COORDINATION OF ALL DRAWINGS PRIOR TO ANY CONSTRUCTION, INCLUDING ARCHITECTURAL, STRUCTURAL, MECHANICAL, PLUMBING, AND ELECTRICAL. ANY WORK PERFORMED IN CONFLICT WITH THE CONTRACT DOCUMENTS OR ANY CODE REQUIREMENT SHALL BE CORRECTED BY THE CONTRACTOR AT HIS OWN EXPENSE AND AT NO EXPENSE TO THE OWNER OR THE OWNER REPRESENTATIVE.
- 5. MINIMUM SLOPE FOR SEWER IS 1/4"PER FT, UNLESS OTHERWISE NOTED.
- 6. ALL ROOF PENETRATIONS SHALL BE COMPATIBLE WITH ROOF SYSTEM WITH AS FEW PENETRATIONS AS POSSIBLE.
- 7. MINIMUM DOMESTIC WATER PIPE SIZE TO BE 3/4" UNLESS OTHERWISE NOTED. USE A REDUCING ELL AT FIXTURE, IF
- 8. ALL PLUMBING FIXTURES, VALVES, FAUCETS, FIXTURE STOPS, ETC. WHICH PROVIDE WATER FOR HUMAN CONSUMPTION MUST MEET THE "LEAD FREE" REQUIREMENT FOR THE STATE OF CALIFORNIA.
- 9. PIPING DISTRIBUTION SYSTEMS SHALL BE BRACED TO COMPLY WITH THE FORCES AND DISPLACEMENTS PRESCRIBED IN ASCE 7-16 SECTION 13.3 AS DEFINED IN ASCE 7-16 SECTIONS 13.6.5, 13.6.6, 13.6.7, 13.6.8; AND 2019 CBC, SECTIONS 1617A.1.24, 1617A.1.25 AND 1617A.1.26.

e PIPE TURN DOWN



DROP INLET

IDENTIFICATION STAME DIV. OF THE STATE ARCHITE APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹






CLASSRO

23-12901

1/2" = 1'-0" | 4



DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹

DATE: 12/18/2024

CLASSROOM

EXECUTES WE KEYNOTES

METAL ROOFING PANELS

METAL SOFFIT PANELS

SHEET METAL FLASHING/TRIM

7.52 SHEET METAL COPING

55 SHEET METAL DOWN SPOUT (SPILL AT GRADE) AND BRACKETS PROVIDED BY CLASS LEASING. SITE CONTRACTOR TO REMOVE AND SALVAGE FOR RE-INSTALLATION AFTER FINISHES HAVE BEEN INSTALLED.

10.11 DEDICATION PLAQUE

3.01 HVAC UNIT, SEE NEW RELOCATABLE CLASSROOM BUILDING DRAWINGS

26.22 WALL MOUNTED LIGHT FIXTURE, SEE ELECTRICAL

IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT

APP: 02-122764 INC:

REVIEWED FOR

SS FLS ACS D

DATE: 12/18/2024

ATE DESCRIPTION

ATE DESCRIPTION

ATE DESCRIPTION

AND DESCRIPTION

In whole or in part, for any other project without any other part and the signs in the selection and designs in the select



EXTERIOR FINISH SCHEDULE

| MARK | MATERIAL | DETAIL |
|---------------------|--|-----------|
| <u></u> | ACRYLIC CEMENT PLASTER SYSTEM, COLOR 1 | 4 / A802 |
| | EXTERIOR PAINT: MATCH EXISTING CAMPUS COLORS | |
| | CEMENT PLASTER SYSTEM, COLOR 2 | |
| 2 | EXTERIOR PAINT: MATCH EXISTING CAMPUS COLORS | 4 / A802 |
| (3) | METAL PANEL SYSTEM: LATITUDE SERIES (PAN RIB D 6" COVERAGE 1" REVEAL) | 2 / A802 |
| | EXTERIOR COLOR: MATCH EXISTING CAMPUS COLORS | |
| $\langle 4 \rangle$ | METAL SHEET METAL FLASHING AND DOWNSPOUT | 15 / A801 |
| \ - \ | EXTERIOR COLOR: MATCH EXISTING CAMPUS COLORS | |

GENERAL NOTES

A. CEMENT PLASTER EXPANSION AND CONTROL JOINT PATTERN SHALL BE REVIEWED WITH THE ARCHITECT PRIOR TO INSTALLATION.

LOP RELOCATABLE CLASSF ULLIAM ELEMENTAR 30 PRESIDIO WAY


JECT NO.

23-12901

A300


IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024


CLASSRO NTARY



IDENTIFICATION STAME DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024

CLASSRO(NTARY






- (1) DISCONNECT ALL EXISTING LOAD SIDE FEEDERS AND PRESERVE FOR RECONNECTION. REMOVE EXISTING MAIN SWITCHBOARD AND REPLACE WITH NEW MAIN SWITCHBOARD PER DETAIL 1/E600. RECONNECT ALL EXISTING LOAD SIDE FEEDERS, AND CONNECT NEW LOAD SIDE FEEDER PER SINGLE LINE DIAGRAM 1/E700. MAKE ARRANGEMENTS WITH POWER COMPANY FOR DISCONNECTION AND RECONNECTION OF SERVICE.
- PROVIDE TWO (N) 2"C WITH 4 #3/0 CU THWN, AND 1 #2 CU GND (IN EACH CONDUIT) PER SINGLE LINE DIAGRAM 1/E700.
- (3) PROVIDE (N) UNDERGROUND POWER PULL BOX PER DETAIL 13/E600.
- PROVIDE TWO (N) 2"C WITH 4 #3/0 CU THWN, AND 1 #2 CU GND (IN EACH CONDUIT), AND ONE (N) 2"C WITH 3 #1/0 CU THWN, AND 1 #4 GND, PER SINGLE LINE DIAGRAM 1/E700.
- (5) DISCONNECT ALL EXISTING LOAD SIDE FEEDERS AND PRESERVE FOR RECONNECTION. DISCONNECT AND ABANDON LINE SIDE FEEDER TO BE REPLACED. REMOVE EXISTING POST MOUNTED PANEL AND REPLACE WITH NEW POST MOUNTED PANEL PER DETAIL 2/E600. CONNECT NEW LINE AND LOAD SIDE FEEDERS, AND RECONNECT ALL EXISTING LOAD SIDE FEEDERS, PER SINGLE LINE DIAGRAM 1/E700. PROVIDE GROUNDING FACILITIES PER
- 6 PROVIDE ONE (N) 2"C WITH 3 #1/0 CU THWN, AND 1 #4 GND, PER SINGLE LINE DIAGRAM 1/E700.
- 7 PROVIDE (N) AUDIO SOURCE UNIT WITH PAGING MICROPHONE, AND (N) AMPLIFIER AT (E) FIRE ALARM CONTROL PANEL FOR (N) AUDIO RISER
- 8 ONE (N) 3/4"C WITH ONE 'FAS' CABLE (ADDRESSABLE SLC LOOP), AND ONE (N) 'FXS" CABLE, (AUDIO RISER). ROUTE CONDUIT THROUGH ACCESSIBLE
- 9 PROVIDE (N) 18" SQ. X 6" DEEP NEMA 3R SCREW COVER CAN HIGH ON EXTERIOR BUILDING WALL WITH 2"C SLEEVE INTO ACCESSIBLE ATTIC
- (10) PROVIDE ONE (N) 2"C WITH ONE 'FAS" CABLE, AND ONE 'FXS' CABLE.
- (11) PROVIDE (N) UNDERGROUND SIGNAL PULL BOX PER DETAIL 14/E600.
- (12) (E) FIRE ALARM REMOTE ANNUNCIATOR (EDWARDS #3-LCDANN). DISCONNECT AND REMOVE INTERNAL COMPONENTS, AND PRESERVE COMPONENTS AND CIRCUITING FOR REINSTALLATION AND RECONNECTION. REMOVE (E) BACKBOX AND REPLACE WITH (N) BACKBOX (EDWARDS #4ANN/B). FURNISH, INSTALL, AND CONNECT (N) REMOTE MICROPHONE (EDWARDS #3-REMICA), AND REINSTALL AND RECONNECT (E) REMOTE ANNUNCIATOR.

IDENTIFICATION STAME APP: 02-122764 INC: REVIEWED FOR

DIV. OF THE STATE ARCHITEC SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024

| in whole or in part, for any other project without | 11/13/24 DSA BACKCHECK | 11/13/24 | В |
|---|------------------------|----------|------|
| service, is not to be used | DESCRIPTION | DATE | MARK |
| instrument of professional | | | |
| incorporated herein, as an | | | |
| ideas and designs | | | |
| plans. This document, the | | | |
| property rights in these | | | |
| copyright and other | | | |
| reserves its common law | | | |
| Teter, Inc. expressly | | | |






23-12901

GENERAL NOTES

- PROVIDE ELECTRICAL FEEDERS PER SINGLE LINE DIAGRAM.
- SITE CONDUITS OF TRADE SIZE 2" AND LARGER SHALL BE GROUPED AND INSTALLED PER DETAIL 12/E600. SITE CONDUITS SHALL BE INSTALLED A MINIMUM OF 36" BELOW FINAL GRADE TO TOP OF
- SPECIAL PRECAUTION SHALL BE TAKEN WHEN TRENCHING TO LOCATE, PROTECT AND PRESERVE EXISTING UNDERGROUND UTILITIES. ANY DAMAGE CAUSED DURING THE COURSE OF CONSTRUCTION SHALL BE IMMEDIATELY REPAIRED.
- CONTRACTOR SHALL LINE BORE UNDER ALL EXISTING CONCRETE SIDEWALKS. SAWCUTTING SIDEWALKS IS PROHIBITED.
- CONTRACTOR SHALL SAWCUT AND PATCH EXISTING ASPHALT.



- 1) PROVIDE ONE (N) 2"C WITH 3 #1/0 CU THWN, AND 1 #4 CU GND, FROM (N) PANEL 'P' PER ELECTRICAL SITE PLAN 1/E100.
- (2) CONTRACTOR SHALL LINE BORE UNDER EXISTING CONCRETE SIDEWALKS.
- (3) PROVIDE (N) UNDERGROUND POWER PULL BOX PER DETAIL 13/E600.
- (4) PROVIDE ONE (N) 2"C WITH 3 #1/0 CU THWN, AND 1 #4 CU GND.
- 5 CONNECT PANEL AT NEW RELOCATABLE BUILDING PER SINGLE LINE DIAGRAM 1/E700.
- 6 RECONNECT (E) POWER AND LIGHTING BRANCH CIRCUIT CONNECTIONS BETWEEN BUILDING MODULES.
- (7) PROVIDE SYSTEM GROUND FACILITIES PER DETAILS 10/E600 AND 11/E600.
- 8 PROVIDE GROUNDING LUGS ON BOTH SIDES OF RIGID METAL BEAMS AND BOND SECTIONS OF RELOCATABLE BUILDING TOGETHER WITH 1 #6 CU BONDING JUMPER.
- 9 PROVIDE 120VAC POWER CONNECTION TO IRRIGATION CONTROL PANEL. COORDINATE PRECISE LOCATION WITH IRRIGATION SYSTEM INSTALLER.
- PROVIDE (N) WEATHERPROOF G.F.C.I. DUPLEX RECEPTACLE FOR DRINKING FOUNTAINS AND CONNECT TO NEW BRANCH CIRCUIT.
- (11) EXTEND LIGHT FIXTURE CIRCUIT FROM NEAREST LIGHT FIXTURE.
- PROVIDE (N) ASTRONOMIC ELECTRONIC 1-CIRCUIT TIME CLOCK WITH NEMA 3R ENCLOSURE, INTERMATIC #ET90115CR OR EQUIVALENT. CONNECT TIME CLOCK FOR ON/OFF CONTROL OF (N) BRANCH SITE LIGHTING CIRCUIT.
 MOUNT TIME CLOCK TO EXTERIOR BUILDING WALL.
- (13) PROVIDE ONE (N) 1"C WITH 2 #10 CU THWN AND 1 #10 CU GND.
- PROVIDE (N) POLE MOUNTED LIGHT FIXTURE PER DETAIL 18/E600 AND LIGHT FIXTURE SCHEDULE 16/E800.

IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC

APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 DATE: <u>12/18/2024</u>

| י אווסו אווונפון מתוווסוולמווס | | | |
|--------------------------------|------------------------|----------|------|
| any other project without | 11/13/24 DSA BACKCHECK | 11/13/24 | В |
| service, is not to be used | DESCRIPTION | DAIE | MARK |
| instrument of professions | | L H | |
| incorporated herein, as a | | | |
| ideas and designs | | | |
| plans. This document, the | | | |
| property rights in these | | | |
| copyright and other | | | |
| reserves its common law | | | |






GENERAL NOTES

- PROVIDE ELECTRICAL FEEDERS PER SINGLE LINE DIAGRAM.
- PENETRATIONS THROUGH WALLS, CEILINGS, FLOORS, AND/OR ROOFS SHALL BE SEALED.
- CONTRACTOR SHALL LINE BORE UNDER ALL EXISTING CONCRETE SIDEWALKS. SAWCUTTING SIDEWALKS IS PROHIBITED.
- TRENCH AND BACKFILL PER ARCHITECTURAL PLANS, SPECIFICATIONS, AND DETAIL 12/E600. SITE CONDUITS SHALL BE INSTALLED A MINIMUM OF 36" BELOW FINAL GRADE TO TOP OF CONDUIT.
- SPECIAL PRECAUTION SHALL BE TAKEN WHEN TRENCHING TO LOCATE, PROTECT AND PRESERVE EXISTING UNDERGROUND UTILITIES. ANY DAMAGE CAUSED DURING THE COURSE OF CONSTRUCTION SHALL BE IMMEDIATELY REPAIRED.

23-12901



- 1 PROVIDE THIRTY-ONE (31) NEW TYPE 'D' CABLES FROM (E) IDF TO NEW RELOCATABLE BUILDING.
- PROVIDE (N) 18" SQ. X 6" DEEP NEMA TYPE 3R SCREW COVER CAN HIGH ON EXTERIOR BUILDING WALL AT EXISTING RELOCATABLE BUILDING, WITH 2"C SLEEVE INTO ACCESSIBLE ATTIC SPACE. VERIFY EXACT LOCATION WITH OWNER AT SITE.
- PROVIDE ONE (N) 2-1/2"C WITH THIRTY-ONE (31) TYPE 'D' CABLES, AND ONE (N) 2-1/2"C.O.
- PROVIDE (N) UNDERGROUND SIGNAL PULL BOX PER DETAIL 14/E600. COORDINATE LOCATION WITH LANDSCAPE CONTRACTOR.
- PROVIDE (N) 18" SQ. X 6" DEEP NEMA TYPE 3R SCREW COVER CAN HIGH ON EXTERIOR BUILDING WALL AT NEW RELOCATABLE BUILDING, WITH 2"C SLEEVE INTO ACCESSIBLE ATTIC SPACE. VERIFY EXACT LOCATION WITH OWNER AT SITE.
- 6 PROVIDE ONE (N) 'H' CABLE FROM EACH 'AV1' HDMI JACK TO 'AV2' HDMI
- 7) PROVIDE ONE TYPE 'D' CABLE BACK TO IDF, FROM CALL BUTTON.
- 8 PROVIDE ONE TYPE 'D' CABLE BACK TO IDF. TYPICAL OF ALL SECURITY CAMERA LOCATIONS.
- 9 PROVIDE ONE TYPE 'D' CABLE BACK TO IDF. TYPICAL OF ALL INTERIOR AND EXTERIOR SPEAKER LOCATIONS.

GENERAL NOTES

- A. PENETRATIONS THROUGH WALLS, CEILINGS, FLOORS, AND/OR ROOFS SHALL BE SEALED.
- B. TRENCH AND BACKFILL PER ARCHITECTURAL PLANS, SPECIFICATIONS, AND DETAIL 12/E600. SITE CONDUITS SHALL BE INSTALLED A MINIMUM OF 36" BELOW FINAL GRADE TO TOP OF CONDUIT.
- C. SPECIAL PRECAUTION SHALL BE TAKEN WHEN TRENCHING TO LOCATE, PROTECT AND PRESERVE EXISTING UNDERGROUND UTILITIES. ANY DAMAGE CAUSED DURING THE COURSE OF CONSTRUCTION SHALL BE IMMEDIATELY REPAIRED.

SECURITY AND ACCESS ROUGH-IN NOTES

- A. SECURITY AND ACCESS SYSTEM ROUGH-IN REQUIREMENTS:
 - a. AT DOOR CONTACT LOCATIONS DRILL 1/2" HOLE IN STRIKE SIDE OF DOOR FRAME AND THROUGH HEADER, INSTALL A PULL WIRE BETWEEN OPENING IN DOOR FRAME AND ACCESSIBLE
 - b. AT MOTION DETECTOR LOCATIONS INSTALL A SINGLE-GANG OUTLET BOX WITH A SINGLE-GANG TRIM-RING IN WALL AT 84" A.F.F., INSTALL ONE 1/2"C INTO ACCESSIBLE ATTIC SPACE, INSTALL A PULL WIRE BETWEEN OUTLET BOX AND ACCESSIBLE
 - c. AT KEYPAD LOCATIONS INSTALL A SINGLE-GANG OUTLET BOX WITH A SINGLE-GANG TRIM-RING IN WALL AT 48" A.F.F. TO TOP OF BOX, INSTALL ONE 3/4"C INTO ACCESSIBLE ATTIC SPACE, INSTALL A PULL WIRE BETWEEN OUTLET BOX AND ACCESSIBLE ATTIC.
 - AT CARD READER LOCATIONS INSTALL A SINGLE-GANG OUTLET BOX WITH A SINGLE-GANG TRIM-RING IN WALL AT 48" A.F.F. TO TOP OF BOX, INSTALL ONE 3/4"C INTO ACCESSIBLE ATTIC SPACE, INSTALL A PULL WIRE BETWEEN OUTLET BOX AND ACCESSIBLE ATTIC.

TELECOMMUNICATION CABLING NOTES

- A. CONDUIT AND JUNCTION BOXES PROVIDED BY BUILDING MANUFACTURER.
- PROVIDE THREADED SET SCREW CONNECTORS WITH POLYPROPYLENE BUSHINGS AT EACH END OF CONDUIT SYSTEMS USED FOR TELECOMMUNICATION CABLE INSTALLATION. BUSHINGS SHALL BE INSTALLED AND INSPECTED PRIOR TO CABLE INSTALLATION
- C. EACH TELECOMMUNICATION CABLE SHALL BE HOMERUN FROM THE TELECOMMUNICATION OUTLET TO A PATCH PANEL LOCATED IN THE (E) IDF AT BUILDING 'M' WEST.
- TELECOMMUNICATION CABLES SHALL BE NEATLY BUNDLED WITH VELCRO STRAPS AT 36"O.C.
- TELECOMMUNICATION CABLES SHALL BE INDEPENDENTLY SUPPORTED FROM J-HOOKS WITHIN THE ACCESSIBLE ATTIC SPACE WHERE THEY ARE NOT WITHIN CONDUIT.
- TELECOMMUNICATION CABLES SHALL BE TERMINATED WITH MODULAR JACKS ON PATCH PANELS IN THE TELECOMMUNICATION ENCLOSURE AND ON MODULAR JACKS AT THE TELECOMMUNICATION OUTLETS.
- TELECOMMUNICATION CABLE SERVING WIRELESS ACCESS POINTS SHALL BE TERMINATED WITH PLUG TYPE CONNECTORS AT THE LOCATION OF THE WIRELESS ACCESS POINT.

IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT APP: 02-122764 INC:

REVIEWED FOR

APP: 02-122764 INC:

REVIEWED FOR

SS FLS ACS
DATE: 12/18/2024

| in whole or in part, for any other project without | 11/13/24 DSA BACKCHECK | 11/13/24 | В |
|--|------------------------|----------|------|
| service, is not to be used | DESCRIPTION | DATE | MARK |
| instrument of professional | | | |
| incorporated herein, as an | | | |
| ideas and designs | | | |
| plans. This document, the | | | |
| property rights in these | | | |
| copyright and other | | | |
| reserves its common law | | | |
| leter, Inc. expressly | | | |

RES SAN LUIS OBISPO

FRESNO HEADQUARTERS SALIA | BAKERSFIELD | MODESTO | SANI



LE CLASSROOM
MENTARY
WAY


230 PRESIDIO WAN

....

23-12901

DRAWING

E400



- (1) PROVIDE ONE (N) 2"C WITH ONE 'FAS' CABLE (ADDRESSABLE SLC LOOP) AND ONE 'FXS' CABLE (AUDIO RISER), FROM (È) FIRE ALARM CONTROL PANEL 'FACP' IN ADMINISTRATION BUILDING PER ELECTRICAL SITE PLAN
- (2) CONTRACTOR SHALL LINE BORE UNDER EXISTING CONCRETE SIDEWALKS.
- (3) PROVIDE (N) UNDERGROUND SIGNAL PULL BOX PER DETAIL 14/E600.
- (4) PROVIDE ONE (N) 2"C WITH ONE 'FAS' CABLE, AND ONE 'FXS' CABLE.
- (5) (N) UNDERGROUND SIGNAL PULL BOX PER ENLARGED SIGNAL PLAN 1/E400.
- (6) (N) NEMA TYPE 3R SCREW COVER CAN ON EXTERIOR BUILDING WALL AT RÉLOCATABLE BUILDING PER ENLARGED SIGNAL PLAN 1/E400.
- (7) PROVIDE ONE (N) 1"C WITH 'FAS' CABLE, AND ONE (N) 'FXS' CABLE.
- (8) PROVIDE (N) FIRE ALARM AUXILIARY POWER SUPPLY AND CONNECT TO (E) ADDRÈSSABLE SLC LOOP AND (N) AUDIO RISER CIRCUIT FROM (E) FIRE ÀLARM CONTROL PANEL 'FACP' PER FIRE ALARM RISER DIAGRAM 2/É710. MOUNT PER DETAIL 9/E710.
- (9) CONNECT TO DEDICATED BRANCH CIRCUIT BREAKER AT ELECTRICAL PANEL WITH 1/2"C - 2 #12 CU THWN, AND 1 #12 CU GND. REFER TO FIRE ALARM RISER DIAGRAM 2/E710 FOR BRANCH CIRCUIT REQUIREMENTS.
- PROVIDE ONE (N) 3/4"C WITH ONE 'FA' CABLE IN ACCESSIBLE ATTIC SPACE. TYPICAL BETWÈÉN ADDRESSABLE INITIATION DEVICES.
- 11) PROVIDE ONE (N) 3/4"C WITH ONE 'FS' CABLE, AND ONE 'FV' CABLE IN ACCESSIBLE ATTIC SPACE. TYPICAL BETWEEN SPEAKER/STROBES (U.O.N.).
- (12) PROVIDE ONE (N) 3/4"C WITH TWO 'FS' CABLES AND TWO 'FV' CABLES (SPEAKER AND STROBE CIRCUITS, DOWN/BACK) IN ACCESSIBLE ATTIC
- PROVIDE ONE (N) 3/4"C WITH TWO 'FS' CABLES (SPEAKER CIRCUIT ONLY, DOWN/BACK).
- PROVIDE 'END-OF-LINE' RESISTOR AT LAST VISUAL NOTIFICATION APPLIANCE ON NAC #N1.
- (15) PROVIDE 'END-OF-LINE' RESISTOR AT LAST SPEAKER ON SPEAKER CIRCUIT 'S1'.

GENERAL NOTES


- PENETRATIONS THROUGH WALLS, CEILINGS, FLOORS, AND/OR ROOFS
- CONTRACTOR SHALL LINE BORE UNDER ALL EXISTING CONCRETE SIDEWALKS. SAWCUTTING SIDEWALKS IS PROHIBITED.
- TRENCH AND BACKFILL PER ARCHITECTURAL PLANS, SPECIFICATIONS, AND DETAIL 12/E600. SITE CONDUITS SHALL BE INSTALLED A MINIMUM OF 36" BELOW FINAL GRADE TO TOP OF CONDUIT.
- SPECIAL PRECAUTION SHALL BE TAKEN WHEN TRENCHING TO LOCATE, PROTECT AND PRESERVE EXISTING UNDERGROUND UTILITIES. ANY DAMAGE CAUSED DURING THE COURSE OF CONSTRUCTION SHALL BE IMMEDIATELY REPAIRED.

FIRE ALARM SYSTEM INSTALLATION NOTES

- THE LOCATION OF AUTOMATIC DETECTORS, MANUAL PULL STATIONS AND OTHER FIRE ALARM EQUIPMENT AND DEVICES, AS SHOWN ON PLAN, ARE FOR REFERENCE ONLY, AND DO NOT CONSTITUTE SHOP DRAWINGS WHICH ARE REQUIRED FOR REVIEW AND APPROVAL.
- ALL DRAWINGS ARE DIAGRAMMATIC ONLY, AND SHALL NOT BE USED IN DETERMINING ACTUAL CONDUIT ROUTING. THE CONTRACTOR SHALL VERIFY ALL CONDUIT ROUTING CONDITIONS AT THE PROJECT SITE AS CONSTRUCTION PROGRESSES.
- ALL FIRE ALARM DATA, COMMUNICATIONS AND INITIATING CIRCUITS SHALL BE INSTALLED UTILIZING SOLID COPPER CONDUCTORS WITH OUTER COVERING COLORS PER THE SPECIFICATIONS AND AS SHOWN ON THE DRAWINGS. ALL SMOKE DAMPER AND REMOTE TROUBLE INDICATOR CIRCUITS SHALL BE YELLOW. ALL CIRCUITS SHALL BE INDIVIDUALLY LABELED, BOTH AT THE DEVICE END AND AT THE SIGNAL TERMINAL CABINET AND/OR FIRE ALARM MASTER PANEL TERMINATION
- ALL FIRE ALARM CIRCUITS SHALL BE CONTINUOUS FROM DEVICE TO DEVICE. SPLICES ARE NOT ALLOWED UNLESS IN COVERED JUNCTION BOXES ON APPROVED TERMINAL BLOCKS. 'T' TAPPING IS ALLOWED ONLY IN INITIATION LOOPS CONNECTING ADDRESSABLE DEVICES AND ONLY UNDER THESE CONDITIONS. UNDER NO CIRCUMSTANCES SHALL 'T' TAPPING BE PERMITTED BETWEEN CONVENTIONAL DEVICES.
- SMOKE DETECTORS SHALL BE INSTALLED AWAY FROM AIR SUPPLY GRILLES AT A MINIMUM DISTANCE OF 3' PER NFPA 72 29.8.3.4 OR GREATER AS RECOMMENDED BY THE MANUFACTURER.
- CONTRACTOR SHALL SYNCHRONIZE TWO OR MORE STROBES IN ONE ROOM AND TWO OR MORE SPEAKERS WITHIN HEARING OF EACH
- THE FIRE ALARM SYSTEM SHALL CONFORM TO THE 2022 CALIFORNIA ELECTRICAL CODE (CEC) ARTICLE 760 AND THE 2022 CALIFORNIA FIRE CODE (CFC) § 105.7 & § 907, AND CALIFORNIA BUILDING CODE (CBC)

IDENTIFICATION STAME DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹


DATE: 12/18/2024





23-12901

1/8" = 1'-0"




IDENTIFICATION STAME DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024



P RELOCATABLE CLASSROOM LLIAM ELEMENTARY
) PRESIDIO WAY 40 40 80 80 80

23-12901

DRAWING



IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹

| Teter, Inc. expressly | reserves its common law | copyright and other | property rights in these | plans. This document, the | ideas and designs | incorporated herein, as an | instrument of professional | service, is not to be used | in whole or in part, for | any other project without | |
|-----------------------|-------------------------|---------------------|--------------------------|---------------------------|-------------------|----------------------------|----------------------------|----------------------------|--------------------------|---------------------------|---|
| | | | | | | | | DESCRIPTION | | 11/13/24 DSA BACKCHECK | |
| | | | | | | | | DATE | | 11/13/24 | |
| | | | | | | | | MARK | | മ | _ |



ELOP RELOCATABLE CLASSROOM PULLIAM ELEMENTARY 230 PRESIDIO WAY STOCKTON, CA DRAWING TITLE SINGLE LINE DIAGRAM

23-12901

DRAWING

FIRE ALARM APPROVAL

THE FIRE ALARM SYSTEM DESIGN IS A "COMPLETE PLAN SUBMITTAL" PER DSA FIRE ALARM SUBMITTAL GUIDELINES. THE CONTRACTOR SHALL INSTALL THE SYSTEM AS SHOWN AND AS HEREIN SPECIFIED. IF ANY SUBSTITUTION OF FIRE ALARM EQUIPMENT IS TO BE REQUESTED, SUCH REQUEST SHALL BE MADE A MINIMUM OF TWO WEEKS PRIOR TO PROJECT BID DATE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTING THE SUBSTITUTION PER THE DSA GUIDELINES AND SHALL PAY ALL ADDITIONAL COSTS REQUIRED TO ACCOMMODATE REVIEW OF THE SUBSTITUTED FIRE ALARM SYSTEM BY DSA, WHETHER OR NOT SUCH APPROVAL IS GIVEN. THE CONTRACTOR'S SUBMITTAL SHALL INCLUDE MANUFACTURER'S CATALOG CUT SHEETS AND CSFM LISTING SHEETS FOR THE INDIVIDUAL COMPONENTS COMPRISING THE SUBSTITUTED FIRE ALARM SYSTEM, BATTERY LOAD CALCULATIONS AND VOLTAGE DROP CALCULATIONS FOR EACH

APPLICABLE CODES AND STANDARDS

- 2022 CA BUILDING CODE CCR, TITLE 24, PART 2, VOLUMES 1 & 2
- (2021 IBC AND CALIFORNIA AMENDMENTS) 2022 CA ELECTRICAL CODE - CCR, TITLE 24, PART 3
- (2020 NEC AND CALIFORNIA AMENDMENTS) 2022 CA MECHANICAL CODE - CCR, TITLE 24, PART 4
- (2021 UMC AND CALIFORNIA AMENDMENTS)
- 2022 CA PLUMBING CODE CCR, TITLE 24, PART 5 (2021 UPC AND CALIFORNIA AMENDMENTS)
- 2022 CA FIRE CODE CCR, TITLE 24, PART 9
- (2021 IFC AND CALIFORNIA AMENDMENTS) 2022 CA REFERENCE STANDARDS CODE - CCR, TITLE 24, PART 12
- 2022 NFPA 13, INSTALLATION OF SPRINKLER SYSTEMS AND 2022 CALIFORNIA AMENDMENTS 2022 NFPA 72, NATIONAL FIRE ALARM CODE, AND 2022 CALIFORNIA AMENDMENTS PUBLIC SAFETY, STATE FIRE MARSHAL REGULATIONS - CCR, TITLE 19
- DSA GUIDELINES FOR FIRE AND LIFE SAFETY SYSTEMS, DIVISION OF THE STATE ARCHITECT OFFICE OF REGULATION SERVICES.

FIRE ALARM GENERAL NOTES

- UNDERGROUND AND EXTERIOR CONDUITS WILL HAVE WATERTIGHT FITTINGS. (CEC 110.11 AND CEC 300.6)
- OUTLETS ON OPPOSITE SIDES OF A FIRE RATED WALL SHALL BE INSTALLED WITH A MINIMUM HORIZONTAL SPACING OF TWO FEET.
- FIRE ALARM DEVICE MOUNTING HEIGHTS SHALL BE AS FOLLOWS:
- PULL STATION OPERABLE PART OF A MANUALLY ACTUATED ALARM INITIATING DEVICE SHALL BE NOT LESS THAN 42" FROM FINISHED FLOOR; AND TOP OF BOX SHALL NOT BE MORE THAN 48" FROM FINISHED FLOOR. (CBC 11B 308.1.1, NFPA 72
- INTERIOR AUDIBLE NOTIFICATION APPLIANCE AT LEAST 90" TO THE TOP OF DEVICE ABOVE FINISHED FLOOR AND NOT LESS THAN 6" BELOW FINISHED CEILING. (NFPA 72 18.4.8.1)
- WALL-MOUNTED STROBE OR SPEAKER/STROBE AT LEAST 80" TO BOTTOM OF LENS AND NOT GREATER THAN 96" TO TOP OF LENS ABOVE FINISHED FLOOR. (NFPA 72 18.5.5.1)
- AUDIBLE SIGNAL DEVICES OF A FIRE ALARM SYSTEM INTENDED TO ALERT ALL OCCUPANTS SHALL BE SO LOCATED AND UNOBSTRUCTED AS TO CAUSE A LEVEL OF AUDIBILITY OF AT LEAST 15 dBA ABOVE AVERAGE AMBIENT SOUND LEVEL BUT NOT LESS THAN 75 dBA AT TEN FEET, OR MORE THAN 110 dBA IN TOTAL. (NFPA 72 18.4.3.1, 18.4.1.2 AND CFC 907.5.2.1.2)
- AMBIENT NOISE LEVELS SHALL BE CONSTRUED TO MEAN THAT WHICH CAN NORMALLY BE EXPECTED TO EXIST WHEN THE FACILITY, BUILDING, ROOM OR AREA IS FUNCTIONING UNDER NORMAL OPERATIVE OR WORKING CONDITIONS. (CFC 907.5.2.1.1)
- AUDIBLE DEVICES SHALL SOUND THE CA UNIFORM FIRE ALARM SIGNAL IN TEMPORAL MODE. PROVIDE AT LEAST ONE EXTERIOR AUDIBLE DEVICE ON BUILDING FOR E OCCUPANCIES. (CFC 907.5.2.1.3)
- EMERGENCY VOICE/ALARM COMMUNICATION SYSTEM SHALL COMPLY WITH CBC 907.2.3 AND NFPA 72 24.4.2
- VISUAL DEVICES SHALL NOT EXCEED TWO FLASHES PER SECOND AND SHALL NOT BE SLOWER THAN ONE FLASH EVERY SECOND. (NFPA 72 18.5.3.1)
- AUTOMATIC SMOKE DETECTION SHALL BE PROVIDED AT THE LOCATION OF EACH FIRE ALARM CONTROL UNIT, NOTIFICATION APPLIANCE CIRCUIT POWER EXTENDER AND SUPERVISING STATION TRANSMITTING EQUIPMENT TO PROVIDE NOTIFICATION OF FIRE AT THAT LOCATION. (NFPA 72 10.4.4)
- BRANCH CIRCUITS PROTECTING FIRE ALARM EQUIPMENT SHALL BE LABELED PER NFPA 72 10.6.5.2.2 AND SHALL INCLUDE A LISTED CIRCUIT BREAKER LOCKING DEVICE PER NFPA 72
- COMPLETE THE NFPA 72 RECORD OF COMPLETION, TESTING ALL DEVICES AND APPLIANCES. PROVIDE A COPY OF THE COMPLETED RECORD OF COMPLETION TO THE OWNER (SCHOOL DISTRICT), ARCHITECT, LOCAL FIRE AUTHORITY, AND DSA VIA THE PROJECT INSPECTOR. TESTING OF THE ENTIRE SYSTEM SHALL BE MADE IN THE PRESENCE OF THE LOCAL FIRE AUTHORITY AND THE DSA INSPECTOR OF RECORD (IOR). FINAL TEST SHALL INCLUDE READ OUT VERIFICATION FORM FROM CENTER STATION.
- THE AUTOMATIC ALARM SYSTEM SHALL BE INSTALLED, TESTED, AND MAINTAINED IN ACCORDANCE WITH THE STATE FIRE MARSHAL'S REGULATIONS (CFC 907.8.5, NFPA 72 14.4.1.1, NFPA 72 14.5)

FIRE ALARM SYSTEM EQUIPMENT LEGEND DESCRIPTION EXISTING FIRE ALARM CONTROL PANEL 'FACP': EDWARDS EST3 SERIES W/ E) FACP AUTOMATIC CHARGING SYSTEM C.S.F.M. #7165-1657:0186 **NEW AUDIO SOURCE UNIT** EDWARDS #3-ASU; C.S.F.M. #7165-1657:0186 (MOUNT INSIDE EXISTIN FIRE ALARM CONTROL PANEL 'FACP') NEW 20W ZONE AMPLIFIER EDWARDS #3-ZA20X; C.S.F.M. #7165-1657:0186 (MOUNT INSIDE EXISTING FIRE ALARM CONTROL PANEL 'FACP') EXISTING FIRE ALARM REMOTE ANNUNCIATOR EDWARDS #3-LCDANN; C.S.F.M. #7120-1657:0193 (MOUNT INSIDE NEW BACKBOX - EDWARDS #4ANN/B) NEW FIRE ALARM REMOTE MICROPHONE EDWARDS #3-REMICA; C.S.F.M. #7120-1657:0193 (MOUNT INSIDE NEW BACKBOX - EDWARDS #4ANN/B) NEW FIRE ALARM AUXILIARY POWER SUPPLY 'APS' WITH AUTOMATIC CHARGING SYSTEM, AND INTEGRAL AUDIO AMPLIFIER: EDWARDS #APS-10A, C.S.F.M. #7300-1657:0229 EDWARDS #SIGA-AA50, C.S.F.M. #7300-1657:0121 NEW ADDRESSABLE SYNCRONIZATION OUTPUT MODULE EDWARDS #SIGA-CC1S, C.S.F.M.#7300-1657:0121 (MOUNT INSIDE NEW FIRE ALARM AUXILIARY POWER SUPPLY 'APS') NEW ADDRESSABLE SMOKE DETECTOR AND BASE (ON CEILING): EDWARDS #SIGA-OSD; C.S.F.M. #7272-1657:0511 EDWARDS #SIGA-SB; C.S.F.M. #7300-1657:0120 NEW ADDRESSABLE HEAT DETECTOR AND BASE (ON CEILING): EDWARDS #SIGA-HRD; C.S.F.M. #7270-1657:0333 EDWARDS #SIGA-SB; C.S.F.M. #7300-1657:0120 NEW ADDRESSABLE HEAT DETECTOR AND BASE (IN ATTIC): EDWARDS #SIGA-HRD; C.S.F.M. #7270-1657:0333 EDWARDS #SIGA-SB; C.S.F.M. #7300-1657:0120 NEW SPEAKER/STROBE ANNUNCIATOR - WALL MOUNTED (XX REPRESENTS CANDELA) XX EDWARDS #G4SVRF; C.S.F.M. #7320-1657:0516 NEW VOICE EVACUATION SYSTEM SPEAKER (OUTDOOR - WEATHERPROOF) S D EDWARDS #WG4RF-S, WG4RTS C.S.F.M. #7320-1657:0289 REFER TO FIRE ALARM CABLE SCHEDULE ON SHEET E800 FOR FIRE ALARM CABLE MANUFACTURER, PART NUMBERS, AND C.S.F.M. LISTING NUMBERS

THE TOTAL PROJECT CONSTRUCTION VALUE IS LESS THAN \$200,000,

THE PROJECT CONSISTS OF ONLY MODULAR BUILDINGS WHICH ARE

TEMPORARY; THESE BUILDINGS SHALL BE REMOVED NO MORE THAN THREE YEARS FROM THE INSTALLATION DATE UNLESS A THREE-YEAR

THE PROJECT IS NOT FUNDED UNDER CHAPTER 12.5 OF THE LEROY F. GREENE SCHOOL FACILITIES ACT. IT WILL BE 100% FUNDED BY LOCAL

FIRE ALARM MONITORING NOTE

SUPERVISORY AND TROUBLE SIGNALS TO AN APPROVED SUPERVISING


STATION AS REQUIRED BY NFPA 72 AS AMENDED BY CFC CHAPTER 80. THE SUPERVISING STATION SHALL BE LISTED AS EITHER UUFX OR

STANDARD 3011. SUPERVISION OF SYSTEM AND LEASED TELEPHONE

AUTOMATIC FIRE ALARM SYSTEMS SHALL TRANSMIT THE ALARM.

UUJS BY UNDERWRITERS LABORATORY OR SHALL MEET THE

REQUIREMENTS OF FACTORY MUTUAL RESEARCH APPROVAL



N.T.S. | 14

NOTE: FIRE ALARM PANEL

WEIGHT = 26 LBS.

EXISTING WOOD

BUILDING STRUCTURE

1-5/8" x 7/8" 12 GA. UNISTRUT

WALL STRUCTURE WITH #10

WOOD SCREWS, ONE PER

CHANNEL, PER SIDE, 1 1/2"

PAINT CHANNEL TO MATCH

MINIMUM EMBEDMENT.

EXISTING CONDITIONS

NEW FIRE ALARM PANEL

ATTACH ENCLOSURE TO

UNISTRUT CHANNEL WITH

1/4" LOCKWASHER, AND

1/4"-20 NUT. ONE PER


CHANNEL, PER SIDE.

CHANNEL STUD NUT #P2378-1,

FIRE ALARM PANEL MOUNTING

- SMOKE DETECTOR (★)

P3300 CHANNEL. BOLT TO



| | EXISTI | NG FIRE ALAR | M CONTI | ROL I | PAN | EL FACP | BATTERY C | ALCULATIO | NS | |
|-------|---------------------|--------------------|-------------|--------|--------|------------|-----------|--------------------|-----------------------------|------------------|
| QTY. | DEVICE | | | DESCR | IPTIOI | N | | STANDBY CURRENT | ALARM CURRENT/D EVICE | ALARM CURRENT |
| 1 | Edwards EST3 | (E) Fire Alarm Co | ntrol Panel | | | | | * | * | * |
| 1 | Edwards 3-PPSM | (E) Power Supply | | | | | | * | * | * |
| 1 | 3-CPU3 | (E) Central Proce | ssor | | | | | 0.15500 | 0.16500 | 0.16500 |
| 1 | 3-RS485B | (E) Communicati | ons Card | | | | | 0.09800 | 0.09800 | 0.09800 |
| 1 | 3-LCD | (E) LCD Module | | | | | | 0.04000 | 0.04200 | 0.04200 |
| 1 | 3-SSDC1 | (E) Dual SIGA Co | ntroller | | | | | 0.26400 | 0.33600 | 0.33600 |
| 1 | 3-MODCOM | (E) Dact Module | | | | | | 0.06000 | 0.09500 | 0.09500 |
| 1 | Edwards 3-ASU | (N) Audio Source | e Unit | | | | | 0.08000 | 0.08000 | 0.08000 |
| 1 | 3-ZA20X | (N) 20W Zone Ar | mplifier | | | | | 0.06200 | 1.12000 | 1.12000 |
| 1 | Edwards 3-LCDANN | (E) Fire Alarm Rer | note Annund | ciator | | | | 0.04800 | 0.05000 | 0.05000 |
| 1 | Edwards 3-REMICA | (N) Remote Micr | ophone | | | | | 0.06400 | 0.06400 | 0.06400 |
| 1 | Edwards 4ANN/B | (N) Backbox for | Remote Ann | unciat | or an | d Remote M | icrophone | | | |
| | | TC | DTALS | | | | | 0.7590 | 2.0500 | 2.0500 |
| TOTAL | ALARM AMP-HOURS (| 15 MIN.) = | 0.25 | HR | Х | 2.050 | Α | = | 0.5125 | A-H |
| TOTAL | . STANDBY AMP-HOURS | (24 HRS) = | 24 | HR | Х | 0.759 | Α | = | 18.2160 | A-H |
| TOTAL | REQUIRED AMP-HOUR | S = | | | | | | = | 18.7285 | A-H |
| TOTAL | DESIGN AMP-HOURS V | WITH 25% SAFETY FA | ACTOR = | | | | | = | 23.4106 | A-H |

N.T.S. | 9

FINISH CEILING

| | NEW | FIRE ALARM A | JÄILIA | אז אי | OWI | א שוררו | T APS BAIII | ERT CALC | JLAIION | |
|---|--------------|---|----------|---------|--------|------------|-------------|--------------------|-----------------------------|------------------|
| QTY. | DEVICE | | | DESCR | IPTIOI | N | | STANDBY CURRENT | ALARM CURRENT/D EVICE | ALARM CURRENT |
| 1 | APS-F | (E) Fire Alarm Auxiliar | / Power | Supply | , Edw | ards #APS1 | 0A | 0.1050 | 0.2700 | 0.2700 |
| 1 | SIGA-AA50 | | | | | | | 0.0020 | 2.8000 | 2.8000 |
| | | STROBE CURRENT (NA | C N1) | | | | | | | |
| 3 | SV15 | Multi-Candela Speak | er Strob | e (15cc | d) Ed | wards #G4 | SVRF | | 0.0280 | 0.0840 |
| 1 | SV110 | Multi-Candela Speak | er Strob | e (110c | :d) # | G4SVRF | | | 0.0280 | 0.0280 |
| | | SPEAKER CURRENT (C | KT S1) | | | | | | | |
| 3 SP-1/4W Multi-Candela Speaker Strobe (.25w) Edwards #G4SVRF | | | | | | | | | (3 | |
| 1 | SP-1W | Multi-Candela Speaker Strobe (1w) Edwards #G4SVRF | | | | | | | | (3 |
| 1 | SP-2W | Exterior Weatherproo | f Speake | er (2W) | Edwo | ards #WG41 | RF-S/WG4RTS | | | (3 |
| | | TOTAL | S | | | | | 0.1070 | 3.1260 | 3.1820 |
| TOTAL | . ALARM AMF | P-HOURS (15 MIN.) = | 0.25 | HR | Х | 3.182 | Α | = | 0.7955 | A-H |
| TOTAL | . STANDBY AM | MP-HOURS (24 HRS) = | 24 | HR | X | 0.107 | Α | = | 2.5680 | A-H |
| TOTAL | REQUIRED A | MP-HOURS = | | | | | | = | 3.3635 | A-H |
| TOTAL | DESIGN AM | P-HOURS WITH 25% SA | FETY FAC | CTOR = | : | | | = | 4.2044 | A-H |
| NEW I | ATTERIES | | | | | | | | 7.000 | A-H |

FIRE ALARM CODES AND NOTES

N.T.S. | 19 | FIRE ALARM

SB575

LINES SHALL BE ARRANGED BY OWNER.

EXTENSION IS APPROVED BY DSA, OR

| MONITORING NOTE | N.T.S. | 15 | |
|-----------------|--------|----|--|
|-----------------|--------|----|--|

| FIR | E ALARM | SYSTEM OI | PERATION | IAL MATRIX | X |
|------------------------------------|---|--|----------------------------|---|-----------------------------------|
| DEVICE | ACTIVATE EVACUATION SIGNALS/STROBES | SHUTDOWN FIRE/SMOKE DAMPER, OR ACTIVATE SMOKE VENT RELEASE | SHUTDOWN HVAC EQUIPMENT | ANNUNCIATE AT BUILDING FACP AND ALL REMOTE ANNUNCIATORS | SEND SIGNAL TO CENTRAL STATION |
| FIRE ALARM PANEL SYSTEM TROUBLE | | | | X | X |
| SMOKE DETECTOR | X | X | | X | X |
| HEAT DETECTOR | X | | | X | X |

| ISTING FIRE | ALARM | CONTROL | PANEL | 'FACP' | NOTES |
|-------------|--------------|---------|--------------|--------|--------------|
| | | | | | |


EXISTING BATTERIES

- * FIRE ALARM CONTROL PANEL STANDBY AND ALARM CURRENT IS A CUMLATIVE TOTAL OF ALL INTERNAL COMPONENTS LISTED BELOW. THE POWER SUPPLY
- IS CONNECTED TO A DEDICATED 120V CIRCUIT. THERE IS NO STANDBY OR ALARM CURRENT DRAW ON THE SYSTEM BATTERIES. ** STANDBY AND ALARM CURRENT FOR ALL INITIATION DEVICES ARE INCLUDED IN THE STANDBY AND ALARM CURRENT FOR THE DUAL SIGA CONTROLLER.

| QTY. | DEVICE | DESCRIPTION | ALARM CURRENT/ DEVICE | TOTAL ALARM CURRENT |
|-------|--------------|---|-----------------------------|---------------------------|
| 3 | SV15 | Multi-Candela Speaker Strobe (15cd) Edwards #G4SVRF | 0.0280 | 0.0840 |
| 1 | SV110 | Multi-Candela Speaker Strobe (110cd) Edwards #G4SVRF | 0.0280 | 0.0280 |
| | | TOTAL CURRENT ADDED TO CIRCUIT | 0.000 | 0.112 |
| LENG | TH OF WIRE | FROM FACP TO LAST DEVICE (IN FEET) = | | 125 |
| ACTU/ | al size of v | VIRE INSTALLED = 12 AWG 6530 CIRCULAR MILS | | |
| CALC | ULATED VO | LTAGE DROP (IN VDC) = | | 0.046 |
| CIRCL | JIT VOLTAG | E CALCULATED AT LAST DEVICE (IN VDC) = | | 24 VDC |
| PERC | ENT VOLTAC | GE DROP (%) = | | 0.19 % |
| VOLTA | AGE DROP F | FORMULA: | | |
| VOLTA | AGE DROP | = 2 X 10.8 x LENGTH OF CIRCUIT TO FARTHEST DEVICE x CURRENT | | |
| | | WIRE SIZE IN C.M. | | |
| СОМІ | PLITED WITH | TOTAL CURRENT ON CIRCUIT AT MAXIMUM LENGTH (CLASS A CIRCUIT). | | |

| SPEAKER VOLTAGE = | 70 | | | | | | | |
|---------------------------------|----------------------|------|------------|---------|-------------|--------------|--------------------------|----------|
| | DEVICE DOWED | SIGN | SIGNAL CKT | | SIGNAL CKT | | A4151 A445 | AMP |
| SPEAKERS | DEVICE POWER (WATTS) | \$1 | | | | QTY | MIN. AMP SIZE (WATTS) | |
| | (WAIIS) | QTY. | WATTS | QTY. | WATTS | TOTAL. | SIZE (WAIIS) | |
| SPEAKER - 1/4 WATT TAP | 0.25 | 3 | 0.75 | 0 | 0 | 3 | | |
| SPEAKER - 1 WATT TAP | 1 | 1 | 1 | 0 | 0 | 1 | 4.5 | |
| SPEAKER - 2 WATT TAP | 1 | 1 | 2 | 0 | 0 | 1 | | |
| TOTAL POWER ON CKT (P) WATTS | | 3 | .75 | | 0 | | | |
| LOAD RESISTANCE (LR) OHMS | | 1 | 307 | | - | | | |
| TOTAL WIRE LENGTH (D) FT | | 1 | 25 | | 0 | | | |
| WIRE SIZE | | 14. | AWG | 14 | AWG | | | |
| TOTAL WIRE RESISTANCE (WR) OHMS | | | 815 | | = | | | |
| POWER LOSS (PL) dB | | -(| 0.01 | | - | | | |
| FORMULAS WIRE RESISTANCE (R) (O | HMS/Kft)* | | | | | • | VR) = (R / 1000) | • |
| 18 AWG | = | 8.08 | | LOAD | RESISTANC | E(LR) = (SF) | PEAKER VOLTA | GE)^2 |
| 16 AWG | = | 5.08 | | | | | P | |
| 14 AWG | = | 3.26 | | | | | | |
| 12 AWG | = | 2.05 | | POWER L | INE LOSS (P | L) = 10 * LC | G (1- (WR / (\ | WR+LR))) |
| *VALUES PER NFPA 70 | | | | | | | | |

IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS FLS ACS DATE: 12/18/2024







ELOP RELOCATABLE CLA PULLIAM ELEMEN 230 PRESIDIO WA

46.000 A-H

| | | FIRE ALA | ARM CAB | LE SCH | HEDULE | |
|----------------------|--|--------------------------|-----------------------|------------|---|---------------|
| CABLE DESIGNATION | DESCRIPTION | MANUFACTURER & CATALOG # | OUTER JACKET COLOR | SYSTEM | USE | C.S.F.M. # |
| 'FXS' | 1 PR, #14 AWG STRANDED UNSHIELDED AQUASEAL FPL | WEST PENN #AQ226 | BLACK | FIRE ALARM | SITE AUDIO RISER CABLE - EXTERIOR/OUTDOOR | 7160-0859:010 |
| 'FAS' | 1 PR, #16 AWG STRANDED UNSHIELDED AQUASEAL FPL | WEST PENN #AQC225 | BLACK | FIRE ALARM | SITE ADDRESSABLE SLC LOOP CABLE - EXTERIOR/OUTDOOR | 7160-0859:010 |
| 'FA' | 1 PR, #16 AWG SOLID UNSHIELDED FPL | WEST PENN #D990 | RED | FIRE ALARM | ADDRESSABLE SLC LOOP CABLE - INTERIOR/INDOOR | 7160-0859:010 |
| 'FS' | 1 PR, #14 AWG SOLID SHIELDED, FPLP | WEST PENN #60992B | RED | FIRE ALARM | AUDIBLE (SPEAKER) NOTIFICATION APPLIANCE CIRCUIT - INTERIOR/INDOOR | 7160-0859:010 |
| 'FV' | 1 PR, #12 SOLID UNSHIELDED FPLP | WEST PENN #60995B | RED | FIRE ALARM | VISUAL (STROBE) NOTIFICATION APPLIANCE CIRCUIT - INTERIOR/INDOOR | 7160-0859:010 |

FIRE ALARM CABLE SCHEDULE

N.T.S. | 13

| TELECOMMUNICATION CABLE SCHEDULE | | | | | | | | | | | |
|----------------------------------|---|---|-----------------------|--------|---------------------------------|--|--|--|--|--|--|
| CABLE DESIGNATION | DESCRIPTION | MANUFACTURER & CATALOG # | OUTER JACKET COLOR | SYSTEM | USE | | | | | | |
| 'D' | 4 UTP #24 AWG CATEGORY 6 FILLED OUTDOOR | COMMSCOPE MEDIA 6 #6NF4+ | BLACK | DATA | HORIZONTAL DATA CABLE - OUTDOOR | | | | | | |
| 'H' | ACTIVE FIBER OPTIC HDMI CABLE | CHROMIS #AOC-18G-R-OBXP OR EQUIVALENT | BLACK | VIDEO | BUILDING HDM1 CABLE M/M | | | | | | |

TELECOMMUNICATIONS CABLE SCHEDULE

N.T.S. | **14**

| | LIGHTING FIXTURE SCHEDULE | | | | | | | | | | |
|------------------------|---------------------------|----|---------------------|---------------------------|---|--------------|---|--|--|--|--|
| FIXTURE DESIGNATION | FIXTURE VOLTAGE | | MOUNTING | DRIVER & COLOR TEMP | DESCRIPTION | MANUFACTURER | CATALOG # | | | | |
| S2 | 120 V | 90 | POLE PER 18/E600 | LED - 4000K | DUAL HEAD POLE MOUNTED SITE LIGHT + 20' x 5" SQUARE STRAIGHT STEEL POLE WITH EXTRA HANDHOLE AND COUPLER FOR MOTION SENSOR | LITHONIA | TWO DSX0 LED-P5-40K-70CRI-T5W-MVOLT-SPA-PIR-DDBXD + SSS-20-5G-DM19AS-CPL12/15B-EHH15D-DDBXD | | | | |
| W1 | 120 V | 19 | WALL MOUNTED | | WALL MOUNTED LED LIGHT FIXTURE, +10'AFF (13.5 LBS) | LITHONIA | WDGE2 LED-P2-40K-80CRI-TFTM-MVOLT-SRM | | | | |

LIGHT FIXTURE SCHEDULE

N.T.S. 16

CODES, RULES & REGULATIONS

ALL WORK SHOWN HEREIN SHALL COMPLY WITH THE CURRENT REGULATIONS OF THE CALIFORNIA STATE FIRE MARSHAL, CALIFORNIA BUILDING CODE, TITLES 8 AND 19 THROUGH 24, SERVING UTILITY RULES AND ALL OTHER APPLICABLE STATE ORDINANCES. NOTHING IN THESE PLANS OR SPECIFICATIONS SHALL BE INTERPRETED AS TO PERMIT ANY WORK NOT IN CONFORMANCE WITH THESE CODES, RULES AND REGULATIONS. WHERE WORK OF A GREATER DEGREE IS INDICATED IN THESE PLANS OR SPECIFICATIONS, THAT REQUIREMENT SHALL GOVERN SUCH WORK.

C.E.C. TITLE 24 COMPLIANCE

THE LIGHTING AND LIGHTING CONTROL SYSTEMS DESIGN DEPICTED HEREIN IS IN COMPLIANCE WITH REQUIREMENTS OF THE CURRENT CALIFORNIA ENERGY COMMISSION EFFICIENCY STANDARDS FOR NONRESIDENTIAL BUILDINGS.

GENERAL NOTES (TYPICAL)

- REFER TO THE ARCHITECTURAL REFLECTED CEILING PLAN FOR THE EXACT LOCATION OF ALL CEILING MOUNTED ELECTRICAL EQUIPMENT.
- REFER TO THE MECHANICAL AND PLUMBING PLANS FOR THE EXACT LOCATION OF ALL MECHANICAL, HVAC AND PLUMBING EQUIPMENT. VERIFY THE EXACT LOCATION OF ALL FLOOR BOXES AND ASSOCIATED TRENCH,
- BACKFILL AND SAWCUTTING REQUIREMENTS WITH THE ARCHITECT PRIOR TO COMMENCEMENT OF ANY ROUGH -IN WORK FOR THIS EQUIPMENT.
- COORDINATE ELECTRICAL PANEL AND TERMINAL CABINET LOCATIONS AND ROUTING OF UNDERGROUND CONDUITS WITH THE ARCHITECTURAL AND STRUCTURAL DRAWINGS PRIOR TO COMMENCEMENT OF ANY ROUGH-IN WORK FOR THIS EQUIPMENT.
- COORDINATE ALL ELECTRICAL WORK WITH OTHER TRADES WHOSE WORK WILL IMPACT PLACEMENT OR CONNECTION OF ELECTRICALLY POWERED EQUIPMENT REGARDLESS OF RESPONSIBILITY FOR SUPPLYING EQUIPMENT.

MEP COMPONENT ANCHORAGE NOTE

ALL MECHANICAL, PLUMBING, AND ELECTRICAL COMPONENTS SHALL BE ANCHORED AND INSTALLED PER THE DETAILS ON THE DSA APPROVED CONSTRUCTION DOCUMENTS. THE FOLLOWING COMPONENTS SHALL BE ANCHORED OR BRACED TO MEET THE FORCE AND DISPLACEMENT REQUIREMENTS PRESCRIBED IN THE 2022 CBC, SECTIONS 1617A.1.18 THROUGH 1617A.1.26 AND ASCE 7-16 CHAPTERS 13, 26 AND 30.

- ALL PERMANENT EQUIPMENT AND COMPONENTS.
- TEMPORARY, MOVEABLE OR MOBILE EQUIPMENT THAT IS PERMANENTLY ATTACHED (E.G. HARD WIRED) TO THE BUILDING UTILITY SERVICES SUCH AS ELECTRICITY, GAS OR WATER. "PERMANENTLY ATTACHED" SHALL INCLUDE ALL ELECTRICAL CONNECTIONS EXCEPT PLUGS FOR 110/220 VOLT RECEPTACLES HAVING FLEXIBLE CABLE.
- TEMPORARY, MOVABLE OR MOBILE EQUIPMENT EQUIPMENT WHICH IS HEAVIER THAN 400 POUNDS OR HAS A CENTER OF MASS LOCATED 4 FEET OR MORE ABOVE THE ADJACENT FLOOR OR ROOF LEVEL THAT DIRECTLY SUPPORT THE COMPONENT IS REQUIRED TO BE RESTRAINED IN A MANNER APPROVED BY DSA.

THE FOLLOWING MECHANICAL AND ELECTRICAL COMPONENTS SHALL BE POSITIVELY ATTACHED TO THE STRUCTURE BUT NEED NOT DEMONSTRATE DESIGN COMPLIANCE WITH THE REFERENCES NOTED ABOVE. THESE COMPONENTS SHALL HAVE FLEXIBLE CONNECTIONS PROVIDED BETWEEN THE COMPONENT AND ASSOCIATED DUCTWORK, PIPING, AND CONDUIT. FLEXIBLE CONNECTIONS MUST ALLOW MOVEMENT IN BOTH TRANSVERSE AND LONGITUDINAL DIRECTIONS:

- COMPONENTS WEIGHING LESS THAN 400 POUNDS AND HAVE A CENTER OF MASS LOCATED 4 FEET OR LESS ABOVE THE ADJACENT FLOOR OR ROOF LEVEL THAT DIRECTLY SUPPORT THE COMPONENT.
- COMPONENTS WEIGHING LESS THAN 20 POUNDS, OR IN THE CASE OF DISTRIBUTED SYSTEMS, LESS THAN 5 POUNDS PER FOOT, WHICH ARE SUSPENDED FROM A ROOF OR FLOOR OR HUNG FROM A WALL.

THE ANCHORAGE OF ALL MECHANICAL, ELECTRICAL AND PLUMBING COMPONENTS SHALL BE SUBJECT TO THE APPROVAL OF THE DESIGN PROFESSIONAL IN GENERAL RESPONSIBLE CHARGE OR STRUCTURAL ENGINEER DELEGATED RESPONSIBILITY AND ACCEPTANCE BY DSA. THE PROJECT INSPECTOR WILL VERIFY THAT ALL COMPONENTS AND EQUIPMENT HAVE BEEN ANCHORED IN ACCORDANCE WITH THE ABOVE REQUIREMENTS.

PIPING, DUCTWORK, AND ELECTRICAL DISTRIBUTION SYSTEM BRACING NOTE:

PIPING, DUCTWORK, AND ELECTRICAL DISTRIBUTION SYSTEMS SHALL BE BRACED TO COMPLY WITH THE FORCES AND DISPLACEMENTS PRESCRIBED IN ASCE 7-16 SECTION 13.3 AS DEFINED IN ASCE 7-16 SECTION 13.6.5, 13.6.6, 13.6.7, 13.6.8; AND 2022 CBC, SECTIONS 1617A.1.24, 1617A.1.25, AND 1617A.1.26.

THE METHOD OF SHOWING BRACING AND ATTACHMENTS TO THE STRUCTURE FOR THE IDENTIFIED DISTRIBUTION SYSTEM ARE AS NOTED BELOW. WHEN BRACING AND ATTACHMENTS ARE BASED ON A PREAPPROVED INSTALLATION GUIDE (E.G., OSHPD OPM FOR 2013 CBC OR LATER), COPIES OF THE BRACING SYSTEM INSTALLATION GUIDE OR MANUAL SHALL BE AVAILABLE ON THE JOBSITE PRIOR TO THE START OF AND DURING THE HANGING AND BRACING OF THE DISTRIBUTION SYSTEMS. THE STRUCTURAL ENGINEER OF RECORD SHALL VERIFY THE ADEQUACY OF THE STRUCTURE TO SUPPORT THE HANGER AND BRACE LOADS.

MECHANICAL PIPING (MP), MECHANICAL DUCTS (MD), PLUMBING PIPING (PP), AND ELECTRICAL DISTRIBUTION SYSTEMS (E):

 $\mathsf{MP} \ \square \ \mathsf{MD} \ \square \ \mathsf{PP} \ \square \ \mathsf{E} \ \boxtimes \ \mathsf{OPTION} \ \mathsf{1:} \ \mathsf{DETAILED} \ \mathsf{ON} \ \mathsf{THE} \ \mathsf{APPROVED} \ \mathsf{DRAWINGS} \ \mathsf{WITH}$ PROJECT SPECFIC NOTES AND DETAILS


MP ☐ MD ☐ PP ☐ E ☐ OPTION 2: SHALL COMPLY WITH HCAI (OSHPD) PREAPPROVAL , AS INCLUDED IN THESE DRAWINGS WITH PROJECT-SPECIFIC NOTES AND DÉTAILS.

ELECTRICAL SYMBOL LEGEND DIMENSIONS INDICATED ARE MEASURED TO CENTERLINE OF ENCLOSURE, UNLESS OTHERWISE NOTED NOTE: SOME SYMBOLS SHOWN MAY NOT APPLY TO THIS PROJECT

| E.P. | DESCRIPTION DENOTES EXPLOSION PROOF CONSTRUCTION | SYMBOL \$ a | DESCRIPTION SINGLE POLE AC SNAP SWITCH @ +48" TO TOP LOWER CASE SUBSCRIPT INDICATE CONTROLLED SWITCHLEG OF CIRC |
|----------------------|--|----------------------|--|
| D.T. | DENOTES DUST TIGHT CONSTRUCTION | \$ 2 | TWO POLE AC SNAP SWITCH @ +48" TO TOP OF BOX, U.O.N. |
| O.C. | DENOTES SPACING DIMENSION ON CENTER LINE OF DEVICE | \$ 3 | THREE WAY AC SNAP SWITCH @ +48" TO TOP OF BOX, U.O.N. |
| R.T. | DENOTES RAIN TIGHT CONSTRUCTION | \$ 4 | FOUR WAY AC SNAP SWITCH @ +48" TO TOP OF BOX, U.O.N. |
| U.G. | DENOTES UNDERGROUND INSTALLATION | | HORSEPOWER RATED AC SNAP SWITCH @ +48" TO TOP OF BOX U.O.N. |
| | | \$ M | |
| V.P. | DENOTES VAPOR TIGHT CONSTRUCTION | \$ P | SINGLE POLE AC SNAP SWITCH WITH PILOT LAMP @ +48" TO TOP OF BOX U.O.N. |
| W.P. | DENOTES WEATHERPROOF CONSTRUCTION | \$ T | DIGITAL TIMER SWITCH, FLUSH MOUNTED @ +48" TO TOP OF BOX U.O.N. |
| W.T. | DENOTES WATER TIGHT CONSTRUCTION | \$ A | SINGLE POLE AC SNAP SWITCH @ +48" TO TOP OF BOX, U.O.N. |
| A.F.F. | DENOTES ABOVE FINISHED FLOOR | \$ _K | KEY OPERATED AC SNAP SWITCH @ +48" TO TOP OF BOX U.O.N. |
| A.F.G. | DENOTES ABOVE FINISHED GRADE | (\$) | WALL SWITCH WITH INTEGRAL OCCUPANCY SENSOR @ +48" TO TOP OF BOX, U.O.N. |
| F.B.O. | DENOTES FURNISHED BY OTHERS | $\langle M \rangle$ | OCCUPANCY SENSOR - CEILING MOUNTED |
| U.O.N. | DENOTES UNLESS OTHERWISE NOTED | M _W | OCCUPANCY SENSOR - WALL MOUNTED @ +90" TO TOP OF BOX, U.O.N. |
| (E) | DENOTES EXISTING TO REMAIN, NO WORK U.O.N. | P | LIGHTING CONTROL SYSTEM DIMMING/POWER PACK MOUNTED IN ATTIC |
| | DENOTES NEW | (RP) | LIGHTING CONTROL SYSTEM PLUG LOAD RELAY PACK MOUNTED IN ATTIC |
| | ELECTRICAL KEYNOTES: DENOTES KEYNOTE #1 OF NOTES ON SAME SHEET | (1) | LIGHTING CONTROL SYSTEM 2-BUTTON DIMMING WALL SWITCH |
| \sim | | | @ +48" TO TOP OF BOX, U.O.N. LIGHTING CONTROL SYSTEM 4-BUTTON DIMMING WALL SWITCH |
| | CIRCUIT HOME RUN: DENOTES PANEL A, CKT. #3, - 3/4"C. MINIMUM, U.O.N. | <u>(4)</u> | @ +48" TO TOP OF BOX, U.O.N. LIGHTING CONTROL SYSTEM DIMMING WALL SWITCH WITH LOCKING COVER |
| 1 | CIRCUIT FEEDER: DENOTES FEEDER 'F1' PER SYSTEM FEEDER SCHEDULE | (1) _L | [@ +48" TO TOP OF BOX, U.O.N. |
| | CONDUIT IN ATTIC/WALL: DENOTES 3/4"C-2#12 AWG CU THWN, 1#12 CU GND, U.O.N. | (DS) | LIGHTING CONTROL SYSTEM DAYLIGHT SENSOR - CEILING MOUNTED |
| | CONDUIT IN FLOOR/U.G.: DENOTES 3/4"C-2#12 AWG CU THWN, 1#12 CU GND, U.O.N. | ⟨nB⟩ | LIGHTING CONTROL SYSTEM NETWORK BRIDGE |
| | DENOTES EXISTING CONDUIT RUN TO REMAIN | (nG) | LIGHTING CONTROL SYSTEM NETWORK GATEWAY |
| | CONDUIT RUN - STUBBED, CAPPED AND LABELED. | (AD) | LIGHTING CONTROL SYSTEM AUTOMATED DEMAND RESPONSE MODULE |
| | CONDUIT RUN: DENOTES 3/4"C - 3 #12 AWG CU THWN + 1 #12 CU GND, U.O.N. | (1) | LIGHTING CONTROL SYSTEM TIME CLOCK |
| | CONDUIT RUN: DENOTES 3/4"C - 4 #12 AWG CU THWN + 1 #12 CU GND, U.O.N. | PC | PHOTOCELL CONTROL MOUNTED ON ROOF |
| | CONDUIT RUN: DENOTES 3/4"C - 5 #12 AWG CU THWN + 1 #12 CU GND, U.O.N. | $\langle T \rangle$ | LOW VOLTAGE CONTROL TRANSFORMER |
| | · · | <u> </u> | 25 VOLINGE SORTINGE HARROL ORIGINALIA |
| #### F===1#5 | CONDUIT RUN: DENOTES 1"C - 6 #12 AWG CU THWN + 1 #12 CU GND, U.O.N. | | ELECTRICAL PANEL BOARD RED SLAVO ELIZABETH STATEMENT |
| | SEPARATE POWER AND DATA FLOOR BOXES (2) | V | ELECTRICAL PANELBOARD PER PLANS, FLUSH MOUNTED IN WALL |
| | FLUSH FLOOR BOX WITH DEVICE(S) INSTALLED PER PLANS, U.O.N. (2) | 222 | ELECTRICAL PANELBOARD PER PLANS, SURFACE MOUNTED ON WALL |
| 0- | TAMPER-RESISTANT SINGLE RECEPTACLE IN WALL @ +18", U.O.N. | M | TERMINAL CABINET PER PLANS, FLUSH MOUNTED IN WALL |
| \rightleftharpoons | TAMPER-RESISTANT DUPLEX RECEPTACLE IN WALL @ +18", U.O.N. | \bowtie | TERMINAL CABINET PER PLANS, SURFACE MOUNTED ON WALL |
| = | TAMPER-RESISTANT DUPLEX GFI RECEPTACLE, IN WALL @ 18", U.O.N. | шш | LIGHTING CONTROL PANEL PER PLANS, FLUSH MOUNTED IN WALL |
| — | TAMPER-RESISTANT SWITCHED GFCI RECEPTACLE IN WALL @ +18" A.F.F. U.O.N. (OCC. SENSOR OR WALL SWITCH CONTOLLED) | ш | LIGHTING CONTROL PANEL PER PLANS, SURFACE MOUNTED ON WALL |
| = wp | ITAMPED DECICEANT MEATHED DECICEANT MAD DUDIEV CECHDECEDIACHE MAN DE COVED I | | FIRE ALARM PANEL PER PLANS, FLUSH MOUNTED IN WALL |
| ⊕ | @+18", U.O.N. TAMPER-RESISTANT DUPLEX ISOLATED GROUND RECEPTACLE IN WALL @ +18", U.O.N. (7) | | FIRE ALARM PANEL PER PLANS, SURFACE MOUNTED ON WALL |
| | 9 7 7 77 | | THE ALARMITARLET ERT LAND, SORT AGE MOUNTED ON WALL |
| — | TAMPER-RESISTANT QUADRUPLEX RECEPTACLE IN WALL @ +18", U.O.N. | | |
| € | SPECIAL PURPOSE ELECTRICAL OUTLET PER PLAN IN WALL @ 18" U.O.N. | SWP | EXTERIOR SPEAKER (WALL MOUNTED), ELEVATION AS NOTED |
| = | DUPLEX RECEPTACLE FLUSH IN CEILING | S | SPEAKER IN CEILING, U.O.N. |
| | TAMPER-RESISTANT QUADRUPLEX RECEPTACLE IN WALL @ +18" A.F.F., U.O.N. ONE UNSWITCHED RECEPTACLE AND ONE SWITCHED (OCC. SENSOR CONTROLLED) RECEPTACLE | SC | SPEAKER/CLOCK IN COMMON BACKBOX PER PLAN @ 12" BELOW CEILING, U.O.N. |
| (| JUNCTION BOX | Ф | WALL CLOCK PER PLAN @ 12" BELOW CEILING, U.O.N. |
| O _D | JUNCTION BOX WITH FLEXIBLE CONDUIT CONNECTION TO EQUIPMENT | S | SPEAKER ON WALL @ 12" BELOW CEILING, U.O.N. |
| | NON-FUSIBLE DISCONNECT SWITCH | MD | INTRUSION ALARM SYSTEM MOTION DETECTOR (WALL MOUNTED) |
| | FUSIBLE DISCONNECT SWITCH | © | INTRUSION ALARM SYSTEM MAGNETIC DOOR CONTACT |
| | FUSIBLE DISCONNECT SWITCH WITH INTEGRAL MAGNETIC STARTER | W | INTRUSION ALARM SYSTEM MAGNETIC WINDOW CONTACT |
| | | _ | The second of th |
| \sim | IELECTRIC MOTOR | (CR) | INTRUSION ALARM SYSTEM CLASS REFAX DETECTOR |
| _ | ELECTRIC MOTOR | (B) | INTRUSION ALARM SYSTEM GLASS BREAK DETECTOR |
| Q Q | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR | KP | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) |
| | | KP CR | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR | KP | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. | KP CR | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE | KP CR FR | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP | EP CR FR SS | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP | ER SS | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP | ER S S P A | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM DOOR RELEASE |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM DOOR RELEASE |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM DOOR RELEASE FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP CEILING MOUNTED LIGHTING FIXTURE | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM DOOR RELEASE FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM DOOR RELEASE FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM INDIVIDUAL ADDRESSABLE MODULE |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP RECESSED LIGHTING FIXTURE RECESSED FIXTURE WITH EMERGENCY BATTERY BACKUP | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM HEAT DETECTOR IN HVAC DUCT FIRE ALARM DOOR RELEASE FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM INDIVIDUAL ADDRESSABLE MODULE FIRE ALARM SYNC MODULE FIRE ALARM MANUAL PULL STATION @ +48" TO TOP OF BOX, U.O.N. |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE RECESSED LIGHTING FIXTURE RECESSED FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED ROUND LIGHTING FIXTURE | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM INDIVIDUAL ADDRESSABLE MODULE FIRE ALARM SYNC MODULE FIRE ALARM MANUAL PULL STATION @ +48" TO TOP OF BOX, U.O.N. FIRE ALARM WATERFLOW DETECTION SWITCH |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE RECESSED LIGHTING FIXTURE RECESSED LIGHTING FIXTURE RECESSED FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM INDIVIDUAL ADDRESSABLE MODULE FIRE ALARM SYNC MODULE FIRE ALARM MANUAL PULL STATION @ +48" TO TOP OF BOX, U.O.N. FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM ADDRESSABLE WATERFLOW / TAMPER SWITCH MODULE |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE RECESSED LIGHTING FIXTURE RECESSED FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP ILLUMINATED EXIT SIGN MOUNTED ON CEILING | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM HEAT DETECTOR IN HVAC DUCT FIRE ALARM DOOR RELEASE FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM INDIVIDUAL ADDRESSABLE MODULE FIRE ALARM SYNC MODULE FIRE ALARM MANUAL PULL STATION @ +48" TO TOP OF BOX, U.O.N. FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM ADDRESSABLE WATERFLOW / TAMPER SWITCH MODULE FIRE ALARM ADDRESSABLE WATERFLOW / TAMPER SWITCH MODULE |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP RECESSED LIGHTING FIXTURE RECESSED FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP ILLUMINATED EXIT SIGN MOUNTED ON WALL | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM INDIVIDUAL ADDRESSABLE MODULE FIRE ALARM SYNC MODULE FIRE ALARM SYNC MODULE FIRE ALARM MANUAL PULL STATION @ +48" TO TOP OF BOX, U.O.N. FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM ADDRESSABLE WATERFLOW / TAMPER SWITCH MODULE FIRE ALARM TAMPER SWITCH FIRE ALARM TAMPER SWITCH |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE RECESSED LIGHTING FIXTURE RECESSED FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP ILLUMINATED EXIT SIGN MOUNTED ON CEILING | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM HEAT DETECTOR IN HVAC DUCT FIRE ALARM DOOR RELEASE FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM INDIVIDUAL ADDRESSABLE MODULE FIRE ALARM SYNC MODULE FIRE ALARM MANUAL PULL STATION @ +48" TO TOP OF BOX, U.O.N. FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM ADDRESSABLE WATERFLOW / TAMPER SWITCH MODULE FIRE ALARM ADDRESSABLE WATERFLOW / TAMPER SWITCH MODULE |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP RECESSED LIGHTING FIXTURE RECESSED FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP ILLUMINATED EXIT SIGN MOUNTED ON WALL | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM INDIVIDUAL ADDRESSABLE MODULE FIRE ALARM SYNC MODULE FIRE ALARM SYNC MODULE FIRE ALARM MANUAL PULL STATION @ +48" TO TOP OF BOX, U.O.N. FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM ADDRESSABLE WATERFLOW / TAMPER SWITCH MODULE FIRE ALARM TAMPER SWITCH FIRE ALARM TAMPER SWITCH |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP CEILING MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP CEILING MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP RECESSED LIGHTING FIXTURE RECESSED FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP ILLUMINATED EXIT SIGN MOUNTED ON WALL LOW LEVEL PHOTOLUMINESCENT EXIT SIGN MOUNTED ON WALL | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM DOOR RELEASE FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM INDIVIDUAL ADDRESSABLE MODULE FIRE ALARM SYNC MODULE FIRE ALARM MANUAL PULL STATION @ +48" TO TOP OF BOX, U.O.N. FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM ADDRESSABLE WATERFLOW / TAMPER SWITCH MODULE FIRE ALARM TAMPER SWITCH FIRE ALARM TAMPER SWITCH FIRE ALARM VISUAL ALARM UNIT (WALL@ +80" MINIMUM, U.O.N.) |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP CEILING MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP RECESSED LIGHTING FIXTURE RECESSED LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE SULUMINATED EXIT SIGN MOUNTED ON WALL LOW LEVEL PHOTOLUMINESCENT EXIT SIGN MOUNTED ON WALL POLE MOUNTED EXTERIOR LIGHTING FIXTURE | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM INDIVIDUAL ADDRESSABLE MODULE FIRE ALARM SYNC MODULE FIRE ALARM MANUAL PULL STATION @ +48" TO TOP OF BOX, U.O.N. FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM TAMPER SWITCH FIRE ALARM TAMPER SWITCH FIRE ALARM TAMPER SWITCH FIRE ALARM VISUAL ALARM UNIT (WALL@ +80" MINIMUM, U.O.N.) FIRE ALARM VISUAL ALARM UNIT (CEILING) FIRE ALARM HORN/STROBE ALARM UNIT (WALL @ +80" MINIMUM, U.O.N.) |
| © | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED EXIT SIGN MOUNTED ON WALL LOW LEVEL PHOTOLUMINESCENT EXIT SIGN MOUNTED ON WALL POLE MOUNTED EXTERIOR LIGHTING FIXTURE COMBINATION VOICE AND DATA OUTLET IN WALL, WITH TWO 'D' CABLES TO IDF + TWO 'T' CABLES TO TELEPHONE BACKBOARD. (1) (6) | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM DOOR RELEASE FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM SYNC MODULE FIRE ALARM SYNC MODULE FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM ADDRESSABLE WATERFLOW / TAMPER SWITCH MODULE FIRE ALARM TAMPER SWITCH FIRE ALARM VISUAL ALARM UNIT (WALL@ +80" MINIMUM, U.O.N.) FIRE ALARM VISUAL ALARM UNIT (CEILING) FIRE ALARM VISUAL ALARM UNIT (CEILING) INTERIOR FIRE ALARM HORN (WALL @ +10'-0", U.O.N.) |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WELL MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP CEILING MOUNTED LIGHTING FIXTURE WERCESSED LIGHTING FIXTURE RECESSED FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE LIUMINATED EXIT SIGN MOUNTED ON CEILING ILLUMINATED EXIT SIGN MOUNTED ON WALL LOW LEVEL PHOTOLUMINESCENT EXIT SIGN MOUNTED ON WALL POLE MOUNTED EXTERIOR LIGHTING FIXTURE COMBINATION VOICE AND DATA OUTLET IN WALL, WITH TWO 'D' CABLES TO IDF + TWO 'T' CABLES TO TELEPHONE BACKBOARD. (1) (6) DATA OUTLET IN WALL & WITH 'TO CABLES TO IDF OR MDF (SUBSCRIPT INDICATES QUANTITY OF CABLES AND STATION SIDE JACKS) (1) (6) | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM SYNC MODULE FIRE ALARM SYNC MODULE FIRE ALARM MANUAL PULL STATION @ +48" TO TOP OF BOX, U.O.N. FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM TAMPER SWITCH FIRE ALARM TAMPER SWITCH FIRE ALARM VISUAL ALARM UNIT (WALL@ +80" MINIMUM, U.O.N.) FIRE ALARM VISUAL ALARM UNIT (CEILING) FIRE ALARM VISUAL ALARM UNIT (CEILING) INTERIOR FIRE ALARM HORN (WALL @ +10'-0", U.O.N.) EXTERIOR FIRE ALARM HORN (WALL @ +10'-0", U.O.N.) EXTERIOR FIRE ALARM HORN (EXTERIOR WALL) |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE WERCESSED LIGHTING FIXTURE RECESSED FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE LILUMINATED EXIT SIGN MOUNTED ON CEILING ILLUMINATED EXIT SIGN MOUNTED ON WALL LOW LEVEL PHOTOLUMINESCENT EXIT SIGN MOUNTED ON WALL LOW LEVEL PHOTOLUMINESCENT EXIT SIGN MOUNTED ON WALL COMBINATION VOICE AND DATA OUTLET IN WALL, WITH TWO 'D' CABLES TO IDF + TWO 'T' CABLES TO TELEPHONE BACKBOARD. (1) (6) DATA OUTLET IN WALL @ +18", U.O.N., WITH 'D' CABLES TO IDF OR MDF (SUBSCRIPT INDICATES QUANTITY OF CABLES AND STATION SIDE JACKS) (1) (6) | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM INDIVIDUAL ADDRESSABLE MODULE FIRE ALARM SYNC MODULE FIRE ALARM MANUAL PULL STATION @ +48" TO TOP OF BOX, U.O.N. FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM ADDRESSABLE WATERFLOW / TAMPER SWITCH MODULE FIRE ALARM TAMPER SWITCH FIRE ALARM VISUAL ALARM UNIT (WALL@ +80" MINIMUM, U.O.N.) FIRE ALARM VISUAL ALARM UNIT (CEILING) FIRE ALARM HORN/STROBE ALARM UNIT (WALL @ +80" MINIMUM, U.O.N.) FIRE ALARM VISUAL ALARM UNIT (CEILING) INTERIOR FIRE ALARM HORN (EXTERIOR WALL) VOICE EVACUATION SPEAKER/STROBE ALARM UNIT (WALL @ +80" MINIMUM, U.O.N.) |
| © | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE RECESSED LIGHTING FIXTURE RECESSED FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE LILUMINATED EXIT SIGN MOUNTED ON CEILING ILLUMINATED EXIT SIGN MOUNTED ON WALL LOW LEVEL PHOTOLUMINESCENT EXIT SIGN MOUNTED ON WALL LOW LEVEL PHOTOLUMINESCENT EXIT SIGN MOUNTED ON WALL COMBINATION VOICE AND DATA OUTLET IN WALL, WITH TWO 'D' CABLES TO IDF + TWO 'T' CABLES TO TELEPHONE BACKBOARD. COMBINATION VOICE AND DATA OUTLET IN WALL, WITH TWO 'D' CABLES TO IDF + TWO 'T' CABLES TO TELEPHONE BACKBOARD. (1) (6) DATA OUTLET IN WALL @ +18", U.O.N. (1) MICROPHONE OUTLET IN WALL @ +18", U.O.N. (1) | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM SYNC MODULE FIRE ALARM MANUAL PULL STATION @ +48" TO TOP OF BOX, U.O.N. FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM TAMPER SWITCH FIRE ALARM VISUAL ALARM UNIT (WALL@ +80" MINIMUM, U.O.N.) FIRE ALARM VISUAL ALARM UNIT (CEILING) FIRE ALARM VISUAL ALARM UNIT (CEILING) INTERIOR FIRE ALARM HORN (WALL @ +10"-0", U.O.N.) EXTERIOR FIRE ALARM HORN (EXTERIOR WALL) VOICE EVACUATION SPEAKER/STROBE ALARM UNIT (WALL @ +80" MINIMUM, U.O.N.) |
| | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE WERCESSED LIGHTING FIXTURE RECESSED FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE LILUMINATED EXIT SIGN MOUNTED ON CEILING ILLUMINATED EXIT SIGN MOUNTED ON WALL LOW LEVEL PHOTOLUMINESCENT EXIT SIGN MOUNTED ON WALL LOW LEVEL PHOTOLUMINESCENT EXIT SIGN MOUNTED ON WALL COMBINATION VOICE AND DATA OUTLET IN WALL, WITH TWO 'D' CABLES TO IDF + TWO 'T' CABLES TO TELEPHONE BACKBOARD. (1) (6) DATA OUTLET IN WALL @ +18", U.O.N., WITH 'D' CABLES TO IDF OR MDF (SUBSCRIPT INDICATES QUANTITY OF CABLES AND STATION SIDE JACKS) (1) (6) | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM INDIVIDUAL ADDRESSABLE MODULE FIRE ALARM SYNC MODULE FIRE ALARM MANUAL PULL STATION @ +48" TO TOP OF BOX, U.O.N. FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM ADDRESSABLE WATERFLOW / TAMPER SWITCH MODULE FIRE ALARM TAMPER SWITCH FIRE ALARM VISUAL ALARM UNIT (WALL@ +80" MINIMUM, U.O.N.) FIRE ALARM VISUAL ALARM UNIT (CEILING) FIRE ALARM HORN/STROBE ALARM UNIT (WALL @ +80" MINIMUM, U.O.N.) FIRE ALARM VISUAL ALARM HORN (EXTERIOR WALL) VOICE EVACUATION SPEAKER/STROBE ALARM UNIT (WALL @ +80" MINIMUM, U.O.N.) |
| © | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE RECESSED LIGHTING FIXTURE RECESSED FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE LILUMINATED EXIT SIGN MOUNTED ON CEILING ILLUMINATED EXIT SIGN MOUNTED ON WALL LOW LEVEL PHOTOLUMINESCENT EXIT SIGN MOUNTED ON WALL LOW LEVEL PHOTOLUMINESCENT EXIT SIGN MOUNTED ON WALL COMBINATION VOICE AND DATA OUTLET IN WALL, WITH TWO 'D' CABLES TO IDF + TWO 'T' CABLES TO TELEPHONE BACKBOARD. COMBINATION VOICE AND DATA OUTLET IN WALL, WITH TWO 'D' CABLES TO IDF + TWO 'T' CABLES TO TELEPHONE BACKBOARD. (1) (6) DATA OUTLET IN WALL @ +18", U.O.N. (1) MICROPHONE OUTLET IN WALL @ +18", U.O.N. (1) | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DUCT DETECTOR IN HVAC DUCT FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM SYNC MODULE FIRE ALARM MANUAL PULL STATION @ +48" TO TOP OF BOX, U.O.N. FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM ADDRESSABLE WATERFLOW / TAMPER SWITCH MODULE FIRE ALARM TAMPER SWITCH FIRE ALARM VISUAL ALARM UNIT (WALL@ +80" MINIMUM, U.O.N.) FIRE ALARM VISUAL ALARM UNIT (CEILING) FIRE ALARM VISUAL ALARM UNIT (CEILING) FIRE ALARM VISUAL ALARM UNIT (CEILING) INTERIOR FIRE ALARM HORN (WALL @ +10"-0", U.O.N.) EXTERIOR FIRE ALARM HORN (EXTERIOR WALL) VOICE EVACUATION SPEAKER/STROBE ALARM UNIT (WALL @ +80" MINIMUM, U.O.N.) |
| © | EXHAUST FAN OR FRACTIONAL HORSEPOWER MOTOR SURFACE MOUNTED RACEWAY, MOUNT @ +18" A.F.F. U.ON. RECESSED LED LIGHTING FIXTURE RECESSED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED LIGHTING FIXTURE SURFACE MOUNTED LED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED LED STRIP LIGHT SURFACE MOUNTED LED STRIP LIGHT WITH EMERGENCY BATTERY BACKUP POST TOP MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WALL MOUNTED LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP CEILING MOUNTED LIGHTING FIXTURE CEILING MOUNTED LIGHTING FIXTURE RECESSED LIGHTING FIXTURE RECESSED FIXTURE WITH EMERGENCY BATTERY BACKUP SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE SURFACE MOUNTED ROUND LIGHTING FIXTURE WITH EMERGENCY BATTERY BACKUP ILLUMINATED EXIT SIGN MOUNTED ON CEILING ILLUMINATED EXIT SIGN MOUNTED ON WALL LOW LEVEL PHOTOLUMINESCENT EXIT SIGN MOUNTED ON WALL POLE MOUNTED EXTERIOR LIGHTING FIXTURE COMBINATION VOICE AND DATA OUTLET IN WALL, WITH TWO 'D' CABLES TO IDF + TWO 'T' CABLES TO TELEPHONE BACKBOARD. COMBINATION VOICE AND DATA OUTLET IN WALL, WITH TWO 'D' CABLES TO IDF + TWO 'T' CABLES TO TELEPHONE BACKBOARD. (1) (6) DATA OUTLET IN WALL @ +18", U.O.N. (1) MICROPHONE OUTLET IN WALL @ +18", U.O.N. (1) MICROPHONE OUTLET IN WALL @ +18", U.O.N. (1) | | INTRUSION ALARM SYSTEM KEYPAD (WALL MOUNTED) INTRUSION ALARM SYSTEM CARD READER (WALL MOUNTED) INTRUSION ALARM SYSTEM FOB READER (WALL MOUNTED) SECURITY CAMERA (WALL MOUNTED) ROUGH-IN LOCATION PER PLAN FIRE ALARM SMOKE DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR ON CEILING, U.O.N. FIRE ALARM HEAT DETECTOR IN ATTIC U.O.N. FIRE ALARM DOOR RELEASE FIRE ALARM ADDRESSABLE CONTROL RELAY MODULE FIRE ALARM ADDRESSABLE INPUT/OUTPUT MODULE FIRE ALARM INDIVIDUAL ADDRESSABLE MODULE FIRE ALARM SYNC MODULE FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM WATERFLOW DETECTION SWITCH FIRE ALARM ADDRESSABLE WATERFLOW / TAMPER SWITCH MODULE FIRE ALARM TAMPER SWITCH FIRE ALARM VISUAL ALARM UNIT (WALL @ +80° MINIMUM, U.O.N.) FIRE ALARM VISUAL ALARM UNIT (CEILING) FIRE ALARM FIRE ALARM HORN (WALL @ +10°-0°, U.O.N.) EXTERIOR FIRE ALARM HORN (WALL @ +10°-0°, U.O.N.) EXTERIOR FIRE ALARM HORN (EXTERIOR WALL) VOICE EVACUATION SPEAKER/STROBE ALARM UNIT (CEILING) EXTERIOR VOICE EVACUATION SPEAKER/STROBE ALARM UNIT (CEILING) EXTERIOR VOICE EVACUATION SPEAKER/STROBE ALARM UNIT (CEILING) |


- (2) RUN 1"C TO NEAREST WALL, THEN RISE CONCEALED IN WALL AND STUB INTO ACCESSIBLE ATTIC SPACE ABOVE NEAREST T-BAR CEILING, U.O.N. FOR SINGLE SYSTEMS INDIVIDUAL FLOORBOXES. WHERE MULTIPLE SYSTEMS OCCUR WITHIN A COMMON FLOOR BOX, RUN TWO 1"C PER
- (3) SYSTEM IS ROUGH IN ONLY, PROVIDE BACKBOX, BLANK COVERPLATE AND CONDUIT STUB PER DETAIL PLANS.
- IN ADDITION TO CONDUITS SHOWN ON PLANS, STUB ONE 1 1/4"C, ONE 1"C, AND TWO 3/4"C (SPARE) INTO ACCESSIBLE ATTIC SPACE ABOVE NEAREST T-BAR CEILING, Ù.O.N. THIS REQUIREMENT APPLIES TO EACH POWER AND LIGHTING PANEL INDICATED FLUSH MOUNTED ON POWER PLAN.
- CEILING U.O.N.. REQUIREMENT APPLIES TO EACH SIGNAL SYSTEM T.C. INDICATED FLUSH MOUNTED ON SIGNAL PLAN.
- (6) 4S BACKBOX WITH SINGLE GANG TRIM AND COVERPLATE.
- (7) ORANGE DEVICE (ISOLATED GROUND DUPLEX RECEPT. ONLY) WITH ENGRAVED WORDING ON COVER PLATE ABOVE ISOLATED GROUND RECEPT.: "COMPUTER ONLY".


IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: **REVIEWED FOR** SS FLS ACS DATE: 12/18/2024





N.T.S. | 4






STOCKPILE# 356

(23) 36'X40'

C 24 3154 A/B/C C 24 3162 A/B/C C 24 3170 A/B/C C-24-3156 A/B/C C-24-3164 A/B/C C-24-3172 A/B/C C-24-3157 A/B/C C-24-3165 A/B/C C-24-3173 A/B/C C 24 3158 A/B/C C 24 3166 A/B/C C 24 3174 A/B/C C-24-3159 A/B/C C-24-3167 A/B/C C-24-3175 A/B/C C-24-3160 A/B/C C-24-3168 A/B/C



Acceptance tests be completed on newly installed or replacement of lighting controls, mechanical systems, fenestration, and process equipment before project completion per the California Energy Code Section 10-103. Acceptance tests must be performed by a certified Acceptance Test Technician (ATT). The Acceptance Testing procedures must be repeated, and deficiencies corrected until the installation of the specified systems conform and pass the required acceptance criteria. Completed NRCA forms shall be submitted to the project inspector and the district.

A DSA CERTIFIED INSPECTOR EMPLOYED BY THE DISTRICT (OWNER), AND APPROVED BY THE DIVISION OF THE STATE ARCHITECT SHALL PROVIDE CONTINUOUS INSPECTION OF THE WORK. THE DUTIES OF THE INSPECTOR ARE DEFINED IN SECTION 4-333 AND 4-342, PART 1, TITLE 24, CCR. CLASS R.B.I.P. FOR IN-PLANT INSPECTIONS.

SITE SPECIFIC:

COMPLY WITH CFC CHAPTERS 5 & 7, CBC CHAPTERS 3,5,7,11B & 14

NOTE: "THIS PC IS NOT APPROVED FOR CHAPTER 7A WILDLAND URBAN AREAS". THIS REVIEW IS PART OF THE SITE SPECIFIC PROJECT. THE APPROVAL OF THE PC DOES NOT INCLUDE THE SITE.



HIGH SEISMIC **DESIGN CRITERIA** FILE #: PC-128

2022 CBC

PC # 04-123059

24' x 40' EXPANDABLE TO 120' x 40' AT PULLIAM ELEMENTARY SCHOOL STOCKTON UNIFIED SCHOOL DISTRICT

| | | | | | | CONSTRUCT | TION OF CLASSING | DOM BUILDING (RELOCATABLE) |
|---|---|--|--|---|--|--|--|---|
| @ | AT ANCHOR BOLT | FIXT | FIXTURE | PAR | PARALLEL BOARD | | | |
| AB ABC | ANCHOR BOLT AGGREGATE BASE COURSE | FJT FLR | FLUSH JOINT FLOOR | PBD PCC | PARTICLE BOARD PRECAST CONCRETE | | | NDI/ |
| ABV | ABOVE | FLUR | FLUORESCENT | PCF | POUNDS PER CUBIC FOOT | 1 3COP | PE OF WO | JKK |
| AD ADD | AREA DRAIN ADDENDUM | FLEX FND | FLEXIBLE FOUNDATION | PCS PERF | PIECES PERFORATE (D) | | | |
| ADH | ADHESIVE | FO* | FACE OF | PERI | PERIMETER | BUILDING DESIGN | | |
| ADJ ADOH | ADJACENT, ADJUSTABLE ALTERNATE DIRECTION | FP FP'G | FIREPROOF (ED) FIREPROOFING | PFB PFS | PREFABRICATE (D) POUNDS PER SQUARE FOOT | | | |
| | OF HOOK | FR | FRAME (D)(ING) | PL | PLATE | NUMBER OF STORIES | : 1 | |
| AFF AGG | ABOVE FINISHED FLOOR AGGREGATE | FRC FRGD | FIRE RESISTANT COATING FORGED | PLBG PLF | PLUMBING POUNDS PER LINEAR FOOT | OCCUPANCY: | "E" and "B" (Design with Fl | oor Live Load 150 psf only must be used for occupancy B) |
| _ALT | ALTERNATE | FRMG | FRAMING | P.L. | PARALLAM | CONSTRUCTION TYPE | , - | |
| ALUM ANCH A | ALUMINUM NCHOR (AGE) | FT FTG | FOOT, FEET FOOTING | PLWD PMT | PLYWOOD PAVEMENT | | ¥ 50+15 PSF PARTITIO | ON |
| ANOD | ANODIZED | FURR | FURRED, FURRING | PNL | PANEL | | □ 100 PSF □ 150 PSF | |
| APPRX | APPROXIMATE | FV | FIELD VERIFY | POSTEN | POST TENSION (D) PRETENSIONED | FLOOR DEAD LOAD: | ¥WOOD FLOOR - 11 F | PSF |
| ARCH ASPH | ARCHITECT (URAL) ASPHALT | GA | GAUGE | PRETEN POLY | POLYETHYLENE | | □ CONC. FLOOR - 33 F | |
| AUTO | AUTOMATIC | GALV | GALVANIZED | PR | PAIR | | = 0011011 | 0. |
| В | воттом | GC GI | GENERAL CONTRACTOR GALVANIZED IRON | PRJ PSC | PROJECT PRESTRESSED CONCRETE | ROOF LIVE LOAD: | 20 PSF | |
| BB | BOND BEAM | GKT | GASKET | PSF | POUNDS PER SQUARE FOOT | ROOF SNOW LOAD: | 20 PSF | |
| BC | BOTTOM CHORD | GL GLM | GLASS, GLAZING | PSI PT | POUNDS PER SQUARE INCH | ROOF DEAD LOAD: | | EDDINIZI EDO 9 2DOE COLAD DANEL \ |
| BD BEG | BOARD BEGIN (ING) | GLIVI GP | GLULAM GALVANIZED PIPE | P.T. | POINT PRESSURE TREATED | | 10.5 PSF (INCLUDES 3 | SPRINKLERS & 3PSF SOLAR PANEL) |
| BEL | BELOW | GPM | GALLONS PER MINUTE | PTC | POST-TENSIONED CONCRETE | RAMPLIVE LOAD: | | |
| BIT BJT | BITUMINOUS BED JOINT | GPPL GRVL | GYPSUM PLASTER GRAVEL, GRANULAR | PTD PVC | PAINTED POLYVINYL CHLORIDE | FLOOD DESIGN: | | esigned to accommodate flood loads. If located in a |
| BLDG | BUILDING | GRD | GRADE, GRADING | PVMT | PAVEMENT | | | om a soils engineer is needed to validate the |
| BLK BLW | BLOCK ('G, ING) BELOW | GRN GSS | GRANITE GALVANIZED SHEET STEEL | QTY | QUANTITY | allowable soil values ass | sumed in this PC are still a | applicable. (OWNER SUPPLIED) |
| BM | BEAM | GT | GROUT | R | RADIUS, RISER | | | |
| BMK | BENCH MARK | GVL | GRAVEL | RAD | RADIUS | FLOOD DESIGN DATA | : PROJECT NOT LOCAT | TED IN A FLOOD ZONE |
| BO* BPL | BOTTOM OF BEARING PLATE | GWB GYP | GYPSUM WALLBOARD GYPSUM | RD RECT | ROOF DRAIN RETANGULAR | | | |
| BRD | BOARD | | | REF | REFERENCE, REFER TO | BUILDING AREA | NO OVERHANG | WITH OVERHANG (5' @ EA. END) |
| BRDG BRG | BRIDGING BEARING | H HBD | HIGH HARDBOARD | REINF REM | REFORCE (D) (ING) REMOVE | ALLOWABLE AREA | □ 24x40 960 sf | □ 24x40 1200 sf |
| BRK | BRICK | HC | HOLLOW CORE | REQD | REQUIRED | =9,500 sf | □ 36x40 1440 sf | ★ 36x40 1800 sf |
| BRZ | BRONZE | HD | HEAVY DUTY | REQS | REQUIREMENTS | ACTUAL AREA | □ 48x40 1920 sf | □ 48x40 2400 sf |
| BS BTWN | BOTH SIDES BETWEEN | HDNR HDR | HARDENER HEADER | RETG REV | RETAINING REVISION, REVISED | =4,800 SF | □ 60x40 2400 sf | □ 60x40 3000 sf |
| BVL | BEVELED | HDWR | HARDWARE | RFG | ROOFING | .,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,, | □ 72x40 2880 sf | □ 72x40 3600 sf |
| BW | BOTH WAYS | HDWD HES | HARDWOOD HIGH EARLY STRENGTH CEMENT | RFH RFL | ROOF HATCH REFLECT (ED)(IVE)(OR) | | □ 84x40 3360 sf | □ 84x40 4200 sf* |
| С | CHANNEL, COMPRESSION | HH | HANDHOLE | RFL RM | ROOM | , | □ 96x40 3840 sf | □ 96x40 4800 sf* |
| CAD | CADMIUM | HJT | HEADJOINT | RO | ROUGH OPENING | | □ 108x40 4320 sf* | □ 108x40 5400 sf* |
| CAM C/C | CAMBER CENTER TO CENTER | HK HM | HOOK HOLLOW METAL | RT RT | FIRE RETARDANT TREATED RUBBER TILE | | | |
| CEM | CEMENT | HORIZ | HORIZONTAL | RTG | RATING | *************************************** | □ 120x40 4800 sf* | □ 120x40 6000 sf* |
| CF CHAM | CUBIC FOOT CHAMFER | HPT HR | HIGH POINT HOUR | RVS RVT | REVERSE SIDE RIVET | | c report must be provided | I and approved by CGS for building area more than |
| CI | CAST IRON | HSA | HEADED STUD ANCHOR | KVI | RIVET | 4000 sf | | |
| CIP | CAST-IN-PLACE | HSB | HIGH STRENGHT BOLT | S | SOUTH | | | |
| CIR CIRC | CIRCLE CIRCUMFERENCE | HT HWD | HEIGHT HARDWOOD | SC SCHED | SOLID CORE SCHEDULE | ALLOWABLE SOIL PRI | ESSURE: □ WO | OD FTG -1000PSF 🗆 CONCRETE FTG 1500PSF |
| CJ | CONSTRUCTION JOINT | TIWE | TIARBWOOD | SDL | SUPERIMPOSED DEAD LOAD | | | |
| CJT | CONTROL JOINT | ID | INSIDE DIAMETER | SDS SE | SELF DRILL SCREW | FOUNDATION: | □ WOOD (conditional) | □ CONCRETE ABOVE GRADE |
| CLG CLK | CEILING CAULK, ('G, ING) | IN | INCHE (ES) | SDST | STRUCTURAL ENGINEER SELF-DRILL, SELF-TAP'G SCREW | | □ CONCRETE BELOW | GRADE <2160sf (conditional) |
| CLKG | CAULKING | INCL | INCLUDE (D), INCLUDING | SECT | SECTION | | □ CONCRETE BELOW | GRADE (AMM) |
| CLR CLS | CLEAR CLOSURE | INSUL INT | INSULATE, INSULATION INTERIOR | SF SHO | SQUARE FOOT, SQUARE FEET SHORE, SHORING | | SEE GENERAL NOT | E 14 BELOW |
| CM | CENTIMETER | | INTERMEDIATE | | SHEET | DO IO DEGIGNIED DAGE | TO ONLA DININIED CONINI | ECTION TO THE FOUNDATION. |
| CMP | | INTM | | SHT | | I PC IS DESIGNED BASE | ED ON A PINNED CONN | ECTION TO THE FOUNDATION. |
| | CORRUDATED METAL PIPE | | INVERT | SHTH | SHEATHING | PC IS DESIGNED BASE | ED ON A PINNED CONN | ECTION TO THE POUNDATION. |
| CMU CNTR | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER | INTM INV | INVERT JOIST | | SHEATHING SQUARE INCH SIMILAR | | | ECTION TO THE FOUNDATION. |
| CMU CNTR COL | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN | INTM | INVERT | SHTH SI SIM SL | SHEATHING SQUARE INCH SIMILAR SLOPE | CEC CLIMATE ZONE: | 1-16 | |
| CMU CNTR COL COG | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER | INTM INV | INVERT JOIST JOINT | SHTH SI SIM | SHEATHING SQUARE INCH SIMILAR | CEC CLIMATE ZONE: | | |
| CMU CNTR COL COG COMB CO | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) | INTM INV JST JT K KO | INVERT JOIST JOINT KIP (S) KNOCKOUT | SHTH SI SIM SL SLNT SMS SOG | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE | CEC CLIMATE ZONE: | 1-16 | |
| CMU CNTR COL COG COMB COMP COMP COMPOCOMP | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE | INTM INV JST JT K | INVERT JOIST JOINT KIP (S) | SHTH SI SIM SL SLNT SMS SOG SPA | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) | CEC CLIMATE ZONE: | 1-16 | |
| CMU CNTR COL COG COMB CI COMP CI COMPOCI CONN CONC | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE | INTM INV JST JT K KO KSI L | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) | CEC CLIMATE ZONE: | 1-16 | |
| CMU CNTR COL COG COMB CI COMP CI COMPOCI CONN CONC CONST | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE | INTM INV JST JT K KO KSI L | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE | CEC CLIMATE ZONE: | 1-16 | |
| CMU CNTR COL COG COMB CI COMP CI COMPOCI CONN CONC | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) | INTM INV JST JT K KO KSI L | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED | CEC CLIMATE ZONE: DESCRIPTION OF THE CONTROL OF TH | 1-16 CZ 3-15 RIGID R-5 / 1" SEE ALT-D1 | □ CZ 16 RIGID R-15 / 4" |
| CMU CNTR COL COG COMB C COMP C COMPOC CONN CONC CONST CONT CONTR COR | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED | INTM INV JST JT K KO KSI L LAM LB LBL LC | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STANDARD | CEC CLIMATE ZONE: UCZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SP | 1-16 DEE ALT-D1 SEED: Vult = 110 mph | |
| CMU CNTR COL COG COMB CI COMP CI COMPOCI CONNC CONC CONST CONT CONT COR COR CP | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION | INTM INV JST JT K KO KSI L LAM LB LBL | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL | CEC CLIMATE ZONE: UCZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SP RISK CATEGORY: | 1-16 DEE ALT-D1 SEE SEE ALT-D1 PEED: Vult = 110 mph | □ CZ 16 RIGID R-15 / 4" |
| CMU CNTR COL COG COMB C COMP C COMPOC CONN CONC CONST CONT CONTR COR | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED | INTM INV JST JT K KO KSI L LAM LB LBL LC LD LF LH | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE | CEC CLIMATE ZONE: UCZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SP | 1-16 DEE ALT-D1 SEED: Vult = 110 mph | □ CZ 16 RIGID R-15 / 4" |
| CMU CNTR COL COG COMB C COMP C COMPO CONC CONST CONT CONT COR CP CP CPR | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER | INTM INV JST JT K KO KSI L LAM LB LBL LC LD LF LH LL | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT STR | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURAL | CEC CLIMATE ZONE: UCZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SP RISK CATEGORY: EXPOSURE: | 1-16 CZ 3-15 RIGID R-5 / 1" SEE ALT-D1 PEED: Vult = 110 mph II C | □ CZ 16 RIGID R-15 / 4" |
| CMU CNTR COL COG COMB C COMP C COMPOC CONN CONC CONST CONT COR CP CP CPG | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING | INTM INV JST JT K KO KSI L LAM LB LBL LC LD LF LH | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE | CEC CLIMATE ZONE: UCZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SP RISK CATEGORY: | 1-16 CZ 3-15 RIGID R-5 / 1" SEE ALT-D1 PEED: Vult = 110 mph II C | □ CZ 16 RIGID R-15 / 4" |
| CMU CNTR COL COG COMB C COMP C COMPOC CONN CONC CONST CONT CONT COR CP CPG CPR CRS CS CTSK | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSINK COUNTERSUNK SCREW | INTM INV JST JT K KO KSI L LAM LB LC LD LF LH LLL LLH LLL LLY LPT | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT STR SYM | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURE SYMETRICAL, SYMETRY | CEC CLIMATE ZONE: CZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SP RISK CATEGORY: EXPOSURE: EARTHQUAKE DESIGN | 1-16 CZ 3-15 RIGID R-5 / 1" SEE ALT-D1 PEED: Vult = 110 mph II C | □ CZ 16 RIGID R-15 / 4" I, 3 sec GUST, Kzt = 1.0 |
| CMU CNTR COL COG COMB C COMPOC CONN CONC CONST CONT CONT COR CP CP CP CRS CS CTSK CU | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSINK COUNTERSUNK SCREW CUBIC | INTM INV JST JT K KO KSI L LAM LB LBL LC LD LF LH LLU LLH LLV LPT LT | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT STR SYM SYS | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURE SYMETRICAL, SYMETRY SYSTEM | CEC CLIMATE ZONE: CZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SP RISK CATEGORY: EXPOSURE: EARTHQUAKE DESIGN RISK CATEGORY: | 1-16 CZ 3-15 RIGID R-5 / 1" SEE ALT-D1 EED: Vult = 110 mph II C | □ CZ 16 RIGID R-15 / 4" I, 3 sec GUST, Kzt = 1.0 |
| CMU CNTR COL COG COMB C COMP C COMPOC CONN CONC CONST CONT CONT COR CP CPG CPR CRS CS CTSK | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSINK COUNTERSUNK SCREW | INTM INV JST JT K KO KSI L LAM LB LC LD LF LH LL LLH LLV LPT LT LT LVL | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT LIGHT LINTEL LEVEL (ING) | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT STR SYM SYS | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STANDARD STEEL STORAGE STRUCTURE STRUCTURE STRUCTURE SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM | CEC CLIMATE ZONE: | 1-16 DEED: Vult = 110 mph II C FACTOR: | □ CZ 16 RIGID R-15 / 4" I, 3 sec GUST, Kzt = 1.0 II I = 1 |
| CMU CNTR COL COG COMB C COMP C COMPOC CONN CONC CONST CONT CONT COR CP CPG CPR CRS CS CTSK CU CX CY | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSINK COUNTERSUNK SCREW CUBIC CONNECTION CUBIC YARD | INTM INV JST JT K KO KSI L LAM LB LBL LC LD LF LH LLL LLH LLL LT LT LT LT LT LW | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT LIGHT LINTEL LEVEL (ING) LIGHT WEIGHT | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT STR SYM SYS T T&B T&G | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURE STRUCTURAL SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM TONGUE AND GROOVE | CEC CLIMATE ZONE: CZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SP RISK CATEGORY: EXPOSURE: EARTHQUAKE DESIGN RISK CATEGORY: | 1-16 DEED: Vult = 110 mph II C FACTOR: | □ CZ 16 RIGID R-15 / 4" I, 3 sec GUST, Kzt = 1.0 II I = 1 □Ss = 2.33, □Ss = 2.8** |
| CMU CNTR COL COG COMB C COMP C COMP C CONN CONC CONST CONT CONTR COP CPG CPR CRS CS CTSK CU CX | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSUNK SCREW CUBIC CONNECTION | INTM INV JST JT K KO KSI L LAM LB LC LD LF LH LL LLH LLV LPT LT LT LVL | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT LIGHT LINTEL LEVEL (ING) | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT STR SYM SYS | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURE STRUCTURAL SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM TONGUE AND GROOVE TOP CHORD TESION, TENSILE | CEC CLIMATE ZONE: | 1-16 DEED: Vult = 110 mph II C FACTOR: | □ CZ 16 RIGID R-15 / 4" I, 3 sec GUST, Kzt = 1.0 II I = 1 □Ss = 2.33, □Ss = 2.8** S1 = 1.99 |
| CMU CNTR COL COG COMB C COMP C COMPOC CONN CONC CONT CONT CONT COR CP CPG CPR CRS CS CTSK CU CX CY D DBL DEF | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSINK COUNTERSINK COUNTERSUNK SCREW CUBIC CONNECTION CUBIC YARD DEEP, DEPTH DOUBLE DEFLECTION | INTM INV JST JT K KO KSI L LAM LB LBL LC LD LF LH LLL LLU LLH LLV LPT LT LT LT LVL LW LWC LWF | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LOW POINT LIGHT LINTEL LEVEL (ING) LIGHT WEIGHT LIGHT WEIGHT CONCRETE LIGHT WEIGHT FILL | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT STR SYM SYS T T&B T&G TC TEN TEMP | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STARGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURAL SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM TONGUE AND GROOVE TOP CHORD TESION, TENSILE TEMPORARY, TEMPERATURE | CEC CLIMATE ZONE: CZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SPRISK CATEGORY: EXPOSURE: EARTHQUAKE DESIGN RISK CATEGORY: SEISMIC IMPORTANCE MAPPED SPECTRAL R DRIFT LIMIT: | 1-16 DEED: Vult = 110 mph II C FACTOR: | □ CZ 16 RIGID R-15 / 4" I, 3 sec GUST, Kzt = 1.0 II I = 1 □Ss = 2.33, □Ss = 2.8** |
| CMU CNTR COL COG COMB C COMP C COMPOC CONN CONC CONST CONT CONT COP CPG CPR CRS CS CTSK CU CX CY D DBL | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSUNK SCREW CUBIC CONNECTION CUBIC YARD DEEP, DEPTH DOUBLE | INTM INV JST JT K KO KSI L LAM LB LBL LC LD LF LH LLV LPT LT LTL LVL LW LWC | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT LIGHT LINTEL LEVEL (ING) LIGHT WEIGHT LIGHT WEIGHT LIGHT WEIGHT LONG LEG HORIZONTAL LOW POINT | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STR STRUCT STR SYM SYS T T&B T&G TC TEN | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURE STRUCTURAL SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM TONGUE AND GROOVE TOP CHORD TESION, TENSILE | CEC CLIMATE ZONE: DESCRIPTION OF THE PROPERTY | 1-16 DEED: Vult = 110 mph II C FACTOR: RESPONSE: | □ CZ 16 RIGID R-15 / 4" I, 3 sec GUST, Kzt = 1.0 II I = 1 □Ss = 2.33, □Ss = 2.8** S1 = 1.99 |
| CMU CNTR COL COG COMB C COMPOC CONN CONC CONT CONT CONT CONT COR CP CPG CPR CRS CS CTSK CU CX CY D DBL DEF DEG DEM0 DEP | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSUNK SCREW CUBIC CONNECTION CUBIC YARD DEEP, DEPTH DOUBLE DEFLECTION DEGREE DEMOLISH, DEMOLITION DEPRESSED | INTM INV JST JT K KO KSI L LAM LB LC LD LF LH LL LLH LLV LPT LT LT LT LVL LW LWC LWF M MATL MAS | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT LIGHT LINTEL LEVEL (ING) LIGHT WEIGHT LIGHT WEIGHT LIGHT WEIGHT LIGHT WEIGHT FILL METER (S) MOMENT MATERIAL MASONRY | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT STR SYM SYS T T&B T&G TC TEN TEMP THD THK TMPD | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURE STRUCTURAL SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM TONGUE AND GROOVE TOP CHORD TESION, TENSILE TEMPORARY, TEMPERATURE THREAD (ED) THICK (NESS) TEMPERED | CEC CLIMATE ZONE: CZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SPRISK CATEGORY: EXPOSURE: EARTHQUAKE DESIGN RISK CATEGORY: SEISMIC IMPORTANCE MAPPED SPECTRAL R DRIFT LIMIT: | 1-16 DEED: Vult = 110 mph II C FACTOR: RESPONSE: | □ CZ 16 RIGID R-15 / 4" I, 3 sec GUST, Kzt = 1.0 II I = 1 □Ss = 2.33, □Ss = 2.8** S1 = 1.99 0.02 x H _{story} x 12 = 2.82 PER TABLE 12.12-1 |
| CMU CNTR COL COG COMB C COMP C COMPOC CONN CONC CONST CONT CONT COR CP CPG CPR CRS CS CTSK CU CX CY D DBL DEF DEG DEM0 DEP DEPT | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSINK COUNTERSINK COUNTERSUNK SCREW CUBIC CONNECTION CUBIC YARD DEEP, DEPTH DOUBLE DEFLECTION DEGREE DEMOLISH, DEMOLITION DEPRESSED DEPARTMENT | INTM INV JST JT K KO KSI L LAM LB LBLC LD LF LH LLV LY LUV LY LT LT LT LT LT LT LW LWC LWF M MATL MASS MAX | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT LIGHT LINTEL LEVEL (ING) LIGHT WEIGHT CONCRETE LIGHT WEIGHT FILL METER (S) MOMENT MASONRY MAXIMUM | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT STR SYM SYS T T&B T&G TC TEN TEMP THD THK TMPD TO* | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURE STRUCTURAL SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM TONGUE AND GROOVE TOP CHORD TESION, TENSILE TEMPORARY, TEMPERATURE THREAD (ED) THICK (NESS) TEMPERED TOP OF | CEC CLIMATE ZONE: UCZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SPRISK CATEGORY: EXPOSURE: EARTHQUAKE DESIGN RISK CATEGORY: SEISMIC IMPORTANCE MAPPED SPECTRAL R DRIFT LIMIT: SITE CLASS: SEISMIC DESIGN CATE | 1-16 DEED: Vult = 110 mph II C FACTOR: RESPONSE: | □ CZ 16 RIGID R-15 / 4" I, 3 sec GUST, Kzt = 1.0 II I = 1 □Ss = 2.33, □Ss = 2.8** S1 = 1.99 0.02 x H _{story} x 12 = 2.82 PER TABLE 12.12-1 |
| CMU CNTR COL COG COMB C COMPOC CONN CONC CONT CONT CONT CONT COR CP CPG CPR CRS CS CTSK CU CX CY D DBL DEF DEG DEM0 DEP | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSUNK SCREW CUBIC CONNECTION CUBIC YARD DEEP, DEPTH DOUBLE DEFLECTION DEGREE DEMOLISH, DEMOLITION DEPRESSED | INTM INV JST JT K KO KSI L LAM LB LC LD LF LH LL LLH LLV LPT LT LT LT LVL LW LWC LWF M MATL MAS | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT LIGHT LINTEL LEVEL (ING) LIGHT WEIGHT CONCRETE LIGHT WEIGHT CONCRETE LIGHT WEIGHT FILL METER (S) MOMENT MATERIAL MASONRY MAXIMUM MACHINE BOLT MEMBER | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT STR SYM SYS T T&B T&G TC TEN TEMP THD THK TMPD | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURE STRUCTURAL SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM TONGUE AND GROOVE TOP CHORD TESION, TENSILE TEMPORARY, TEMPERATURE THREAD (ED) THICK (NESS) TEMPERED | CEC CLIMATE ZONE: UCZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SPRISK CATEGORY: EXPOSURE: EARTHQUAKE DESIGN RISK CATEGORY: SEISMIC IMPORTANCE MAPPED SPECTRAL R DRIFT LIMIT: SITE CLASS: SEISMIC DESIGN CATE Note: For SDC (E) site s | 1-16 DEED: Vult = 110 mph II C FACTOR: RESPONSE: CEGORY: CPECTOR = CONTRIBUTE CONTRIB | □ CZ 16 RIGID R-15 / 4" I, 3 sec GUST, Kzt = 1.0 II I = 1 □ Ss = 2.33, □ Ss = 2.8** S1 = 1.99 0.02 x H _{story} x 12 = 2.82 PER TABLE 12.12-1 D-DEFAULT* E |
| CMU CNTR COL COG COMP CC COMPOCC CONN CONC CONT CONT CONT CONT COR CP CPG CPR CRS CS CTSK CU CX CY D DBL DEF DEG DEM0 DEP DEPT DIAG DIA | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSINK COUNTERSINK COUNTERSUNK SCREW CUBIC CONNECTION CUBIC YARD DEEP, DEPTH DOUBLE DEFLECTION DEGREE DEMOLISH, DEMOLITION DEPRESSED DEPARTMENT DETAIL DIAGONAL DIAMETER | INTM INV JST JT K KO KSI L LAM LB LC LD LF LH LL LV LV | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT LIGHT LINTEL LEVEL (ING) LIGHT WEIGHT LIGHT WEIGHT LIGHT WEIGHT FILL METER (S) MOMENT MATERIAL MASONRY MAXIMUM MACHINE BOLT MEMBER MOMENT CONNECTION | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STR STRUCT STR SYM SYS T T&B T&G TC TEN TEMP THD THK TMPD TO* TL TR TS | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURAL SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM TONGUE AND GROOVE TOP CHORD TESION, TENSILE TEMPORARY, TEMPERATURE THREAD (ED) THICK (NESS) TEMPERED TOP OF TOTAL LOAD TREAD TUBE STEEL | CEC CLIMATE ZONE: CZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SPRISK CATEGORY: EXPOSURE: EARTHQUAKE DESIGN RISK CATEGORY: SEISMIC IMPORTANCE MAPPED SPECTRAL R DRIFT LIMIT: SITE CLASS: SEISMIC DESIGN CATE Note: For SDC (E) site s and/or meets other exem | 1-16 DEED: Vult = 110 mph II C EFACTOR: RESPONSE: DEGORY: Specific motion analysis is notions in DSA IR A-4 | II |
| CMU CNTR COL COG COMP CC COMP CC CONN CONC CONST CONT CONT COP CPG CPR CRS CS CTSK CU CX CY D DBL DEF DEG DEMO DEP DEPT DIAG | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSINK COUNTERSUNK SCREW CUBIC CONNECTION CUBIC YARD DEEP, DEPTH DOUBLE DEFLECTION DEGREE DEMOLISH, DEMOLITION DEPRESSED DEPARTMENT DETAIL DIAGONAL DIAMETER DIMENSION (ED) | INTM INV JST JT K KO KSI L LAM LB LBL LC LD LF LH LLV LPT LTL LTL LVL LWC LWF M MATL MAS MAX MB MBR | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT LIGHT LINTEL LEVEL (ING) LIGHT WEIGHT LIGHT WEIGHT LIGHT WEIGHT LIGHT WEIGHT FILL METER (S) MOMENT MATERIAL MASONRY MAXIMUM MACHINE BOLT MEMBER MOMENT CONNECTION MECHANICAL | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT STR SYM SYS T T&B T&G TC TEN TEMP THD THK TMPD TO* TIL TR | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURE STRUCTURAL SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM TONGUE AND GROOVE TOP CHORD TESION, TENSILE TEMPORARY, TEMPERATURE THREAD (ED) THICK (NESS) TEMPERED TOP OF TOTAL LOAD TREAD | CEC CLIMATE ZONE: CZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SPRISK CATEGORY: EXPOSURE: EARTHQUAKE DESIGN RISK CATEGORY: SEISMIC IMPORTANCE MAPPED SPECTRAL R DRIFT LIMIT: SITE CLASS: SEISMIC DESIGN CATE Note: For SDC (E) site sand/or meets other exem SHORT/LONG PERIOD | 1-16 DEED: Vult = 110 mph II C EFACTOR: RESPONSE: EGORY: Specific motion analysis is nptions in DSA IR A-4 D SITE COEFFICIENT: | II I = 1 □Ss = 2.33, □Ss = 2.8** S1 = 1.99 0.02 x H _{story} x 12 = 2.82 PER TABLE 12.12-1 D-DEFAULT* E not required if not in a seismic hazard zone □Fa = 1.2, □Fa=1.0**, Fv = 1.7 |
| CMU CNTR COL COG COMP CC COMPOCC CONN CONC CONST CONT CONT COR CP CPG CPR CRS CS CTSK CU CX CY D DBL DEF DEG DEM0 DEP DEPT DET DIAG DIM DIV DL | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSINK COUNTERSINK COUNTERSUNK SCREW CUBIC CONNECTION CUBIC CONNECTION CUBIC YARD DEEP, DEPTH DOUBLE DEFLECTION DEGREE DEMOLISH, DEMOLITION DEPRESSED DEPARTMENT DETAIL DIAGONAL DIAMETER DIMENSION (ED) DIVISION DEAD LOAD | INTM INV JST JT K KO KSI L LAM LB LBL LC LD LF LH LL LL LL LH LLV LPT LT LT LT LV LW LWC LWC M MATL MAS MAX MB MCON MECH MECH MET | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT LIGHT LINTEL LEVEL (ING) LIGHT WEIGHT CONCRETE LIGHT WEIGHT FILL METER (S) MOMENT MATERIAL MASONRY MAXIMUM MACHINE BOLT MEMBER MOMENT CONNECTION MECHANICAL MEDIUM METAL | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STRUCT STR SYM SYS T T&B T&G TC TEN TEMP THK TMPD TO* TL TS TYP UC | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURAL SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM TONGUE AND GROOVE TOP CHORD TESION, TENSILE TEMPORARY, TEMPERATURE THREAD (ED) THICK (NESS) TEMPERED TOP OF TOTAL LOAD TREAD TUBE STEEL TYPICAL UNDERCUT | CEC CLIMATE ZONE: CZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SPRISK CATEGORY: EXPOSURE: EARTHQUAKE DESIGN RISK CATEGORY: SEISMIC IMPORTANCE MAPPED SPECTRAL R DRIFT LIMIT: SITE CLASS: SEISMIC DESIGN CATE Note: For SDC (E) site s and/or meets other exem | 1-16 DEED: Vult = 110 mph II C EFACTOR: RESPONSE: EGORY: Specific motion analysis is nptions in DSA IR A-4 D SITE COEFFICIENT: | II I = 1 □Ss = 2.33, □Ss = 2.8** S1 = 1.99 0.02 x H _{story} x 12 = 2.82 PER TABLE 12.12-1 D-DEFAULT* E not required if not in a seismic hazard zone □Fa = 1.2, □Fa=1.0**, Fv = 1.7 Sds = 1.86 |
| CMU CNTR COL COG COMP OC COMPOCI CONN CONC CONT CONT CONT CONT COR CP CPG CPR CRS CS CTSK CU CX CY D DBL DEF DEG DEM0 DEP DEPT DET DIAG DIM DIV DL DN | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSINK COUNTERSINK COUNTERSUNK SCREW CUBIC CONNECTION CUBIC YARD DEEP, DEPTH DOUBLE DEFLECTION DEGREE DEMOLISH, DEMOLITION DEPRESSED DEPARTMENT DETAIL DIAGONAL DIAMETER DIMENSION (ED) DIVISION DEAL TERMONTORION DEAL TO THE TO | INTM INV JST JT K KO KSI L LAM LB LBLC LD LF LH LLV LV LV LV LW LWC LWF M MATL MASS MAX MB MBR MCOH MED MET MEMB | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT LIGHT LINTEL LEVEL (ING) LIGHT WEIGHT LIGHT WEIGHT LIGHT WEIGHT LIGHT WEIGHT FILL METER (S) MOMENT MATERIAL MASONRY MAXIMUM MACHINE BOLT MEMBER MOMENT CONNECTION MECHANICAL MEDIUM METAL METAL MEMBER | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT STR SYM SYS T T&B T&G TC TEMP THD THK TMPD TO* TL TR TYP UC UGD | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURE STRUCTURAL SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM TONGUE AND GROOVE TOP CHORD TESION, TENSILE TEMPORARY, TEMPERATURE THREAD (ED) THICK (NESS) TEMPERED TOP OF TOTAL LOAD TREAD TUBE STEEL TYPICAL UNDERCUT UNDERGROUND | CEC CLIMATE ZONE: CZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SPRISK CATEGORY: EXPOSURE: EARTHQUAKE DESIGN RISK CATEGORY: SEISMIC IMPORTANCE MAPPED SPECTRAL RISTE CLASS: SEISMIC DESIGN CATE Note: For SDC (E) site sand/or meets other exem SHORT/LONG PERIOD DEISIGN SPECTRAL R | 1-16 DEED: Vult = 110 mph II C FACTOR: RESPONSE: EGORY: Specific motion analysis is nptions in DSA IR A-4 SITE COEFFICIENT: ESPONSE: | II I = 1 □Ss = 2.33, □Ss = 2.8** S1 = 1.99 0.02 x H _{story} x 12 = 2.82 PER TABLE 12.12-1 D-DEFAULT* E not required if not in a seismic hazard zone □Fa = 1.2, □Fa=1.0**, Fv = 1.7 Sds = 1.86 Sd1 = 2.26 |
| CMU CNTR COL COG COMP CC COMPOCC CONN CONC CONST CONT CONTR COR CP CPG CPR CRS CS CTSK CU CX CY D DBL DEF DEG DEMO DEP DEPT DET DIAG DIM DIV DL DN DO DP | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSINK COUNTERSINK COUNTERSINK COUNTERSUNK SCREW CUBIC CONNECTION CUBIC YARD DEEP, DEPTH DOUBLE DEFLECTION DEGREE DEMOLISH, DEMOLITION DEPRESSED DEPARTMENT DETAIL DIAGONAL DIAMETER DIMENSION (ED) DIVISION DEAD LOAD DOWN DITTO DAMPROOFING | INTM INV JST JT K KO KSI L LAM LB LBL LC LD LF LH LLV LPT LT LTL LV LWC LWF M MATL MAS MAX MB MBR MCONN MECD MET MEMB MEP | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT LIGHT LINTEL LEVEL (ING) LIGHT WEIGHT CONCRETE LIGHT WEIGHT CONCRETE LIGHT WEIGHT FILL METER (S) MOMENT MATERIAL MASONRY MAXIMUM MACHINE BOLT MEMBER MOMENT CONNECTION MECHANICAL MEDIUM METAL MEDIUM METAL MEMBER MICHANICAL, ELECTRICAL, & PLUMBING | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT STR SYM SYS T T&B T&B TC TEN TEMP THD TO* TL TR TS TYP UC UGD UND | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURE STRUCTURAL SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM TONGUE AND GROOVE TOP CHORD TESION, TENSILE TEMPORARY, TEMPERATURE THREAD (ED) THICK (NESS) TEMPERED TOP OF TOTAL LOAD TREAD TUBE STEEL TYPICAL UNDERCUT UNDERGROUND UNDERGROUND UNDERGROUND UNDERGROUND UNDER SEALEN SLAME SL | CEC CLIMATE ZONE: CZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SPRISK CATEGORY: EXPOSURE: EARTHQUAKE DESIGN RISK CATEGORY: SEISMIC IMPORTANCE MAPPED SPECTRAL R DRIFT LIMIT: SITE CLASS: SEISMIC DESIGN CATE Note: For SDC (E) site sand/or meets other exem SHORT/LONG PERIOD | 1-16 DEED: Vult = 110 mph II C FACTOR: RESPONSE: EGORY: Specific motion analysis is nptions in DSA IR A-4 SITE COEFFICIENT: ESPONSE: | II I = 1 □Ss = 2.33, □Ss = 2.8** S1 = 1.99 0.02 x H _{story} x 12 = 2.82 PER TABLE 12.12-1 D-DEFAULT* E not required if not in a seismic hazard zone □Fa = 1.2, □Fa=1.0**, Fv = 1.7 Sds = 1.86 Sd1 = 2.26 0.373 (using reduced Sds as allowed by ASCE |
| CMU CNTR COL COG COMP CC COMPOCC CONN CONC CONST CONT CONT CONT COR CP CPG CPR CRS CS CTSK CU CX CY D DBL DEF DEG DEMO DEP DEPT DET DIAG DIM DIV DN DO DP DWL | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSINK COUNTERSUNK SCREW CUBIC CONNECTION CUBIC YARD DEEP, DEPTH DOUBLE DEFLECTION DEGREE DEMOLISH, DEMOLITION DEPRESSED DEPARTMENT DETAIL DIAGONAL DIAMETER DIMENSION (ED) DIVISION DEAD LOAD DOWN DITTO DAMPROOFING DOWEL (ED) | INTM INV JST JT K KO KSI L LAM LB LBL LC LD LF LH LL LL LL LL LL LL LL LL LL LV LW LWC LWF M MATL MAS MB MBR MCOH MED MED MED MED MEM MEP MFD | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT LIGHT LINTEL LEVEL (ING) LIGHT WEIGHT LIGHT WEIGHT LIGHT WEIGHT LIGHT WEIGHT FILL METER (S) MOMENT MATERIAL MASONRY MAXIMUM MACHINE BOLT MEMBER MOMENT CONNECTION MECHANICAL MEDIUM METAL MEMBER MECHANICAL, ELECTRICAL, & PLUMBING METAL FLOOR DECKING | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STRUCT STR SYM SYS T T&B T&C TEN TEMP THK TMPD TO* TL TS TY UC UGD UL UND UNF | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURAL SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM TONGUE AND GROOVE TOP CHORD TESION, TENSILE TEMPORARY, TEMPERATURE THREAD (ED) THICK (NESS) TEMPERED TOP OF TOTAL LOAD TREAD TUBE STEEL TYPICAL UNDERCUT UNDERGROUND UNDERWRITERS LABORATORY UNDER UNFINISHED | CEC CLIMATE ZONE: CZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SPRISK CATEGORY: EXPOSURE: EARTHQUAKE DESIGN RISK CATEGORY: SEISMIC IMPORTANCE MAPPED SPECTRAL RISTE CLASS: SEISMIC DESIGN CATE Note: For SDC (E) site sand/or meets other exem SHORT/LONG PERIOD DEISIGN SPECTRAL R | 1-16 DEED: Vult = 110 mph II C FACTOR: RESPONSE: EGORY: Specific motion analysis is nptions in DSA IR A-4 SITE COEFFICIENT: ESPONSE: | II I = 1 □Ss = 2.33, □Ss = 2.8** S1 = 1.99 0.02 x H _{story} x 12 = 2.82 PER TABLE 12.12-1 D-DEFAULT* E not required if not in a seismic hazard zone □Fa = 1.2, □Fa=1.0**, Fv = 1.7 Sds = 1.86 Sd1 = 2.26 |
| CMU CNTR COL COG COMP CC COMPOCC CONN CONC CONST CONT CONTR COR CP CPG CPR CRS CS CTSK CU CX CY D DBL DEF DEG DEMO DEP DEPT DET DIAG DIM DIV DL DN DO DP | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSINK COUNTERSINK COUNTERSINK COUNTERSUNK SCREW CUBIC CONNECTION CUBIC YARD DEEP, DEPTH DOUBLE DEFLECTION DEGREE DEMOLISH, DEMOLITION DEPRESSED DEPARTMENT DETAIL DIAGONAL DIAMETER DIMENSION (ED) DIVISION DEAD LOAD DOWN DITTO DAMPROOFING | INTM INV JST JT K KO KSI L LAM LB LBL LC LD LF LH LLV LPT LT LTL LV LWC LWF M MATL MAS MAX MB MBR MCONN MECD MET MEMB MEP | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT LIGHT LINTEL LEVEL (ING) LIGHT WEIGHT CONCRETE LIGHT WEIGHT CONCRETE LIGHT WEIGHT FILL METER (S) MOMENT MATERIAL MASONRY MAXIMUM MACHINE BOLT MEMBER MOMENT CONNECTION MECHANICAL MEDIUM METAL MEDIUM METAL MEMBER MICHANICAL, ELECTRICAL, & PLUMBING | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STD STL STOR STRUCT STR SYM SYS T T&B T&B TC TEN TEMP THD TO* TL TR TS TYP UC UGD UND | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURE STRUCTURAL SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM TONGUE AND GROOVE TOP CHORD TESION, TENSILE TEMPORARY, TEMPERATURE THREAD (ED) THICK (NESS) TEMPERED TOP OF TOTAL LOAD TREAD TUBE STEEL TYPICAL UNDERCUT UNDERGROUND UNDERGROUND UNDERGROUND UNDERGROUND UNDER SEALEN SLAME SL | CEC CLIMATE ZONE: CZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SPRISK CATEGORY: EXPOSURE: EARTHQUAKE DESIGN RISK CATEGORY: SEISMIC IMPORTANCE MAPPED SPECTRAL RISTE CLASS: SEISMIC DESIGN CATE Note: For SDC (E) site sand/or meets other exem SHORT/LONG PERIOD DEISIGN SPECTRAL R | 1-16 DEED: Vult = 110 mph II C FACTOR: RESPONSE: EGORY: Specific motion analysis is nptions in DSA IR A-4 SITE COEFFICIENT: ESPONSE: | II I = 1 □Ss = 2.33, □Ss = 2.8** S1 = 1.99 0.02 x H _{story} x 12 = 2.82 PER TABLE 12.12-1 D-DEFAULT* E not required if not in a seismic hazard zone □Fa = 1.2, □Fa=1.0**, Fv = 1.7 Sds = 1.86 Sd1 = 2.26 0.373 (using reduced Sds as allowed by ASCE |
| CMU CNTR COL COG COMP CC COMPOCC CONN CONC CONST CONT CONT CONT COR CP CPG CPR CRS CS CTSK CU CX CY D DBL DEF DEG DEMO DEP DEPT DET DIAG DIM DIV DN DO DP DWL | CORRUDATED METAL PIPE CONCRETE MASONRY UNIT CENTER COLUMN CENTER OF GRAVITY OMBINATION OMPRESS (ED)(ION)(IBLE) OMPOSITE CONNECT (ION) CONCRETE CONSTRUCT (ION) (ED) CONTINUE, CONTINUOUS CONTRACTOR CORRUGATED COMPLETE PENETRATION COPING COPPER COURSE (S) COUNTERSINK COUNTERSUNK SCREW CUBIC CONNECTION CUBIC YARD DEEP, DEPTH DOUBLE DEFLECTION DEGREE DEMOLISH, DEMOLITION DEPRESSED DEPARTMENT DETAIL DIAGONAL DIAMETER DIMENSION (ED) DIVISION DEAD LOAD DOWN DITTO DAMPROOFING DOWEL (ED) | INTM INV JST JT K KO KSI L LAM LB LBLC LD LF LH LLV LY LT LT LT LT LT LT LV LW LWC LWF MATS MAX MB MBR MCON MED MET MED MFD MFR | INVERT JOIST JOINT KIP (S) KNOCKOUT KIPS PER SQUARE INCH LONG, LENGTH LAMINATE (D) POUND, LAG BOLT LABEL LIGHT CONTROL DEVELOPMENT LENGHT LINEAR FOOT LEFT HAND LIVE LOAD LONG LEG HORIZONTAL LONG LEG VERTICAL LOW POINT LIGHT LINTEL LEVEL (ING) LIGHT WEIGHT LIGHT WEIGHT LIGHT WEIGHT LIGHT WEIGHT FILL METER (S) MOMENT MATERIAL MASONRY MAXIMUM MACHINE BOLT MEMBER MOMENT CONNECTION MECHANICAL MEDIUM METAL MEMBER MECHANICAL, ELECTRICAL, & PLUMBING METAL FLOOR DECKING MANUFACTURE (R) (ED) | SHTH SI SIM SL SLNT SMS SOG SPA SPC SPEC SQ SSTL STG STRUCT STR SYM SYS T T&B T&C TEN TEMP THK TMPD TO* TL TS TY UC UGD UL UND UNF | SHEATHING SQUARE INCH SIMILAR SLOPE SEALANT SHEET METAL SCREW SLAB ON GRADE SPACE, (ING) SPACER SPECIFICATION (S) SQUARE STAINLESS STEEL STAGGERED STANDARD STEEL STORAGE STRUCTURE STRUCTURAL SYMETRICAL, SYMETRY SYSTEM TOP, TORSION, TREAD TOP AND BOTTOM TONGUE AND GROOVE TOP CHORD TESION, TENSILE TEMPORARY, TEMPERATURE THREAD (ED) THICK (NESS) TEMPERED TOP OF TOTAL LOAD TREAD TUBE STEEL TYPICAL UNDERCUT UNDERGROUND UNDERWRITERS LABORATORY UNDER UNFINISHED | CEC CLIMATE ZONE: CZ 1-2 RIGID R-10 / 2" WIND DESIGN ULTIMATE DESIGN SPRISK CATEGORY: EXPOSURE: EARTHQUAKE DESIGN RISK CATEGORY: SEISMIC IMPORTANCE MAPPED SPECTRAL RISTE CLASS: SEISMIC DESIGN CATE Note: For SDC (E) site sand/or meets other exem SHORT/LONG PERIOD DEISIGN SPECTRAL R | 1-16 DEED: Vult = 110 mph II C FACTOR: RESPONSE: EGORY: Specific motion analysis is nptions in DSA IR A-4 SITE COEFFICIENT: ESPONSE: | II I = 1 □Ss = 2.33, □Ss = 2.8** S1 = 1.99 0.02 x H _{story} x 12 = 2.82 PER TABLE 12.12-1 D-DEFAULT* E not required if not in a seismic hazard zone □Fa = 1.2, □Fa=1.0**, Fv = 1.7 Sds = 1.86 Sd1 = 2.26 0.373 (using reduced Sds as allowed by ASCE |

VERTICAL VERTICAL GRAIN

VERIFY IN FIELD

WIDE FLANGE

WROUGHT IRON

WATERPROFFING

WORKING POINT

WATER STOP

WATER REPELLENT

WALL TO WALL (W/W)

WIRE MESH

WITHOUT

WOOD

V-JOINTED

MEMBRANE MASONRY OPENING

MOVABLE

NATURAL NAILABLE

NORTH, NEW

NONMETALLIC

NOT TO SCALE

ON CENTER

OVERHEAD

OUTSIDE DIAMETER

OVALHEAD MACHINE SCREW

OPNG OPENING
OPP OPPOSITE
OFOI OWNER FURNISHED OWNER INSTALLED

OVALHEAD WOOD SCREW

OPEN-WEB JOINT (S)

OPPOSITE HAND

EXPANSION BOLT

EXPANSION JOINT

EQUAL, EQUALIBRIUM

EXCAVATE (D) (ION)

EXPANDED METAL PLATE

FURNISHED BY OTHERS

FLATHEAD MACHINE SCREW

FLATHEAD WOOD SCREW

FLOOR DRAIN

CONSTRUCTION OF CLASSROOM BUILDING (RELOCATABLE)

BASIC SEISMIC FORCE-RESISTING SYS: **EQUIVALENT LATERAL FORCE ANALYSIS PROCEDURE:** WOOD FLOOR, LL ≤ 100, BASE SHEAR= 26.44 kip BASE SHEAR PER 24X40 MODULE: WOOD FLOOR, LL = 150, BASE SHEAR= 39.87 kip CONC. FLOOR, LL ≤ 100, BASE SHEAR= 34.68 kip CONC. FLOOR, LL = 150, BASE SHEAR= 48.1 kip

NOTE: FOR SDC (E) SITE SPECIFIC MOTION ANALYSIS IS NOT REQUIRED IF NOT IN A SEISMIC HAZARD ZONE AND/OR MEETS OTHER EXEMPTION IN DSA IR A-4 Site Specific Ground Motion Analysis is not required because the value of SM1 is increased by 50% in accordance with excecption of item #1 of section 11.4.8 per supplement 3 of ASCE 7-16 **Geo-Hazard report with verification of site Class D must be provided and approved by CGS for site specific ARES with Ss>2.33

PARTIAL LIST OF APPLICABLE CODES AS OF January 1, 2023

2022 California Administrative Code (CAC), Part 1, Title 24 CCR

2022 California Building Code (CBC), Part 2, Title 24 CCR

2022 California Electrical Code (CEC), Part 3, Title 24 CCR

2022 California Mechanical Code (CMC), Part 4, Title 24 CCR

2022 California Plumbing Code (CPC), Part 5, Title 24 CCR

2022 California Energy Code, Part 6, Title 24 CCR

2022 California Fire Code (CFC), Part 9, Title 24 CCR

2022 California Existing Building Code (CEBC), Part 10, Title 24 CCR

2022 California Green Building Standards Code (CALGreen), Part 11, Title 24 CCR 2022 California Referenced Standards Code, Part 12, Title 24 CCR

Title 19 CCR, Public Safety, State Fire Marshal Regulations

APPLICABLE STANDARDS

For a list of applicable standards, including California amendments to the NFPA Standards, refer to CBC Chapter 35 and CFC Chapter 80.

| | | RI | EQUIRE | D PV S | YSTEM | SIZE (k\ | N) | | | | | |
|---------|---------------|---------|---------|----------|-----------|----------|---------|----------|---------|--|--|--|
| | BUILDING SIZE | | | | | | | | | | | |
| CLIMATE | 24'x40' | 36'x40' | 48'x40' | 60'x40' | 72'x40' | 84'x40' | 96'x40' | 108'x40' | 120'x40 | | | |
| ZONE | T T | | APP | ROXIMATE | CONDITION | ED FLOOR | AREA | | | | | |
| | 960 | 1440 | 1920 | 2400 | 2880 | 3360 | 3840 | 4320 | 4800 | | | |
| -1 | NONE | NONE | NONE | NONE | NONE | 4.3 | 4.9 | 5,5 | 6.1 | | | |
| 2 | NONE | NONE | NONE | NONE | 4.7 | 5.5 | 6.3 | 7.0 | 7.8 | | | |
| 3 | NONE | NONE | NONE | NONE | NONE | 4.3 | 4.9 | 5.5 | 6.1 | | | |
| 4 | NONE | NONE | NONE | NONE | 4.7 | 5.5 | 6.3 | 7.0 | 7.8 | | | |
| .5 | NONE | NONE | NONE | NONE | NONE | 4.3 | 4.9 | 5.5 | 6.1 | | | |
| 6 | NONE | NONE | NONE | NONE | 4.7 | 5.5 | 6.3 | 7.0 | 7.8 | | | |
| 7 | NONE | NONE | NONE | NONE | 4.7 | 5.5 | 6.3 | 7.0 | 7.8 | | | |
| 8 | NONE | NONE | NONE | NONE | 4.7 | 5.5 | 6.3 | 7.0 | 7.8 | | | |
| 9 | NONE | NONE | NONE | NONE | 4.7 | 5.5 | 6.3 | 7.0 | 7.8 | | | |
| 10 | NONE | NONE | NONE | NONE | 4.7 | 5.5 | 6.3 | 7.0 | 7.8 | | | |
| 11 | NONE | NONE | NONE | NONE | 4.7 | 5.5 | 6.3 | 7.0 | 7.8 | | | |
| 12 | NONE | NONE | NONE | NONE | 4.7 | 5,5 | 6.3 | 7.0 | 7.8 | | | |
| 13 | NONE | NONE | NONE | NONE | 4.7 | 5.5 | 6.3 | 7.0 | 7.8 | | | |
| 14 | NONE | NONE | NONE | NONE | 4.7 | 5.5 | 6.3 | 7.0 | 7.8 | | | |
| 15 | NONE | NONE | 4.7 | 5.9 | 7.1 | 8,3 | 9.4 | 10.6 | 11.8 | | | |
| 16 | NONE | NONE | NONE | NONE | NONE | 4,3 | 4.9 | 5,5 | 6.1 | | | |
| ALL | NONE | NONE | 4.7 | 5.9 | 7.1 | 8.3 | 9.4 | 10.6 | 11.8 | | | |

FOR SITE-SPECIFIC PROJECT, INDICATE BUILDING SIZE IF PV IS REQUIRED, SEE GENERAL NOTES ITEM 15.

PV SIZING CHART

ADOPTED YEAR NFPA 13 NFPA 72

AUTOMATIC SPRINKLER SYSTEMS NATIONAL FIRE ALARM CODE w/ CALIFORNIA AMENDMENTS

NOTE: VISUAL DEVICES PER UL STANDARD 1971


GENERAL NOTES

- ARCHITECT OF RECORD SHALL PROVIDE FIRE ALARM DRAWINGS WITH SITE ADAPTED PROJECTS. FIRE ALARM IS NOT PART OF THIS PC. THIS PC HAS BEEN STRUCTURALLY DESIGNED TO SUPPORT THE
- WEIGHT OF A FIRE SPRINKLER SYSTEM ALLOWABLE AREA IS BASED ON 10'-0" SETBACK FROM ASSUMED LINE PC DESIGNED AS A SINGLE-STORY MODULAR BUILDING
- SEE STRUCTURAL FOR SOIL TYPES & BEARING STRENGTHS WORK SHALL CONFORM TO TITLE 24 OF THE CALIFORNIA CODE OF REGULATIONS THIS PC IS NOT APPROVED FOR "A" OCCUPANCY USAGE
- EXTERIOR PROJECTIONS TO BE FIRE PROTECTED WHERE REQUIRED SEE A0.5 AND ENGERY CALC M-SHEETS FOR REQUIRED ENVELOPE ASSEMBLIES & HVAC SYSTEMS
- ALL SPECIFICATIONS BASED ON PERFORMANCE AND ABLE TO BE SUBSTITUTED BY "EQUAL" PRODUCTS
- BUILDINGS TO COMPLY WITH WILDLAND URBAN INTERFACE GUIDELINES WHERE APPLICABLE BUILDING AND SITE FEATURES MUST COMPLY WITH CALGREEN CODE
- FOR ITS SPECIFIC LOCATION WHEN ADAPTED FOR SITE-USE SHOULD THIS P.C. CLASSROOM BE DESIGNED TO CONNECT TO ANOTHER P.C. CLASSROOM, INTERIOR SOUND TRANSMISSION IN THE WALL AND FLOOR-CEILING ASSEMBLY MUST MEET A MINIMUM STC OF
- 40 PER CALGREEN THE CONCRETE BELOW GRADE FOUNDATION (AMM) OPTION IN THIS PC USES A DSA-APPROVED ALTERNATE MEANS OF COMPLIANCE FOR FOUNDATION DURABILITY REQUIREMENTS OF CBC SECTIONS 1402.2 AND 1403.2 FOR PROVIDING A WEATHER-RESISTANT EXTERIOR WALL ENVELOPE AND CONTINUOUS WATER-RESISTIVE BARRIER ON WALLS DOWN TO THE FOUNDATION, AND CBC SECTION 2304.12.1.2 FOR PROTECTION AGAINST DECAY AND TERMITES.
- PC DOESN'T INCLUDE THE DESIGN OF PV RACK SYSTEM ON ROOF- A SEPARATE DESIGN AND DSA APPLICATION WILL BE REQUIRED. PV ON ROOF WILL NOT BE ALLOWED FOR OTC APPLICATION

ROJECT SPECIFIC STATE AGENCY APPROVAL IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: **REVIEWED FOR** SS FLS ACS 12/18/2024



PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF **R&S TAVARES ASSOCIATES, INC. DEVISED** SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE **EXPRESS WRITTEN CONSENT OF R&S** TAVARES ASSOCIATES, INC. ©



Voice (951) 943-1908 Fax (951)943-5768

ORIGINAL PC STATE AGENCY APPROVAL

APPROVED DIV. OF THE STATE ARCHITECT APP: 04-123059 PC SS D FLS D ACS Q CG D

Revision Schedule

Description

PRE-CHECK (PC) DOCUMENT

Code: 2022 CBC

A separate project application for construction is required

PC 2022 CBC: 24' x 40' **EXPANDABLE TO**

120' x 40'

COVER SHEET

PROJECT NUMBER

22088

rMc/SC CHECKED BY

DATE

DRAWN BY

RH/RT

ARCHITECTURAL

| 6 General Architectu 1/4" = 1'-0" | ral S | She | — ets GE | | RA | AL ARCH | HITECTU | JRAL S | HEETS | | | | | | | Sheet |
|---|-------|-----|----------------|-----|------|-----------|---------|----------|--------|------|------|------------|------------|---------|---------|---------------|
| COVER SHEET | | | <u> </u> | | | | | | | | | | | | | A0.0 |
| PROJECT OPTIONS SC | :HF | OUI | F | | | | | | | | | | | | | A0.0.1 |
| TYPICAL KEY PLAN AN | | | | ULI | E. (| GEN NO | TES | | | | | | | | | A0.1 |
| SIGNAGE AND SYMBOL | | | | | | | | | | | | | | | | A0.2 |
| DSA-103 T&I CONCRET | E Fl | LOC |)R | S | | | | | | | | | | | | A0.3 |
| DSA-103 T&I PLYWOOD FLOORS | | | | | | | | | | | A0.4 | | | | | |
| CALGREEN SPEC'S | | | | | | | | | | A0.5 | | | | | | |
| CALGREEN SHEET | | | | | | | | | | | | | | | | A0.6 |
| CALGREEN SHEET | | | | | | | | | | | | | | | | A0.7 |
| CALGREEN SHEET | | | | | | | | | | | | | | | | A0.8 |
| 5 Floor Plan Details 1/4" = 1'-0" | | | | AF | RCI | HITECTU | JRAL FI | LOOR F | PLANS | | | | | | | Sheet |
| ¥ Floor Plans | | | | Flo | or | Plan - 24 | 1'x40' | | | | | | | | | A1.0 |
| | | | X | Flo | or | Plan - 36 | 6'x40' | | | | | | | | | A3.1 & ALT-01 |
| | | | | Flo | or | Plan - 48 | 3'x40' | | | | | | | | | A1.2 |
| 1 Arch Floor Framing Details 1/4" = 1'-0" ARCHITECTURAL FLOOR FRAMING DETAILS | | | | | | | | | | | | | | | | |
| 1/4 - 1-0 | | | | | | | | | | | | | | | | Sheet |
| x Wood Floor | | | | | | | | | 1 | 2 | | 3 | 4 | 5 | 6 | A2.9 |
| □ Concrete Floor | | | | | | | | | 7 | 8 | | 9 | 10 | 11 | 12 | A2.9 |
| 2 Wall Schedule 1/4" = 1'-0" | | | | | | ARCHII | ECTUF | RAL WA | LL DET | AILS | } | | | | | |
| Wood Studs | | | | | | | | De | tail | | | | | | | Sheet |
| | Do | oor | | ML | | Window | Corner | HVAC | Top PL | T6" | SEP | 1-HR OPT 1 | 1-HR OPT 2 | EXT HDR | INT HDR | |
| ⊠ Sheating | 8 | 9 | 2 | 3 4 | 5 | 11 | 1 | 16 | . 17 | | 5 | x | x | 10A | 10B | A2.1(A) |
| □ Sheating | 8 | 9 | 2 | 3 4 | 5 | 11 | 1 | 16 | 17 | | 5 | х | х | 10A | 10B | A2.1(B) |
| □ Plaster | 8 | 9 | 3 | 4 | 5 | 11 | 1 | 16 | 17 | | 5 | х | х | 10A | 10B | A2.2 |
| □ 1-HR Sheating | 8 | 9 | | 3 4 | | | 1 | 16 | 17 | | 5 | - | - | 10A | | A2.5(A) |
| □ 1-HR Sheating | 8 | 9 | | 3 4 | | | 1 | 16 | 17 | | 5 | - | - | 10A | - | A2.5(B) |
| □ 1-HR Plaster | 8 | 9 | | 3 4 | | | 1 | 16 | 17 | | 4 | - | - | 10A | - | A2.6 |
| □ Additional Fire Rating Details and Notes | | | | | | | | | A3.0 | | | | | | | |
| | | | | | | | | & ALT-01 | | | | | | | | |
| □ Single OCC. Bathroom | | | | | | | | | | | | | | | | A3.1.1 |

| 4 Ceiling Plans 1/4" = 1'-0" | | RCHITECTURAL CEILING I | PLANS | | | | Sheet |
|---------------------------------|--|----------------------------|-------------|--------|--------|----------|--------|
| Reflected Ceiling | □ 24' x 40' | □ 8 (2'x4') Recessed Light | ht Fixture | | | | A3.2 |
| Plans: | | □ 12 (1'x8') Pendant Ligh | | | | | |
| | | (1'x16') Recessed Light | | | | | A3.2 |
| | ≱ 36' x 40' | □ 12 (2'x4') Recessed Lig | ght Fixture | | | | A3.2 |
| | | ★ 16 (1'x8') Pendant Light | nt w/ 4 | | | | A3.2 & |
| | 101 101 | (1'x16') Recessed Light | | | | | ALT-01 |
| | □ 48' x 40' | □ 16 (2'x4') Recessed Lig | _ | | | | A3.2 |
| | □ 18 (1'x8') Pendant Light w/ 4 (1'x16') Recessed Light | | | | | | |
| Celing Notes | Celing Notes | | | | | | |
| O 'II' D (| ils | | | | | | A3.2.1 |
| 3 Ceiling Deta 1/4" = 1'-0" | | ARCHITECTURAL (| CEILING DE | TAILS | | | |
| Celing Framing | g | | | De | tail | | Sheet |
| | | | Wall | Joists | Access | BLK'G | |
| ⋉T-GRID | | | | | | SEE PLAN | |
| □ Wood | | | 1 | 2 | 5 | Тур | A3.4 |
| - D (D) | | | | | | | |
| 7 Roof Plans 1/4" = 1'-0" | | ARCHITECTURAL | ROOF PLA | NS | | | |
| <u> </u> | | | | | | | Sheet |
| | | | □ EPDM | | | | A4.2.1 |
| | | | ⋉ Standing | Seam | | | A4.0.1 |
| | | | □ Parapet | | | | A4.4.1 |
| □ Dual | | | | | | | |
| | | | □ EPDM | | | | A4.2.2 |
| | | | □ Standing | Seam | | | A4.0.2 |
| 22 Roof Details 1/4" = 1'-0" | ; | ARCHITECTURAL | ROOF DET | AILS | | | |
| <u> </u> | | | | | | | Sheet |
| A | | | □ EPDM | | | | A4.3 |
| | | | ∡ Standing | Seam | | | A4.1 |
| | | | □ Parapet | | | | A4.5 |
| □ Dual | | | | | | | |
| | | | □ EPDM | | | | A4.3 |
| | | | □ Standing | Seam | | | A4.1 |
| 8 Arch Buildin | g Section | ARCHITECTURAL | BUILDING S | ECTION | | | |
| <u> </u> | | (3 | | | | [| Sheet |
| M INIONIO | | | □ EPDM | | | | A6.3 |
| | | | ⊠ Standing | Seam | | | A6.0 |
| | | | <u> </u> | | | | |
| □ Dual | | | | | | | |
| | | | □ EPDM | | | | A6.1 |
| | | | □ Standing | Seam | | | A6.0.1 |
| Section | | | | | | | A6.2 |

ARCHITECTURAL

| 1/4" = 1'-0" | ARCHITECTURAL EXT | | etail | Sheet | Det | tail | Sheet |
|---------------------------------|----------------------------------|-----------|--------|---------|---------|------|---------|
| Exterior Elevations: | □ 24'x40' | Left | Right | Officet | Front | Rear | Officer |
| | □ Mono Slope | 1 | 2 | A5.0 | 1 | 2 | A5.1 |
| | □ Parapet Roof - Mono Slope | 3 | 4 | A5.0 | 3 | 4 | A5.1 |
| | □ Dual Slope | 5 | 6 | A5.0 | 1 | 2 | A5.1 |
| | ∡ 36'x40' | | | | | | |
| | ⋉ Mono Slope | 1 | 2 | A5.0 | 5 | 6 | ALT-06 |
| | □ Parapet Roof - Mono Slope | 3 | 4 | A5.0 | 7 | 8 | A5.1 |
| | □ Dual Slope | 5 | 6 | A5.0 | 5 | 6 | A5.1 |
| | □ 48'x40'- 120'X40' | | | | | | |
| | □ Mono Slope | 1 | 2 | A5.0 | 9 | 10 | A5.1 |
| | □ Parapet Roof - Mono Slope | 3 | 4 | A5.0 | 11 | 12 | A5.1 |
| | □ Dual Slope | 5 | 6 | A5.0 | 9 | 10 | A5.1 |
| Interior Elevatio | ns ARCHITECTURAL INTE | ERIOR EL | EVATIO | NS | | | |
| 1/4 = 1 =0 | | | | | Detail | | Sheet |
| Interior Elevations: | | | Le | ft Righ | t Front | Rear | |
| | □ 24'x40' | | 1 | 2 | 3 | 4 | A5.2 |
| | x 36'x40' | | 1 | 2 | 5 | 6 | ALT-0 |
| | □ 48'x40' - 120'X40' | | 1 | 2 | 8 | 7 | A5.2 |
| 23 ADDITIONAL O 1/4" = 1'-0" | PTIONS DETAILS ADDITIONAL OPTION | IS DETAII | _S | | | | |
| ., | | | | | | | Sheet |
| ADDITIONAL OPTIO | NS DETAILS | | | | | | A7.0 |
| | NO DETAIL O | | | | | | A7.1 |
| ADDITIONAL OPTIO | INO DETAILO | | | | | | , |

| | | MEP | | |
|---------------------------------|-------------------|--|--------------|-------------------|
| 9 Plumbing 1/4" = 1'-0 | | PLUMBING | | Sheet |
| | ils and Schedules | | | P1.0 |
| 10 Mechanic | al | MECHANICAL | She | eet |
| 1/4" = 1'-0 MISCELLANEOUS NO | | WEST IN WITON IE | MO | |
| WIGOLLLANLOGO INC | JIEG & BETAILG | | Ceiling Plan | Roof Plan |
| Mechanical | □ 24' x 40' | □ Wall Mount | M5.1 | M5.2 |
| Plans: | | □ Roof Mount | M5.1 | M5.2 |
| | x 36' x 40' | ⋉Wall Mount | M6.1 | -M6.2- |
| | | □ Roof Mount | M6.1 | M6.2 |
| | □ 48' x 40' | □ Wall Mount | M7.1 | M7.2 |
| | | □ Roof Mount | M7.1 | M7.2 |
| | □ 60' x 40' | □ Wall Mount | • | |
| | | □ Roof Mount | | |
| | □ 72' x 40' | □ Wall Mount | | |
| | | □ Roof Mount | | |
| | □ 84' x 40' | □ Wall Mount | | |
| | | □ Roof Mount | AC |).1 |
| | □ 96' x 40' | □ Wall Mount | | |
| | | □ Roof Mount | | |
| | □ 108' x 40' | □ Wall Mount | | |
| | | □ Roof Mount | | |
| | □120' x 40' | □ Wall Mount | | |
| | | □ Roof Mount | | |
| 11) Electrical 1/4" = 1'-0 | | ELECTRICAL | She | eet |
| Reflected Ceiling | □ 24' x 40' | □ 8 (2'x4') Recessed Light Fixture | | |
| Plans: | | □ 12 (1'x8') Pendant Light w/ 4 (1'x16') Recessed Light | E1.0 | E1.1 |
| | 💢 36' x 40' | □ 12 (2'x4') Recessed Light Fixture | | |
| | | □ 18 (1'x8') Pendant Light w/ 4 | | |
| | | (1'x16') Recessed Light | E1.2 | E1.3 |
| | □ 48' x 40' | □ 16 (2'x4') Recessed Light Fixture | | |
| | | □ 24 (1'x8') Pendant Light w/ 4 (1'x16') Recessed Light | E1.4 | E1.5 |
| | □ 60' x 40' | □ 20 (2'x4') Recessed Light Fixture | | |
| | | □ 30 (1'x8') Pendant Light w/ 4 (1'x16') Recessed Light | | |
| | □ 72' x 40' | □ 24 (2'x4') Recessed Light Fixture | | |
| | | □ 36 (1'x8') Pendant Light w/ 4 (1'x16') Recessed Light | | |
| | □ 84' x 40' | □ 28 (2'x4') Recessed Light Fixture | | |
| | | □ 42 (1'x8') Pendant Light w/ 4 (1'x16') Recessed Light | | |
| | □ 96' x 40' | □ 32 (2'x4') Recessed Light Fixture | | |
| | | □ 48 (1'x8') Pendant Light w/ 4 (1'x16') Recessed Light | | |
| | □ 108' x 40' | □ 36 (2'x4') Recessed Light Fixture | | |
| | | □ 54 (1'x8') Pendant Light w/ 4 (1'x16') Recessed Light | | |
| | □ 120' x 40' | □ 40 (2'x4') Recessed Light Fixture | | |
| | | □ 60 (1'x8') Pendant Light w/ 4 (1'x16') Recessed Light | | |

STRUCTURAL

| Foundations Plans 1/4" = 1'-0" | FOUNDATION | |
|---|---|------|
| □ Wood | | Sh |
| Foundation | Wood Foundation NOTES SCHED FOR BLDG W/ 50+15 | F1 |
| Plan: | □ 24'x40' (50+15 PSF) | F1 |
| | □ 24'x40' (100 PSF) | F1. |
| | □ 24'x40' (150 PSF) | F1 |
| | | |
| | □ 36'x40' (50+15 PSF) | F1 |
| | □ 36'x40' (100 PSF) | F1 |
| | □ 36'x40' (150 PSF) | F1 |
| | _ 49\v40\ (50 + 15 DQT) | |
| | □ 48'x40' (50+15 PSF) | F1 |
| | □ 48'x40' (100 PSF) | F1 |
| | □ 48'x40' (150 PSF) | F1. |
| 0 1 5 1 1 2 | Wood Foundation Details | F1. |
| ⊠ Concrete Foundation Plan | | F2 |
| | | F2 |
| | | F2 |
| General Structural Sheets | L | F2 |
| 16 1/4" = 1'-0" | GENERAL STRUCTURAL SHEETS | Sh |
| STRUCTURAL GEN NOTES | | S0 |
| Floor Framing Plans 1/4" = 1'-0" STF | RUCTURAL FLOOR FRAMING PLANS | |
| ⋉ Wood | | Sh |
| Sheating Floor: | ⋉(50+15 PSF) | S1 |
| | □ (100 PSF) | S1 |
| | □ (150 PSF) | S1 |
| □ Concrete | | |
| Framing Floor: | □ (50+15 PSF) | S1 |
| | □ (100 PSF) | S1 |
| | □(150 PSF) | S1 |
| Floor Framing Details 1/4" = 1'-0" STF | RUCTURAL FLOOR FRAMING DETAILS | Sh |
| ⋉ Wood Framing | | S1 |
| □ Concrete Framing | | S1 |
| Poof Framing Plans | RUCTURAL ROOF FRAMING PLANS | Sh |
| Mono Slope Roof Framing Mono Slope Roof Framing | | S3 |
| □ Dual Slope Roof Framing | | S3 |
| · | RUCTURAL DETAILS ROOF | Sh |
| STRUCTURAL DETAILS | NOOTOTAL DETAILO NOOT | S3 |
| ROOF DETAILS(SOFFIT/ PARRAPET) | | S3 |
| ROOF PERIMETER TRUSS | | S3 |
| - Mall Francisco Dataila | | - 55 |
| 20 wall Framing Details 1/4" = 1'-0" STF | RUCTURAL WALL FRAMING DETAILS | |
| x Wood: | | Sh |
| শু Framing Elevation | | S4 |
| ⋉Wall Details | | S4 |
| □ Typ Framing: | | S4 |
| □ Framing Schedule: | | S4 |

| Building Section 1/4" = 1'-0" | STRUCTURAL BUILDING SECTION | Shee |
|-------------------------------|-----------------------------|------|
| ⋉ Mono | | S5.0 |
| □ Dual | | S5.1 |

IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT

APP: 02-122764 INC:

REVIEWED FOR
SS FLS ACS D

DATE: 12/18/2024

PROJECT SPECIFIC STATE AGENCY APPROVAL




PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©





PRE-CHECK (PC) DOCUMENT

CODE: 2019 CBC
ate project application for constr

A separate project application for construction is required

PROJECT TITLE

PC 2022 CBC: 24' x 40' EXPANDABLE TO 120' x 40'

PROJECT OPTIONS
SCHEDULE

PROJECT NUMBER

22088

DRAWN BY


rMc/SC

CHECKED BY

RH/RT

06/15/2021

A0.0.1



PROJECT SPECIFIC STATE AGENCY APPROVAL

IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: **REVIEWED FOR** SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024

DESIGN ♦ CONSULTING ♦ PROJECT MG 11590 W BERNARDO COURT, SUITE 100 SAN DIEGO, CA 92127

PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©

1651Juanita Street, San Jacinto, CA 92583 Voice (951) 943-1908 Fax (951)943-5768



Revision Schedule Description

PRE-CHECK (PC) DOCUMENT

Code: 2022 CBC

A separate project application for construction is require

PROJECT TITLE PC 2022 CBC: 24' x 40' **EXPANDABLE TO** 120' x 40'

TYPICAL KEY PLAN AND SCHEDULES GEN NOTES,

PROJECT NUMBER

22088

rMc/SC CHECKED BY RH/RT

A0.


11B.703.2.6 Stroke Thickness for raised characters. Stroke thickness of the uppercase letter "I" shall be 15 percent maximum of the height of the character.

11B.703.2.7 Character Spacing. Character spacing shall be measured between the two closest points of adjacent raised characters within a message, excluding word spaces. Where characters have rectangular cross sections, spacing between individual raised characters shall be 1/8 inch (3.2 mm) minimum and 4 times the raised character stroke width maximum. Where characters have other cross sections, spacing between individual raised characters shall be 1/16 inch (1.6 mm) minimum and 4 times the raised character stroke width maximum at the base of the cross sections, and 1/8 inch (3.2 mm) minimum and 4 times the raised character stroke width maximum at the top of the cross sections. Characters shall be separated from raised borders and decorative elements 3/8 inch (9.5 mm) minimum.

11B.703.2.8 Line Spacing. Spacing between the baselines of separate lines of raised characters within a message shall be 135 percent minimum and 170 percent maximum of the raised character height.

11B.703.3 Braille. Braille shall be contracted (Grade 2) and shall comply with 703.3 and 703.4.

11B.703.3.1 Dimensions and Capitalization. Braille dots shall have a domed or rounded shape and shall comply with Table 703.3.1. The indication of an uppercase letter or letters shall only be used before the first word of sentences, proper nouns and names, individual letters of the alphabet, initials, and acronyms.



11B.703.3.2 Position. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

Figure 703.3.1 Braille Measurement




Figure 703.3.2 Position of Braille

1/32" RAISED TEXT

MARGIN AREA

PAINT-FILLED
TEXT IF PREFERRED

PLASTIC LAMINATE FACE

OVER ACRYLIC BACK

DEMARCATION LINE EITHER

RAISED AND CHEMICALLY

CORE OR ENGRAVED AND PAINT FILLED PER USER

GRADE II BRAILLE BEADS

SEE FIGURE AND TABLE.

CORNER TREATMENT

(EITHER SQUARE

OR RADIUS) PER

SEE 9/A0.2

WELDED TO ACRYLIC

LINE SIZE PER USER

11B.703.4 Installation Height and Location. Signs with tactile characters shall comply with 703.4. 11B.703.4.1 Height Above Finish Floor or Ground. Tactile characters on signs shall be located 48 inches (1220 mm) minimum above the finish floor or ground surface, measured from the baseline of the lowest braille




Figure 703.4.1 Height of Tactile Characters Above Finish Floor or Ground

MOUNTING TAPE

SILICONE ADHESIVE

MOUNTING TAPE

11B.703.4.2 Location. Where a tactile sign is provided at a door, the sign shall be located alongside the door at the latch side. Where a tactile sign is provided at double doors with one active leaf, the sign shall be located on the inactive leaf. Where a tactile sign is provided at double doors with two active leafs, the sign shall be located to the right of the right hand door. Where there is no wall space at the latch side of a single door or at the right side of double doors, signs shall be located on the nearest adjacent wall. Signs containing tactile characters shall be located so that a clear floor space of 18 inches (455 mm) minimum by 18 inches (455 mm) minimum, centered on the tactile characters, is provided beyond the arc of any door swing between the closed position and 45 degree open position.




Figure 703.4.2 Location of Tactile Signs at Doors

11B.703.5 Visual Characters. Visual characters shall comply with 703.5.

11B.703.5.1 Finish and Contrast. Characters and their background shall have a non-glare finish. Characters shall contrast with their background with either light characters on a dark background or dark characters

11B.703.5.2 Case. Characters shall be uppercase or lowercase or a combination of both.

11B.703.5.3 Style. Characters shall be conventional in form. Characters shall not be italic, oblique, script, highly decorative, or of other unusual forms.

11B.703.5.4 Character Proportions. Characters shall be selected from fonts where the width of the uppercase letter "O" is 60 percent minimum and 110 percent maximum of the height of the uppercase letter "I".

11B.703.5.5 Character Height. Minimum character height shall comply with Table 703.5.5. Viewing distance shall be measured as the horizontal distance between the character and an obstruction preventing further approach towards the sign. Character height shall be based on the uppercase letter "I".

11B.703.5.6 Height From Finish Floor or Ground. Visual characters shall be 40 inches (1015 mm) minimum above the finish floor or ground.


11B.703.5.7 Stroke Thickness. Stroke thickness of the uppercase letter "I" shall be 10 percent minimum and 20 percent maximum of the height of the character.


11B.703.5.8 Character Spacing. Character spacing shall be measured between the two closest points of adjacent characters, excluding word spaces. Spacing between individual characters shall be 10 percent minimum and 35 percent maximum of character height.

11B.703.5.9 Line Spacing. Spacing between the baselines of separate lines of characters within a message shall be 135 percent minimum and 170 percent maximum of the character height.

11B.703.6 Pictograms. Pictograms shall comply with 703.6.

11B.703.6.1 Pictogram Field. Pictograms shall have a field height of 6 inches (150 mm) minimum. Characters and braille shall not be located in the pictogram field.







NOTE: TEXT ON THIS SIGN IN VISUAL

Distance between corresponding dots in adjacent cells

Distance between corresponding dots from once cell directly below¹

distance between corresponding dots

in adjacent cells

distance between dots

in the same cell

distance between corresponding dots from one cell directly below

Dot base diameter

THE "INTERNATIONAL SYMBOL FOR ACCESS FOR

HEARING LOSS" PROPORTIONS SHALL BE

OCCUPANT LOAD SIGN REQUIRED PER DSA BU11-08.

MAXIMUM

OCCUPANCY

PERSONS


SECTION LABEL

- PAGE NUMBER

EVERY ROOM OR SPACE WHICH IS USED FOR ASSEMBLY, CLASSROOM. DINING OR SIMILAR PURPOSES HAVING AN OCCUPANT LOAD OF 50 OR MORE SHALL HAVE THE OCCUPANT LOAD OF THE ROOM OR SPACE POSTED IN A CONSPICUOUS PLACE, NEAR THE MAIN EXIT OR EXIT ACCESS DOORWAY

7 | 1" = 1'-0" Assistive Listening System Symbol

BRAILLE DIMENSIONS





distance between dots

in the same cell

0.300 (7.6 mm)

blank cell space

raised dot

base diameter

0.025 (0.6 mm) to 0.037 (0.09mm)

0.395 (10 mm) to 0.400 (10.2 mm)

PRE-CHECK (PC) DOCUMENT Code: 2022 CBC

ROJECT SPECIFIC STATE AGENCY APPROVAC

IDENTIFICATION STAMP

DIV. OF THE STATE ARCHITEC

REVIEWED FOR

SS 🗹 FLS 🗹 ACS 🗹

12/18/2024

DESIGN ♦ CONSULTING ♦ PROJECT MG

THE PLANS, IDEAS & DESIGNS SHOWN ON

THESE DRAWINGS ARE THE PROPERTY OF

R&S TAVARES ASSOCIATES, INC. DEVISED

PLANS SHALL NOT BE USED, IN WHOLE OR

IN PART, FOR ANY PURPOSE FOR WHICH

THEY WERE NOT INTENDED WITHOUT THE **EXPRESS WRITTEN CONSENT OF R&S**

1651Juanita Street, San Jacinto, CA 92583

Voice (951) 943-1908 Fax (951)943-5768

ORIGINAL PC STATE AGENCY APPROVAL

APPROVED

DIV. OF THE STATE ARCHITECT

REVIEWED FOR

SS / FLS / ACS / CG /

APP: 04-123059 PC

Description

SOLELY FOR THIS CONTRACT. THESE

TAVARES ASSOCIATES, INC. ©

CLIENT

PROFESSIONAL STAMP

11590 W BERNARDO COURT, SUITE 100 SAN DIEGO, CA 92127

APP: 02-122764 INC:

A separate project application for construction is require

PROJECT TITLE PC 2022 CBC: 24' x 40'

EXPANDABLE TO 120' x 40'

SIGNAGE AND **SYMBOLS**

22088 DRAWN BY rMc/SC

CHECKED BY DATE

PROJECT NUMBER

SHEET NO.

SHEET OF

RH/RT

Sign Notes

1/4" = 1'-0'

Measured center to center

1/32" RAISED SYMBOLS CHEMICALLY WELDED TO ACRYLIC CORE (TYP) PLASTIC LAMINATE FACE OVER ACRYLIC BACK MARGIN AREA DEMARCATION LINE EITHER RAISED AND CHEMICALLY MOUNTING TAPE WELDED TO ACRYLIC CORE OR ENGRAVED AND PAINT FILLED PER USER LINE SIZE PER USER MEN B106 WOMEN SILICONE ADHESIVE AND PAINT-FILLED TEXT IF PREFERRED NOTE: LETTERS REQ'D MOUNTING TAPE RESTROOM GIRLS BOYS CORNER TREATMENT (EITHER SQUARE OR RADIUS) PER ELEVATIONS GRADE II BRAILLE BEADS RAISED 1/32"
SEE FIGURE AND TABLE SEE 9/A0.2

CHAPTER 11:COMMUNICATION ELEMENTS AND FEATURES

communication features shall comply with NFPA 72 (2022 edition)

11B.702.1 General. Fire alarm systems shall have permanently installed audible and visible alarms complying with

except that the maximum allowable sound level of audible notification appliances complying with section

11B.703.1 General. Signs shall comply with 703. Where both visual and tactile characters are required, either

11B.703.2 Raised Characters. Raised characters shall comply with 703.2 and shall be duplicated in braille

hearing distance from the audible appliance. In addition, alarms in guest rooms required to provide

one sign with both visual and tactile characters, or two separate signs, one with visual, and one with

11B.703.2.1 Depth. Raised characters shall be 1/32 inch (0.8 mm) minimum above their background.

11B.703.2.3 Style. Characters shall be sans serif. Characters shall not be italic, oblique, script, highly

letter "O" is 60 percent minimum and 110 percent maximum of the height of the uppercase letter "I".

11B.703.2.4 Character Proportions. Characters shall be selected from fonts where the width of the uppercase

11B.703.2.5 Character Height. Character height measured vertically from the baseline of the character shall be

Figure 703.2.5 Height of Raised Characters

TABLE 11B-703.3.1

MINIMUM IN INCHE

0.059 (1.5 mm) to 0.063 (1.6 mm)

0.100 (2.5 mm)

0.300 (7.6 mm)

0.025 (0.6 mm) to 0.037 (0.9 mm)

0.395 (10 mm) to 0.400 (10.2 mm

BRAILLE DIMENSIONS

5/8 inch (15.9 mm) minimum and 2 inches (51 mm) maximum based on the height of the uppercase letter

11B.4-3.2.1 of NFPA 72 shall have a sound level no more than 110 dB at the minimum

complying with 703.3. Raised characters shall be installed in accordance with 703.4.

11B.702 Fire Alarm Systems

tactile characters, shall be provided.

decorative, or of other unusual forms.

11B.703.2.2 Case. Characters shall be uppercase.

MEASUREMENT RANGE

Dot base diamete

Distance between two dots in the same cel

Distance between corresponding dots in adjacent cells1

ace between corresponding dots from one cell directly below

NFPA 72 (2022 edition)

11B.703 Signs





D113

PARENT

GYMNASIUM

ELEVATION





NOTE: TACTILE SIGN TEXT SHALL BE CENTERED 18"

FIRSTCELL TO THE FIRST COLUMN OF DOTS IN THE SECOND CELL DOTS SHALL BE RAISED A MINIMUM OF 1/40 INCHES ABOVE THE BACKGROUND. SEE FIGURE AND TABLE. SEE 2/A0.2

* NOTE FOR UNISEX OR SINGLE USER RESTROOM DOOR SYMBOL THE COLOR OF THE TRIANGLE SHALL CONTRAST WITH THE COLOR OF THE CIRCLE SYMBOL, EITHER LIGHT ON A DARK BACKGROUND OR DARK ON A LIGHT BACKGROUND. THE COLOR OF THE CIRCLE SYMBOL SHALL CONTRAST WITH THE COLOR OF THE DOOR OR SURFACE ON WHICH THE COMBINED CIRCLE AND TRIANGLE SYMBOL IS MOUNTED, EITHER LIGHT ON A DARK BACKGROUND OR DARK ON A LIGHT BACKGROUND.

1/4" = 1'-0" Signage and Notes

1/2" = 1'-0" Signage (OFOI - UNO)

BRAILLE DIMENSIONS

| | | _ DEF | FAULT CONCRETE MIX DESIGN FO | OR BELOW GRADE NORMA | L WEIGHT CONCRETE | | | |
|--------------------|--------------------|---------------------|--|----------------------|---|--|--|--|
| CONCRETE ELEMENT | MAXIMUM W/CM RATIO | MINIMUM COMPRESSIVE | CEMENTITIOUS MATERIALS - | MAX AGGREGATE SIZE | TARGET AIR CONTENT (%) | | | |
| | WAXIWOW W/CW RATIO | STRENGTH, f'c (PSI) | TYPES (ASTM C150) | WAX AGGREGATE SIZE | CONCRETE NOT EXPOSED TO FREEZING AND THAWING CYCLES | CONCRETE EXPOSED TO FREEZING AN THAWING CYCLES | | |
| FOUNDATION | 0.45 | 4,500 | TYPE V PLUS POZZOLAN OR SLAG CEMENT | 1" +/- 1/4" | N/A | 6 | | |
| FOUNDATION VENTS & | 0.45 | 4.500 | TYPE V PLUS POZZOLAN OR | 3/8" | N/A | 7.5 | | |
| ACCESS WELLS | 0.45 | 4,500 | SLAG CEMENT | 1/2" | N/A | 7 | | |
| | | | | 1" +/- 1/4" | N/A | 6 | | |

IN THE DEFAULT CONCRETE MIX DESIGN REQUIREMENTS MAY BE SELECTED AND USED FOR CONSTRUCTION PROVIDED THE THE PC DRAWINGS DO NOT REQUIRE A SITE-SPECIFIC GEOTECHNICAL REPORT THAT QUANTIFIES SULFATE CONTENT IN THE SOIL (IR PC-6, SECTION 5.5.1)

(2) DOCUMENTATION OF CONCRETE MIXTURES CHARACTERISTICS SHALL BE IN ACCORDANCE WITH ACI, SECTION 26.4.4

(3) CEMENT SHALL BE CERTIFIED PER TITLE 24, PART 2, SECTION 1910.1

(4) THE FOUNDATION DESIGN HAS BEEN PREPARED USING A MINIMUM 28-DAY COMPRESSIVE CONCRETE STRENGTH (FC) OF 3500 PSI

1 SCALE DEFAULT CONCRETE MIX DESIGN

| | | EXPOSURE CATEGORY | : FREEZING AND | THAWING (F | =) | | |
|----------|------------|---|----------------|------------|----------------------------|---------------------------|---------------------------------|
| | | | MAXIMUM | MINIMU | REQUIRED AII | R CONTENT | LIMITS ON |
| EXPO | SURE CLASS | CONDITION | W/CM | M f'c | MAX AGGREGATE SIZE (IN) | TARGET AIR CONTENT (%) | CEMENTITIOUS MATERIALS |
| | FO | CONCRETE NOT EXPOSED TO FREEZING-AND-THAWING CYCLES | 0.55 | 3500 | N/A | N/A | N/A |
| <u> </u> | | | | | 3/8" | 6 | |
| | | CONCRETE EXPOSED TO FREEZING-AND-THAWING CYCLES WITH LIMITED EXPOSURE TO WATER | 0.55 | 3500 | 1/2" | 5.5 | |
| | F1 | | | | 3/4" | 5 | N/A |
| | | | | | 1" | 4.5 | |
| | | | | | 1 1/2" | 4.5 | |
| | | | | | 3/8" | 7.5 | N/A |
| | | CONCRETE EXPOSED TO FREEZING-AND-THAWING CYCLES WITH FREQUENT EXPOSURE TO WATER | 0.45 | | 1/2" | 7 | |
| | F2 | | | 4500 | 3/4" | 6 | |
| | | | | | 1" | 6 | |
| | | | | | 1 1/2" | 5.5 | |
| | | | | | 3/8" | 7.5 | |
| | | CONCRETE EXPOSED TO FREEZING-AND-THAWING CYCLES | | | 1/2" | 7 | ACI 318, SECTION 26.4.2.2(b) |
| | F3 | WITH FREQUENT EXPOSURE TO WATER AND EXPOSURE TO | 0.4 | 5000 | 3/4" | 6 | |
| | | DEICING CHEMICALS | | | 1" | 6 | |
| | | | | | 1 1/2" | 5.5 | |

☐ A.1 WITH OUT GEOTECH REPORT

Maximum water/cement ratio of 0.45; minimum compressive strength of 4,500 pounds

per square inch (psi); Type V cement plus pozzolan or slag cement complying with Footnote 7 of ACI

table 19.3.2.1; prohibition of admixtures containing calcium chloride; and 4" max slump.

A.2 Optional (Site-Specific) concrete Strength: WITH GEOTECH REPORT
When the PC drawings require a site-specific geotechnical report that quantifies sulfate
content in the soil, the PC drawings shall require a concrete mix shall comply with one
of the following based on the exposure class for each category from ACI 318 Table 19.3.2.1 below
*(The minimum compressive strength shall not be less than 3500 psi with 4" max Slump)

| | EXPOSURE CATEGORY: SULFATE (S) | | | | | | | | | | |
|------|--------------------------------|---|--|--------------|-------------|-----------------------------------|---|------------------------------------|------------------|--|--|
| | | CONDITI | | | | CEM | ENTITIOUS MATERIALS T | YPES | CALCIUM CHLORIDE | | |
| EXPO | SURE CLASS | WATER-SOLUBLE SULFATE (SO ₄ ²⁻) IN SOIL, PERCENT BY MASS | DISSOLVED SULFATE (SO ₄ ² ·) IN WATER, PPM | MAXIMUM W/CM | MINIMUM f'c | ASTM C150 | ASTM C595 | ASTM C1157 | ADMIXTURE | | |
| | S0 | SO ₄ ²⁻ < 0.10 | SO ₄ ²⁻ < 150 | 0.55 | 3500 | NO TYPE RESTRICTION | NO TYPE RESTRICTION | NO TYPE RESTRICTION | NO RESTRICTION | | |
| | \$1 | 0.10 ≤ SO ₄ ²⁻ < 0.20 | 150 ≤ SO ₄ ²⁻ < 1500 OR SEAWATER | 0.50 | 4000 | 11 | TYPES WITH (MS) DESIGNATION | MS | NO RESTRICTION | | |
| | S2 | 0.20 ≤ SO ₄ ²⁻ ≤ 2.0 | 1500 ≤ SO ₄ ²⁻ ≤ 10,000 | 0.45 | 4500 | V | TYPES WITH (HS) DESIGNATION | HS | NOT PERMITTED | | |
| | S3 (OPTION 1) | SO ₄ ²⁻ > 2.0 | SO ₄ ²⁻ > 10,000 | 0.45 | 4500 | V PLUS POZZOLAN OR SLAG CEMENT | TYPES WITH (HS) DESIGNATION PLUS POZZOLAN OR SLAG CEMENT | HS PLUS POZZOLAN OR SLAG CEMENT | NOT PERMITTED | | |
| | S3 (OPTION 2) | SO ₄ ²⁻ > 2.0 | SO ₄ ²⁻ > 10,000 | 0.50 | 5000 | V | TYPES WITH (HS) DESIGNATION | нѕ | NOT PERMITTED | | |

| EXPOSURE CATEGORY: IN CONTACT WITH WATER (W) | | | | | | | | | | |
|--|----|--|---------------------------|------|---|--|--|--|--|--|
| EXPOSURE CLASS | | CONDITION | MAXIMUM MINIMU W/CM M f'c | | ADDITIONAL REQUIREMENTS | | | | | |
| | WO | CONCRETE DRY IN SERVICE OR CONCRETE IN CONTACT WITH WATER AND LOW PERMEABILITY IS NOT REQUIRED | 0.55 | 3500 | N/A | | | | | |
| | W1 | CONCRETE IN CONTACT WITH WATER AND LOW PERMEABILITY IS REQUIRED | 0.50 | 3500 | AGGREGATES ARE NOT ALKALI-SILCA OR ALKALI-CARBONATE REACTIVE | | | | | |
| | W2 | CONCRETE IN CONTACT WITH WATER AND LOW PERMEABILITY IS REQUIRED | 0.50 | 4000 | AGGREGATES ARE NOT ALKALI-SILCA OR ALKALI-CARBONATE REACTIVE | | | | | |

| | EXPOSURE CATEGORY: CORROSION PROTECTION OF REINFORCEMENT | | | | | | | | | | | |
|--------------------------|--|---|-----------------|-----------------|---|---|--|--|--|--|--|--|
| EXPOSURE CLASS CONDITION | | CONDITION | MAXIMUM W/CM | MINIMU M f'c | MAXIMUM WATER-SOLUBLE CHLORIDE ION (CL) CONTENT IN CONCRETE, PERCENT BY WEIGHT OF CEMENT (NON-PRESTRESSED CONCRETE) | ADDITIONAL REQUIREMENTS | | | | | | |
| | со | CONCRETE NOT EXPOSED TO MOISTURE OR TO AN EXTERNAL SOURCE OF | 0.55 | 3500 | 1.00 | N/A | | | | | | |
| | C1 | CONCRETE EXPOSED TO MOISTURE BUT NOT TO AN EXTERNAL SOURCE OF CHLORIDES | 0.55 | 3500 | 0.30 | N/A | | | | | | |
| | C2 | CONCRETE EXPOSED TO MOISTURE AND AN EXTERNAL SOURCE OF CHLORIDES (DEICING | 0.40 | 5000 | 0.15 | CONCRETE COVER PER ACI 318, SECTION 20.5 | | | | | | |

NOTES:

(1) THE ALTERNATIVE CONCRETE MIX DESIGN REQUIREMENTS MAY BE SELECTED AND USED FOR CONSTRUCTION PROVIDE A SITE-SPECIFIC GEOTECHNICAL REPORT HAS BEEN PROVIDED AND CONFIRMS ALL APPLICABLE EXPOSURE CLASS PER ACI 318, SECTION (2) DOCUMENTATION OF CONCRETE MIXTURES CHARACTERISTICS SHALL BE IN ACCORDANCE WITH ACI, SECTION 26.4.4

(3) CEMENT SHALL BE CERTIFIED PER TITLE 24, PART 2, SECTION 1910A-1
(4) THE FOUNDATION DESIGN HAS BEEN PREPARED USINGA MINIMUM 28-DAY COMPRESSIVE CONCRETE STRENGTH (I°C) OF 3500 PSI
(5) FOR SITE-SPECIFIC LOCATIONS WITH MULTIPLE EXPOSURE CLASSES IDENTIFIED IN THE GEOTECHNICAL EXPLORATION REPORT, THE GREATER I°C ASSOCIATED WITH THE APPLICABLE EXPOSURE CLASS SHALL BE USED FOR CONSTRUCTION

SCALE
ALTERNATIVE CONCRETE MIX-DESIGN: SITE-SPECIFIC

DSA 103-22: LISTING OF STRUCTURAL TESTS & SPECIAL INSPECTIONS, 2022 CBC Application Number: School Name: DSA File Number: **Date Created: Increment Number:** 2023-05-16 13:25:31 2022 CBC \IMPORTANT: This form is only a summary list of structural tests and some of the special inspections required for the project. Generally, the structural tests and special inspections noted on this form are those that will be performed by the Geotechnical Éngineer of Record, Laboratory of Record, or Special Inspector. The actual complete test and inspection program must be performed as detailed on the DSA approved documents. The appendix at the bottom of this form identifies work NOT subject to DSA requirements for special inspection or structural testing. The project inspector is responsible for providing inspection of all facets of construction, including but not limited to, special inspections not listed on this form such as structural wood framing, high-load wood diaphragms, cold-formed steel framing, anchorage of non-structural components, etc., per Title 24, Part 2, Chapter 17A (2022 CBC). **NOTE: Undefined section and table references found in this document are from the CBC, or California Building Code. **KEY TO COLUMNS** 1. TYPE 2. PERFORMED BY **GE (Geotechnical Engineer)** – Indicates that the special inspection shall be performed by a registered geotechnical engineer or his or her authorized **Continuous** – Indicates that a continuous special inspection is LOR (Laboratory of Record) – Indicates that the test or special inspection shall be performed by a testing laboratory accepted in the DSA Laboratory Evaluation and Acceptance (LEA) Program. See CAC/Section 4-335. **Periodic** – Indicates that a periodic special inspection is required PI (Project Inspector) – Indicates that/the special inspection may be performed by a project inspector when specifically approved by DSA. **Test** – Indicates that a test is required SI (Special Inspection) – Indicates that the special inspection shall be performed by an appropriately qualified/approved special inspector. C1. CAST-IN-PLACE CONCRETE Test or Special Inspection Performed By | Code References and Notes ☑ a. Verify use of required design mix. Periodic Table 1705A.3 Item 5, 1910A.1. **b.** Identifiy, sample, and test reinforcing steel. Test **1910A.2**; A¢ 318-19 Ch.20 and Section 26.6.1.2; DSA IR 17-10. (See Appendix (end of this form) for exemptions.) **Table 1705A.3 Item 6**; ACI 318-19 Sections 26.5 & 26.12. ☑ c. During concrete placement, fabricate specimens for strength tests, perform slump and air content tests, and determine the temperature of the ✓ **d**. Test concrete (f'c). **1905A.1.17**; ACI 318-19 Section 26.12. ☑ e. Batch plant inspection: Continuous See Notes SI Default of 'Continuous' per 1705A.3.3. If approved by DSA, batch plant inspection may be reduced to 'Periodic' subject to requirements in Section **1705A.3.3.1**, or eliminated per **1705A.3.3.2**. See IR 17-13. (See Appendix (end of this form) for exemptions.) S/A1. STRUCTURAL STEEL, COLD-FORMED STEEL AND ALUMINUM USED FOR STRUCTURAL PURPOSES Test or Special Inspection Performed By | Code References and Notes ☑ a. Verify identification of all materials and: Periodic\ **Table 1705A.2.1 Item 3a 3c.** 2202A.1; AISI S100-20 Section A3.1 & • Mill certificates indicate material properties that comply A3.2, AISI S240-20 Section A3 & A5, AISI S220-20 Sections A4 & A6. * By special inspector or qualified technician when performed off-site. with requirements. • Material sizes, types and grades comply with **b**. Test unidentified materials Periodic / | C. Examine seam welds of HSS shapes ☑ d. Verify and document steel fabrication per DSA-Not applicable to cold-formed steel light-frame construction, except for trusses (1705A.2.4). approved construction documents. S/A3. WELDING: Performed By | Code References and Notes Test or Special Inspection **1705A.2.5, Table 1705A.2.1 Items 4 & 5**; AWS D1.1 and AWS D1.8 for ☑ a. Verify weld filler material identification markings per AWS designation listed on the DSA-approved documents structural steel; AWS D1.2 for Aluminum; AWS D1.3 for cold-formed steel; AWS D1.4 for reinforcing steel; DSA IR 17-3. ☑ **b.** Verify weld filler material manufacturer's certificate of c. Verify WPS, welder qualifications and equipment. SI DSA NR 17-3. S/A4. SHOP WELDING (IN ADDITION TO SECTION \$/A3): Test or Special Inspection Performed By | Code References and Notes a. Inspect groove welds, multi-pass fillet welds, single pass | Continuous **Table 1705**(**A.2.1 Items 5a.1 4**; AISC 360-16 (and AISC 341-16 as fillet welds > 5/16", plug and slot welds. applicable); DSA IR 17-3. **1705A.2.2, Talyle 1705A.2.1 Items 5a.5 & 5a.6**; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. ☑ c. Inspect welding of stairs and railing systems. Periodic **1705A.2.1**; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; DSA IR 17-3. Type | Performed By | Code References and Notes Test or Special Inspection S/A6. NONDESTRUCTIVE TESTING: | Performed By | Code References and Notes Test or Special Inspection **1705A.2.1, 1705A.2.5**; A\SC 341-16 J6.2, AISC 360-16 N5.5; AWS ☑ a. Ultrasonic D1.1, AWS D1.8; DSA IR 17-2. ☑ **b.** Magnetic Particle Test **1705A.2.1, 1705A.2.5**; AISC 341-16 J6.2, AISC 360-16 N5.5; AWS D1.1, AWS D1.8; DSA IR 17-2. 1. Structural Testing and Inspection: Laboratory Verified Report Form DSA 291

NOTE:
THE EXAMPLE OF FORM DSA-103s SHOWN ON THIS SHEET ARE FOR ILLUSTRATION PURPOSE ONLY.
A FORM DSA-103 IS TO BE COMPLETED FOR EACH APPLICATION THAT THIS PC BEING
INCORPORATED INTO AND EXAMPLE FORM DSA-103s ARE TO BE CROSSED OUT ON THIS DRAWING.

Shop Welding Inspection: Laboratory Verified Report Form DSA 291, or, for independently contracting SI, Special Inspection Verified Report Form

2. Concrete Batch Plant Inspection: Laboratory Verified Report Form DSA 291

. DSA 292

DSA-103 CONCRETE FLOOR (STOCKPILE)

DSA 103-22: LISTING OF STRUCTURAL TESTS & SPECIAL INSPECTIONS, 2022 CBC
Application Number: School Name: School District:

KEY TO COLUMNS

1. TYPE

2022 CBC

IMPORTANT: This form is only a summary list of structural tests and some of the special inspections required for the project.

Generally, the structural tests and special inspections noted on this form are those that will be performed by the Geotechnical Engineer of Record, Laboratory of Record, or Special Inspector. The actual complete test and inspection program must be performed as detailed on the DSA approved documents. The appendix at the bottom of this form identifies work NOT subject to DSA requirements for special inspection or structural testing. The project inspector is responsible for providing inspection of all facets of construction, including but not limited to, special inspections not listed on this form such as structural wood framing, high-load wood diaphragms, cold-formed steel framing, anchorage of non-structural components, etc., per Title 24, Part 2, Chapter 17A (2022 CBC).

**NOTE: Undefined section and table references found in this document are from the CBC, or California Building Cod

2 PERFORMED BY

GE (Geotechnical Engineer) – Indicates that the special in pection shall be

| _ | | | | med by a testing laboratory accepted in the DSA Laboratory Evaluation ptance (LEA) Program. See CAC Section 4-385. |
|----------|---|------------------|--------------------|---|
| Peri | odic – Indicates that a periodic special inspection is required | | PI (Projed | ct Inspector) – Indicates that the special inspection may be performe |
| Tost | t – Indicates that a test is required | | | when specifically approved by DSA. |
| rest | a - indicates that a test is required | | | al Inspection) – Indicates that the special inspection shall be perform |
| Geo | technical Reports: Project does NOT have and | does NOT re | | oropriately qualified/approved specifal inspector. hnical report |
| | S1. GENERAL: | | 1 | |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| V | a. Verify that: Site has been prepared properly prior to placement of controlled fill and/or excavations for foundations. Foundation excavations are extended to proper depth and have reached proper material. | See Notes | PI | Refer to specific items identified in the Appendix listing exemptions for limitations. Placement of controlled fill exceeding 12" depth uncondations is not permitted without a geotechnical report. |
| | Materials below footing are adequate to achieve the design bearing capacity. S2. SOIL COMPACTION AND FILL: | | | |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| V | a. Verify use of proper materials densities and inspect lift thicknesses, placement and compaction during placement of fill. | Continuous | LOR* | * Under the supervision of a geotechnical engineer or LOR's engineering manager. Refer to specific items identified in the Appendix listing exemptions for limitations. |
| V | b. Compaction testing. | Test | LOR* | * Under the supervision of a geotechnical engineer or LOR's engineering manager. Refer to specific items identified in the Appendix listing exemptions for limitations. |
| | C1. CAST-IN-PLACE CONCRETE | | | |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| / | a. Verify use of required design mix. | Periodic | SI | Table 1705A.3 Item 5, 1910A.1. |
| V | b. Identifiy, sample, and test reinforcing steel | Test | LOR | 1910A.2; ACI 318-19 Ch.20 and Section 26.6.1.2; DSA IR 17-10. (See |
| V | c. During concrete placement, fabricate specimens for strength tests, perform slump and air content tests, and determine the temperature of the | Test | LOR | Appendix (end of this form) for exemptions.) Table 1705A.3 Item 6; ACI 318-19 Sections 26.5 & 26.12. |
| _ | tests, and determine the temperature of the concrete. | <u>L</u> _ | / | |
| V | d. Test concrete (fc). | Test | LOR | 1905A.1.17 ; ACI 318-19 Section 26.12. |
| V | e. Batch plant inspection: Continuous | See Notes | SI | Default of 'Continuous' per 1705A.3.3. If approved by DSA, batch plant inspection may be reduced to 'Periodic' subject to requireme in Section 1705A.3.3.1, or eliminated per 1705A.3.3.2. See IR 17-1. |
| | \ | \setminus | / | (See Appendix (end of this form) for exemptions.) |
| | C5. POST-INSTALLED ANCHORS: | | | |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| 7 | a. Inspect installation of post-installed anchors | See Notes | SI* | 1617A.1.19, Table 1705A.3 Item 4a (Continuous) & 4b (Periodic) 1705A.3.8 (See Appendix (end of this form) for exemptions). ACI 318-14 Sections 17.8 & 26.13. * May be performed by the project inspector when specifically approved by DSA. |
| / | b. Test post-installed anchors. | Test | LOR | 1910A.5. (See Appendix (end of this form) for exemptions.) |
| | S/A1. STRUCTURAL STEEL, COLD-FORMED STEEL AND A | LUMINUM USE | D FOR STRUCTUE | RAL PURPOSES |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| ✓ | a. Verify identification of all materials and: Mill certificates indicate material properties that comply | Periodic | * | Table 1705A.2.1 Item 3a 3c. 2202A.1; AISI S100-20 Section A3.1 & A3.2, AISI S240-20 Section A3 & A5, AISI S220-20 Sections A4 & A6.* |
| | with requirements. • Material sizes, types and grades comply with requirements. | | | special inspector or qualified technician when performed off-site. |
| / | b. Test unidentified materials | Test | OR | 2202A.1. |
| / | c. Examine seam welds of HSS shapes | Periodic | s | DSA IR 17-3. |
| ✓ | d. Verify and document steel fabrication per DSA- approved construction documents. S/A3. WELDING: | Periodic | SI | Not applicable to cold-formed steel light-frame construction, excep for trusses (1705A.2.4). |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| V | a. Verify weld filler material identification markings per AWS designation listed on the DSA-approved documents and the WPS. | Periodic | SI | 1705A.2.5, Table 1705A.2.1 Items 4 & 5; AWS D1.1 and AWS D1.8 structural steel; AWS D1.2 for Aluminum; AWS D1.3 for cold-formed steel; AWS D1.4 for reinforcing steel; DSA IR 17-3. |
| / | b. Verify weld filler material manufacturer's certificate of compliance. | Periodic | SI | D9A IR 17-3. |
| 7 | c. Verify WPS, welder qualifications and equipment. S/A4. SHOP WELDING (IN ADDITION TO SECTION S/A3): | Periodic | SI | DSA R 17-3. |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| V | a. Inspect groove welds, multi-pass fillet welds, single pass fillet welds > 5/16", plug and slot welds. | Continuous | SI | Table 1705A.2.1 Items 5a.1 4 ; AISC 360-16 (and AISC 341-16 as applicable) DSA IR 17-3. |
| 7 | b. Inspect single-pass fillet welds \$ 5/16", floor and roof deck welds. | Periodic | SI | 1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. |
| | c. Inspect welding of stairs and failing systems. d. Verification of reinforcing steel weldability | Periodic | SI | 1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 D1.3; DSA IR 17-3 1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reporte |
| | d. Verification of reinforcing steel weldability other than ASTM A706. | Periodic | SI | on mill certificates. |
| V | e. Inspect welding of reinforcing steel. | Continuous | SI | Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8; AWS D1.4; D5A IR 17-3. |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| | S/A5. FIELD WELDING (IN ADDITION TO SECTION S/A3): | | | |
| 7 | b. Inspect single-pass fillet welds ≤ 5/16". | Periodic | SI | Table 1705A.2.1 Item 5a.5 AISC 360-16 (AISC 341-16 as applicable DSA IR 17-3. |
| ✓ | d. Inspect floor and roof deck welds. Test or Special Inspection | Periodic Type | SI Performed By | 1705A.2.2, Table 1705A.2.1 Item 5a.6; AISC 360-16 (AISC 341-16 applicable); AWS D1.3; DSA IR 17-3. Code References and Notes |
| | S/A6. NONDESTRUCTIVE TESTING: | | | |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| ✓ | a. Ultrasonic | Test | LOR | 1705A.2.1, 1705A.2.5 ; AISC 341-16 J6.2, AISC 360-16 N5.5; A D1.1, AWS D1.8; DSA IR 17-2. |
| | 1 / | | a. | |

THE EXAMPLE OF FORM DSA-103s SHOWN ON THIS SHEET ARE FOR ILLUSTRATION PURPOSE ONLY.
A FORM DSA-103 IS TO BE COMPLETED FOR EACH APPLICATION THAT THIS PC BEING
INCORPORATED INTO AND EXAMPLE FORM DSA-103s ARE TO BE CROSSED OUT ON THIS DRAWING.

Post-installed Anchors: Laboratory Verified Report Form DSA 291, or, for independently contracting SI, Special Inspection Verified Report Form DSA

Shop Welding Inspection: Laboratory Verified Report Form DSA 291, or, for independently contracting SI, Special Inspection Verified Report Form

Field Welding Inspection: Laboratory Verified Report Form DSA 291, or, for independently contracting SI, Special Inspection Verified Report Form DSA

IF THERE IS A GEOTECHNICAL REPORT, THE GEOTECH ENGINEER SHOULD DO THE INSPECTION INSTEAD OF PROJECT INSPECTOR (PI).

DSA-103 CONCRETE FLOOR (CONCRETE FOUNDATION)

Concrete Batch Plant Inspection: Laboratory Verified Report Form DSA 291

IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT

APP: 02-122764 INC:

REVIEWED FOR
SS FLS ACS D

DATE: 12/18/2024

ROJECT SPECIFIC STATE AGENCY APPROVAC



PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©



APPROVED
DIV. OF THE STATE ABCHITECT

APP: 04-123059 PC

REVIEWED FOR
SS PLS ACS CG P

Revision Schedule

Description

PRE-CHECK (PC) DOCUMENT

Code: 2022 CBC

A separate project application for construction is required

PROJECT TITLE
PC 2022 CBC: 24' x 40'
EXPANDABLE TO
120' x 40'

DSA-103 T&I CONCRETE FLOORS

PROJECT NUMBER

22088

DRAWN BY

rMc/SC

CHECKED BY RH/RT

DATE

νο.

SHEET OF

NOT IN USE

DSA File Number: **Increment Number: Date Created:** 2023-05-16 13:57:04

2022 CBC

IMPORTANT: This form is only a summary list of structural tests and some of the special inspections required for the project. Generally, the structural tests and special inspections noted on this form are those that will be performed by the Geotechnical Engineer of Record, Laboratory of Record, or Special Inspector. The actual complete test and inspection program must be performed/as detailed on the DSA approved documents. The appendix at the bottom of this form identifies work NOT subject to DSA requirements for special inspection or structural testing. The project inspector is responsible for providing inspection of all facets of construction, including but not limited to, special inspections not listed on this form such as structural wood framing, high-load wood diaphragms, cold-formed steel framing, anchorage of non-structural components, etc., per Title 24, Part 2, Chapter 17A (2022 CBC). /

**NOTE: Undefined section and table references found in this document are from the CBC, or California Building Code.

| FY 1 | TO COLUMNS | | | |
|---------------|--|------------|--|--|
| _ I | 1. TYPE | | | PERFORMED BY |
| requ Perio | tinuous – Indicates that a continuous special inspection is aired odic – Indicates that a periodic special inspection is required t – Indicates that a test is required S/A1. STRUCTURAL STEEL, COLD-FORMED STEEL AND A | | GE (Geot performe represent LOR (Lab be perfor and Acce PI (Project by a project inspector SI (Special by an app | rechnical Engineer) – Indicates that the special inspection shall be ad by a registered geotechnical engineer or his or her authorized stative. Poratory of Record) – Indicates that the test or special inspection shall med by a testing laboratory accepted in the DSA Laboratory Evaluation ptance (LEA) Program. See CAC Section 4-335. Cot Inspector) – Indicates that the special inspection may be performed ect when specifically approved by DSA. al Inspection) – Indicates that the special inspection shall be performed propriately qualified/approved special inspector. |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| V | a. Verify identification of all materials and: • Mill certificates indicate material properties that comply with requirements. • Material sizes, types and grades comply with requirements. | Periodic | * | Table 1705A/2.1 Item 3a 3c. 2202A.1; AISI S100-20 Section A3.1 & A3.2, AISI S240-20 Section A3 & A5, AISI S220-20 Sections A4 & A6. * By special inspector or qualified technician when performed off-site. |
| √ | b. Test unidentified materials | Test | LOR | 22024.1. |
| ✓ | c. Examine seam welds of HSS shapes | Periodic | SI | DSA/IR 17-3. |
| 7 | d. Verify and document steel fabrication per DSA-approved construction documents. | Periodic | SI | Not applicable to cold-formed steel light-frame construction, except for trusses (1705A.2.4). |
| | S/A3. WELDING: | | | |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| V | a. Verify weld filler material identification markings per AWS designation listed on the DSA-approved documents and the WPS. | Periodic | SI | 1705A.2.5 , Table 1705A.2.1 Items 4 & 5 ; AWS D1.1 and AWS D1.8 for structural steel; AWS D1.2 for Aluminum; AWS D1.3 for cold-formed steel; AWS D1.4 for reinforcing steel; DSA IR 17-3. |
| V | b . Verify weld filler material manufacturer's certificate of compliance. | Periodic | \$I | DSA IR 17-3. |
| ✓ | c. Verify WPS, welder qualifications and equipment. | Periodic | SI | DSA IR 17-3. |
| | S/A4. SHOP WELDING (IN ADDITION TO SECTION S/A3): | | X | |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| 7 | a. Inspect groove welds, multi-pass fillet welds, single pass fillet welds > 5/16", plug and slot welds. | Continuous | SI | Table 1705A.2.1 Items 5a.1 4 ; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. |
| V | b. Inspect single-pass fillet welds ≤ 5/16", floor and roof deck welds. | Periodic | si | 1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6 ; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. |
| 7 | c. Inspect welding of stairs and railing systems. | Periodic | SI | 1705A.2.1 ; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; DSA IR 17-3. |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| | S/A6. NONDESTRUCTIVE TESTING: | | | |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| V | a. Ultrasonic | Test | LOR | 1705A.2.1, 1705A.2.5 ; AISC 341-16 J6.2, AISC 360-16 N5.5; AW D1.1, AWS D1.8; DSA IR 17-2. |
| V | b. Magnetic Particle | Test | LOR | 1705A.2.1, 1705A.2.5 ; AISC 341-16 J6.2, AISC 360-16 N5.5; AW |

1. Structural Testing and Inspection: Laboratory Verified Report Form DSA 291

Shop Welding Inspection: Laboratory Verified Report Form DSA 291, or, for independently contracting \$1, Special Inspection Verified Report Form

D1.1, AW\ D1.8; DSA IR 17-2.

THE EXAMPLE OF FORM DSA-1/03s SHOWN ON THIS SHEET ARE FOR ILLUSTRATION PURPOSE ONLY. A FORM DSA-103 IS TO BE COMPLETED FOR EACH APPLICATION THAT THIS PC BEING INCORPORATED INTO AND EXAMPLE FORM DSA-103s ARE TO BE CROSSED OUT ON THIS DRAWING, DSA 103-22: LISTING OF STRUCTURAL TESTS & SPECIAL INSPECTIONS, 2022 CBC **Application Number:**

Increment Number:

DSA File Number:

2022 CBC

IMPORTANT: This form is only a summary list of structural tests and some of the special inspections required for the project. Generally, the structural tests and special inspections noted on this form are those that will be performed by the Geotechnical Engineer of Record, Laboratory of Record, or Special Inspector. The actual complete test and inspection program must be performed as detailed on the DSA approved documents. The appendix at the bottom of this form identifies work NOT subject to DSA requirements for special inspection or structural testing. The project inspector is responsible for providing inspection of all facets of construction, including but not limited to, special inspections not listed on this form such as structural wood framing, high-load wood diaphragms, cold-formed steel framing, anchorage of non-structural components, etc., per Title 24, Part 2, Chapter 17A (2022 CBC).

Date Created:

2023-05-16 14:08:48

**NOTE: Undefined section and table references found in this document are from the CBC, or California Building Code.

| | , |
|---|--|
| KEYTO COLUMNS | |
| \ 1. TYPE | 2. PERFORMED BY |
| Continuous – Indicates that a continuous special inspection is | GE (Geotechnical Engineer) – Indicates that the special inspection shall be performed by a registered geotechnical engineer or his or her authorized representative. |
| required | LOR (Laboratory of Record) – Indicates that the test or special inspection shall be performed by a testing laboratory accepted in the DSA Laboratory Evaluation and Acceptance (LEA) Program. See CAC Section 4-335. |
| Periodic – Indicates that a periodic special inspection is required | |
| | PI (Project Inspector) – Indicates that the special inspection may be performed by a project |
| | inspector when specifically approved by DSA. |
| Test – Indicates that a test is required | |
| | SI (Special Inspection) – Indicates that the special inspection shall be performe by an appropriately qualified/approved special inspector. |

| | S1. GENERAL: | | | / |
|---------------------|---|---|--|---|
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| 7 | a. Verify that: • Site has been prepared properly prior to placement of controlled fill and/or excavations for foundations. • Foundation excavations are extended to proper | See Notes | PI | Refer to specific items identified in the Appendix listing exemptions for limitations. Placement of controlled fill exceeding 12" depth und foundations is not permitted without a geotechnical report. |
| | depth and have reached proper material. • Materials below footings are adequate to achieve the design bearing capacity. S2. SOIL COMPACTION AND FILL: | | | |
| | \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ | Typo | Dorformed Pu | Code References and Notes |
| V | Test or Special Inspection a. Verify use of proper materials, densities and inspect lift thicknesses, placement and compaction during placement of fill. | Type Continuous | Performed By LOR* | * Under the supervision of a geotechnical engineer or LOR's engineering manager. Refer to specific items identified in the Appendix listing exemptions for limitations. |
| V | b. Compaction testing. | Test | LOR* | * Under the supervision of a geotechnical engineer or LOR's engineering manager. Refer to specific tems identified in the Appendix listing exemptions for limitations. |
| | C1. CAST-IN-PLACE CONCRETE | • | • | |
| V | Test or Special Inspection a. Verify use of required design mix. | Type Periodic | Performed By | Code References and Notes Table 1705A.3 Item 5, 1910A.1. |
| ✓ | b. Identifiy, sample, and test reinforcing steel. | Test | LOR | 1910A.2 ; ACI 318-19 Ch.20 and Section 26.6.1.2; DSA IR 17-10. (See |
| | \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ | \ <u>-</u> . | 100 | Appendix (end of this formy for exemptions.) |
| ✓ | c. During concrete placement, fabricate specimens for strength tests, perform slump and air content tests, and determine the temperature of the concrete. | Test | LOR | Table 1705A.3 Item 6 ; ACI 318-19 Sections 26.5 & 26.12. |
| √ | d. Test concrete (fc). | Test | LOR | 1905A.1.17 ; ACI 318-19 Section 26.12. |
| 7 | e. Batch plant inspection: Continuous | See Notes | SI | Default of 'Continuous' per 1705A.3.3. If approved by DSA, batch plant inspection may be reduced to 'Periodic' subject to requirement in Section 1705A.3.3.1, or eliminated per 1705A.3.3.2. See IR 17-13 (See Appendix (end of this form) for exemptions.) |
| | C5. POST-INSTALLED ANCHORS: | | $\overline{}$ | |
| | Test or Special Inspection | Туре | Pekformed By | Code References and Notes |
| V | a. Inspect installation of post-installed anchors | See Notes | SI* | 1617A.1.19, Table 1705A.3 Item 4a (Continuous) & 4b (Periodic) 1705A.3.8 (See Appendix (end of this form) for exemptions). ACI 318-14 Sections 17.8 & 26.13.* May be performed by the project in spector when specifically approved by DSA. |
| 7 | b. Test post-installed anchors. | Test | LOR | 1910A.5. (See Appendix (end of this form) for exemptions.) |
| | S/A1. STRUCTURAL STEEL, COLD-FORMED STEEL AND A | LUMINUM USE | D FOR STRUCTUR | RAL PURPOSES |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| V | a. Verify identification of all materials and: Mill certificates indicate material properties that comply with requirements. Material sizes, types and grades comply with | Periodic | / | Table 1705A.2.1 Item 3a 3c. 2202A.1; AISI S100-20 Section A3.1 & A3.2, AISI S240-20 Section A3 & A5, AISI S220-20 Sections A4 & A6. * special inspector or qualified technician when performed off-site. |
| V | requirements. b. Test unidentified materials | Test | LOR | 2202A.1. |
| ✓ | c. Examine seam welds of HSS shapes d. Verify and document steel fabrication per DSA- | Periodic Periodic | SI SI | DSA IR 17-3 Not applicable to cold-formed steel light-frame construction, excep |
| | approved construction documents. S/A3. WELDING: | | | for trusses (1705A.2.4). |
| | Test or Special Inspection | Type | Performed By | Code References and Notes |
| V | a. Verify weld filler material identification markings per AWS designation listed on the DSA-approved documents and the WPS. | Periodic | SI | 1705A.2.5, Table 1705A.2.1 Items 4 & 5; AWS D1.1 and AWS D1.8 structural steel; AWS D1.2 for Aluminum; AWS D1.3 for cold-formed steel; AWS D1.4 for reinforcing steel; DSA IR 17-3. |
| 7 | b. Verify weld filler material manufacturer's certificate of compliance. | Periodic | SI | DSA IR 17-3. |
| 7 | c. Verify WPS, welder qualifications and equipment. | Periodic | SI | DSA IR 17-3. |
| | | | J 31 | |
| | S/A4. SHOP WELDING (IN ADDITION TO SECTION S/A3): | | 31 | |
| 7 | S/A4. SHOP WELDING (IN ADDITION TO SECTION S//3): Test or Special Inspection a. Inspect groove welds, multi-pass fillet welds, single pass | Type Continuous | Performed By | Code References and Notes |
| ✓ | Test or Special Inspection a. Inspect groove welds, multi-pass fillet welds, single pass fillet welds > 5/16", plug and slot welds. b. Inspect single-pass fillet welds ≤ 5/16", floor and roof | | Performed By | Code References and Notes Table 1705A.2.1 Items 5a.1 4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and |
| | Test or Special Inspection a. Inspect groove welds, multi-pass fillet welds, single pass fillet welds > 5/16", plug and slot welds. | Continuous | Performed By | Code References and Notes Table 1705A.2.1 Items 5a.1 4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1.6 |
| V | Test or Special Inspection a. Inspect groove welds, multi-pass fillet welds, single pass fillet welds > 5/16", plug and slot welds. b. Inspect single-pass fillet welds ≤ 5/16", floor and roof deck welds. c. Inspect welding of stairs and railing systems. d. Verification of reinforcing steel weldability | Continuous Periodic | Performed By SI | Code References and Notes Table 1705A.2.1 Items 5a.1 4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 applicable); DSA IR 17-3. 1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reporter. |
| ✓ | Test or Special Inspection a. Inspect groove welds, multi-pass fillet welds, single pass fillet welds > 5/16", plug and slot welds. b. Inspect single-pass fillet welds ≤ 5/16", floor and roof deck welds. c. Inspect welding of stairs and railing systems. | Periodic Periodic | Performed By SI SI | Code References and Notes Table 1705A.2.1 Items 5a.1 4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 and D1.3; DSA IR 17-3. 1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported on mill certificates. Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, |
| | Test or Special Inspection a. Inspect groove welds, multi-pass fillet welds, single pass fillet welds > 5/16", plug and slot welds. b. Inspect single-pass fillet welds ≤ 5/16", floor and roof deck welds. c. Inspect welding of stairs and railing systems. d. Verification of reinforcing steel weldal filty other than ASTM A706. | Periodic Periodic Periodic | Performed By SI SI SI | Code References and Notes Table 1705A.2.1 Items 5a.1 4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; DSA IR 17-3. 1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported on mill certificates. |
| | Test or Special Inspection a. Inspect groove welds, multi-pass fillet welds, single pass fillet welds > 5/16", plug and slot welds. b. Inspect single-pass fillet welds ≤ 5/16", floor and roof deck welds. c. Inspect welding of stairs and railing systems. d. Verification of reinforcing steel weldability other than ASTM A706. e. Inspect welding of reinforcing steel. | Periodic Periodic Periodic | Performed By SI SI SI | Code References and Notes Table 1705A.2.1 Items 5a.1 4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; DSA IR 17-3. 1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported on mill certificates. Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, |
| V | Test or Special Inspection a. Inspect groove welds, multi-pass fillet welds, single pass fillet welds > 5/16", plug and slot welds. b. Inspect single-pass fillet welds ≤ 5/16", floor and roof deck welds. c. Inspect welding of stairs and railing systems. d. Verification of reinforcing steel weldability other than ASTM A706. e. Inspect welding of reinforcing steel. S/A5. FIELD WELDING (IN ADDITION TO SECTION S/A3): | Periodic Periodic Periodic Continuous | Performed By SI SI SI SI SI | Code References and Notes Table 1705A.2.1 Items 5a.1 4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 (D1.3; DSA IR 17-3. 1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported on mill certificates. Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8; AWS D1.4; DSA IR 17-3. |
| V | Test or Special Inspection a. Inspect groove welds, multi-pass fillet welds, single pass fillet welds > 5/16", plug and slot welds. b. Inspect single-pass fillet welds ≤ 5/16", floor and roof deck welds. c. Inspect welding of stairs and railing systems. d. Verification of reinforcing steel weldability other than ASTM A706. e. Inspect welding of reinforcing steel. S/A5. FIELD WELDING (IN ADDIT/ON TO SECTION S/A3): Test or Special Inspection | Periodic Periodic Periodic Continuous | Performed By SI SI SI SI Performed By | Code References and Notes Table 1705A.2.1 Items 5a.1 4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; DSA IR 17-3. 1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reporte on mill certificates. Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8; AWS D1.4; DSA IR 17-3. |
| V | Test or Special Inspection a. Inspect groove welds, multi-pass fillet welds, single pass fillet welds > 5/16", plug and slot welds. b. Inspect single-pass fillet welds ≤ 5/16", floor and roof deck welds. c. Inspect welding of stairs and railing systems. d. Verification of reinforcing steel weldability other than ASTM A706. e. Inspect welding of reinforcing steel. S/A5. FIELD WELDING (IN ADDITION TO SECTION S/A3): Test or Special Inspection b. Inspect single-pass fillet welds ≤ 5/16". | Periodic Periodic Periodic Continuous Type Periodic | Performed By SI SI SI SI SI SI SI | Code References and Notes Table 1705A.2.1 Items 5a.1 4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; DSA IR 17-3. 1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reporte on mill certificates. Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8; AWS D1.4; DSA IR 17-3. Code References and Notes Table 1705A.2.1 Item 5a.5; AISC 360-16 (AISC 341-16 as applicable DSA IR 17-3. |
| V | Test or Special Inspection a. Inspect groove welds, multi-pass fillet welds, single pass fillet welds > 5/16", plug and slot welds. b. Inspect single-pass fillet welds ≤ 5/16", floor and roof deck welds. c. Inspect welding of stairs and railing systems. d. Verification of reinforcing steel weldal fility other than ASTM A706. e. Inspect welding of reinforcing steel. S/A5. FIELD WELDING (IN ADDITION TO SECTION S/A3): Test or Special Inspection b. Inspect single-pass fillet welds ≤ 5/16". Test or Special Inspection | Periodic Periodic Periodic Continuous Type Periodic | Performed By SI SI SI SI SI SI SI | Code References and Notes Table 1705A.2.1 Items 5a.1 4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; DSA IR 17-3. 1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reporte on mill certificates. Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8; AWS D1.4; DSA IR 17-3. Code References and Notes Table 1705A.2.1 Item 5a.5; AISC 360-16 (AISC 341-16 as applicable) DSA IR 17-3. |
| V V V V | Test or Special Inspection a. Inspect groove welds, multi-pass fillet welds, single pass fillet welds > 5/16", plug and slot welds. b. Inspect single-pass fillet welds ≤ 5/16", floor and roof deck welds. c. Inspect welding of stairs and railing systems. d. Verification of reinforcing steel weldability other than ASTM A706. e. Inspect welding of reinforcing steel. S/A5. FIELD WELDING (IN ADDITION TO SECTION S/A3): Test or Special Inspection b. Inspect single-pass fillet welds ≤ 5/16". Test or Special Inspection S/A6. NONDESTRUCTIVE TESTING: | Periodic Periodic Periodic Continuous Type Periodic Type | Performed By SI SI SI SI SI Performed By SI Performed By | Code References and Notes Table 1705A.2.1 Items 5a.1 4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. 1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; DSA IR 17-3. 1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reporte on mill certificates. Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8; AWS D1.4; DSA IR 17-3. Code References and Notes Table 1705A.2.1 Item 5a.5; AISC 360-16 (AISC 341-16 as applicable DSA IR 17-3. |

1. Structural/Testing and Inspection: Laboratory Verified Report Form DSA 291

2. Concrete Batch Plant Inspection: Laboratory Verified Report Form DSA 291

Posyfinstalled Anchors: Laboratory Verified Report Form DSA 291, or, for independently contracting SI, Special Inspection Verified Report Form DSA

hop Welding Inspection: Laboratory Verified Report Form DSA 291, or, for independently contracting SI, Special Inspection Verified Report Form

Field Welding Inspection: Laboratory Verified Report Form DSA 291, or, for independently contracting SI, Special Inspection Verified Report Form DSA

DSA-103 PLYWOOD FLOOR (CONCRETE FOUNDATION)

NOTES:
THE EXAMPLE OF FORM DSA-103s SHOWN ON THIS SHEET ARE FOR ILLUSTRATION PURPOSE ONLY. A FORM DSA-103 IS TO BE COMPLETED FOR EACH APPLICATION THAT THIS PC BEING INCORPORATED INTO AND EXAMPLE FORM DSA-103s ARE TO BE CROSSED OUT ON THIS DRAWING.

IF THERE IS A GEOTECHNICAL REPORT, THE GEOTECH ENGINEER SHOULD DO THE INSPECTION INSTEAD OF PROJECT INSPECTOR (PI).

DSA 103-22: LISTING OF STRUCTURAL TESTS & SPECIAL INSPECTIONS, 2022 CBC School Name: School District:

DSA File Number: **Increment Number:** Date Created: 2023-05-16 14:19:31

2022 CBC

IMPORTANT: This form is only a summary list of structural tests and some of the special inspections required for the project. Generally, the structural tests and special inspections noted on this form are those that will be performed by the Geotechnical Engineer of Record, Daboratory of Record, or Special Inspector. The actual complete test and inspection program must be performed as detailed on the DSA approved documents. The appendix at the bottom of this form identifies work NOT subject to DSA requirements for special inspection or structural testing. The project inspector is responsible for providing inspection of all facets of construction, including but not limited to, special inspections not listed on this form such as structural wood framing, high-load wood diaphragms, cold-formed steel \framing, anchorage of non-structural components, etc., per Title 24, Part 2, Chapter 17A (2022 CB $\not Q$).

**NOTE: Undefined section and table references found in this document are from the CBC, or California Building Code.

| | 1. TYPE | | 2. | PERFORMED BY |
|----------|---|-------------|----------------|--|
| | tinuous – Indicates that a continuous special inspection is | | | echnical Engineer) – Indicates that the special inspection shall be d by a registered geotechnical engineer or his or her authorized rative. |
| · | uired \ | | be perfor | Poratory of Record) – Indicates that the test or special inspection shall med by a testing laboratory accepted in the DSA Laboratory Evaluatio ptance (LEA) Program. See CAC Section 4-335. |
| Peri | odic – Indicates that a periodic special inspection is required | | by a proje | ct Inspector) – Indicates that the special inspection may be performed ect when specifically approved by DSA. |
| Test | t – Indicates that a test is required | | | al Inspection) – Indicates that the special inspection shall be performed propriately qualified/approved special inspector. |
| | S/A1. STRUCTURAL STEEL, COLD-FORMED STEEL AND A | LUMINUM USE | D FOR STRUCTUR | RAL PURPOSES |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| V | a. Verify identification of all materials and: Mill certificates indicate material properties that comply with requirements. Material sizes, types and grades comply with requirements. | Periodic | * | Table 1705A.2.1 Item 3a 3c. 2202A.1; AISI S100-20 Section A3.1 & A3.2, AISI S240-20 Section A3 & A5, AISI S220-20 Sections A4 & A6. * E special inspector or qualified technician when performed off-site. |
| V | b. Test unidentified materials | Test | LOR | 2202A.1. |
| V | c. Examine seam welds of HSS shapes | Periodic | SI | / ØSA IR 17-3. |
| V | d. Verify and document steel fabrication per DSA-approved construction documents. | Periodic | SI | Not applicable to cold-formed steel light-frame construction, except for trusses (1705A.2.4). |
| | S/A3. WELDING: | | | |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| V | a. Verify weld filler material identification markings per AWS designation listed on the DSA-approved documents and the WPS. | Periodic | S | 1705A.2.5, Table 1705A.2.1 Items 4 & 5; AWS D1.1 and AWS D1.8 structural steel; AWS D1.2 for Aluminum; AWS D1.3 for cold-formed steel; AWS D1.4 for reinforcing steel; DSA IR 17-3. |
| / | b. Verify weld filler material manufacturer's certificate of compliance. | Periodic | SI | DSA IR 17-3. |
| / | c. Verify WPS, welder qualifications and equipment. | Periodic | SI | DSA IR 17-3. |
| | S/A4. SHOP WELDING (IN ADDITION TO SECTION S/A3): | | | |
| | Test or Special Inspection | Type / | Performed By | Code References and Notes |
| 7 | a. Inspect groove welds, multi-pass fillet welds, single pass fillet welds > 5/16", plug and slot welds. | Continuous | si | Table 1705A.2.1 Items 5a.1 4 ; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. |
| ✓ | b. Inspect single-pass fillet welds ≤ 5/16", floor and roof deck welds. | Periodic | SI | 1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6 ; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3. |
| V | c. Inspect welding of stairs and railing systems. | Periodic | SI \ | 1705A.2.1 ; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; DSA IR 17-3. |
| | Test or Special Inspection | / Type | Performed By | Opde References and Notes |
| | S/A5. FIELD WELDING (IN ADDITION TO SECTION S/A3) | | | |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| | a. Inspect groove welds, multi-pass fillet welds, single pass fillet welds > 5/16", plug and slot welds. | Continuous | SI | Table 1705A.2.1 Items 5a.1 4 ; AISC 360-16 (AISC 341-16 as applicable); DSA IR 17-3. |
| V | b. Inspect single-pass fillet welds ≤ 5/16". | Periodic | SI | Table 1705A.2.1 Item 5a.5 ; AISC 360-16 (AISC 341-16 as applicable DSA IR 17-3. |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| | S/A6. NONDESTRUCTIVE TESTING: | | | |
| | Test or Special Inspection | Туре | Performed By | Code References and Notes |
| √ | a. Ultrasonic | Test | LOR | 1705A.2.1, 1705A.2.5 ; AISC 341-16 J6.2, AISC 360-16 N5.5; AID1.1, AWS D1.8; DSA IR 17-2. |
| | | | | ' |

Shop Welding Inspection:/Laboratory Verified Report Form DSA 291, or, for independently contracting SI, Special Inspection Verified Report Form

Field Welding Inspection: Laboratory Verified Report Form DSA 291, or, for independently contracting SI, Special Inspection Verified Report Form DSA

THE EXAMPLE OF FORM DSA-103s SHOWN ON THIS SHEET ARE FOR ILLUSTRATION PURPOSE ONLY. A FORM DSA-103 IS TO BE COMPLETED FOR EACH APPLICATION THAT THIS PC BEING INCORPORATED INTO AND EXAMPLE FORM DSA-103s ARE TO BE CROSSED OUT ON THIS DRAWING.


DSA-103 PLYWOOD FLOOR (WOOD FOUNDATION)

IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 DATE: _____12/18/2024

ROJECT SPECIFIC STATE AGENCY APPROVAL



PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©

1651Juanita Street, San Jacinto, CA 92583 Voice (951) 943-1908 Fax (951)943-5768

ORIGINAL PC STATE AGENCY APPROVAL



Revision Schedule

Description

PRE-CHECK (PC) DOCUMENT

A separate project application for construction is required

PC 2022 CBC: 24' x 40' **EXPANDABLE TO**

120' x 40'

PROJECT NUMBER

DSA-103 T&I **PLYWOOD FLOORS**

DSA-103 PLYWOOD FLOOR (STOCKPILE)

Fine Test **UL U457** Steel Stud (Non-loadbearing) Interior Partitions Sound Test: USG-840222


- 4-3/4" Steel Studs 3-5/8 in. wide by 1-1/4 in. deep, min. 20 gauge steel, max 16 in. OC 362S125-30
 - . Batts and Blankets 3 in. mineral wool batt insulation
 - Gypsum Board 5/8 in. thick gypsum board applied vertically SHEETROCK Brand FIRECODE Core (Type X)

Visit U457 @ U457 @

PROJECT SPECIFIC STATE AGENCY APPROVAC IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT APP: 02-122764 INC: **REVIEWED FOR** SS 🗹 FLS 🗹 ACS 🗹 12/18/2024



PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©



ORIGINAL PC STATE AGENCY APPROVAL APPROVED DIV. OF THE STATE ARCHITECT

> Revision Schedule Description

> > PRE-CHECK (PC) DOCUMENT

PC 2022 CBC: 24' x 40' **EXPANDABLE TO** 120' x 40'

SHEET TITLE
CALGREEN SPEC'S

PROJECT NUMBER

22088 rMc/SC

CHECKED BY

DATE

ACOUSTIC CONTROL- When

the Pre-check building is site

adapted, the building and site

CALGreen Code, Section

5.507.4 for the specific site

place adjacent to another PC

building, the adjoining wall

transmission must meet the

minimum requirement of a STC

rating of 40 (per 2022 CALGreen

section for interior sound

Code, Section 507.4.3).

features need to comply with the

location, and when PC building is

A0.5

UL U419 OR UL U465 (OR EQ) TO BE USED FOR INT. STC RATING. WOOD STUD MAY BE USED ILO OF MTL STUD (WHEN NON-RATED WALLS ARE BEING APPLIED "X" BOARD IS NOT REQUIRED -STC RATINGS STILL APPLY)

| 47/*" | UL U419 or MEA 81- 98-M Steel Stud (Non-loadbearing) Interior Partitions Sound Test: RAL-TL11-125 | Fire Rating 1 hr. | 40 | Thickness (In.) 4-7/8" | Gypsum Board - 5/8 in. thick gypsum board applied vertically or horizontally SHEETROCK Brand FIRECODE Core (Type X) Steel Studs - 3-5/8 in. wide min. 25 gauge steel studs @ max 24 in. OC - 362S125-18 Gypsum Board - 5/8 in. thick gypsum board applied vertically or horizontally SHEETROCK Brand FIRECODE Core (Type X) Visit U419 |
|-------|---|-------------------|-----------|---------------------------|--|
| 47/8" | UL U465 Steel Stud (Non-loadbearing) Interior Partitions Sound Test: RAL-TL11-125 | Fine Rating 1 hr. | sтс 40 | Thickness (in.) 4-7/8" | Gypsum Board - 5/8 in. thick board, applied vertically, attached to studs with 1 in. long, Type S -12 screws, spaced 8 in. OC along the edges and 12 in. OC of the board - SHEETROCK Brand FIRECODE Core (Type X) Steel Studs - 3-5/8 in. wide min. 25 gauge steel. Attached to floor and ceiling with fasteners, 24 in. OC - 362S125-18 Gypsum Board - 5/8 in. thick gypsum board applied vertically or horizontally SHEETROCK Brand FIRECODE Core (Type X) Visit U465 ☑ |

UL U457 (OR EQ) TO BE USED FOR EXT. STC RATING. WOOD STUD MAY BE USED ILO OF MTL STUD

Fire Rating

1 hr.

STG Thickness (in.) • Cement Board - 1/2 thick board, square edge - DUROCK Brand Cement Board Next Gen

301.1 SCOPE. Buildings shall be designed to include the green building measures specified as mandatory in

but are not required unless adopted by a city, county, or city and county as specified in Section 101.7.

301.3 NONRESIDENTIAL ADDITIONS AND ALTERATIONS. [BSC-CG] The provisions

the authority of California Building Standards Commission). Code sections relevant to additions and

alterations shall only apply to the portions of the building being added or altered within the scope of the

A code section will be designated by a banner to indicate where the code section only applies to newly

types of commercial real property affected, effective dates, circumstances necessitating

302.1 MIXED OCCUPANCY BUILDINGS. In mixed occupancy buildings, each portion of a building

303.1 PHASED PROJECTS. For shell buildings and others constructed for future tenant improvements

303.1.1 Initial Tenant improvements. The provisions of this code shall apply only to the initial tenant

improvements to a project. Subsequent tenant improvements shall comply with the scoping provisions in

only those code measures relevant to the building components and systems considered to be new

The provisions of this chapter outline planning, design and development methods that include environmentally responsible site selection, building design, building siting and development to protect, restore and enhance the

CUTOFF LUMINAIRES. Luminaires whose light distribution is such that the candela per 1000 lamp lumens does not

numerically exceed 25 (2.5 percent) at an angle of 90 degrees above nadir, and 100 (10 percent) at a vertical angle of

1. Zero emission vehicle (ZEV), enhanced advanced technology PZEV (enhanced AT ZEV) or transitional zero

2. High-efficiency vehicles, regulated by U.S. EPA, bearing a fuel economy and greenhouse gas rating od 9 oe

NEIGHBORHOOD ELECTRIC VEHICLE (NEV). A motor vehicle that meets the definition of "low-speed vehicle"

either in Section 385.5 of the Vehicle Code or in 49CFR571.500 (as it existed on July 1, 2000), and is certified to

VANPOOL VEHICLE. Eligible vehicles are limited to any motor vehicle, other than a motortruck or truck tractor,

occupants, such as employees, as distinguished from customers and other transient visitors.

primarily for the nonprofit work-related transportation of adults for the purpose of ridesharing.

TENANT-OCCUPANTS. Building occupants who inhabit a building during its normal hours of operation as permanen

designed for carrying more than 10 but not more than 15 persons including the driver, which is maintained and used

5.106.1 STORM WATER POLLUTION PREVENTION FOR PROJECTS THAT DISTURB LESS THAN ONE ACRE

OF LAND. Newly constructed projects and additions which disturb less than one acre of land, and are not part of a larger common plan of development or sale, shall prevent the pollution of storm water runoff from the construction

5.106.1.1 Local ordinance. Comply with a lawfully enacted storm water management and/or erosion control

5.106.1.2 Best Management Practices (BMPs). Prevent the loss of soil through wind or water erosion by

I. Soil loss BMPs that should be considered for implementation as appropriate for each project include,

2. Good housekeeping BMPs to manage construction equipment, materials, non-stormwater discharges

and wastes that should be considered for implementation as appropriate for each project include, but

b. Preservation of natural features, vegetation, soil, and buffers around surface waters.

implementing an effective combination of erosion and sediment control and good housekeeping BMPs.

a. Scheduling construction activity during dry weather, when possible.

Protection of storm drain inlets (gravel bags or catch basin inserts).

c. Drainage swales or lined ditches to control stormwater flow.

g. Perimeter sediment control (perimeter silt fence, fiber rolls).

k. Other soil loss BMPs acceptable to the enforcing agency.

Sediment trap or sediment basin to retain sediment on site.

h. Other housekeeping BMPs acceptable to the enforcing agency.

d. Mulching or hydroseeding to stabilize disturbed soils.

shall comply with the specific green building measures applicable to each specific occupancy.

replacement of noncompliant plumbing fixtures, and duties and responsibilities for

alterations whenever a permit is required for work.

301.4 PUBLIC SCHOOLS AND COMMUNITY COLLEGES. (see GBSC)

SECTION 302 MIXED OCCUPANCY BUILDINGS

301.5 HEALTH FACILITIES. (see GBSC)

SECTION 303 PHASED PROJECTS

ABBREVIATION DEFINITIONS:

Additions and Alterations

Low Rise

CHAPTER 5

5.102.1 DEFINITIONS

High Rise

SECTION 5.101 GENERAL

SECTION 5.102 DEFINITIONS

Eligible vehicles are limited to the following:

LOW-EMITTING AND FUEL EFFICIENT VEHICLES.

0 as regulated under 40 CFR Section 600 Subpart D.

OSHPD

construction (or newly constructed) shall apply.

Section 301.3 non-residential additions and alterations.

California Building Standards Commission

Division of the State Architect, Structural Safety

Department of Housing and Community Development

Office of Statewide Health Planning and Development

NONRESIDENTIAL MANDATORY MEASURES

environmental quality of the site and respect the integrity of adjacent properties.

The following terms are defined in Chapter 2 (and are included here for reference)

80 degrees above nadir. This applies to all lateral angles around the luminaire.

emission vehicles (TZEV) regulated under CCR, Title 13, Section 1962.

Note: Source: Vehicle Code, Division 1, Section 668

ZEV. Any vehicle certified to zero-emission standards.

SECTION 5.106 SITE DEVELOPMENT

activities through one or more of the following measures:

but are not limited to, the following:

Erosion control to protect slopes.

Stabilized construction exits.

Wind erosion control.

DIVISION 5.1 PLANNING AND DESIGN

constructed buildings [N] or to additions and/or alterations [A]. When the code section applies to both, no

301.3.1 Nonresidential additions and alterations that cause updates to plumbing fixtures only:

1101.3, shall have its noncompliant plumbing fixtures replaced with appropriate water-conserving

301.3.2 Waste Diversion. The requirements of Section 5.408 shall be required for additions and

plumbing fixtures under specific circumstances. See Civil Code Section 1101.1 et seg. for definitions,

Note: On and after January 1, 2014, certain commercial real property, as defined in Civil Code Section

of individual sections of Chapter 5 apply to newly constructed buildings, building additions of 1,000 square

feet or greater, and/or building alterations with a permit valuation of \$200,000 or above (for occupancies within

the application checklists contained in this code. Voluntary green building measures are also included in the

application checklists and may be included in the design and construction of structures covered by this code,

CHAPTER 3

GREEN BUILDING

SECTION 301 GENERAL

5.106.2 STORMWATER POLLUTION PREVENTION FOR PROJECTS THAT DISTURB ONE OR MORE ACRES OF

LAND. Comply with all lawfully enacted stormwater discharge regulations for projects that (1) disturb one acre or

more of land, or (2) disturb less than one acre of land but are part of a larger common plan of development sale.

Note: Projects that (1) disturb one acre or more of land, or (2) disturb less than one acre of land but are part of the

larger common plan of development or sale must comply with the post-construction requirements detailed in the

the Lahontan Regional Water Quality Control Board (for projects in the Lake Tahoe Hydrologic Unit).

Refer to the current applicable permits on the State Water Resources Control Board website at:

should be given during the initial design process for appropriate integration into site development.

practices and be approved by the enforcing agency.

Architect pursuant to Section 105, comply with Section 5.106.4.2

added with a minimum of one two-bike capacity rack.

spaces with a minimum of one bicycle parking facility.

be convenient from the street and shall meet one of the following:

Lockable, permanently anchored bicycle lockers.

Sacramento Area Bicycle Advocates

5.106.4.2.1 and 5.106.4.2.2

minimum of one bicycle parking facility.

applicable local ordinance, whichever is stricter.

applicable National Pollutant Discharge Elimination System (NPDES) General permit for Stormwater Discharges

The NPDES permits require postconstruction runoff (post-project hydrology) to match the preconstruction runoff

(pre-project hydrology) with the installation of postconstruction stormwater management measures. The NPDES

permits emphasize runoff reduction through on-site stormwater use, interception, evapotranspiration, and infiltration

Stormwater volume that cannot be addressed using nonstructural practices is required to be captured in structural

www.waterboards.ca.gov/constructionstormwater. Consideration to the stormwater runoff management measures

5.106.4 BICYCLE PARKING. For buildings within the authority of California Building Standards Commission as

specified in Section 103, comply with Section 5.106.4.1. For buildings within the authority of the Division of the State

5.106.4.1 Bicycle parking. [BSC-CG] Comply with Sections 5.106.4.1.1 and 5.106.4.1.2; or meet the

5.106.4.1.1 Short-term bicycle parking. If the new project or an addition or alteration is anticipated

Exception: Additions or alterations which add nine or less visitor vehicular parking spaces.

5.106.4.1.2 Long-term bicycle parking. For new buildings with tenant spaces that have 10 or more

tenant-occupants, provide secure bicycle parking for 5 percent of the tenant-occupant vehicular parking

5.106.4.1.3 For additions or alterations that add 10 or more tenant-occupant vehicular parking spaces,

provide secure bicycle parking for 5 percent of the tenant vehicular parking spaces being added, with a

5.106.4.1.4 For new shell buildings in phased projects provide secure bicycle parking for 5 percent of the

5.106.4.1.5 Acceptable bicycle parking facility for Sections 5.106.4.1.2, 5.106.4.1.3, and 5.106.4.1.4 shall

Note: Additional information on recommended bicycle accommodations may be obtained from

anticipated tenant-occupant vehicular parking spaces with a minimum of one bicycle parking facility.

Covered, lockable enclosures with permanently anchored racks for bicycles;

5.106.4.2 Bicycle parking. [DSA-SS] For public schools and community colleges, comply with Sections

shall be convenient from the street or staff parking area and shall meet one of the following:

Covered, lockable enclosures with permanently anchored racks for bicycles;

5.106.5.3 Electric vehicle (EV) charging. [N] Construction to provide electric vehicle infrastructure and facilitate

this section is not feasible based upon one of the following conditions:

b. Where the local utility is unable to supply adequate power.

5.106.4.2.1 Student bicycle parking. Provide permanently anchored bicycle racks conveniently

5.106.4.2.2 Staff bicycle parking. Provide permanent, secure bicycle parking conveniently accessed

with a minimum of two staff bicycle parking spaces per new building. Acceptable bicycle parking facilities

1. On a case-by-case basis where the local enforcing agency has determined compliance with

c. Where there is evidence suitable to the local enforcement agency substantiating the

Section 5.106.5.3, may adversely impact the construction cost of the project.

2. Parking spaces accessible only by automated mechanical car parking systems are not

1. Raceways complying with the California Electrical Code and no less that 1-inch (25 mm)

2. A service panel or subpanel (s) shall be provided with panel space and electrical load

4. The service panel or subpanel circuit directory shall identify the reserved overcurrent

complying with any applicable minimum parking space requirements established by an enforcement

Note: A parking space served by electric vehicle supply equipment or designed as a future EV charging space shall count as at least one standard automobile parking space only for the purpose of

capacity for a dedicated 208/240 volt, 40-ampere minimum branch circuit for each EV

capable space, with delivery of 30-ampere minimum to an installed EVSE at each EVCS.

protective devices space(s) as "EV CAPABLE". The raceway termination location shall be

3. The electrical system and any on-site distribution transformers shall have sufficient capacity

diameter shall be provided and shall originate at a service panel or a subpanel(s) serving

the area, and shall terminate in close proximity to the proposed location of the EV capable

and into a suitable listed cabinet, box,enclosure or equivalent. A common raceway may be

[N] EV capable spaces shall be provided in accordance with Table 5.106.5.3.1 and the following

local utility infrastructure design requirements, directly related to the implementation of

2. Lockable bicycle rooms with permanently anchored racks; or

accessed with a minimum of four two-bike capacity racks per new building.

2. Lockable bicycle rooms with permanently anchored racks; or

a. Where there is no local utility power supply

required to comply with this code section

used to serve multiple EV charging spaces.

agency. See vehicle Code Section 22511.2 for further details.

to supply full rated amperage at each EV capable space.

permanently and visibly marked as "EV CAPABLE."

electric vehicle charging shall comply with Section 5.106.5.3.1 and shall be provided in accordance with

Lockable, permanently anchored bicycle lockers.

regulations in the California Building Code and the California Electrical Code

5.106.5.3.1 EV capable spaces.

to generate visitor traffic, provide permanently anchored bicycle racks within 200 feet of the visitors'

entrance, readily visible to passers-by, for 5% of new visitor motorized vehicle parking spaces being

through nonstructural controls, such as Low Impact Development (LID) practices, and conversation design measures.

Associated with Construction and Land Disturbance Activities issued by the State Water Resources Control Board or

ROJECT SPECIFIC STATE AGENCY APPROVAL

THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE **EXPRESS WRITTEN CONSENT OF R&S** TAVARES ASSOCIATES, INC. ©



ORIGINAL PC STATE AGENCY APPROVAL APPROVED DIV. OF THE STATE ARCHITECT APP: 04-123059 PC

SS / FCS / ACS / CG /

Revision Schedule

PRE-CHECK (PC) DOCUMENT

Code: 2022 CBC

A separate project application for construction is required

PC 2022 CBC: 24' x 40'

EXPANDABLE TO

CAL GREEN

CHECKLIST

Description

materials that comply with Table A5.106.11.2.2 in Appendix A5 shall be permitted in whole or in part in lieu of shade tree planting.

NOT APPLICABLE

G2

G1

G0

G1

G0

G0

G0

I. IESNA Lighting Zones 0 and 5 are not applicable; refer to Lighting Zones as defined in the California Energy

considered to be 5 feet beyond the actual property line for purpose of determining compliance with this section. For

property lines that abut public roadways and public transit corridors, the property line may be considered to be the

3. General lighting luminaires in areas such as outdoor parking, sales or storage lots shall meet these reduced

Luminaries within 2MH of a property line shall be oriented so that the nearest property line is behind the fixture,

and shall comply with the backlight rating specified in Table 5.106.8 based on the lighting zone and distance to

Exception: Corners. If two property lines (or two segments of the same property line) have equidistant point

directly behind the luminaire. The luminaire shall still use the distance to the nearest points(s) on the property

to the luminaire, then the luminaire may be oriented so that the intersection of the two lines (the corner) is

For luminaires covered by 5.106.8.1, if a property line also exists within or extends into the front hemisphere within

5.106.8 based on the lighting zone and distance to the nearest point on the nearest property line within the front

1.See also California Building Code, Chapter 12, Section 1205.6 for college campus lighting requirements for

2.Refer to Chapter 8 (Compliance Forms, Worksheets and Reference Material) for IES TM-15-11 Table

.106.10 GRADING AND PAVING. Construction plans shall indicate how site grading or a drainage system will

5. Other water measures which keep surface water away from buildings and aid in groundwater recharge.

.106.12 SHADE TREES [DSA-SS]. Shade Trees shall be planted to comply with Sections 5.106.12.1, 5.106.12.2,

and 5.106.12.3. Percentages shown shall be measured at noon on the summer solstice. Landscape irrigation

5.106.12.1 Surface parking areas. Shade tree plantings, minimum #10 container size or equal, shall be installed

Exceptions: Surface parking area covered by solar photovoltaic shade structures with roofing

manage all surface water flows to keep water from entering buildings. Examples of methods to manage surface

3. Refer to the California Building Code for requirements for additions and alterations.

Exception: Additions and alterations not altering the drainage path.

necessary to establish and maintain tree health shall comply with Section 5.304.6.

to provide shade over 50 percent of the parking area within 15 years.

2MH of the luminaire then the luminaire shall comply with the more stringent glare rating specified in Table

2. For property lines that abut public walkways, bikeways, plazas and parking lots, the property line may be

centerline of the public roadway or public transit corridor for the purpose of determining compliance with this

ratings. Decorative luminaries located in these areas shall meet *U*-value limits for "all other outdoor lighting"

N/A

N/A

Code and Chapter 10 of the Callifornia Administrative Code.

lines to determine the required backlight rating.

A-1, California Energy Code Tables 130.2-A and 130.2-B.

water include, but are not limited to, the following:

Water collection and disposal systems.

French drains.

Water retention gardens

the nearest point of that property line.

parking facilities and walkways.

RESPONSIBLE PARTY (ie: ARCHITECT, ENGINEER,

G1

G1

G2

G1

5.106.12.2 Landscape areas. Shade tress plantings, minimum #10 container size or equal shall be installed to provide shade of 20% of the landscape area within 15 years.

Exceptions: Playfields for organized sport activity are not included in the total area calculation. **5.106.12.3.** Hardscape areas. Shade tree plantings, minimum #10 container size or equal shall be installed to

provide shade over 20 percent of the hardscape area within 15 years. 1. Walks, hardscape areas covered by solar photovoltaic shade structures or shade structures with roofing

2. Designated and marked play areas of organized sport activity are not included in the total area calculation. **DIVISION 5.2 ENERGY EFFICIENCY**

materials that comply with Table A5.106.11.2.2 in Appendix A5 shall be permitted in whole or in part in lieu

SECTION 5.201 GENERAL

5.201.1 Scope [BSC-CG]. California Energy Code [DSA-SS]. For the purposes of mandatory energy efficiency standards in this code, the California Energy Commission will continue to adopt mandatory building standards.

DIVISION 5.3 WATER EFFICIENCY AND CONSERVATION

SECTION 5.301 GENERAL 5.301.1 Scope. The provisions of this chapter shall establish the means of conserving water use indoors, outdoors and in wastewater conveyance.

MAXIMUM ALLOWABLE

MAXIMUM ALLOWABLE

GLARE RATING 5 (G)

MAXIMUM ALLOWABLE

MAXIMUM ALLOWABLE

MAXIMUM ALLOWABLE

SECTION 5.302 DEFINITIONS

5.302.1 Definitions. The following terms are defined in Chapter 2 (and are included here for reference)

EVAPOTRANSPIRATION ADJUSTMENT FACTOR (ETAF) [DSA-SS]. An adjustment factor when applied to reference evapotranspiration that adjusts for plant factors and irrigation efficiency, which ae two major influences on

the amount of water that needs to be applied to the landscape. FOOTPRINT AREA [DSA-SS]. The total area of the furthest exterior wall of the structure projected to natural grade,

not including exterior areas such as stairs, covered walkways, patios and decks.

METERING FAUCET. A self-closing faucet that dispenses a specific volume of water for each actuation cycle. The volume or cycle duration can be fixed or adjustable.

GRAYWATER. Pursuant to Health and Safety Code Section 17922.12, "graywater" means untreated wastewater that has not been contaminated by any toilet discharge, has not been affected by infectious, contaminated, or unhealthy bodily wastes, and does not present a threat from contamination by unhealthful processing, manufacturing, or operating wastes. "Graywater" includes, but is not limited to wastewater from bathtubs, showers, bathroom washbasins, clothes washing machines and laundry tubs, but does not include waste water from kitchen sinks or

MODEL WATER EFFICIENT LANDSCAPE ORDINANCE (MWELO). The California ordinance regulating landscape design, installation and maintenance practices that will ensure commercial, multifamily and other developer installed landscapes greater than 2500 square feet meet an irrigation water budget developed based on landscaped area and

MODEL WATER EFFICIENT LANDSCAPE ORDINANCE (MWELO). [HCD] The California model ordinance (California Code of Regulations, Title 23, Division 2, Chapter 2.7), regulating landscape design, installation and maintenance practices. Local agencies are required to adopt the updated MWELO, or adopt a local ordinance at least as effective as the MWELO.

POTABLE WATER. Water that is drinkable and meets the U.S. Environmental Protection Agency (EPA) Drinking Water Standards. See definition in the California Plumbing Code, Part 5.

POTABLE WATER. [HCD] Water that is satisfactory for drinking, culinary, and domestic purposes, and meets the U.S. Environmental Protection Agency (EPA) Drinking Water Standards and the requirements of the Health Authority

WATER BUDGET. Is the estimated total landscape irrigation water use which shall not exceed the maximum applied water allowance calculated in accordance with the Department of Water Resources Model Efficient Landscape

5.106.5.3.3 Use of automatic load management systems (ALMS).

ALMS shall be permitted for EVCS. When ALMS is installed, the required electrical load capacity 5.106.5.3.1 for each EVCS may be reduced when serviced by an EVSE controlled by an ALMS. Each EVSE controlled by an ALMS shall deliver a minimum 30 amperes to an EV when charging one vehicle and shall deliver a minimum 3.3 kW while simultaneously charging multiple EVs.

5.106.5.3.4 Accessible EVCS. When EVSE is installed, accessible EVSC shall be provided in accordance with the California Building

Code, Chapter 11B, Section 11B-228.3. Note: For EVCS signs, refer to Caltrans Traffic Operations Policy Directive 13-01 (Zero Emission Vehicle Signs and Pavement Markings) or its successor(s).

5.106.5.4 Electric Vehicle (EV) charging: medium-duty and heavy-duty. [N] Construction shall comply with section 5.106.5.4.1 to facilitate future installation of electric vehicle supply equipment (EVSE). Construction for warehouses, grocery stores and retail stores with planned off-street loading spaces shall also comply with Section 5.106.5.4.1 for future installation of medium- and heavy-duty EVSE.

1. On a case-by-case basis where the local enforcing agency has determined compliance with this section is not feasible based upon one of the following conditions:

a. Where there is no local utility power supply. b. Where the local utility is unable to supply adequate power.

c. Where there is evidence suitable to the local enforcing agency substantiating that additional local utility infrastructure design requirements, directly related to the implementation of Section 5.106.5.3, may adversely impact the construction cost of the project. When EVSE(s) is/are installed, it shall be in accordance with the California Building Code, the California Electrical Code and as follows:

5.106.5.4.1 Electric vehicle charging readiness requirements for warehouse, grocery stores and retail stores with planned off-street loading spaces.

[N] In order to avoid future demolition when adding EV charging supply and distribution equipment, spare raceways(s) or busway(s) and adequate capacity for transformers(s), service panels(s) or subpanel(s) shall be installed at the time of construction in accordance with the California Electrical Code. Construction plans and specifications shall include but are not limited to, the following:

1. The transformer, main service equipment and subpanel shall meet the minimum power requirement in Table 5.106.5.4.1 to accommodate the dedicated branch circuits for the future

2. The construction documents shall indicate on or more location(s) convenient to the planned offstreet loading space(s) reserved for medium-and heavy-duty ŽEV charging cabinets and charging dispensers, and a pathway reserved for routing of conduit from the termination of the raceway(s) or busway(s) to the charging cabinet(s) and dispenser(s) as shown in Table

3. Raceway(s) or busway(s) originating at a main service panel or a subpanel(s) serving the area where potential future medium-and heavy-duty EVSE will be located and shall terminate in close proximity to the potential future location of the charging equipments for medium- and heavy-duty

4. The raceway(s) or busway(s) shall be sufficient size to carry the minimum additional system load to the future location of the charging for medium- and heavy-duty ZEVs as shown in Table

TABLE 5.106.5.4.1 RACEWAY CONDUIT AND PANEL POWER REQUIREMENTS FOR MEDIUM- AND HEAVY-DUTY EVSE IN

| | | • | • | |
|---------------|-------------------------|---|---|--|
| BUILDING TYPE | BUILDING SIZE (SQ. FT.) | NUMBER OF OFF-STREET LOADING SPACES | ADDITIONAL CAPACITY REQUIRED (KVA) FOR RACEWAY & BUSWAY AND TRANSFORMER & PANEL | |
| | 10,000 to 90,000 | 1 or 2 | 200 | |
| Grocery | 10,000 to 30,000 | 3 or Greater | 400 | |
| | Greater than 90,000 | 1 or Greater | 400 | |
| | 10,000 to 135,000 | 1 or 2 | 200 | |
| Retail | 10,000 to 133,000 | 3 or Greater | 400 | |
| | Greater than 135,000 | 1 or Greater | 400 | |
| | | 1 or 2 | 200 | |
| Warehouse | 20,000 to 256,000 | 3 or Greater | 400 | |
| | Greater than 256,000 | 1 or Greater | 400 | |

5.106.8 LIGHT POLLUTION REDUCTION. [N]. I Outdoor lighting systems shall be designed and installed to comply

1. The minimum requirements in the California Energy Code for Lighting Zones 0-4 as defined in Chapter 10,

Section 10-114 of the California Administrative Code; and 2. Backlight (B) ratings as defined in IES TM-15-11 (shown in Table A-1 in Chapter 8); 3. Uplight and Glare ratings as defined in California Energy Code (shown in Tables 130.2-A and 130.2-B in

4. Allowable BUG ratings not exceeding those shown in Table 5.106.8, [N] or Comply with a local ordinance lawfully enacted pursuant to Section 101.7, whichever is more stringent.

1. Luminaires that qualify as exceptions in Sections 130.2 (b) and 140.7 of the California Energy Code.

U0

U0

3. Building facade meeting the requirements in Table 140.7-B of the California Energy Code, Part 6.

4. Custom lighting features as allowed by the local enforcing agency, as permitted by Section 101.8

5. Luminaires with less than 6,200 initial luminaire lumens.

TABLE 5.106.8 [N] $\,$ MAXIMUM ALLOWABLE BACKLIGHT,

Alternate materials, designs and methods of construction.

U0

U0

| ALLOWABLE RATING | LIGHTING ZONE LZ0 | LIGHTING ZONE LZ1 | LIGHTING ZONE LZ2 | LIGHTING ZONE LZ3 | LIGHTI ZONE I |
|---|-------------------------|----------------------|----------------------|----------------------|------------------|
| MAXIMUM ALLOWABLE BACKLIGHT RATING 3 | | | | | |
| Luminaire greater than 2 mounting heights (MH) from property line | N/A | No Limit | No Limit | No Limit | No Lin |
| Luminaire back hemisphere is 1-2 MH from property line | N/A | B2 | В3 | B4 | B4 |
| Luminaire back hemisphere is 0.5-1 MH from property line | N/A | B1 | B2 | В3 | В3 |
| Luminaire back hemisphere is less than 0.5 MH from property line | N/A | В0 | В0 | B1 | B2 |
| MAXIMUM ALLOWABLE UPLIGHT RATING (U) | | | | | |

| TOTAL NUMBER OF ACTUAL PARKING SPACES | NUMBER OF REQUIRED EV CAPABLE SPACES | NUMBER OF EVCS (EV CAPABLE SPACES PROVIDED WITH EVSE)^2 | |
|---------------------------------------|---|---|--|
| 0-9 | 0 | 0 | |
| 10-25 | 2 | 0 | |
| 26-50 | 8 | 2 | |
| 51-75 | 13 | 3 | |
| 76-100 | 17 | 4 | |
| 101-150 | 25 | 6 | |
| 151-200 | 35 | 9 | |
| 201 AND OVER | 20% of total ¹ | 25% of EV capable spaces ¹ | |

2. The number of required EVCS (EV capable spaces provided with EVSE) in column 3 count towards the total number of required EV capable spaces shown in column 2.

5.106.5.3.2 Electric vehicle charging stations (EVCS)

permitted if the electrical load capacity required by Section 5.106.5.3.1 for each EV capable space is accumulatively supplied to the EV charger.

The installation of each DCFC EVSE shall be permitted to reduce the minimum number of required EV capable spaces without EVSE by five and reduce proportionally the required electrical load capacity to the

DISCLAIMER: THIS DOCUMENT IS PROVIDED AND INTENDED TO BE USED AS A MEANS TO INDICATE AREAS OF COMPLIANCE WITH THE CALIFORNIA GREEN BUILDING STANDARDS (CALGREEN) CODE. DUE TO THE VARIABLES BETWEEN BUILDING DEPARTMENT JURISDICTIONS, THIS CHECKLIST IS TO BE USED ON AN INDIVIDUAL PROJECT BASIS AND MAY BE MODIFIED BY THE END USER TO MEET THOSE INDIVIDUAL NEEDS. THE END USER ASSUMES ALL RESPONSIBILITY ASSOCIATED WITH THE USE OF THIS DOCUMENT, INCLUDING VERIFICATION WITH THE FULL CODE.

For all other outdoor are not limited to, the following: EV capable spaces shall be provided with EVSE to create EVCS in the number indicated in Table N/A U1 U2 **RECYCLED WATER.** Water which, as a result of treatment of waste, is suitable for a direct beneficial use or a U3 lighting,including decorative Dewatering activities. 5.106.5.3.1. The EVCS required by Table 5.106.5.3.1 may be provided with EVSE in any combination of controlled use that would not otherwise occur [Water Code Section 13050 (n)]. Simply put, recycled water is water b. Material handling and waste management. Level 2 and Direct Current Fast Charging (DCFC), except that at least one Level 2 EVSE shall be treated to remove waste matter attaining a quality that is suitable to use the water again. c. Building materials stockpile management. d. Management of washout areas (concrete, paints, stucco, etc.). SUBMETER. [HCD 1] A secondary device beyond a meter that measures water consumption of an individual rental e. Control of vehicle/equipment fueling to contractor's staging area. unit within a multiunit residential structure or mixed-use residential and commercial structure. (See Civic Code Section One EV charger with multiple connectors capable of charging multiple EVs simultaneously shall be f. Vehicle and equipment cleaning performed off site. 1954.202 (g) and Water code Section 517 for additional details.) Spill prevention and control.

For area lighting 3

PROJECT NUMBER 22088

rMc/SC CHECKED BY

RH/RT DATE

SECTION 5.303 INDOOR WATER USE

following subsystems:

5.303.1 METERS. Separate submeters or metering devices shall be installed for the uses described in Sections

5.303.1.1 Buildings in excess of 50,000 square feet. Separate submeters shall be installed as follows:

1. For each individual leased, rented or other tenant space within the building projected to consume

restaurant or food service, medical or dental office, laboratory, or beauty salon or barber shop.

2. Where separate submeters for individual building tenants are unfeasible, for water supplied to the

more than 100 gal/day (380 L/day), including, but not limited to, spaces used for laundry or cleaners.

DIVISION 5.4 MATERIAL CONSERVATION AND RESOURCE

efficiency through protection of buildings from exterior moisture, construction waste diversion, employment of

5.401.1 SCOPE. The provisions of this chapter shall outline means of achieving material conservation and resource

techniques to reduce pollution through recycling of materials, and building commissioning or testing and adjusting.

EFFICIENCY

SECTION 5.401 GENERAL

SECTION 5.402 DEFINITIONS **5.402.1 DEFINITIONS.** The following terms are defined in Chapter 2 (and are included here for reference) ADJUST. To regulate fluid flow rate and air patterns at the terminal equipment, such as to reduce fan speed or adjust a damper BALANCE. To proportion flows within the distribution system, including sub-mains, branches and terminals, according to design quantities. BUILDING COMMISSIONING. A systematic quality assurance process that spans the entire design and construction process, including verifying and documenting that building systems and components are planned, designed, installed, tested, operated and maintained to meet the owner's project requirements. ORGANIC WASTE. Food waste, green waste, landscape and pruning wste, nonhazardous wood waste, and food soiled paper waste that is mixed in with food waste. TEST. A procedure to determine quantitative performance of a system or equipment SECTION 5.407 WATER RESISTANCE AND MOISTURE MANAGEMENT **5.407.1 WEATHER PROTECTION.** Provide a weather-resistant exterior wall and foundation envelope as required by California Building Code Section 1402.2 (Weather Protection), manufacturer's installation instructions or local ordinance, whichever is more stringent. **5.407.2 MOISTURE CONTROL.** Employ moisture control measures by the following methods. **5.407.2.1 Sprinklers.** Design and maintain landscape irrigation systems to prevent spray on structures. 5.407.2.2 Entries and openings. Design exterior entries and/or openings subject to foot traffic or wind-driven rain to prevent water intrusion into buildings as follows: **5.407.2.2.1 Exterior door protection.** Primary exterior entries shall be covered to prevent water intrusion by using nonabsorbent floor and wall finishes within at least 2 feet around and perpendicular to such openings plus at least one of the following: 1. An installed awning at least 4 feet in depth. 2. The door is protected by a roof overhang at least 4 feet in depth. The door is recessed at least 4 feet. 4. Other methods which provide equivalent protection. **5.407.2.2.2 Flashing.** Install flashings integrated with a drainage plane. SECTION 5.408 CONSTRUCTION WASTE REDUCTION, DISPOSAL AND RECYCLING

NONRESIDENTIAL MANDATORY MEASURES, SHEET 2 (January 2023)

5.408.1 CONSTRUCTION WASTE MANAGEMENT. Recycle and/or salvage for reuse a minimum of 65% of the non-hazardous construction and demolition waste in accordance with Section 5.408.1.1, 5.408.1.2 or 5.408.1.3; or meet a local construction and demolition waste management ordinance, whichever is more stringent.

5.408.1.1 Construction waste management plan. Where a local jurisdiction does not have a construction and demolition waste management ordinance, submit a construction waste management plan that:

1. Identifies the construction and demolition waste materials to be diverted from disposal by efficient usage, recycling, reuse on the project or salvage for future use or sale.

Determines if construction and demolition waste materials will be sorted on-site (source-separated) or bulk mixed (single stream).

Identifies diversion facilities where construction and demolition waste material collected will be taken. . Specifies that the amount of construction and demolition waste materials diverted shall be calculated by weight or volume, but not by both.

5.408.1.2 Waste Management Company. Utilize a waste management company that can provide verifiable documentation that the percentage of construction and demolition waste material diverted from the landfill complies with this section.

Note: The owner or contractor shall make the determination if the construction and demolition waste material will be diverted by a waste management compar

Exceptions to Sections 5.408.1.1 and 5.408.1.2:

Excavated soil and land-clearing debris

2. Alternate waste reduction methods developed by working with local agencies if diversion or recycle facilities capable of compliance with this item do not exist. 3. Demolition waste meeting local ordinance or calculated in consideration of local recycling facilities

5.408.1.3 Waste stream reduction alternative. The combined weight of new construction disposal that does not exceed two pounds per square foot of building area may be deemed to meet the 65% minimum requirement as approved by the enforcing agency.

5.408.1.4 Documentation. Documentation shall be provided to the enforcing agency which demonstrates compliance with Sections 5.408.1.1, through 5.408.1.3. The waste management plan shall be updated as necessary and shall be accessible during construction for examination by the enforcing agency.

Sample forms found in "A Guide to the California Green Building Standards Code (Nonresidential)" located www.dgs.ca.gov/BSC/Resources/Page-Content/Building-Standards-Commission-Resources-List-Folder/CALGreen may be used to assist in documenting compliance with the waste management plan.

2. Mixed construction and demolition debris processors can be located at the California Department of Resources Recycling and Recovery (CalRecycle).

5.408.2 UNIVERSAL WASTE. [A] Additions and alterations to a building or tenant space that meet the scoping provisions in Section 301.3 for nonresidential additions and alterations, shall require verification that Universal Waste tems such as fluorescent lamps and ballast and mercury containing thermostats as well as other California prohibited Universal Waste materials are disposed of properly and are diverted from landfills. A list of prohibited Universal Waste materials shall be included in the construction documents.

Note: Refer to the Universal Waste Rule link at: http://www.dtsc.ca.gov/universalwaste/

5.408.3 EXCAVATED SOIL AND LAND CLEARING DEBRIS. 100 percent of trees, stumps, rocks and associated vegetation and soils resulting primarily from land clearing shall be reused or recycled. For a phased project, such material may be stockpiled on site until the storage site is developed.

Exception: Reuse, either on or off-site, of vegetation or soil contaminated by disease or pest infestation.

. If contamination by disease or pest infestation is suspected, contact the County Agricultural Commissioner and follow its direction for recycling or disposal of the material. 2. For a map of know pest and/or disease quarantine zones, consult with the California Department of Food and Agriculture. (www.cdfa.ca.gov)

SECTION 5.410 BUILDING MAINTENANCE AND OPERATIONS **5.410.1 RECYCLING BY OCCUPANTS.** Provide readily accessible areas that serve the entire building and are

paper, corrugated cardboard, glass, plastics, organic waste, and metals or meet a lawfully enacted local recycling ordinance, if more restrictive. **Exception**: Rural jurisdictions that meet and apply for the exemption in Public Resources

Code 42649.82 (a)(2)(A) et seq. shall also be exempt from the organic waste portion of this section.

5.410.1.1 Additions. All additions conducted within a 12-month period under single or multiple permits, resulting in an increase of 30% or more in floor area, shall provide recycling areas on site.

identified for the depositing, storage and collection of non-hazardous materials for recycling, including (at a minimum)

Exception: Additions within a tenant space resulting in less than a 30% increase in the tenant space

5.410.1.2 Sample ordinance. Space allocation for recycling areas shall comply with Chapter 18, Part 3, Division 30 of the Public Resources Code. Chapter 18 is known as the California Solid Waste Reuse and Recycling Access Act of 1991 (Act).

Note: A sample ordinance for use by local agencies may be found in Appendix A of the document at the

5.410.2 COMMISSIONING. [N] New buildings 10,000 square feet and over. For new buildings 10,000 square feet and over, building commissioning shall be included in the design and construction processes of the building project to verify that the building systems and components meet the owner's or owner representative's project requirements. Commissioning shall be performed in accordance with this section by trained personnel with experience on projects of omparable size and complexity. For I-occupancies that are not regulated by OSHPD or for I-occupancies and L-occupancies that are not regulated y the California Energy Code Section 100.0 Scope, all requirements in Sections 5.410.2 through 5.410.2.6 shall apply.

Note: For energy-related systems under the scope (Section 100) of the California Energy Code, including heating, ventilation, air conditioning (HVAC) systems and controls, indoor lighting systems and controls, as well as water heating systems and controls, refer to California Energy Code Section 120.8 for commissioning requirements

Commissioning requirements shall include:

1. Owner's or Owner representative's project requirements.

. Basis of design. 3. Commissioning measures shown in the construction documents.

4. Commissioning plan. 5. Functional performance testing

6. Documentation and training. 7. Commissioning report.

1. Unconditioned warehouses of any size. 2. Areas less than 10,000 square feet used for offices or other conditioned accessory spaces within

unconditioned warehouses. 3. Tenant improvements less than 10,000 square feet as described in Section 303.1.1.

4. Open parking garages of any size, or open parking garage areas, of any size, within a structure.

Note: For the purposes of this section, unconditioned shall mean a building, area, or room which does not provide heating and or air conditioning.

Informational Notes

1. IAS AC 476 is an accreditation criteria for organizations providing training and/or certification of commissioning personnel. AC 476 is available to the Authority Having Jurisdiction as a reference for qualifications of commissioning personnel. AC 476 des not certify individuals to conduct functional performance tests or to adjust and balance systems.

2. Functional performance testing for heating, ventilation, air conditioning systems and lighting controls must be performed in compliance with the California Energy Code.

5.410.2.1 Owner's or Owner Representative's Project Requirements (OPR). [N] The expectations and requirements of the building appropriate to its phase shall be documented before the design phase of the project begins. This documentation shall include the following:

Environmental and sustainability goals. 2. Building sustainable goals.

3. Indoor environmental quality requirements.

4. Project program, including facility functions and hours of operation, and need for after hours

5. Equipment and systems expectations.

6. Building occupant and operation and maintenance (O&M) personnel expectations.

5.410.2.2 Basis of Design (BOD). [N] A written explanation of how the design of the building systems meets the OPR shall be completed at the design phase of the building project. The Basis of Design document shall cover the following systems:

1. Renewable energy systems.

2. Landscape irrigation systems. Water reuse system.

5.410.2.3 Commissioning plan. [N] Prior to permit issuance a commissioning plan shall be completed to document how the project will be commissioned. The commissioning plan shall include the following: 1. General project information

2. Commissioning goals. 3. Systems to be commissioned. Plans to test systems and components shall include:

 a. An explanation of the original design intent. Equipment and systems to be tested, including the extent of tests

c. Functions to be tested d. Conditions under which the test shall be performed.

e. Measurable criteria for acceptable performance.

5. Commissioning process activities, schedules and responsibilities. Plans for the completion of commissioning shall be included.

5.410.2.4 Functional performance testing. [N] Functional performance tests shall demonstrate the correct installation and operation of each component, system and system-to-system interface in accordance with the approved plans and specifications. Functional performance testing reports shall contain information addressing each of the building components tested, the testing methods utilized, and include any readings and adjustments

5.410.2.5 Documentation and training. [N] A Systems Manual and Systems Operations Training are required, including Occupational Safety and Health Act (OSHA) requirements in California Code of Regulations (CCR), Title 8, Section 5142, and other related regulations.

5.410.2.5.1 Systems manual. [N] Documentation of the operational aspects of the building shall be

completed within the systems manual and delivered to the building owner or representative. The systems manual shall include the following:

1. Site information, including facility description, history and current requirements. Site contact information.

3. Basic operations and maintenance, including general site operating procedures, basic

troubleshooting, recommended maintenance requirements, site events log. Maior systems.

5. Site equipment inventory and maintenance notes.

6. A copy of verifications required by the enforcing agency or this code.

7. Other resources and documentation, if applicable.

5.410.2.5.2 Systems operations training. [N] A program for training of the appropriate maintenance staff for each equipment type and/or system shall be developed and documented in the commissioning

report and shall include the following: 1. System/equipment overview (what it is, what it does and with what other systems and/or

equipment it interfaces).

2. Review and demonstration of servicing/preventive maintenance.

3. Review of the information in the Systems Manual.

4. Review of the record drawings on the system/equipment.

5.410.2.6 Commissioning report. [N] A report of commissioning process activities undertaken through the design and construction phases of the building project shall be completed and provided to the owner or

5.410.4 TESTING AND ADJUSTING. New buildings less than 10,000 square feet. Testing and adjusting of systems shall be required for new buildings less than 10,000 square feet or new systems to serve an addition or alteration subject to Section 303.1.

5.410.4.2 (Reserved)

Note: For energy-related systems under the scope (Section 100) of the California Energy Code, including heating, ventilation, air conditioning (HVAC) systems and controls, indoor lighting system and controls, as well as water heating systems and controls, refer to California Energy Code Section 120.8 for commissioning requirements and Sections 120.5, 120.6, 130.4, and 140.9(b)3 for additional testing requirements of specific

5.410.4.2 Systems. Develop a written plan of procedures for testing and adjusting systems. Systems to be included for testing and adjusting shall include at a minimum, as applicable to the project:

1. Renewable energy systems.

2. Landscape irrigation systems. Water reuse systems.

5.410.4.3 Procedures. Perform testing and adjusting procedures in accordance with manufacturer's specifications and applicable standards on each system.

5.410.4.3.1 HVAC balancing. In addition to testing and adjusting, before a new space-conditioning system serving a building or space is operated for normal use, the system shall be balanced in accordance with the procedures defined by the Testing Adjusting and Balancing Bureau National Standards; the National Environmental Balancing Bureau Procedural Standards; Associated Air Balance Council National Standards or as approved by the enforcing agency.

5.410.4.4 Reporting. After completion of testing, adjusting and balancing, provide a final report of testing signed by the individual responsible for performing these services.

5.410.4.5 Operation and maintenance (O & M) manual. Provide the building owner or representative with detailed operating and maintenance instructions and copies of guaranties/warranties for each system. O & M instructions shall be consistent with OSHA requirements in CCR, Title 8, Section 5142, and other related

5.410.4.5.1 Inspections and reports. Include a copy of all inspection verifications and reports required by the enforcing agency.

DIVISION 5.5 ENVIRONMENTAL QUALITY

SECTION 5.501 GENERAL 5.501.1 SCOPE. The provisions of this chapter shall outline means of reducing the quantity of air contaminants that are odorous, irritating, and/or harmful to the comfort and well-being of a building's installers, occupants and neighbors.

SECTION 5.502 DEFINITIONS **5.502.1 DEFINITIONS.** The following terms are defined in Chapter 2 (and are included here for reference)

ARTERIAL HIGHWAY. A general term denoting a highway primarily for through traffic usually on a continuous route. A-WEIGHTED SOUND LEVEL (dBA). The sound pressure level in decibels as measured on a sound level meter using the internationally standardized A-weighting filter or as computed from sound spectral data to which A-weighting

1 BTU/HOUR. British thermal units per hour, also referred to as Btu. The amount of heat required to raise one pound of water one degree Fahrenheit per hour, a common measure of heat transfer rate. A ton of refrigeration is 12,000 Btu. the amount of heat required to melt a ton (2,000 pounds) of ice at 32⁰ Fahrenheit.

COMMUNITY NOISE EQUIVALENT LEVEL (CNEL). A metric similar to the day-night average sound level (Ldn), except that a 5 decibel adjustment is added to the equivalent continuous sound exposure level for evening hours (7pm to 10pm) in addition to the 10 dB nighttime adjustment used in the Ldn.

COMPOSITE WOOD PRODUCTS. Composite wood products include hardwood plywood, particleboard and medium density fiberboard. "Composite wood products" does not include hardboard, structural plywood, structural panels, structural composite lumber, oriented strand board, glued laminated timber, timber, prefabricated wood I-joists or finger-jointed lumber, all as specified in California Code of Regulations (CCR), Title 17, Section 93120.1(a).

Note: See CCR, Title 17, Section 93120.1.

adjustments have been made.

DAY-NIGHT AVERAGE SOUND LEVEL (Ldn). The A-weighted equivalent continuous sound exposure level for a 24-hour period with a 10 dB adjustment added to sound levels occurring during nighttime hours (10p.m. to 7 a.m.).

DECIBEL (db). A measure on a logarithmic scale of the magnitude of a particular quantity (such as sound pressure, sound power, sound intensity) with respect to a reference quantity.

ELECTRIC VEHICLE (EV). An automotive-type vehicle for on-road use, such as passenger automobiles, buses, trucks, vans, neighborhood electric vehicles, electric motorcycles, and the like, primarily powered by an electric motor that draws current from a rechargeable storage battery, fuel cell, photovoltaic array, or other source of electric current. Plug-in hybrid electric vehicles (PHEV) are considered electric vehicles. For purposes of the California Electrical Code, off-road. self-propoelled electric vehicles, such as industrial trucks, hoists, lifts, transports, golf carts, airline ground support equipment, tractors, boats, and the like, are not included.

ELECTRIC VEHICLE CHARGING STATION(S) (EVCSj). One or more spaces intended for charging electric vehicles

ELECTRIC VEHICLE SUPPLY EQUIPMENT (EVSE). The conductors, including the ungrounded, grounded, and equipment grounding conductors and the electric vehicle connectors, attachment plugs, and all other fittings, devices, power outlets, or apparatus installed specifically for the purpose of transferring energy between the premises wiring and the electric vehicle.

ENERGY EQUIVALENT (NOISE) LEVEL (Leq). The level of a steady noise which would have the same energy as the fluctuating noise level integrated over the time of period of interest.

not be divided or have grade separations at intersections.

FREEWAY. A divided arterial highway with full control of access and with grade separations at intersections. GLOBAL WARMING POTENTIAL (GWP). The radiative forcing impact of one mass-based unit of a given greenhouse

EXPRESSWAY. An arterial highway for through traffic which may have partial control of access, but which may or may

gas relative to an equivalent unit of carbon dioxide over a given period of time. Carbon dioxide is the reference compound with a GWP of one. GLOBAL WARMING POTENTIAL VALUE (GWP VALUE). A 100-year GWP value published by the

Intergovernmental Panel on Climate Change (IPCC) in either its Second Assessment Report (SAR) (IPCC, 1995); or its Fourth Assessment A-3 Report (AR4) (IPCC, 2007). The SAR GWP values are found in column "SAR (100-yr)" of Table 2.14.; the AR4 GWP values are found in column "100 yr" of Table 2.14.

HIGH-GWP REFRIGERANT. A compound used as a heat transfer fluid or gas that is: (a) a chlorofluorocarbon, a hdrochlorofluorocarbon, a hydrofluorocarbon, a perfluorocarbon, or any compound or blend of compounds, with a GWP value equal to or greater than 150, or (B) any ozone depleting substance as defined in Title 40 of the Code of Federal Regulations, Part 82, sec.82.3 (as amended March 10, 2009).

LONG RADIUS ELBOW. Pipe fitting installed between two lengths of pipe or tubing to allow a change of direction, with a radius 1.5 times the pipe diameter.

LOW-GWP REFRIGERANT. A compound used as a heat transfer fluid or gas that: (A) has a GWP value less than 150, and (B) is not an ozone depleting substance as defined in Title 40 of the Code of Federal Regulations, Part 82, sec.82.3 (as amended March 10, 2009).

MERV. Filter minimum efficiency reporting value, based on ASHRAE 52.2–1999.

MAXIMUM INCREMENTAL REACTIVITY (MIR). The maximum change in weight of ozone formed by adding a compound to the "Base REactive Organic Gas (ROG) Mixture" per weight of compound added, expressed to hundreths of a gram (g O³/g ROC).

PRODUCT-WEIGHTED MIR (PWMIR). The sum of all weighted-MIR for all ingredients in a product subject to this article. The PWMIR is the total product reactivity expressed to hundredths of a gram of ozone formed per gram of product (excluding container and packaging).

PSIG. Pounds per square inch, guage.

REACTIVE ORGANIC COMPOUND (ROC). Any compound that has the potential, once emitted, to contribute to

SCHRADER ACCESS VALVES. Access fittings with a valve core installed.

SHORT RADIUS ELBOW. Pipe fitting installed between two lengths of pipe or tubing to allow a change of direction, with a radius 1.0 times the pipe diameter.

SUPERMARKET. For the purposes of Section 5.508.2, a supermarket is any retail food facility with 8,000 square feet or more conditioned area, and that utilizes either refrigerated display cases, or walk-in coolers or freezers connected to remote compressor units or condensing units. **VOC.** A volatile organic compound broadly defined as a chemical compound based on carbon chains or rings with

vapor pressures greater than 0.1 millimeters of mercury at room temperature. These compounds typically contain hydrogen and may contain oxygen, nitrogen and other elements. See CCR Title 17, Section 94508(a) Note: Where specific regulations are cited from different agencies such as SCAQMD, ARB, etc., the VOC definition

included in that specific regulation is the one that prevails for the specific measure in question. SECTION 5.503 FIREPLACES 5.503.1 FIREPLACES. Install only a direct-vent sealed-combustion gas or sealed wood-burning fireplace, or a sealed

woodstove or pellet stove, and refer to residential requirements in the California Energy Code, Title 24, Part 6, Subchapter 7, Section 150. Woodstoves, pellet stoves and fireplaces shall comply with applicable local ordinances.

5.503.1.1 Woodstoves. Woodstoves and pellet stoves shall comply with U.S. EPA New Source Performance Standards (NSPS) emission limits as applicable, and shall have a permanent label indicating they are certified to meet the emission limits.

SECTION 5.504 POLLUTANT CONTROL

5.504.1 TEMPORARY VENTILATION. The permanent HVAC system shall only be used during construction if necessary to condition the building or areas of addition or alteration within the required temperature range for material and equipment installation. If the HVAC system is used during construction, use return air filters with a Minimum Efficiency Reporting Value (MERV) of 8, based on ASHRAE 52.2-1999, or an average efficiency of 30% based on ASHRAE 52.1-1992 Replace all filters immediately prior to occupancy, or, if the building is occupied during alteration, at the conclusion of construction.

5.504.3 Covering of duct openings and protection of mechanical equipment during construction. At the time of rough installation and during storage on the construction site until final startup of the heating, cooling and ventilation equipment, all duct and other related air distribution component openings shall be covered with tape, plastic, sheetmetal or other methods acceptable to the enforcing agency to reduce the amount of dust, water and debris which ROJECT SPECIFIC STATE AGENCY APPROVAL IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 12/18/2024



PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE **EXPRESS WRITTEN CONSENT OF R&S** TAVARES ASSOCIATES, INC. ©



APPROVED DIV. OF THE STATE ARCHITECT APP: 04-123059 PC REVIEWED FOR SS / F(S / ACS / CG /

Revision Schedule Description

PRE-CHECK (PC) DOCUMENT

Code: 2022 CBC

A separate project application for construction is required PC 2022 CBC: 24' x 40'

EXPANDABLE TO

120' x 40'

CAL GREEN

CHECKLIST

PROJECT NUMBER 22088

rMc/SC

RH/RT DATE

CHECKED BY

DISCLAIMER: THIS DOCUMENT IS PROVIDED AND INTENDED TO BE USED AS A MEANS TO INDICATE AREAS OF COMPLIANCE WITH THE END USER ASSUMES ALL RESPONSIBILITY ASSOCIATED WITH THE USE OF THIS DOCUMENT, INCLUDING VERIFICATION WITH THE FULL CODE.

5.504.4 FINISH MATERIAL POLLUTANT CONTROL. Finish materials shall comply with Sections 5.504.4.1 through

aerosol products as specified in subsection 2, below.

5.504.4.1 Adhesives, sealants and caulks. Adhesives, sealants, and caulks used on the project shall meet the requirements of the following standards: 1. Adhesives, adhesive bonding primers, adhesive primers, sealants, sealant primers and caulks shall comply with local or regional air pollution control or air quality management district rules where applicable, or SCAQMD Rule 1168 VOC limits, as shown in Tables 5.504.4.1 and 5.504.4.2. Such products also shall comply with the Rule 1168 prohibition on the use of certain toxic compounds (chloroform, ethylene dichloride, methylene chloride, perchloroethylene and trichloroethylene), except for

2. Aerosol adhesives, and smaller unit sizes of adhesives, and sealant or caulking compounds (in units of product, less packaging, which do not weigh more than one pound and do not consist of more than 16 fluid ounces) shall comply with statewide VOC standards and other requirements, including prohibitions on use of certain toxic compounds, of California Code of Regulations, Title 17, commencing

| Less Water and Less Exempt Compounds in Grams per Liter | |
|---|-------------------|
| ARCHITECTURAL APPLICATIONS | CURRENT VOC LIMIT |
| INDOOR CARPET ADHESIVES | 50 |
| CARPET PAD ADHESIVES | 50 |
| OUTDOOR CARPET ADHESIVES | 150 |
| WOOD FLOORING ADHESIVES | 100 |
| RUBBER FLOOR ADHESIVES | 60 |
| SUBFLOOR ADHESIVES | 50 |
| CERAMIC TILE ADHESIVES | 65 |
| VCT & ASPHALT TILE ADHESIVES | 50 |
| DRYWALL & PANEL ADHESIVES | 50 |
| COVE BASE ADHESIVES | 50 |
| MULTIPURPOSE CONSTRUCTION ADHESIVES | 70 |
| STRUCTURAL GLAZING ADHESIVES | 100 |
| SINGLE-PLY ROOF MEMBRANE ADHESIVES | 250 |
| OTHER ADHESIVES NOT SPECIFICALLY LISTED | 50 |
| SPECIALTY APPLICATIONS | |
| PVC WELDING | 510 |
| CPVC WELDING | 490 |
| ABS WELDING | 325 |
| PLASTIC CEMENT WELDING | 250 |
| ADHESIVE PRIMER FOR PLASTIC | 550 |
| CONTACT ADHESIVE | 80 |
| SPECIAL PURPOSE CONTACT ADHESIVE | 250 |
| STRUCTURAL WOOD MEMBER ADHESIVE | 140 |
| TOP & TRIM ADHESIVE | 250 |
| SUBSTRATE SPECIFIC APPLICATIONS | |
| METAL TO METAL | 30 |
| PLASTIC FOAMS | 50 |
| POROUS MATERIAL (EXCEPT WOOD) | 50 |
| WOOD | 30 |
| | |

1. IF AN ADHESIVE IS USED TO BOND DISSIMILAR SUBSTRATES TOGETHER, THE ADHESIVE WITH THE HIGHEST VOC CONTENT SHALL BE ALLOWED.

2. FOR ADDITIONAL INFORMATION REGARDING METHODS TO MEASURE THE VOC CONTENT SPECIFIED IN THIS TABLE, SEE SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT RULE 1168, www.arb.ca.gov/DRDB/SC/CURHTML/R1168.PDF

FIBERGLASS

| TABLE 5.504.4.2 - SEALANT VOC LIMIT | | | | |
|---|-------------------|--|--|--|
| Less Water and Less Exempt Compounds in Grams per Liter | | | | |
| SEALANTS | CURRENT VOC LIMIT | | | |
| ARCHITECTURAL | 250 | | | |
| MARINE DECK | 760 | | | |
| NONMEMBRANE ROOF | 300 | | | |
| ROADWAY | 250 | | | |
| SINGLE-PLY ROOF MEMBRANE | 450 | | | |
| OTHER | 420 | | | |
| SEALANT PRIMERS | | | | |
| ARCHITECTURAL | | | | |
| NONPOROUS | 250 | | | |
| POROUS | 775 | | | |
| MODIFIED BITUMINOUS | 500 | | | |
| MARINE DECK | 760 | | | |
| OTHER | 750 | | | |

NOTE: FOR ADDITIONAL INFORMATION REGARDING METHODS TO MEASURE THE VOC CONTENT SPECIFIED IN THESE TABLES, SEE SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT RULE 1168.

5.504.4.3 Paints and coatings. Architectural paints and coatings shall comply with VOC limits in Table 1 of the ARB Architectural Coatings Suggested Control Measure, as shown in Table 5.504.4.3, unless more stringent local limits apply. The VOC content limit for coatings that do not meet the definitions for the specialty coatings categories listed in Table 5.504.4.3 shall be determined by classifying the coating as a Flat, Nonflat or Nonflat-High Gloss coating, based on its gloss, as defined in Subsections 4.21, 4.36 and 4.37 of the 2007 California Air Resources Board Suggested Control Measure, and the corresponding Flat, Nonflat or Nonflat-High Gloss VOC limit in Table 5.504.4.3 shall apply.

5.504.4.3.1 Aerosol Paints and coatings. Aerosol paints and coatings shall meet the PWMIR Limits for ROC in Section 94522(a)(3) and other requirements, including prohibitions on use of certain toxic compounds and ozone depleting substances, in Sections 94522(c)(2) and (d)(2) of California Code of Regulations, Title 17, commencing with Section 94520; and in areas under the jurisdiction of the Bay Area Air Quality Management District additionally comply with the percent VOC by weight of product limits of Regulation 8 Rule 49.

| GRAMS OF VOC PER LITER OF COATING, LESS WATER & LESS EXEMP COATING CATEGORY | CURRENT VOC LIMIT |
|--|-------------------|
| SPECIALTY COATINGS | |
| ALUMINUM ROOF COATINGS | 400 |
| BASEMENT SPECIALTY COATINGS | 400 |
| BITUMINOUS ROOF COATINGS | 50 |
| BITUMINOUS ROOF PRIMERS | 350 |
| BOND BREAKERS | 350 |
| CONCRETE CURING COMPOUNDS | 350 |
| CONCRETE/MASONRY SEALERS | 100 |
| DRIVEWAY SEALERS | 50 |
| DRY FOG COATINGS | 150 |
| FAUX FINISHING COATINGS | 350 |
| FIRE RESISTIVE COATINGS | 350 |
| FLOOR COATINGS | 100 |
| FORM-RELEASE COMPOUNDS | 250 |
| GRAPHIC ARTS COATINGS (SIGN PAINTS) | 500 |
| HIGH-TEMPERATURE COATINGS | 420 |
| INDUSTRIAL MAINTENANCE COATINGS | 250 |
| LOW SOLIDS COATINGS ₁ | 120 |
| MAGNESITE CEMENT COATINGS | 450 |
| MASTIC TEXTURE COATINGS | 100 |
| METALLIC PIGMENTED COATINGS | 500 |
| MULTICOLOR COATINGS | 250 |
| PRETREATMENT WASH PRIMERS | 420 |
| PRIMERS, SEALERS, & UNDERCOATERS | 100 |
| REACTIVE PENETRATING SEALERS | 350 |
| RECYCLED COATINGS | 250 |
| ROOF COATINGS | 50 |
| RUST PREVENTATIVE COATINGS | 250 |
| SHELLACS: | |
| CLEAR | 730 |
| OPAQUE | 550 |
| SPECIALTY PRIMERS, SEALERS & UNDERCOATERS | 100 |
| STAINS | 250 |
| STONE CONSOLIDANTS | 450 |
| SWIMMING POOL COATINGS | 340 |
| TRAFFIC MARKING COATINGS | 100 |
| TUB & TILE REFINISH COATINGS | 420 |
| WATERPROOFING MEMBRANES | 250 |
| WOOD COATINGS | 275 |
| WOOD PRESERVATIVES | 350 |

 GRAMS OF VOC PER LITER OF COATING, INCLUDING WATER & EXEMPT COMPOUNDS. 2. THE SPECIFIED LIMITS REMAIN IN EFFECT UNLESS REVISED LIMITS ARE LISTED IN SUBSEQUENT COLUMNS IN

3. VALUES IN THIS TABLE ARE DERIVED FROM THOSE SPECIFIED BY THE CALIFORNIA AIR RESOURCES BOARD, ARCHITECTURAL COATINGS SUGGESTED CONTROL MEASURE, FEB. 1, 2008. MORE INFORMATION IS AVAILABLE FROM THE AIR RESOURCES BOARD.

5.504.4.3.2 Verification. Verification of compliance with this section shall be provided at the request of the enforcing agency. Documentation may include, but is not limited to, the following: 1. Manufacturer's product specification

5.504.4.4 Carpet Systems

All carpet installed in the building interior shall meet the requirements of the California Department of Public Health, "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers." Version 1.2, January 2017 (Emission testing method for California Specifications 01350).

See California Department of Public Health's website for certification programs and testing labs. https://www.cdph.ca.gov/Programs/CCDPHP/DEODC/EHLB/IAQ/Pages/VOC.aspx#material

2. Field verification of on-site product containers

5.504.4.4.1 Carpet cushion. All carpet cushion installed in the building interior shall meet the requirements of the California Department of Public Health, "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers,"Version 1.2, January 2017 (Emission testing method for California Specifications

See California Department of Public Health's website for certification programs and testing labs.

https://www.cdph.ca.gov/Programs/CCDPHP/DEODC/EHLB/IAQ/Pages/VOC.aspx#material 5.504.4.4.2 Carpet adhesive. All carpet adhesive shall meet the requirements of Table 5.504.4.1.

5.504.4.5 Composite wood products. Hardwood plywood, particleboard and medium density fiberboard composite wood products used on the interior or exterior of the buildings shall meet the requirements for formaldehyde as specified in ARB's Air Toxics Control Measure (ATCM) for Composite Wood (17 CCR 93120 et seq.). Those materials not exempted under the ATCM must meet the specified emission limits, as shown in

5.504.4.5.3 Documentation. Verification of compliance with this section shall be provided as requested by the enforcing agency. Documentation shall include at least one of the following:

Product certifications and specifications.

Chain of custody certifications. Product labeled and invoiced as meeting the Composite Wood Products regulation (see

CCR, Title 17, Section 93120, et seq.). 4. Exterior grade products marked as meeting the PS-1 or PS-2 standards of the Engineered Wood Association, the Australian AS/NZS 2269 or European 636 3S

Other methods acceptable to the enforcing agency.

| MAXIMUM FORMALDEHYDE EMISSIONS IN PARTS PER M | ILLION |
|---|---------------|
| PRODUCT | CURRENT LIMIT |
| HARDWOOD PLYWOOD VENEER CORE | 0.05 |
| HARDWOOD PLYWOOD COMPOSITE CORE | 0.05 |
| PARTICLE BOARD | 0.09 |
| MEDIUM DENSITY FIBERBOARD | 0.11 |
| THIN MEDIUM DENSITY FIBERBOARD2 | 0.13 |

THIN MEDIUM DENSITY FIBERBOARD HAS A MAXIMUM THICKNESS OF 5/16 INCHES (8 MM).

5.504.4.6 Resilient flooring systems. Where resilient flooring is installed, at least 80 percent of floor area receiving resilient flooring shall meet the requirements of the California Department of Public Health, "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers," Version 1.2, January 2017 (Emission testing method for California Specifications

See California Department of Public Health's website for certification programs and testing labs. https://www.cdph.ca.gov/Programs/CCDPHP/DEODC/EHLB/IAQ/Pages/VOC.aspx#material

5.504.4.6.1 Verification of compliance. Documentation shall be provided verifying that resilient flooring materials meet the pollutant emission limits.

5.504.4.7 Thermal insulation

Comply with the requirements of the California Department of Public Health, "Standard Method of the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers, "Version 1.2, January 1.2, January 2017 (Emission testing method for California Specification 01350). See California Department of Public Health's website for certification programs and testing labs. https://www.cdph.ca.gov/Programs/CCDPHP/DEODC/EHLB/IAQ/Pages/VOC.aspx#material

5.504.4.7.1 Verification of compliance. Documentation shall be provided verifying that thermal insulation materials meet the pollutant emission

5.504.4.8 Acoustical ceiling and wall panels. Comply with the requirements of the California Department of Public Health, "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers, Version 1.2, January 2017 (Emission testing method for California Specification 01350). See California Department of Public Health's website for certification programs and testing labs.

5.504.4.8.1 Verification of compliance. Documentation shall be provided verifying that acoustical finish materials meet the pollutant emission limits.

5.504.5.3 Filters. In mechanically ventilated buildings, provide regularly occupied areas of the building with air filtration media for outside and return air that provides at least a Minimum Efficiency Reporting Value (MERV) of 13. MERV 13 filters shall be installed prior to occupancy, and recommendations for maintenance with filters of the same value shall be included in the operation and maintenance manual.

Exceptions: Existing mechanical equipment

5.504.5.3.1 Labeling. Installed filters shall be clearly labeled by the manufacturer indicating the MERV

5.504.7 ENVIRONMENTAL TOBACCO SMOKE (ETS) CONTROL. Where outdoor areas are provided for smoking, prohibit smoking within 25 feet of building entries, outdoor air intakes and operable windows and within the building as already prohibited by other laws or regulations; or as enforced by ordinances, regulations or policies of any city, county, city and county, California Community College, campus of the California State University, or campus of the University of California, whichever are more stringent. When ordinances, regulations or policies are not in place, post signage to inform building occupants of the prohibitions.

SECTION 5.505 INDOOR MOISTURE CONTROL

5.505.1 INDOOR MOISTURE CONTROL. Buildings shall meet or exceed the provisions of California Building Code, CCR, Title 24, Part 2, Sections 1202 (Ventilation) and Chapter 14 (Exterior Walls). For additional measures, see Section 5.407.2 of this code.

SECTION 5.506 INDOOR AIR QUALITY

5.506.1 OUTSIDE AIR DELIVERY. For mechanically or naturally ventilated spaces in buildings, meet the minimum requirements of Section 120.1 (Requirements For Ventilation) of the California Energy Code, or the applicable local code, whichever is more stringent, and Division 1, Chapter 4 of CCR, Title 8.

5.506.2 CARBON DIOXIDE (CO2) MONITORING. For buildings or additions equipped with demand control ventilation, CO₂ sensors and ventilation controls shall be specified and installed in accordance with the requirements of the California Energy Code, Section 120(c)(4).

5.506.3 Carbon dioxide (CO2) monitoring in classrooms. (DSA-SS) Each public K-12 school classroom, as listed in Table 120.1-A of the California Energy Code, shall be equipped with a carbon dioxide monitor or sensor that meets the following requirements

The monitor or sensor shall be permanently affixed in a tamper-proof manner in each classroom between 3 and 6 feet (914 mm and 1829 mm) above the floor and at least 5 feet (1524 mm) away from door and operable

When the monitor or sensor is not integral to an Energy Management Control System (EMCS), the monitor or sensor shall display the carbon dioxide readings on the device. When the sensor is integral to an EMCS, the carbon dioxide readings shall be available to and regularly monitored by facility personnel. A monitor shall provide notification though a visual indicator on the monitor when the carbon dioxide levels in the classroom have exceeded 1.100ppm. A sensor integral to an EMCS shall provide notification to facility personnel through a visual and/or audible indicator when the carbon dioxide levels in the classroom have

The monitor or sensor shall measure carbon dioxide levels at minimum 15- minute intervals and shall maintain a

record of previous carbon dioxide measurements of not less than 30 days duration. The monitor or sensor used to measure carbon dioxide levels shall have the capacity to measure carbon dioxide levels with a range of 400ppm to 2000ppm or greater. The monitor or sensor shall be certified by the manufacturer to be accurate within 75ppm at 1,000ppm carbon

dioxide concentration and shall be certified by the manufacturer to require calibration no more frequently than

SECTION 5.507 ENVIRONMENTAL COMFORT

(STC) values determined in accordance with ASTM E 90 and ASTM E 413, or Outdoor-Indoor Sound Transmission Class (OITC) determined in accordance with ASTM E 1332, using either the prescriptive or performance method in

Exception: Buildings with few or no occupants or where occupants are not likely to be affected by exterior noise, as determined by the enforcement authority, such as factories, stadiums, storage, enclosed parking

Exception: [DSA-SS] For public schools and community colleges, the requirements of this section and all subsections apply only to new construction.

5.507.4.1 Exterior noise transmission, prescriptive method. Wall and roof-ceiling assemblies exposed to the noise source making up the building or addition envelope or altered envelope shall meet a composite STC rating of at least 50 or a composite OITC rating of no less than 40, with exterior windows of a minimum STC of 40 or OITC of 30 in the following locations:

1. Within the 65 CNEL noise contour of an airport.

1. Lan or CNEL for military airports shall be determined by the facility Air Installation Compatible

2. Lan or CNEL for other airports and heliports for which a land use plan has not been developed shall be determined by the local general plan noise element.

2. Within the 65 CNEL or Ldn noise contour of a freeway or expressway, railroad, industrial source or fixed-guideway source as determined by the Noise Element of the General Plan.

5.507.4.1.1. Noise exposure where noise contours are not readily available. Buildings exposed to a noise level of 65 dB L_{eq} - 1-hr during any hour of operation shall have building, addition or alteration exterior wall and roof-ceiling assemblies exposed to the noise source meeting a composite STC rating of at least 45 (or OITC 35), with exterior windows of a minimum STC of 40 (or OITC 30).

5.507.4.2 Performance Method. For buildings located as defined in Section 5.507.4.1 or 5.507.4.1.1, wall and roof-ceiling assemblies exposed to the noise source making up the building or addition envelope or altered envelope shall be constructed to provide an interior noise environment attributable to exterior sources that does not exceed an hourly equivalent noise level (Leq-1Hr) of 50 dBA in occupied areas during any hour of operation

5.507.4.2.1 Site Features. Exterior features such as sound walls or earth berms may be utilized as appropriate to the building, addition or alteration project to mitigate sound migration to the interior.

5.507.4.2.2 Documentation of Compliance. An acoustical analysis documenting complying interior sound levels shall be prepared by personnel approved by the architect or engineer of record.

5.507.4.3 Interior sound transmission. Wall and floor-ceiling assemblies separating tenant spaces and tenant spaces and public places shall have an STC of at least 40.

Note: Examples of assemblies and their various STC ratings may be found at the California Office of Noise Control: www.toolbase.org/PDF/CaseStudies/stc_icc_ratings.pdf.

SECTION 5.508 OUTDOOR AIR QUALITY

5.508.1 Ozone depletion and greenhouse gas reductions. Installations of HVAC, refrigeration and fire suppression equipment shall comply with Sections 5.508.1.1 and 5.508.1.2. 5.508.1.1 Chlorofluorocarbons (CFCs). Install HVAC, refrigeration and fire suppression equipment that do not

5.508.1.2 Halons. Install HVAC, refrigeration and fire suppression equipment that do not contain Halons.

5.508.2 Supermarket refrigerant leak reduction. New commercial refrigeration systems shall comply with the provisions of this section when installed in retail food stores 8,000 square feet or more conditioned area, and that utilize either refrigerated display cases, or walk-in coolers or freezers connected to remote compressor units or condensing units. The leak reduction measures apply to refrigeration systems containing high-global-warming potential (high-GWP) refrigerants with a GWP of 150 or greater. New refrigeration systems include both new facilities and the eplacement of existing refrigeration systems in existing facilities.

Exception: Refrigeration systems containing low-global warming potential (low-GWP) refrigerant with a GWP value less than 150 are not subject to this section. Low-GWP refrigerants are nonozone-depleting refrigerants that include ammonia, carbon dioxide (CO₂), and potentially other refrigerants.

5.508.2.1 Refrigerant piping. Piping compliant with the California Mechanical Code shall be installed to be accessible for leak protection and repairs. Piping runs using threaded pipe, copper tubing with an outside diameter (OD) less than 1/4 inch, flared tubing connections and short radius elbows shall not be used in refrigerant systems except as noted below

5.508.2.1.1 Threaded pipe. Threaded connections are permitted at the compressor rack.

5.508.2.1.2 Copper pipe. Copper tubing with an OD less than 1/4 inch may be used in systems with a refrigerant charge of 5 pounds or less.

keep vibration levels below 8 mils.

5.508.2.1.2.1 Anchorage. One-fouth-inch OD tubing shall be securely clamped to a rigid base to

5.508.2.1.3 Flared tubing connections. Double-flared tubing connections may be used for pressure controls, valve pilot lines and oil.

Exception: Single-flared tubing connections may be used with a multiring seal coated with industrial sealant suitable for use with refrigerants and tightened in accordance with manufacturer's

5.508.2.1.4 Elbows. Short radius elbows are only permitted where space limitations prohibit use of

long radius elbows. 5.508.2.2 Valves. Valves Valves and fittings shall comply with the California Mechanical Code and as

5.508.2.2.1 Pressure relief valves. For vessels containing high-GWP refrigerant, a rupture disc shall

be installed between the outlet of the vessel and the inlet of the pressure relief valve. **5.508.2.2.1.1 Pressure detection.** A pressure gauge, pressure transducer or other device shall

be installed in the space between the rupture disc and the relief valve inlet to indicate a disc rupture or discharge of the relief valve. **5.508.2.2.2 Access valves.** Only Schrader access valves with a brass or steel body are

5.508.2.2.2.1 Valve caps. For systems with a refrigerant charge of 5 pounds or more, valve caps

shall be brass or steel and not plastic

5.508.2.2.2.2 Seal caps. If designed for it, the cap shall have a neoprene O-ring in place. 5.508.2.2.2.1 Chain tethers. Chain tethers to fit ovr the stem are required for valves designed to have seal caps.

Exception: Valves with seal caps that are not removed from the valve during stem

5.508.2.3 Refrigerated service cases. Refrigerated service cases holding food products containing vinegar and salt shall have evaporator coils of corrosion-resistant material, such as stainless steel; or be coated to prevent corrosion from these substances.

5.508.2.3.1 Coil coating. Consideration shall be given to the heat transfer efficiency of coil coating to maximize energy efficiency.

5.508.2.4 Refrigerant receivers. Refrigerant receivers with capacities greater than 200 pounds shall be fitted with a device tha indicates the level of refrigerant in the receiver.

5.508.2.5 Pressure testing. The system shall be pressure tested during installation prior to evacuation and

5.508.2.5.1 Minimum pressure. The system shall be charged with regulated dry nitrogen and appropriate tracer gas to bring system pressure up to 300 psig minimum.

5.508.2.5.2 Leaks. Check the system for leaks, repair any leaks, and retest for pressure using the same

5.508.2.5.3 Allowable pressure change. The system shall stand, unaltered, for 24 hours with no more

than a +/- one pound pressure change from 300 psig, measured with the same gauge. **5.508.2.6 Evacuation.** The system shall be evacuated after pressure testing and prior to charging.

5.508.2.6.1 First vacuum. Pull a system vacuum down to at least 1000 microns (+/- 50 microns), and

5.508.2.6.2 Second vacuum. Pull a second system vacuum to a minimum of 500 microns and hold for 30

5.508.2.6.3 Third vacuum. Pull a third vacuum down to a minimum of 300 microns, and hold for 24 hours

CHAPTER 7 **INSTALLER & SPECIAL INSPECTOR QUALIFICATIONS**

with a maximum drift of 100 microns over a 24-hour period

702 QUALIFICATIONS

702.1 INSTALLER TRAINING. HVAC system installers shall be trained and certified in the proper nstallation of HVAC systems including ducts and equipment by a nationally or regionally recognized training or certification program. Uncertified persons may perform HVAC installations when under the direct supervision and esponsibility of a person trained and certified to install HVAC systems or contractor licensed to install HVAC systems. Examples of acceptable HVAC training and certification programs include but are not limited to the following:

1. State certified apprenticeship programs.

. Public utility training programs. Training programs sponsored by trade, labor or statewide energy consulting or verification organizations.

Programs sponsored by manufacturing organizations. 5. Other programs acceptable to the enforcing agency.

702.2 SPECIAL INSPECTION [HCD]. When required by the enforcing agency, the owner or the esponsible entity acting as the owner's agent shall employ one or more special inspectors to provide inspection or other duties necessary to substantiate compliance with this code. Special inspectors shall demonstrate competence to the satisfaction of the enforcing agency for the particular type of inspection or task to be performed. In addition to

other certifications or qualifications acceptable to the enforcing agency, the following certifications or education may be

Certification by a national or regional green building program or standard publisher. 2. Certification by a statewide energy consulting or verification organization, such as HERS raters, building

considered by the enforcing agency when evaluating the qualifications of a special inspector:

performance contractors, and home energy auditors.

3. Successful completion of a third party apprentice training program in the appropriate trade. 4. Other programs acceptable to the enforcing agency.

1. Special inspectors shall be independent entities with no financial interest in the materials or the project they are inspecting for compliance with this code. HERS raters are special inspectors certified by the California Energy Commission (CEC) to rate homes in California according to the Home Energy Rating System (HERS).

[BSC-CG] When required by the enforcing agency, the owner or the responsible entity acting as the owner's agent shall employ one or more special inspectors to provide inspection or other duties necessary to substantiate compliance with this code. Special inspectors shall demonstrate competence to the satisfaction of the enforcing agency for the particular type of inspection or task to be performed. In addition, the special inspector shall have a certification from a recognized state, national or international association, as determined by the local agency. The

area of certification shall be closely related to the primary job function, as determined by the local agency.

Note: Special inspectors shall be independent entities with no financial interest in the materials or the project they are inspecting for compliance with this code.


703 VERIFICATIONS

703.1 DOCUMENTATION. Documentation used to show compliance with this code shall include but is not limited to, construction documents, plans, specifications, builder or installer certification, inspection reports, or other methods acceptable to the enforcing agency which demonstrate substantial conformance. When specific documentation or special inspection is necessary to verify compliance, that method of compliance will be specified in the appropriate section or identified applicable checklist.

IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: **REVIEWED FOR** SS 🗹 FLS 🗹 ACS 🗹 12/18/2024

ROJECT SPECIFIC STATE AGENCY APPROVAC





THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©



APPROVED DIV. OF THE STATE ARCHITECT APP: 04-123059 PC

Revision Schedule

Description

PRE-CHECK (PC) DOCUMENT Code: 2022 CBC

PC 2022 CBC: 24' x 40' **EXPANDABLE TO**

A separate project application for construction is required

CAL GREEN


PROJECT NUMBER


22088


CHECKED BY


DATE


DISCLAIMER: THIS DOCUMENT IS PROVIDED AND INTENDED TO BE USED AS A MEANS TO INDICATE AREAS OF COMPLIANCE WITH THE CALIFORNIA GREEN BUILDING VERIFICATION WITH THE FULL CODE.











1. CEILING SYSTEM GENERAL NOTES

- 1.01 Ceiling system components shall comply with ASTM C635 and Section 5.1 of ASTM
- 1.02 The ceiling grid system must be rated heavy duty as defined by ASTM C635.
- 1.03 Ceiling systems. The following ceiling system(s) is/are part of the scope of this project: Manufacturer:

Product Name: PRELUDE XL AND PRELUDE XL HIGH RECYLED CONTENT(HRC) Evaluation Report Type and Number: ICC ESR#1308 Main Runner Part, Model, or Catalog Number 7301 Cross Runner Part, Model, Catalog Number: 4" CROSS T # XL7341 / 2" CROSS T # XL7328 1.04 Seismic Wall Clip:

STANDARD 7/8" WALL ANGLE CLIP w/ BERC2 CLIP

Manufacturer's Model:

1.05 Ceiling panels shall not support any luminaires, air terminals or devices.

1.06 For ceiling installations utilizing acoustical tile panels of mineral or glass fiber, it is not mandatory to provide 3/4" clearance between the acoustical tile panels and the wall on the sides of the ceiling which are free to slip. For all other ceiling panel types, provide 3/4" clearance between the ceiling panel and the wall on the sides of the ceiling free to slip. Clearance between ceiling grid runners/members and walls shall comply with the details on these drawings regardless of ceiling tile material.

2. MATERIALS

- 2.01 Ceiling wire shall be Class 1 zinc coated (galvanized) carbon steel conforming to ASTM A641. Wire shall be #12 gauge (0.106" diameter) with soft temper and minimum ultimate tensile strength = 70 ksi.
- 2.02 Galvanized sheet steel (including that used for metal stud and track compression struts/post) shall conform to ASTM A653, or other equivalent sheet steel listed in Section A3.1 of the North American Specification for the Design of Cold-Formed Steel Structural Members, (AISI S100). Material 43 mil (18 gauge) and lighter shall have minimum yield strength of 33 ksi. Material 54 mil (16 gauge) and heavier shall have a minimum yield strength of 50 ksi.
- 2.03 Electrical metallic tube (EMT) shall be ANSI C80.3/UL 797 carbon steel with G90 galvanizing. EMT shall have minimum yield strength (F_Y) of 30 ksi and minimum ultimate strength (F_U) of 48 ksi.

3. ATTACHMENT OF HANGER AND BRACING WIRES

- 3.01 Separate all ceiling hanger and bracing wires at least 6 inches from all unbraced ducts, pipes, conduit, etc.
- 3.02 Hanger and bracing wires shall not attach to or bend around obstructions including but not limited to piping, ductwork, conduit and equipment.

| Detail Title: | REV: 09/21/2015 | Detail No. |
|---------------|-----------------|------------|
| | REV: 03/2022 | |
| CEILING NOTES | | □ 1.00 |
| 02:2:::(0::20 | | 7 |

IR 25-2 (Revised 03/18/22) DIVISION OF THE STATE ARCHITECT DEPARTMENT OF GENERAL SERVICES STATE OF CĂLIFORNIA

BERG2 2" BEAM-END RETAINING CLIP -Allows you to create a code-compliant Seismic D, E, F ceiling installation while eliminating the need to use 2" wall molding or spreader bars.

| TABLE 1: LATERAL FORCE BRACE ASSEMBLY SPACING | | | | |
|---|------------------------|--------------------------|--|--|
| Design Spectral Acceleration | Brace Assembly Spacing | | | |
| Parameter, (S _{DS}) | z/h ≤ 0.5 ^a | z/h > 0.5 ^{a,b} | | |
| S _{DS} ≤ 1.15 | 12'-0" x 12'-0" | 12'-0" x 12'-0" | | |
| 1.15 < S _{DS} ≤ 1.73 | 12'-0" x 12'-0" | 8'-0" x 12'-0" | | |
| S _{DS} > 1.73 | 8'-0" x 12'-0" | 8'-0" x 8'-0" | | |
| Footnotes: a. Where, as defined in ASCE 7 Section 2 z = height in structure of point of attach | | base. | | |

SEE ALT SHEET FOR FINAL CONFIGURATION OF CEILING AND S_{DS} VALUE SITE

b. It shall be permitted to use the brace assembly spacing for "z/h > 0.5" for the full building height.

h = average roof height of the structure with respect to the base.

- 3.03 Hanger wires that are more than one (horizontal) in six (vertical) out of plumb shall have counter-sloping wires.
- 3.04 Slack safety wires shall be considered hanger wires for installation and testing requirements.
- 3.05 Hanger and bracing wire anchorage to the structure shall be installed in such a manner that the direction of the anchorage aligns closely with the direction of the wire (e.g., bracing wire ceiling clips must be bent as shown in the details and rotated as required to align closely with the direction of the wire, screw eyes in wood must be installed so they align closely with the direction of the wire, etc.).

4. FASTENERS AND WELDING

- 4.01 Sheet metal screws shall comply with ASTM C1513 and ASME B18.6.3. Penetration of screws through joined material shall not be less than three exposed threads.
- 4.02 Expansion anchors shall be: NA
- 4.03 Power-Actuated Fasteners shall be:
- 4.04 If not otherwise specified in the evaluation report, power-actuated fasteners installed in steel shall be installed so the entire pointed end of the fastener is driven through the steel
- 4.05 Power-actuated fasteners in concrete or masonry are not permitted for bracing wires.
- 4.06 Concrete reinforcement and prestressing tendons shall be located by non-destructive means prior to installing post-installed anchors.
- 4.07 Welding shall be in accordance with AWS D1.3 using E60XX series electrodes.

5. TESTING

IR 25-2

- 5.01 All field testing must be performed in the presence of the project inspector.
- 5.02 Post-installed anchors in concrete used to support hanger wires shall be tested at a frequency of 10 percent. Power-actuated fasteners in concrete shall be field tested for 200 pounds in tension. All other post-installed anchors in concrete shall be tested in accordance with CBC Section 1910A.5.
- 5.03 Post-installed anchors in concrete used to attach bracing wires shall be tested at a frequency of 50 percent in accordance with CBC Section 1910A5.

6. LUMINAIRES

- 6.01 All luminaires shall be positively attached to the ceiling suspension systems by mechanical means to resist a horizontal force equal to the weight of the luminaire. A minimum of two screws or approved fasteners are required at each luminaire, per ASTM E580 Section 5.3.1.
- 6.02 Surface-mounted luminaires shall be attached to the main runner with at least two positive clamping devices. The clamping device shall completely surround the supporting

| Detail Title: | REV: 09/21/2015 | Detail No. |
|---------------|-----------------|------------|
| | REV: 03/2022 | |
| CEILING NOTES | | 1.00 |
| | | |

IR 25-2 (Revised 03/18/22) DIVISION OF THE STATE ARCHITECT DEPARTMENT OF GENERAL SERVICES STATE OF CALIFORNIA

ceiling runner and be made of steel with a minimum thickness of #14 gauge. Rotational spring catches do not comply. A #12 gauge slack safety wire shall be connected from each clamping device to the structure above. Provide additional supports when a luminaire is 8 feet or longer or exceeds 56 pounds. Maximum spacing between supports shall not exceed 8 feet.

- 6.03 Luminaires weighing less than or equal to 10 pounds may be supported directly on the ceiling runners, shall have a minimum of one #12 gauge slack safety wire connected from the fixture housing to the structure above.
- 6.04 Luminaires weighing greater than 10 pounds but less than or equal to 56 pounds may be supported directly on the ceiling runners, but they shall have a minimum of two #12 gauge slack safety wires connected from the fixture housing at diagonal corners to the structure above.
 - **Exception:** All luminaires greater than two by four feet weighing less than 56 pounds shall have a #12 gauge slack safety wire at each corner.
- 6.05 All luminaires weighing greater than 56 pounds shall be independently supported by not less than four taut #12 gauge hanger wires (one at each corner) attached from the fixture housing to the structure above or other approved hangers. The four taut #12 gauge wires or other approved hangers, including their attachment to the structure above, shall be capable of supporting four times the weight of the fixture.

7. SERVICES WITHIN THE CEILING

IR 25-2

- 7.01 All flexible sprinkler hose fitting mounting brackets, ceiling-mounted air terminals or other services shall be positively attached to the ceiling suspension systems by mechanical means. Screws or approved fasteners are required. A minimum of two attachments are required at each component.
- 7.02 Ceiling-mounted air terminals or other services weighing less than or equal to 20 pounds shall have one #12 gauge slack safety wire attached from the terminal or service to the structure above.
- 7.03 Flexible sprinkler hose fittings, ceiling-mounted air terminals or other services weighing more than 20 pounds but less than or equal to 56 pounds shall have two #12 gauge slack safety wires (at diagonal corners) connected from the terminal or service to the structure above.
- 7.04 Flexible sprinkler hose fittings, ceiling-mounted air terminals or other services weighing more than 56 pounds shall be supported directly from the structure above by not less than four taut #12 gauge hanger wires attached from the terminal or service to the structure above or other approved hangers.

8. OTHER DEVICES WITHIN THE CEILING

8.01 All lightweight miscellaneous devices, such as strobe lights, occupancy sensors, speakers, exit signs, etc., shall be attached to the ceiling grid. In addition, devices weighing more than 10 pounds shall have a #12 gauge slack safety wire anchored to the structure above. Devices weighing more than 20 pounds shall be supported independently from the structure above.

| Detail Title: | REV: 09/21/2015 | Detail No. |
|---------------|-----------------|---------------|
| OFW INCOMES | REV: 03/2022 | 4 00 |
| CEILING NOTES | | ↓ 1.00 |
| | | |


DIVISION OF THE STATE ARCHITECT DEPARTMENT OF GENERAL SERVICES STATE OF CALIFORNIA

1.ITEMS SHOWN WITH A MFR CALLOUT MAY BE SUBSTITUTED WITH AN OR EQUAL OR GREATER PRODUCT

WITH DSA APPROVAL








THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©





Revision Schedule Description

PRE-CHECK (PC) DOCUMENT

A separate project application for construction is required

PC 2022 CBC: 24' x 40'


EXPANDABLE TO 120' x 40'


CEILING NOTES


PROJECT NUMBER 22088


CHECKED BY


A3.2.1

















PROJECT SPECIFIC STATE AGENCY APPROVAL IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024



PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE **EXPRESS WRITTEN CONSENT OF R&S** TAVARES ASSOCIATES, INC. ©



ORIGINAL PC STATE AGENCY APPROVAL

APPROVED DIV. OF THE STATE ARCHITECT

Revision Schedule Description

PRE-CHECK (PC) DOCUMENT


A separate project application for construction is required

PC 2022 CBC: 24' x 40' **EXPANDABLE TO** 120' x 40'

SHEET TITLE
SECTION -STANDING SEAM (MONO)

22088

A6.0




IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT

APP: 02-122764 INC:
REVIEWED FOR
SS FLS ACS D

DATE: 12/18/2024



PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©

0 -----



ORIGINAL PC STATE AGENCY APPROVAL



Revision Schedule

Description

PRE-CHECK (PC) DOCUMENT

separate project application for construction is

PROJECT TITLE
PC 2022 CBC: 24' x 40'
EXPANDABLE TO
120' x 40'

HEET TITLE

SECTION

PROJECT NUMBER
22088

WN BY rMc/S


CHECKED BY


ATE

EET NO.

SHEET OF

[°] A6.2





IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT

APP: 02-122764 INC:

REVIEWED FOR
SS FLS ACS D

DATE: 12/18/2024



PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©

JLIENI



ORIGINAL PC STATE AGENCY APPROVAL

APPROVED
DIV. OF THE STATE ARCHITECT

APP: 04-123059 PC

REVIEWED FOR
SS FLS ACS CG
DATE: 02/20/2024

Revision Schedule

Description Date

PRE-CHECK (PC) DOCUMENT

Code: 2022 CBC

A separate project application for construction is required PROJECT TITLE

PC 2022 CBC: 24' x 40' EXPANDABLE TO 120' x 40'

EET TITLE_

ADDITIONAL OPTION DETAILS

PROJECT NUMBER

22088

DRAWN BY

rMc/SC


CHECKED BY


DATE

SHEET NO. A7.0

SHEET OF

RH/RT





(ALL CONDUCTORS SHALL BE TYPE THHN/THWN 75 DEG. C. COPPER)

CONDUIT FILL AND CONDUCTOR CAPACITY TABLE

| | I | I | I | | | |
|-----|--------------------|---------|-----------------------|-----|----|----|
| BOX | BOX SIZE | CU. IN. | MAX NO. OF CONDUCTORS | | | |
| BOX | | | #12 | #10 | #8 | #6 |
| 4SS | 1 1/4"x4" SQ | 18.0 | 8 | 7 | 6 | 0 |
| 4S | 1 1/2"x4" SQ | 21.0 | 9 | 8 | 7 | 0 |
| 4SD | 2 1/8"x4" SQ | 30.3 | 13 | 12 | 10 | 6 |
| 4SX | 2 7/8"x4" SQ | 43.5 | 23 | 21 | 17 | 10 |
| 5SD | 2 1/8"x4-11/16" SQ | 42.0 | 18 | 16 | 14 | 6 |
| 5SX | 3 7/8"x4-11/16" SQ | 86.0 | 38 | 34 | 28 | 17 |
| 664 | 4"x6" SQ | 144.0 | 64 | 57 | 48 | 28 |

* DEDUCT ONE CONDUCTOR FOR (1) OR MORE GROUNDING CONDUCTORS ENTERING THE BOX

2 JUNCTION BOX SIZE TABLE


915.4 CARBON MONOXIDE ALARMS. CARBON MONOXIDE ALARMS SHALL COMPLY WITH SECTIONS 915.4.1 THROUGH 915.4.4.

[F] 915.4.1 POWER SOURCE. CARBON MONOXIDE ALARMS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING WHERE SUCH WIRING IS SERVED FROM A COMMERCIAL SOURCE, AND WHEN PRIMARY POWER IS INTERRUPTED, SHALL RECEIVE POWER FROM BATTERY. WIRING SHALL BE PERMANENT AND WITH-OUT A DISCONNECTING SWITCH OTHER THAN REQUIRED FOR OVERCURRENT PROTECTION.

915.2.3 GROUP E OCCUPANCIES. CARBONS MONOXIDE DETECTION SHALL BE INSTALLED IN CLASSROOMS IN GROUP E OCCUPANCIES. CARBON MONOXIDE ALARM SIGNALS SHALL BE AUTOMATICALLY TRANSMITTED TO AN ON-SITE LOCATION THAT IS STAFFED BY SCHOOL PERSONNEL.

915.3 DETECTION EQUIPMENT. CARBON MONOXIDE DETECTION REQUIRED BY SECTIONS 915.1 THROUGH 915.2.3 SHALL BE PROVIDED BY CARBON MONOXIDE DETECTION SYSTEMS COMPLYING WITH SECTION 915.5.

CARBON MONOXIDE DETECTION - SECTION 915



MOUTING ELEV

1. PROVIDE MIN 30"x48" CLR FLOOR SPACE FOR PERPENDICULAR APPROACH AT EACH LOCATION.

THE KNEE/TOE SPACE MUST EXTEND TO THE SAME

ABOVE- 25" MAX 11.B308.2.2

DEPTH AS THE ACCESSIBLE OUTLET/SWITCH LOCATED


2. THE SWITCH OR SWITCHES INSTALLED IN EMERGENCY LIGHTING CIRCUITS SHALL BE SO ARRANGED THAT ONLY AUTHORIZED PERSONNEL WILL HAVE CONTROL OF EMERGENCY LIGHTING. (CEC art. 700.20)

3. PROVIDE SPACE ON ELECTRICAL PANEL FOR LOCK-ON BREAKER, IDENTIFIED WITH RED MARKING, FOR 120 VOLTS FIRE ALARM CIRCUIT, WITH BREAKER LABELED AS FIRE ALARM CIRCUIT, CEC 760.41 (B). BREAKER AND CIRCUIT PROVIDED AND INSTALLED ON SITE BY OTHERS.

4. SMOKE AND HEAT DETECTOR CONDUIT AND DEVICES TO BE PROVIDED AND INTERCONNECTED TO THE FIRE ALARM SYSTEMS ON SITE BY OTHERS.

5. APPROVAL OF THIS PLAN DOES NOT CONSTITUTE APPROVAL OF THIS FIRE ALARM SYSTEM FOR ALL SITES. THE FIRE ALARM SYSTEM AND COMPONENTS MAYBE REQUIRED TO BE CHANGED DUE TO EXISTING CONDITIONS OR INCOMPATIBLE COMPONENTS.

ACCEPTANCE TESTS BE COMPLETED ON NEWLY INSTALLED OR REPLACEMENT OF LIGHTING CONTROLS BEFORE PROJECT COMPLETION PER THE CALIFORNIA ENERGY CODE SECTION 10-103. ACCEPTANCE TESTS MUST BE PERFORMED BY A CERTIFIED ACCEPTANCE TEST TECHNICIAN (ATT). THE ACCEPTANCE TESTING PROCEDURES MUST BE REPEATED, AND DEFICIENCES CORRECTED UNTIL THE INSTALLATION OF THE SPECIFIED SYSTEMS CONFORM AND PASS THE REQUIRED ACCEPTANCE CRITERIA. COMPLETED NRCA FORMS SHALL BE SUBMITTED TO THE PROJECT INSPECTOR AND THE DISTRICT



IN ADDITION TO THE DETAIL SHOWN ABOVE. BOND THE ELECTRICAL GROUND TO METAL UNDERGROUND WATER PIPE IN DIRECT CONTACT WITH THE EARTH FOR 10 FT. OR MORE, IF AVAILABLE (CEC 250.52)

2. TESTING FOR RESISTANCE TO GROUND, IF RESISTANCE EXCEEDS 25 OHMS INSTALL ADDITIONAL GROUND RODS SEPARATED AT LEAST 6 FEET, UNTIL RESISTANCE REDUCES TO 25 OHMS OR LESS. GROUND TEST MUST BE DONE IN THE PRESENCE OF THE PROJECT INSPECTOR AND ALL GROUNDING SHALL BE IN ACCORDANCE WITH CEC ARTICLE

3. ELEC. TRADE SHALL CHECK AREA FOR EXISTING CONDUITS, SEWER, GAS & WATER PIPING BEFORE DRIVING GROUND RODS.

4. ALL MODULES OF STEEL FRAME BLDGS. SHALL BE ELECTRICALLY BONDED TOGETHER (BOLTING ONLY IS NOT ACCEPTABLE BONDING). BONDING SHALL INCLUDE METAL RAMP & STAIRS.

5. SIZE OF CONDUCTORS SHALL COMPLY WITH CEC TABLE 250.66

6. EACH BUILDING SHALL BE GROUNDED SEPARARELY WITH A 3/4" ROUND X 8 FEET COPPERCLAD STEEL GROUND ROD. WHERE ROCK BOTOOM IS FOUND, DRIVE ROD AT 45 DEGREES MAXIMUM FROM THE VERTICAL OR HAVE IT BURIED IN A TRENCH 30" DEEP MINIMUM.

ACCEPTANCE TESTS BE COMPLETED ON NEWLY INSTALLED OR REPLACEMENT OF LIGHTING CONTROLS BEFORE PROJECT COMPLETION PER THE CALIFORNAI ENERGY CODE SECTION 10-103. ACCEPTANCE TESTS MUST BE PERFORMED BY A CERTIFIED ACCEPTANCE TEST TECHNICIAN (ATT). THE ACCEPTANCE TESTING PROCEDURES MUST BE REPEATED, AND DEFICIENCIES CORRECTED UNTIL THE INSTALLATION OF THE SPECIFIED SYSTEMS CONFORM AND PASS THE REQUIRED ACCEPTANCE CRITERIA. COMPLETED NRCA FORMS SHALL BE SUBMITTED TO THE PROJECT INSPECTOR AND THE DISTRICT.

TYPICAL GROUNDING DETAILS


REFER TO DSA IR 16-8 & STATE FIRE MARSHAL SOLAR PHOTOVOLTAIC INSTALLATION GUIDELINE

REFER TO SECTION 110.10 - MANDATORY REQUIREMENTS FOR SOLAR READY BUILDINGS SOLAR ZONE AREAS WILL VARY DEPENDING ON PC BUILDING LOCATION.

MINIMUM AREA:

15% OF ROOF AREA (EXCLUDING ANY SKYLIGHT AREA) TO BE RESERVED FOR SOLAR PANEL APPLICATION OR SOLAR READY WILL BE SUPPLIED FROM A BUILDING OR STRUCTURE WITHIN 250 FT OF PC BUILDING.

ALL SECTIONS OF THE SOLAR ZONE LOCATED ON STEEP-SLOPED ROOFS GREATER THAN 2:12 SHALL BE ORIENTED



 $D \ge 2 \times H$

ANY OBSTRUCTION, LOCATED ON THE ROOF OR ANY OTHER PART OF THE BUILDING THAT PROJECTS ABOVE THE SOLAR ZONE SHALL BE LOCATED AT A SUFFICIENT HORIZONTAL DISTANCE AWAY FROM THE SOLAR ZONE, IN ORDER TO REDUCE THE RESULTING SHADING OF THE SOLAR ZONE. FOR EACH OBSTRUCTION, THE HORIZONTAL DISTANCE ("D") FROM THE OBSTRUCTION TO THE SOLAR ZONE SHALL BE AT LEAST TWO TIMES THE HEIGHT DIFFERENCE ("H") BETWEEN THE HIGHEST POINT OF THE OBSTRUCTION AND THE HORIZONTAL PROJECTION OF THE NEAREST POINT OF THE SOLAR ZONE.

SOURCE: CALIFORNIA ENERGY COMMISSION

STRUCTURAL DESIGN LOADS:

ENTIRE ROOF SURFACE IS DESIGNED STRUCTURALLY TO ACCOMMODATE SOLAR PANELS = 3 PSF

INTERCONNECTION PATHWAYS:

THE LOCATION FOR INVERTERS AND METERING EQUIPMENT AND A PATHWAY FOR ROUTING OF CONDUIT FROM THE SOLAR ZONE TO THE POINT OF INTERCONNECTION WITH THE ELECTRICAL SERVICE WILL VARY DEPENDING ON PC BUILDING LOCATION.

SOLAR ZONE AREA

LEGEND

ELECTRICAL PANEL AT +60" AFF TO TOP OF ELECTRICAL PANEL WITH 1 1/2" DIA POWER STUB OUT

ROOF MOUNTED HVAC UNIT-SEE MECHANICAL DWGS

WALL MOUNTED HVAC UNIT, SEE MECHANICAL DWGS

100 CFM CEILING MOUNTED EXHAUST FAN. INTERLOCKED WITH LIGHT SWITCH

4SD J-BOX FOR WATER HEATER LOCATE ABOVE CEILING W/ COVER PLATE, HARD WIRE TO UNIT 4SD J-BOX IN ATTIC FOR ATTIC MOUNTED HEAT DETECTOR (DEVICE BY OTHERS). MAXIMUM 35'-0" FROM ANY POINT IN ATTIC BUT NOT MORE THAN 25'-0" FROM TWO PERPENDICULAR WALL AND 50'-0" BETWEEN THEM. PROVIDE A 6'-0" CONDUIT FROM EACH J-BOX TO HEAT DETECTOR LOCATION. CONDUIT & CONNECTION TO CEILING DEVICE & DEVICE BY OTHERS (ALARM NOTE #1)

4SD J-BOX IN ATTIC FOR CEILING MOUNTED SMOKE DETECTOR (DEVICE BY OTHERS), MAXIMUM 21'-0" FROM ANY POINT IN ROOM BUT NOT MORE THAN 15'-0" TO A PERPENDICULAR WALL AND 30'-0" BETWEEN THEM. PROVIDE A 6'-O" CONDUIT FROM EACH J-BOX TO SMOKE DETECTOR LOCATION. CONDUIT & CONNECTION TO CEILING DEVICE & DEVICE BY OTHERS (ALARM NOTE #1)

RECESSED 4SD J-BOX W/ COVER PLATE FOR FUTURE FIRE ALARM SYSTEM BY OTHERS, MOUNT AT +18" AFF U.O.N. TO CENTERLINE OF BOX AND PROVIDE 1" CO STUB TO ATTIC SPACE WITH PULLSTRING

4SD J-BOX FOR EXTERIOR FIRE ALARM HORN (DEVICE BY OTHERS). MOUNT AT +90" AFF TO TOP OF DEVICE WITH 3/4" CONDUIT STUBBED TO ATTIC WITH PULLSTRING

4SD J-BOX/SINGLE GANG MUD RING FOR FIRE ALARM STROBE (DEVICE BY OTHERS). BOTTOM OF LENS 80" MIN TOP OF LENS 96" MAX AFF WITH 3/4"CONDUIT TO EXTERIOR FIRE ALARM HORN WITH PULLSTRING

4SD J-BOX/ SINGLE GANG MUD RING FOR FIRE ALARM PULL STATION (DEVICE BY OTHERS). MOUNT AT +48" AFF TO TOP OF CONTROL BOX WITH 3/4" CONDUIT TO FIRE ALARM STROBE WITH PULLSTRING

EXIT SIGN WITH BATTERY BACK UP. EXIT SIGN REQUIRED FOR CLASSROOMS WITH TWO OR MORE EXTERIOR DOORS. FLS 90' BACK UP. CLASSROOMS WITH ONE EXTERIOR DOOR-OPTIONAL

CLOCK OUTLET AT +90" AFF TO CENTERLINE OF DEVICE EXTERIOR LED LIGHT FIXTURE. 30w MAX WITH PHOTOCELL

MOUNT AT +93" AFF ROOF MOUNTED WEATHER PROOF GFI RECEPTACLE

GROUND FAULT CIRCUIT INTERRUPT RECEPTACLE WITHIN 6'-0" OF ALL SINKS

EXTERIOR WEATHER PROOF GFI RECEPTACLE AT +24" AFF FOR A/C SERVICES (MAX 25'-0" FROM UNITS) DUPLEX (WALL MOUNTED) RECEPTACLE 15A-125V-3 WIRE.

MOUNT AT +15" AFF U.O.N. TO BOTTOM OF OUTLET BOX

3-WAY LIGHT SWITCH. MOUNT AT+48" AFF TO TOP OF SWITCH BOX

LIGHT SWITCH. MOUNT AT+48" AFF TO TOP OF SWTICH BOX

SINGLE BUTTON DIMMER SWITCH, AT +48" AFF, TO TOP OF SWITCH

BOX, WATTSTOPPER #LMDM-101 OR EQUAL

<u>SINGLE SWITCH WALL OCCUPANCY SENSOR</u> WATTSTOPPER PW-100 OR EQUAL. SENSOR TO BE

AT +44" AFF AND USE FOR OPEN ROOM (OR RESTROOM) LESS THAN 100 SQ FT W/ (1) CIRCUIT. AS NEEDED **ULTRASONIC CEILING OCCUPANCY SENSOF**

WATTSTOPPER W-500A OR EQUAL. SENSOR TO BE CONNECTED TO KEYED LIGHT SWITCHES FOR MANUAL OVERRIDE AND USE FOR RESTROOM W/ PARTITIONS.AS NEEDED

CEILING MOUNTED PHOTOCELL, WATTSTOPPER #LMLS-500 OR EQUAL AS NEEDED

CEILING MOUNTED OCCUPANCY SENSOR. WATTSTOPPER #LMPC-100 OR EQUAL. AS NEEDED

> 2x4 CEILING LIGHT WITH (3) LED PANELIGHT, LAY-IN LIGHT FIXTURE WITH DIMMABLE BALLAST DIMI LIGHTING-MODEL DM-P72448W-40K-ZZ WATTAGE: 48W (48" LG) OR EQUAL

2x4 CEILING LIGHT WITH (3) LED PANELIGHT, LAY-IN LIGHT FIXTURE WITH DIMMABLE BALLAST DIMI LIGHTING-MODEL DM-P72448W-40K-ZZ WATTAGE: 48W (48" LG) OR EQUAL EACH LIGHT FIXTURE WHICH IS INDICATED AS BEING AN EMERGENCY LIGHT SHALL HAVE A BALLAST BATTERY PACK INSTALLED ON THE FIXTURE. THE BATTERY PACK SHALL PROVIDE POWER TO A SINGLE LAMP WITHIN THE FIXTURE FOR NO LESS THAN 90 MINUTES. ANY LIGHT FIXTURE Equipped WITH A BATTERY PACK SHALL BE WIRED IN SUCH A MANNER THAT THE BATTERY WILL BE ACTIVATED IMMEDIATELY UPON LOSS OF POWER TO THE FIXTURE. ADDITIONALLY THE BATTERY PACK SHALL BE OPERATED USING BATTERY POWER LIGHTING CONTROL SWITCHES AND SENSORS SHALL NOT BE ABLE TO SHUT

NOTE: SEE 4/A3.2 FOR PHOTOMETRIC DATA 8 1" = 1'-0"
ELECTRICAL LEGEND

THE FIXTURE OFF.

INSTALLATION SHALL BE IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE (NEC) -2020 EDITION AND NATIONAL FIRE PROTECTION ASSOCIATION FIRE CODES (NFPA). AND 2022 CBC ELECTRICAL CODE.

ELECTRICAL EQUIPMENT LOCATIONS INDICATED ARE SHOWN DIAGRAMMATICALLY, EXACT LOCATION SHALL BE VERIFIED AND ADJUSTED FOR FIELD CONDITIONS.

RECEPTACLES AND TELEPHONE/DATA OUTLETS SHALL BE INSTALLED 18" AFF TO THE CENTER OF THE DEVICE. UNLESS NOTED OTHERWISE.

CONTRACTOR SHALL FIELD TEST AND PROVIDE TEST REPORT VERIFYING THAT RECEPTACLES ARE WIRED AND FUCTION PROPERLY.

CONTRACTOR SHALL LABEL EACH RECEPTACLE, LIGHT FIXTURE, TOGGLE SWITCH, SAFETY SWITCH AND OCCUPANCY SENSOR WITH PANEL NAME AND BRANCH CIRCUIT ID.

WEATHERPROOF RECEPTACLES SHALL BE TYPE TO PROTECT RECEPTACLE FROM

WEATHER WHEN PLUG INSERTED. THE MATERIAL REQUIRED FOR THE WORK SHALL BE CONTRACTOR FURNISHED AND

CONTRACTOR INSTALLED, UNLESS SPECIFICALLY NOTED OTHERWISE. CONTRACTOR SHALL ASSUME NOTES LISTING MATERIAL AND/OR EQUIPMENT BEGIN WITH THE WORDS "SUPPLY AND INSTALL" U.O.N.". CONTRACTOR SHALL VERIFY EXISTING CONDITIONS BEFORE SUBMITTING MATERIAL AND BECOME THOROUGHLY FAMILIAR WITH ACTUAL EXISTING CONDITIONS AT THE SITE. BY THE

VALID, DUE TO FAILURE TO ALLOW FOR CONDITIONS, WHICH MAY EXIST CONTRACTOR'S SCOPE SHALL INCLUDE ALL WORK SHOWN ON THE PLANS AND SPECIFICATIONS. SUBSTITUTION REQUESTS FOR EQUIPMENT SPECIFIED SHALL BE SUBMITTED FOR CONSIDERATION TO THE OWNER AND ENGINEER IN WRITING. ALL SUBSTITUTIONS MUST BE REVIEWED BY THE ENGINEER. SUCH REVIEW SHALL NOT RELIEVE THE CONTRACTOR COMPLYING WITH THE REQUIREMENTS OF THE DRAWINGS AND SPECIFICATIONS, AND THE CONTRACTOR SHALL BE RESPONSIBLE AT HIS OWN EXPENSE FOR ANY CHARGES RESULTING FROM HIS PROPOSED SUBSTITUTIONS WHICH AFFECT

ACT OF SUBMITTING PROPOSED MATERIALS FOR THE WORK, THE CONTRACTOR SHALL BE

DEEMED TO HAVE MADE SUCH STUDY AND EXAMINATION AND TO ACCEPT ALL CONDITIONS

RESENT AT THE SITE. NO REQUEST FOR ADDITIONAL PAYMENT WILL BE CONSIDERED AS

OTHER PARTS OF HIS OWN WORK, THE OWNER, ENGINEER OF RECORD, OR THE WORK OF

COORDINATE ALL WORK WITH OTHER TRADES. OBTAIN ALL DRAWINGS THAT WILL REQUIRE COORDINATION AND PROVIDE ALL ELECTRICAL CONNECTIONS REQUIRED WHETHER SHOWN ON ELECTRICAL DRAWINGS OR NOT.

UNINTERRUPTED EXISTING ELECTRICAL POWER SHALL BE MAINTAINED TO OTHER TRADES FOR TEMPORARY POWER AREAS OF THE SITE DURING CONSTRUCTION. PROVIDE ANY TEMPORARY SERVICES AS MAY BE REQUIRED. IDENTIFY AT BID TIME.

ALL PENETRATIONS IN RATED WALLS (INDICATED IN ARCHITECTURAL LIFE SAFETY PLANS), ARE TO BE INSTALLED USING THE APPROPRIATE UL RATED PENETRATION ASSEMBLIES.

EQUIPMENT SHALL BE LISTED, LABELED OR CERTIFIED FOR ITS USE BY A NATIONALLY RECOGNIZED TESTING LABORATORY (NRTL) AS RECOGNIZED BY THE U.S. DEPARTMENT OF LABOR, OCCUPATIONAL SAFETY AN HEALTH ADMINISTRATION.

14. ALL ELECTRICAL EQUIPMENT CONNECTORS SHALL BE 75° RATED.

OTHER CONTRACTORS.

ТО ВОТТОМ

OF BOX

ALL ELECTRICAL COMPONENTS SHALL BE ANCHORED AND INSTALLED PER THE DETAILS ON THE DSA APPROVED CONSTRUCTION DOCUMENTS. WHERE NO DETAIL IS INDICATED, THE FOLLOWING COMPONENTS SHALL BE ANCHORED OR BRACED TO MEET THE FORCE AND DISPLACEMENT REQUIREMENTS PRESCRIBED IN THE 2022 CBC, SECTIONS 1616A.1.18 THROUGH 1616A.1.26 AND ASCE 7-10 CHAPTER 13, 26 AND 30.

A. ALL PERMANENT EQUIPMENT AND COMPONENTS. B. TEMPORARY OR MOVABLE EQUIPMENT THAT IS PERMANENTLY ATTACHED (E.G. HARD WIRED) TO THE BUILDING UTILITY SERVICES SUCH AS ELECTRICITY, GAS OR WATER C. MOVABLE EQUIPMENT WHICH IS STATIONED IN ONE PLACE FOR MORE THAN 8 HOURS AND HEAVIER THAN 400 POUNDS ARE REQUIRED TO BE ANCHORED WITH TEMPORARY

THE ATTACHMENT OF THE FOLLOWING ELECTRICAL COMPONENTS SHALL BE POSITIVELY ATTACHED TO THE STRUCTURE, BUT NEED NOT BE DETAILED ON THE PLANS. THESE COMPONENTS SHALL HAVE FLEXIBLE CONNECTIONS PROVIDED BETWEEN THE COMPONENT AND ASSOCIATED DUCTWORK, PIPING, AND CONDUIT.

A. COMPONENTS WEIGHING LESS THAN 400 POUNDS AND HAVE A CENTER OF MASS LOCATED 4 FEET OR LESS ABOVE THE ADJACENT FLOOR OR ROOF LEVEL THAT DIRECTLY B. COMPONENTS WEIGHING LESS THAN 20 POUNDS, OR IN THE CASE OF DISTRIBUTED SYSTEMS, LESS THAN 5 POUNDS PER FOOT, WHICH ARE SUSPENDED FROM A ROOF OR

FLOOR OR HUNG FROM A WALL FOR THOSE ELEMENTS THAT DO NOT REQUIRE DETAILS ON THE APPROVED DRAWINGS, THE INSTALLATION SHALL BE SUBJECT TO THE APPROVAL OF THE STRUCTURAL ENGINEER OF RECORD AND THE DSA DISTRICT STRUCTURAL ENGINEER. THE PROJECT I NSPECTOR WILL VERIFY THAT ALL COMPONENTS AND EQUIPMENT HAVE BEEN ANCHORED IN ACCORDANCE

WITH ABOVE REQUIREMENTS. ELECTRICAL DISTRIBUTION SYSTEMS SHALL BE BRACED TO COMPLY WITH THE FORCES AND DISPLACEMENTS PRESCRIBED IN ASCE 7-10 SECTION 13.3 AS DEFINED IN ASCE 7-10 SECTION

13.6.8, 13.6.7, 13.6.5.6 AND 2022 CBC SECTIONS 1616A.1.23, 1616A.1.24, 1616A.1.25 AND THE BRACING AND ATTACHMENTS TO THE STRUCTURE SHALL BE DETAILED ON THE

APPROVED DRAWINGS OR THEY SHALL COMPLY WITH ONE OF THE OSHPD PRE-APPROVALS (OPA #) AS MODIFIED TO SATISFY ANCHORAGE REQUIREMENTS OF ACI 318, APPENDIX D.

COPIES OF THE MANUAL SHALL BE AVAILABLE ON THE JOBSITE PRIOR TO THE START OF HANGING AN BRACING OF THE PIPE, DUCTWORK AND ELECTRICAL DISTRIBUTION SYSTEMS.

THE STRUCTURAL ENGINEER OF RECORD SHALL VERIFY THE ADEQUACY OF THE STRUCTURE TO SUPPORT THE HANGER AND BRACE LOADS.

ELEC. TRADE SHALL CHECK AREA FOR EXISTING CONDUITS, SEWER, GAS & WATER PIPING BEFORE DRIVING GROUND RODS.

NON-CURRENT CARRYING METAL PARTS OF THE SYSTEM SHALL BE PROPERLY GROUNDED TO COMPLY WITH NEC REQUIREMENTS.

EACH BUILDING SHALL BE GROUNDED SEPARARELY WITH A ¾" ROUND X 8 FEET COPPERCLAD STEEL GROUND ROD. WHERE ROCK BOTOOM IS FOUND, DRIVE ROD AT 45 DEGREES MAXIMUM FROM THE VERTICAL OR HAVE IT BURIED IN A TRENCH 30" DEEP

TESTING FOR RESISTANCE TO GROUND, IF RESISTANCE EXCEEDS 25 OHMS INSTALL ADDITIONAL GROUND RODS SEPARATED AT LEAST 6 FEET, UNTIL RESISTANCE REDUCES TO 25 OHMS OR LESS. GROUND TEST MUST BE DONE IN THE PRESENCE OF THE PROJECT INSPECTOR AND ALL GROUNDING SHALL BE IN ACCORDANCE WITH CEC ARTICLE 250

PROVIDE A GREEN WIRE GROUND CONDUCTOR IN ALL CONDUITS WITH POWER OR LIGHTING CONDUCTORS.

BOND SEPARATE CONDUCTORS FROM GROUND ROD TO ELEC'L. PANEL & TO METAL BUILDING FRAME (CEC 250.52) IN ADDITION TO THE DETAIL SHOWN ABOVE. BOND THE ELECTRICAL GROUND TO METAL UNDERGROUND WATER PIPE IN DIRECT CONTACT WITH THE EARTH FOR 10 FT. OR MORE, IF AVAILABLE (CEC 250.52)

CHECK RESISTANT TO GROUND ROD. IF RESISTANCE EXCEEDS 25 OHMS. INSTALL ADDITIONAL GROUND RODS WITH CONDUCTORS AS SHOWN SEPARATED AT LEAST 6'-0" UNTIL RESISTANCE IS REDUCED TO 25 OHMS OR LESS (CEC 250.56).

ALL MODULES OF STEEL FRAME BLDGS. SHALL BE ELECTRICALLY BONDED TOGETHER (BOLTING ONLY IS NOT ACCEPTABLE BONDING). BONDING SHALL INCLUDE METAL RAMP &


SIZE OF CONDUCTORS SHALL COMPLY WITH CEC TABLE 250.66

PER CEC210.8(B) ALL RECEPTACLES AT THE FOLLOWING LOCATIONS SHALL HAVE GROUND-FAULT CIRCUIT INTERRUPTER (GFCI) - (1) BATHROOMS, (2) KITCHENS, (3) SINKS (WITHIN 6 FT), (4) INDOOR WET AREAS, (5) LOCKER ROOMS, (6) GARAGE, SERVICE BAYS OR SIMILAR, (7) ROOFTOPS, (8) OUTDOORS.

IF CLOSED BY GWB INSTALL ONE ATTIC HEAT DETECTOR PER MODULE: WHEN STANDARD OPEN WEB TRUSS SYSTEM IS USED ADDITIONAL ATTIC HEAT DETECTORS ARE NOT

ELECTRICAL GENERAL NOTES

ROJECT SPECIFIC STATE AGENCY APPROVAL **IDENTIFICATION STAMP** DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: **REVIEWED FOR** SS 🗹 FLS 🗹 ACS 🗹 12/18/2024




DESIGN ♦ CONSULTING ♦ PROJECT MG

11590 W. BERNARDO COURT, SUITE 100

SAN DIEGO, CA 92127

WWW.RSTAVARES.COM



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©

1651Juanita Street, San Jacinto, CA 92583 Voice (951) 943-1908 Fax (951)943-5768

ORIGINAL PC STATE AGENCY APPROVAL APPROVED DIV. OF THE STATE ARCHITECT APP: 04-123059 PC REVIEWED FOR SS D FLS D ACS Q CG D

Revision Schedule

Description

PRE-CHECK (PC) DOCUMENT

A separate project application for construction is required


PROJECT TITLE PC 2022 CBC: 24' x 40' **EXPANDABLE TO** 120' x 40'

ELECTRICAL GENERAL NOTES

PROJECT NUMBER 22088 CHECKED BY

DATE

FIRE ALARM MOUNTING HEIGHTS



IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR



12/18/2024

SAN DIEGO, CA 92127

WWW.RSTAVARES.COM

PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©



ORIGINAL PC STATE AGENCY APPROVAL APPROVED DIV. OF THE STATE ARCHITEC APP: 04-1230*5*9 PC SS / FLS / ACS / CG /

> **Revision Schedule** Description

PRE-CHECK (PC) DOCUMENT

Code: 2022 CBC

A separate project application for construction is required

PC 2022 CBC: 24' x 40' **EXPANDABLE TO** 120' x 40'

ELECTRICAL PLAN 36x40

| | 22088 |
|----------|--------|
| DRAWN BY | rMc/SC |

rMc/SC CHECKED BY RH/RT

| PANEL A= 100A | 120/208 VOLTS, 1 φ, 3 WIRE | | | | MAIN LUGS ONLY | | | | | |
|------------------------|----------------------------|-------|-----|-----|----------------|-----|-----|----------------------------|-----------|-----------------|
| TANLL A- TOOA | LOADCENTER RECESSED | | | | | | | GRD & NEU | TRAL BARS | AMP BUS |
| | VOL | TAMPS | | 100 | 000 | AIC | | VC | LTAMPS | |
| DESCRIPTION | φА | φВ | C/B | СКТ | ф | СКТ | C/B | φА | φВ | DESCRIPTION |
| AC WALL MOUNTED- 5 TON | 7705 | | 30 | 1 | Α | 2 | 20 | 900 | | OUTLETS |
| | | 7705 | 30 | 3 | В | 4 | 20 | | 1080 | OUTLETS |
| GENERAL LIGHTING | 1440 | | 20 | 5 | Α | 6 | 20 | 180 | | EXTERIOR GFI/WP |
| EXTERIOR LIGHTING | | 80 | 20 | 7 | В | 8 | 20 | | 180 | ROOF GFI/WP |
| DED SOLAR READY | | | | | | | | | | |
| DED SOLAR READY | | | | | | | | | | |
| | фА | φВ | | | | | | φА | φВ | |
| SUBTOTAL | 9145 | 7785 | | | | | | 1080 | 1260 | SUBTOTAL |
| TOTAL | 10225 | 9045 | | | | | - | 5/120 VOLT .21+ 1.7= 82 | _ | |

SEE ALT SHEETS

MAIN LUGS ONLY 120/208 VOLTS, 1 φ, 3 WIRE PANEL A= 100A GRD & NEUTRAL BARS AMP BUS LOADCENTER RECESSED 10000 AIC VOLTAMPS VOLTAMPS DESCRIPTION ϕ B | C/B | CKT | ϕ | CKT | C/B | ϕ A DESCRIPTION 8280 30 | 1 | A | 2 | 20 | OUTLETS AC ROOF MOUNTED- 5 TON 8280 | 30 | 3 | B | 4 | 20 1080 OUTLETS GENERAL LIGHTING 20 | 5 | A | 6 | 20 | EXTERIOR GFI/WP 1440 EXTERIOR LIGHTING 20 7 B 8 20 180 ROOF GFI/WP DED SOLAR READY DED SOLAR READY 1080 1260 8360 SUBTOTAL SUBTOTAL 10800/120 VOLTS= 90 10800 9620 90 + 1.15= 9115 TOTAL

LEGEND

ELECTRICAL PANEL AT +60" AFF TO TOP OF ELECTRICAL PANEL WITH 1 1/2" DIA POWER STUB OUT

ROOF MOUNTED HVAC UNIT-SEE MECHANICAL DWGS

WALL MOUNTED HVAC UNIT, SEE MECHANICAL DWGS

IN IN

100 CFM CEILING MOUNTED EXHAUST FAN.
INTERLOCKED WITH LIGHT SWITCH

HM)

4SD J-BOX FOR WATER HEATER LOCATE ABOVE CEILING W/ COVER PLATE, HARD WIRE TO UNIT 4SD J-BOX IN ATTIC FOR ATTIC MOUNTED HEAT DETECTOR (DEVICE BY OTHERS). MAXIMUM 35'-0" FROM ANY POINT IN ATTIC BUT NOT MORE THAN 25'-0" FROM TWO PERPENDICULAR WALL AND 50'-0" BETWEEN THEM. PROVIDE A 6'-0" CONDUIT FROM EACH J-BOX TO HEAT DETECTOR LOCATION. CONDUIT & CONNECTION TO CEILING DEVICE & DEVICE BY OTHERS (ALARM NOTE #1)

4SD J-BOX IN ATTIC FOR CEILING MOUNTED SMOKE
DETECTOR (DEVICE BY OTHERS). MAXIMUM 21'-0" FROM ANY
POINT IN ROOM BUT NOT MORE THAN 15'-0" TO A PERPENDICULAR
WALL AND 30'-0" BETWEEN THEM. PROVIDE A 6'-O"
CONDUIT FROM EACH J-BOX TO SMOKE DETECTOR
LOCATION. CONDUIT & CONNECTION TO CEILING DEVICE &
DEVICE BY OTHERS (ALARM NOTE #1)

RECESSED 4SD J-BOX W/ COVER PLATE FOR FUTURE FIRE ALARM SYSTEM BY OTHERS. MOUNT AT +18" AFF U.O.N. TO CENTERLINE OF BOX AND PROVIDE 1" CO STUB TO ATTIC SPACE WITH PULLSTRING

4SD J-BOX FOR EXTERIOR FIRE ALARM HORN (DEVICE BY OTHERS). MOUNT AT +90" AFF TO TOP OF DEVICE WITH 3/4" CONDUIT STUBBED TO ATTIC WITH PULLSTRING

4SD J-BOX/SINGLE GANG MUD RING FOR FIRE ALARM STROBE (DEVICE BY OTHERS).
BOTTOM OF LENS 80" MIN TOP OF LENS 96" MAX AFF WITH 3/4"CONDUIT TO EXTERIOR FIRE ALARM HORN WITH PULLSTRING

4SD J-BOX/ SINGLE GANG MUD RING FOR FIRE ALARM PULL STATION (DEVICE BY OTHERS). MOUNT AT +48" AFF TO TOP OF CONTROL BOX WITH 3/4" CONDUIT TO FIRE ALARM STROBE WITH PULLSTRING

EXIT SIGN WITH BATTERY BACK UP. EXIT SIGN REQUIRED FOR CLASSROOMS WITH TWO OR MORE EXTERIOR DOORS. FLS 90' BACK UP. CLASSROOMS WITH ONE EXTERIOR DOOR-OPTIONAL.

CLOCK OUTLET AT +90" AFF TO CENTERLINE OF DEVICE

EXTERIOR LED LIGHT FIXTURE. 30w MAX WITH PHOTOCELL

MOUNT AT +93" AFF

ROOF ROOF MOUNTED WEATHER PROOF GFI RECEPTACLE

GROUND FAULT CIRCUIT INTERRUPT RECEPTACLE WITHIN 6'-0" OF ALL SINKS

EXTERIOR WEATHER PROOF GFI RECEPTACLE AT +24" AFF FOR A/C SERVICES (MAX 25'-0" FROM UNITS)

MOUNT AT +15" AFF U.O.N. TO BOTTOM OF OUTLET BOX

3-WAY LIGHT SWITCH. MOUNT AT+48" AFF TO TOP OF SWITCH BOX

DUPLEX (WALL MOUNTED) RECEPTACLE 15A-125V-3 WIRE.

\$ LIGHT SWITCH. MOUNT AT+48" AFF TO TOP OF SWTICH BOX

\$ SINGLE BUTTON DIMMER SWITCH, AT +48" AFF, TO TOP OF SWITCH BOX, WATTSTOPPER #LMDM-101 OR EQUAL


WS-1

SINGLE SWITCH WALL OCCUPANCY SENSOR.
WATTSTOPPER PW-100 OR EQUAL. SENSOR TO BE
MOUNTED
AT +44" AFF AND USE FOR OPEN ROOM (OR RESTROOM)
LESS THAN 100 SQ FT W/ (1) CIRCUIT.


ULTRASONIC CEILING OCCUPANCY SENSOR.
WATTSTOPPER W-500A OR EQUAL. SENSOR TO BE
CONNECTED TO KEYED LIGHT SWITCHES FOR MANUAL
OVERRIDE AND USE FOR RESTROOM W/ PARTITIONS.

PC CEILING MOUNTED PHOTOCELL, WATTSTOPPER #LMLS-500 OR EQUAL

OS CEILING MOUNTED OCCUPANCY SENSOR. WATTSTOPPER #LMPC-100 OR EQUAL.



2x4 CEILING LIGHT WITH (3) LED PANELIGHT, LAY-IN LIGHT FIXTURE WITH DIMMABLE BALLAST DIMI LIGHTING-MODEL DM-P72448W-40K-ZZ WATTAGE: 48W (48" LG) OR EQUAL




2x4 CEILING LIGHT WITH (3) LED PANELIGHT, LAY-IN LIGHT FIXTURE WITH DIMMABLE BALLAST DIMI LIGHTING-MODEL DM-P72448W-40K-ZZ WATTAGE: 48W (48" LG) OR EQUAL EACH LIGHT FIXTURE WHICH IS INDICATED AS BEING AN EMERGENCY LIGHT SHALL HAVE A BALLAST BATTERY PACK INSTALLED ON THE FIXTURE. THE BATTERY PACK SHALL PROVIDE POWER TO A SINGLE LAMP WITHIN THE FIXTURE FOR NO LESS THAN 90 MINUTES. ANY LIGHT FIXTURE Equipped WITH A BATTERY PACK SHALL BE WIRED IN SUCH A MANNER THAT THE BATTERY WILL BE ACTIVATED IMMEDIATELY UPON LOSS OF POWER TO THE FIXTURE. ADDITIONALLY THE BATTERY PACK SHALL BE OPERATED USING BATTERY POWER LIGHTING CONTROL SWITCHES AND SENSORS SHALL NOT BE ABLE TO SHUT THE FIXTURE OFF.

NOTE: SEE 4/A3.2 FOR PHOTOMETRIC DATA

IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT
APP: 02-122764 INC:
REVIEWED FOR
SS FLS ACS D
DATE: 12/18/2024





THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©

CLILINI

TO BOTTOM

OF BOX



ORIGINAL PC STATE AGENCY APPROVAL



Revision Schedule

Description

PRE-CHECK (PC) DOCUMENT

Code: 2022 CBC

A separate project application for construction is required

PROJECT TITLE
PC 2022 CBC: 24' x 40'
EXPANDABLE TO
120' x 40'

ELECTRICAL

SCHEDULE 36x40

22088

PROJECT NUMBER

rMc/SC

RH/RT


DATE

ET NO.

SHEET OF

3 1" = 1'-0" ELECTRICAL PANEL_ROOF MOUNTED

ELECTRICAL PANEL WALL MOUNTED



SYSTEMS CONFORM AND PASS THE REQUIRED ACCEPTANCE CRITERIA. COMPLETED NRCA FORMS SHALL BE SUBMITTED TO THE PROJECT

PFG SCHED (RETURN)

STANDARD OPTION #I WM-1 WM-1 NOMINAL TONNAGE 3.0 TONS 4.0 TONS MANUFACTURER **BARD **BARD MODEL# W36HB-A W48HC-A 1150 STATIC PRESSURE 0.15 MIN OSA 365 548 DIRECT DIRECT 20.4 MOCP VOLTAGE 208/230-1 208/230-1 WIRE SIZE (PWR/GRND) #6/#10 #6/#10 DESIGN RETURN AIR (DB/WB) 80/67 SENSIBLE COOLING @ 95° F (PART/FULL) 24.00/28.00 25.900/36.00 TOTAL COOLING @ 95° F (PART/FULL) 32.00/36.00 34.000/45.500 HEATING CAP. BTUH @ 47° F (PART/FULL) | 29.200/32.200 29.200/41.500 HEATING CAP. BTUH @ 17° F 20.000 26.000

10.6 EER and 11 EER

SINGLE PACKAGE VERTICAL HEAT PUMP SCHEDULE

380#

11.10

3.30

550#

11.00

2.00

14 SEER SINGLE PACKAGE ROOF TOP HEAT PUMP SCHEDULE STANDARD OP∕TION #I NOMINAL TONNA 3.0 TONS 4 TONS **MANUFACTURER** **CARRIER **CARRIER MODEL# 50VTC48 50VTC48 1200 1500 STATIC PRESSURE 0.4 MIN OSA 548 DRIVE BELT MOCP 74 **VOLTAGE** 208)230-1 208/230-1 WIRE SIZE (PWR/GRND) #4/#8 #6/#10 DESIGN RETURN AIR (DB/WB 80/67 SENSIBLE COOLING @ 195° F 30.500 35.260 TOTAL COOLING @ 9/5° 35.600 49.600 HEATING CAP. BTMH @ 47° F 35.500 45.5000 HEATING CAP. BYTUH @ 17° F 18.400 OPERATING WEIGHT 572# SEER 14.00 14.00 **HSPF** 3.4 COP/@ 17° F 2.3 2.4

Indicate NA for all non-applicable boxes.

LIST OF MECHANICAL EQUIPMENT

Any substitutions of equipment made to the approved PC must be equal or better than the equipment listed below.

Modular size and equipment type

| Responsible for programmy commissioning programmy continues and Model Equipment III of Plans
| HVAC Equipment III of Plans
| HV

This attachment summarizes all the HVAC equipment and controls required for each size modular building.

ATTACHMENT 3: Mechanical Equipment List

if DDC to the zone § 120.2(h

| HVAC SCHEDULE | | | | | | | |
|---------------|--------------|-------------------|---------------|--|--|--|--|
| # OF HVAC | | | | | | | |
| BU | JILDING SIZE | 3 1/2 TON HVAC | 4 TON HVAC | | | | |
| | 24' x 40' | 1 | | | | | |
| × | 36' x 40' | | 1 | | | | |
| | 48' x 40' | 2 | | | | | |
| | 60' x 40' | | 2 | | | | |
| | 72' x 40' | 3 | | | | | |
| | 84' x 40' | | 3 | | | | |
| | 96' x 40' | 4 | | | | | |
| | 108' x 40' | | 4 | | | | |
| | 120' x 40' | 5 | | | | | |

MERV 13 AND 2-INCH DEPTH PER ENERGY CODE 120.1(C)1. FILTERS REQ'D FOR ALL UNITS

HVAC NOTES

1. SET BACK THERMOSTAT SHALL BE PROVIDED

SHOWN MAY NOT BE USED.

MINIMUM OUTSIDE AIR 15 CFM PER OCCUPANT AND THE UNIT SHALL UTILIZE DEMAND CONTROL VENTILATION
 MODEL NUMBERS FOR HEAT PUMP UNITS WITH OPTIONAL 5.0 AUXILIARY HEAT STRIPS, WHEN THE HEAT STRIP IS NOT USED, THE MCA AND MOCP MUST BE VERIFIED AND HEAT STRIPS LARGER THAN THE SIZES

120.1(D)
THERMOSTAT SHALL BE PROGRAMED WITH EXPECTED OCCUPIED
TIMES.AIR HANDLER FAN WILL BE PROGRAMED TO RUN DURING ALL
OCCUPIED TIMES.PRE-OCCUPANCY PURGE SHALL BE PROGRAMED ONE
HOUR PRIOR TO THE MODULAR BUILDING BEING NORMALLY OCCUPIED.

FOR ROOF MOUNTED HVAC UNITS A GASKET SHALL BE PLACED BETWEEN THE CURB AND THE HVAC UNIT.MASTIC SEALANT SHALL BE USED TO SEAL ALL SEAMS BETWEEN THE HVAC UNIT AND THE CURB. THE SUPPLY AND RETURN DUCTS SHALL BE ATTACHED TO THE CURB AND MASTIC SHALL BE USED TO SEAL THE DUCTS TO THE CURB. THE SUPPLY AND RETURN DUCTS SHALL BE THE SAME SIZE AND ALIGN WITH THE HVAC UNIT.

FLEXIBLE AIR DUCTS AND CONNECTORS SHALL BE NOT MORE THAN 5 FEET IN LENGTH AND SHALL NOT BE USED IN LIEU OF RIGID ELBOWS OR FITTINGS. FLEXIBLE AIR DUCTS SHALL BE PERMITTED TO BE USED AS AN ELBOW AT A TERMINAL DEVICE PER ENERGY CODE 120.4.

DUCT INSTALLATION AND PLENUMS SHALL MEET THE REQUIREMENTS OF ENERGY CODE SECTION 120.4 AND THE MANUFACTURERS INSTALLATION INSTRUCTIONS.
HORIZONTAL FLEX DUCT SHALL BE SUPPORTED AT A MAXIMUM 4 FT INTERVALS, WITH HANGING STRAPS A MINIMUM 1 1/2 IN. WIDE. DUCTS MUST BE PULLED TIGHT WITH A MAXIMUM SAG OF ½" PER FOOT OF HORIZONTAL RUN.

BEND/RADIUS EQUAL TO THE DUCT DIAMETER OR GREATER.

DUCT SHALL NOT BE KINKED OR CRUSHED.

10 | 1" = 1'-0" | ELEV. @ WORKSTATION

SECTION 915 CARBON MONOXIDE DETECTION

915.2.3 Group E occupancies. Carbon monoxide detection shall be installed in classrooms in Group E occupancies. Carbon monoxide alarm signals shall be automatically transmitted to an on-site location that is staffed byschool personnel.

915.3 Detection equipment. Carbon monoxide detection required by Sections 915.1 through 915.2.3 shall be provided by carbon monoxide alarms complying with Section 915.4 or carbon monoxide detection systems complying with Section 915.5.

CFC 915.1 - Classrooms which contain a fuel-burning appliance or a fuel-burning fireplace or are supplied by a forced-air furnace shall be provided with a carbon monoxide detexction system. Provide a carbon monoxide detection system

GENERAL NOTE:
UTLILITIES THAT SPAN BETWEEN UNITS OR ACROSS SEISMIC SEPARATION
JOINTS MUST BE DESIGNED WITH A FLEXIBLE CONNECTION THAT CAN
ACCOMMODATE DIFFERENTIAL MOVEMENTS

IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT

APP: 02-122764 INC:

REVIEWED FOR
SS FLS ACS D

DATE: 12/18/2024



PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©

CLIENT



APPROVED
DIV. OF THE STATE ARCHITECT

APP: 04-123059 PC

REVIEWED FOR
SS PLS ACS CG

Revision Schedule

Description

PRE-CHECK (PC) DOCUMENT

Code: 2022 CBC

A separate project application for construction is required

PROJECT TITLE
PC 2022 CBC: 24' x 40'
EXPANDABLE TO
120' x 40'

MISCELLANEOUS
NOTES & DETAILS

PROJECT NUMBER
22088

DRAWN BY rMc/SC

DATE

SHEET NO.

SHEET OF

M0.1

RH/RT

—20" max.

THERMOSTAT SHALL BE PROGRAMED WITH EXPECTED OCCUPIED TIMES.AIR HANDLER FAN WILL BE PROGRAMED TO RUN DURING ALL OCCUPIED TIMES.PRE-OCCUPANCY PURGE SHALL BE PROGRAMED ONE HOUR PRIOR TO THE MODULAR BUILDING BEING NORMALLY OCCUPIED.

FOR ROOF MOUNTED HVAC UNITS A GASKET SHALL BE PLACED BETWEEN THE CURB AND THE HVAC UNIT.MASTIC SEALANT SHALL BE USED TO SEAL ALL SEAMS BETWEEN THE HVAC UNIT AND THE CURB. THE SUPPLY AND RETURN DUCTS SHALL BE ATTACHED TO THE CURB AND MASTIC SHALL BE USED TO SEAL THE DUCTS TO THE CURB. THE SUPPLY AND RETURN DUCTS SHALL BE THE SAME SIZE AND ALIGN WITH THE HVAC UNIT.

FLEXIBLE AIR DUCTS AND CONNECTORS SHALL BE NOT MORE THAN 5 FEET IN LENGTH AND SHALL NOT BE USED IN LIEU OF RIGID ELBOWS OR FITTINGS. FLEXIBLE AIR DUCTS SHALL BE PERMITTED TO BE USED AS AN ELBOW AT A TERMINAL DEVICE PER ENERGY

DUCT INSTALLATION AND PLENUMS SHALL MEET THE REQUIREMENTS OF ENERGY CODE SECTION 120.4 AND THE MANUFACTURERS INSTALLATION INSTRUCTIONS. HORIZONTAL FLEX DUCT SHALL BE SUPPORTED AT A MAXIMUM 4 FT

INTERVALS, WITH HANGING STRAPS A MINIMUM 1 1/2 IN. WIDE. DUCTS MUST BE PULLED TIGHT WITH A MAXIMUM SAG OF 1/2" PER FOOT OF HORIZONTAL RUN. DUCT SHALL NOT BE KINKED OR CRUSHED.

BEND/RADIUS EQUAL TO THE DUCT DIAMETER OR GREATER.

UPON SITE PLACEMENT OR SITE CONSTRUCTION, THE **OPERATION AND MAINTENANCE** DOCUMENTATION FOR ALL MECHANICAL AND LIGHTING SYSTEMS AND CONTROLS SHALL

BE PROVIDED BY THE MODULAR BUILDING MANUFACTURER, OR THE GENERAL CONTRACTOR FOR THE PERMANENT MODULAR RELOCATABLE BUILDING AND DELIVERED TO THE OWNER.

AT THE TIME OF ROUGH INSTALLATION, DURING IN THE FACTORY OR ON THE CONSTRUCTION SITE, DURING SHIPMENT (IF APPLICABLE) AND UNTIL FINAL STARTUP OF THE HEATING COOLING AND VENTILATING EQUIPMENT, ALL DUCT AND OTHER RELATED

DISTRIBUTION COMPONENT OPENINGS SHALL BE PROCTED TO REDUCE THE AMOUNT OF DUST, WATER AND DEBRIS WHICH MAY ENTER THE SYSTEM

1/4" = 1'-0" **MECHANICAL NOTES**

TABLE 140.4-E AIR ECONOMIZER HIGH LIMIT SHUT OFF CONTROL REQUIREMENTS

| | Climate | Required High Lin | equired High Limit (Economizer Off When): | | | |
|--|----------------|--|--|--|--|--|
| Device Type ^a | Zones | Equation ^b | Description | | | |
| | 1, 3, 5, 11-16 | T _{OA} > 75°F | Outdoor air temperature exceeds 75°F | | | |
| Fixed Day Bulb | 2, 4, 10 | T _{OA} > 73°F | Outdoor air temperature exceeds 73°F | | | |
| Fixed Dry Bulb | 6, 8, 9 | T _{OA} > 71°F | Outdoor air temperature exceeds 71°F | | | |
| | 7 | T _{OA} > 69°F | Outdoor air temperature exceeds 69°F | | | |
| | 1, 3, 5, 11-16 | T _{OA} > T _{RA} °F | Outdoor air temperature exceeds return air temperature | | | |
| Differential Dry | 2, 4, 10 | T _{OA} > T _{RA} -2°F | Outdoor air temperature exceeds return air temperature minus 2°F | | | |
| Bulb | 6, 8, 9 | T _{OA} > T _{RA} -4°F | Outdoor air temperature exceeds return air temperature minus 4°F | | | |
| | 7 | T _{OA} > T _{RA} -6°F | Outdoor air temperature exceeds return air temperature minus 6°F | | | |
| Fixed Enthalpy ^C + Fixed Drybulb | All | h _{OA} > 28 Btu/lb ^C or T _{OA} > 75°F | Outdoor air enthalpy exceeds 28 Btu/lb of dry air ^C or Outdoor air temperature exceeds 75°F | | | |

Only the high limit control devices listed are allowed to be used and at the setpoints listed. Others such as Dew Point, Fixed Enthalpy, Electronic Enthalpy, and Differential Enthalpy Controls, may not be used in any Climate Zone for compliance with Section 140.4(e)1 unless approval for use is provided by the Energy Commission

Devices with selectable (rather than adjustable) setpoints shall be capable of being set to within 2°F and 2 Btu/lb At altitudes substantially different than sea level, the Fixed Enthalpy limit value shall be set to the enthalpy value t 75°F and 50% relative humidity. As an example, at approximately 6,000 foot elevation, the fixed enthalpy limit is oproximately 30.7 Btu/lb.

ALL ECONOMIZERS MUST BE PROGRAMMED IN THE FIELD BY THE HVAC CONTRACTOR TO THE TEMPERATURE IN TABLE 140.4-E

PER TITLE

| | | DSA Application Calculation Date/Time of End | | | | |
|--------------------------------|--|---|---|---|--|----------|
| | | Model Name and Option: 24 | | | | |
| | | Total Floor A HVAC System Type: | | | | |
| | | TIVAC System Type. | Wall Woulded Ay C | | | |
| Climata Zana 14 | (Delm dele) | 1 | | | | I |
| Climate Zone 14 | (Paimdale) | | | | | |
| Azimuth (Front Orientation) | | Standard Design | Proposed Design | Margin | Margin % | Worst 0 |
| 200 | TDV-E | 366.40 | 297.14 | 69.26 | 18.9028% | |
| 30° | TDV-T SOURCE | 366.40 36.24 | 297.14 30.65 | 69.26 5.59 | 18.9028% 15.4249% | |
| | TDV-E | 358.72 | 295.30 | 63.42 | 17.6795% | ** |
| 75° | TDV-T | 358.72 | 295.30 | 63.42 | 17.6795% | ** |
| | SOURCE | 35.63 | 30.56 | 5.07 | 14.2296% | ** |
| | TDV-E | 363.47 | 296.43 | 67.04 | 18.4444% | |
| 120° | TDV-T | 363.47 | 296.43 | 67.04 | 18.4444% | |
| | SOURCE | 36.01 | 30.64 | 5.37 | 14.9125% | |
| | TDV-E | 366.46 | 297.42 | 69.04 | 18.8397% | |
| 165° | TDV-T | 366.46 | 297.42 | 69.04 | 18.8397% | |
| | SOURCE | 36.22 | 30.64 | 5.58 | 15.4059% | |
| | TDV-E | 366.40 | 297.14 | 69.26 | 18.9028% | |
| 210° | TDV-T | 366.40 | 297.14 | 69.26 | 18.9028% | |
| | SOURCE | 36.24 | 30.65 | 5.59 | 15.4249% | ** |
| 255° | TDV-E | 358.72 | 295.30 | 63.42 | 17.6795% | ** |
| 233 | TDV-T SOURCE | 358.72 35.63 | 295.30 30.56 | 63.42 5.07 | 17.6795% 14.2296% | ** |
| | TDV-E | 363.47 | 30.56 296.44 | 67.03 | 14.2296% 18.4417% | - |
| 300° | TDV-E | 363.47 | 296.44 | 67.03 | 18.4417% | 1 |
| | SOURCE | 36.01 | 30.64 | 5.37 | 14.9125% | |
| | TDV-E | 366.46 | 297.42 | 69.04 | 18.8397% | |
| 345° | TDV-T | 366.46 | 297.42 | 69.04 | 18.8397% | |
| | SOURCE | 36.22 | 30.64 | 5.58 | 15.4059% | |
| | | | | | | |
| Climate Zone 15 (| Palm Springs) | | | | | |
| Azimuth (Front Orientation) | | Standard Design | Proposed Design | Margin | Margin % | Worst (|
| | TDV-E | 378.51 | 303.65 | 74.86 | 19.7775% | |
| 30° | TDV-T | 378.51 | 303.65 | 74.86 | 19.7775% | |
| | SOURCE | 33.26 | 26.66 | 6.60 | 19.8437% | |
| | TDV-E | 369.92 | 301.77 | 68.15 | 18.4229% | ** |
| 75° | TDV-T | 369.92 | 301.77 | 68.15 | 18.4229% | ** |
| | SOURCE | 32.57 | 26.55 | 6.02 | 18.4833% | ** |
| _ | TDV-E | 370.43 | 302.74 | 67.69 | 18.2734% | |
| 120° | TDV-T | 370.43 | 302.74 | 67.69 | 18.2734% | |
| | SOURCE | 32.71 | 26.64 | 6.07 | 18.5570% | |
| 165° | TDV-E TDV-T | 378.42 378.42 | 303.43 303.43 | 74.99 74.99 | 19.8166% 19.8166% | |
| - IOS | SOURCE | 33.23 | 26.65 | 6.58 | 19.8014% | |
| | TDV-E | 378.51 | 303.65 | 74.86 | 19.7775% | |
| 210° | TDV-T | 378.51 | 303.65 | 74.86 | 19.7775% | |
| | SOURCE | 33.26 | 26.66 | 6.60 | 19.8437% | |
| | TDV-E | 369.92 | 301.77 | 68.15 | 18.4229% | ** |
| 255° | TDV-T | 369.92 | 301.77 | 68.15 | 18.4229% | ** |
| | SOURCE | 32.57 | 26.55 | 6.02 | 18.4833% | ** |
| | TDV-E | 370.43 | 302.74 | 67.69 | 18.2734% | |
| 300° | TDV-T | 370.43 | 302.74 | 67.69 | 18.2734% | |
| | SOURCE | 32.71 | 26.64 | 6.07 | 18.5570% | |
| 2.4=2 | TDV-E | 378.42 | 303.43 | 74.99 | 19.8166% | |
| 345° | TDV-T | 378.42 | 303.43 | 74.99 | 19.8166% | |
| | SOURCE | 33.23 | 26.65 | 6.58 | 19.8014% | |
| Climate Zone 16 (| Blue Canyon) | | | | | |
| Azimuth | :,=, | a | | | | l |
| (Front Orientation) | | Standard Design | Proposed Design | Margin | Margin % | Worst C |
| - ' | TDV-E | 307.24 | 278.52 | 28.72 | 9.3477% | ** |
| 30° | TDV-T | 307.24 | 278.52 | 28.72 | 9.3477% | |
| | SOURCE | 54.83 | 41.05 | 13.78 | | ** |
| + | TDV-E | 341.77 | 272.69 | 69.08 | 20.2124% | 1 |
| 75° | TDV-T | 341.77 | 272.69 | 69.08 | 20.2124% | 1 |
| | SOURCE | 65.39 | 40.97 | 24.42 | 37.3452% | |
| | TDV-E | 307.35 | 273.40 | 33.95 | 11.0460% | 1 |
| 1200 | | | | | | 1 |
| 120° | TDV-T SOURCE | 307.35 | 273.40 | 33.95 | 11.0460% | - |
| 120 | SCHUDCE | 54.88 | 41.01 | 13.87 | 25.2733% | |
| 120 | | | 273.26 | 35.76 | 11.5721% | |
| | TDV-E | 309.02 | | | | |
| 165° | TDV-E TDV-T | 309.02 | 273.26 | 35.76 | 11.5721% | |
| | TDV-E TDV-T SOURCE | 309.02 54.91 | 41.02 | 13.89 | 25.2959% | |
| 165° | TDV-E TDV-T SOURCE TDV-E | 309.02 54.91 307.24 | 41.02 273.52 | 13.89 33.72 | 25.2959% 10.9751% | |
| | TDV-E TDV-T SOURCE TDV-E TDV-T | 309.02 54.91 | 41.02 | 13.89 33.72 33.72 | 25.2959% | |
| 165° | TDV-E TDV-T SOURCE TDV-E | 309.02 54.91 307.24 | 41.02 273.52 | 13.89 33.72 | 25.2959% 10.9751% | |
| 165° | TDV-E TDV-T SOURCE TDV-E TDV-T | 309.02 54.91 307.24 307.24 | 41.02 273.52 273.52 | 13.89 33.72 33.72 | 25.2959% 10.9751% 10.9751% | |
| 165° | TDV-E TDV-T SOURCE TDV-E TDV-T SOURCE | 309.02 54.91 307.24 307.24 54.83 | 41.02 273.52 273.52 41.05 | 13.89 33.72 33.72 13.78 | 25.2959% 10.9751% 10.9751% 25.1322% | |
| 165° | TDV-E TDV-T SOURCE TDV-E TDV-T SOURCE TDV-E | 309.02 54.91 307.24 307.24 54.83 341.77 | 41.02 273.52 273.52 41.05 272.69 | 13.89 33.72 33.72 13.78 69.08 | 25.2959% 10.9751% 10.9751% 25.1322% 20.2124% | |
| 165° | TDV-E TDV-T SOURCE TDV-E TDV-T SOURCE TDV-E TDV-T SOURCE TDV-E TDV-T | 309.02 54.91 307.24 307.24 54.83 341.77 | 41.02 273.52 273.52 41.05 272.69 272.69 | 13.89 33.72 33.72 13.78 69.08 69.08 | 25.2959% 10.9751% 10.9751% 25.1322% 20.2124% 20.2124% | |
| 165° | TDV-E TDV-T SOURCE TDV-E TDV-T SOURCE TDV-C TDV-E TDV-E TDV-E | 309.02 54.91 307.24 307.24 54.83 341.77 65.39 | 41.02 273.52 273.52 41.05 272.69 272.69 40.97 | 13.89 33.72 33.72 13.78 69.08 69.08 24.42 | 25.2959% 10.9751% 10.9751% 25.1322% 20.2124% 20.2124% 37.3452% | |

ATTACHMENT 3: Mechanical Equipment List

Indicate NA for all non-applicable boxes

This attachment summarizes all the HVAC equipment and controls required for each size modular building.

| LIST OF MECHANICAL EQUIPMENT | | | | | | | | | |
|--|------------------------------|------------------------------|------------------------------|---|--|--|--|--|--|
| Any substitutions of equipment made to the approved PC must be equal or better than the equipment listed below | | | | | | | | | |
| Modular size and equipment type | 4.0 TON WM HVAC | WM HVAC WM HVAC pr | | Responsible for programing/commissioning (builder or HVAC contractor) | | | | | |
| HVAC Equipment Make and Model | BARD W46HC-A | BARD W60H1 | BARD W36 HB | NA | | | | | |
| BTUH Heating Cooling | 41,500 45,500 | 51,000 55,500 | 38,500 40,000 | NA | | | | | |
| Indoor/Blower Fan BHP/HP CFM @ at ? inch WC | 1/3-825-2 2.5 24"-2900 | 1/3-825-2 4.1 24"-3700 | 1/3-825-2 2.5 24"-2900 | NA | | | | | |
| Strip Heating Maximum allowed or Not Allowed if not modeled | PER TITLE 24 | PER TITLE 24 | PER TITLE 24 | NA | | | | | |
| Minimum allowed SEER, EER, HSPF and/or COP, and Phase | 14, 11, 3.40, 3 | 14, 11, 3.30 ,3 | 14, 11, 3.40, 3 | NA | | | | | |

Cooling Indoor/B BHP/HP CFM @ at ? in Strip Hea Maximu Allowed i Minimun HSPF and/ Thermostat (Responsible Person) #8403-061 #8403-061 #8403-061 Make and Model Required Acceptance Test Setback – § 110.2(c) NRCA-MCH-03-A C48H1 C60H1 C42H1 Heat Pumps - § 110.2(b) Shut-off and Reset Responsible Person) STANDARD STANDARD **STANDARD** Make and Model Required Acceptance Test BUILT-IN BUILT-IN BUILT-IN NRCA-MCH-03-A Occupancy Sensor or 4 hr override – § 120.2(e) Economizer Responsible Person) ECON-NC5 ECON-NC5 ECON-NC5 Required Acceptance Test Equipment NRCA-MCH-02-A and 05-A Make and Model – § 140.4(e) Economizer Responsible Person) ECON-WD5 ECON-WD5 ECON-WD5 Required Acceptance Test Make and Model - § 140.4(e) NRCA-MCH-02-A and 05-A Responsible Person) ECON-DB5 Required Acceptance Test ECON-DB5 ECON-DB5 Fault Detection Software Make and Model - § 120.2(i) NRCA-MCH-12-A or 13-A Outside Air (Responsible Person) PER TITLE PER TITLE PER TITLE Required Acceptance Test In CFM - § 120.1(c)3 NRCA-MCH-02-A Responsible Person) Ventilation Kit N/A N/A If economizer is not installed Required Acceptance Test specify Make and Model. NRCA-MCH-02-A **Demand Control Ventilation** (esponsible Person PER BARD PER BARD PER BARD Required Acceptance Test Co2 Sensor with ppm display SPECIFICAIONS SPECIFICAIONS SPECIFICAIONS NRCA-MCH-06-A Make and Model - §120.1(d)4

Responsible Person)

(Responsible Person)

NRCA-MCH-02-A

NRCA-MCH-11-A

Required Acceptance Test

Required Acceptance Test

NOTE: SEE M0.1 AND CUT SHEETS FOR ADDITIONAL EQUIPMENT OPTIONS

Minimum Designed Outside Air in

CFM - § 120.1(c)3

Make Model

Demand Shed Thermostat

If DDC to the zone § 120.2(h)

HVAC @ WALL SECTION

SEQUENCE OF OPERATIONS

BARD W48HC-A

Sequence of Operation

Circuit R-Y1 makes at thermostat pulling in compressor contactor, starting the compressor and outdoor motor. (See *NOTE* under **Condenser Fan Operation** concerning models equipped with low ambient control.) The G (indoor motor) circuit is automatically completed by the thermostat on any call for cooling operation or can be energized by manual fan switch on subbase for constant air circulation. On a call for 2nd stage heating, circuit R-W2 makes at the thermostat pulling in heat contactor for the strip heat and blower operation. On a call for third stage heat, R-W3 makes

Heating A 24V solenoid coil on reversing valve controls heating cycle operation. Two thermostat options, one allowing "Auto" changeover from cycle to cycle and the other constantly energizing solenoid coil during heating season—thus eliminating pressure equalization noise

except during defrost, are to be used.

bringing on second heat contactor, if so equipped.

On "Auto" option, a circuit is completed from R-B/W1 and R-Y1 on each heating "on" cycle, energizing reversing valve solenoid and pulling in compressor contactor, starting compressor and outdoor motor. R-G also make starting indoor blower motor. Heat pump heating cycle now in operation.

The second option has no "Auto" changeover position, but instead energizes the reversing valve solenoid constantly whenever the system switch on subbase is placed in "Heat" position, the "B" terminal being constantly energized from R. A thermostat demand for heat completes R-Y1 circuit, pulling in compressor contactor starting compressor and outdoor motor. R-G also make starting indoor blower motor.

On a call for 2nd stage heating, circuit R-W2 makes at the thermostat pulling in the heat contactor for the strip heat and blower operation. On a call for third stage heat, R-B/W1 breaks, dropping out heat pump, and R-W3 makes, bringing on second heat contactor, if so equipped.

Balanced Climate™ Mode

Balanced Climate™ is a great comfort feature that can easily be applied under any normal circumstances. If the Bard air conditioning system is being set up in a typical environment where 72°F is the lowest cooling setpoint, remove the Y1/Y2 jumper and install a 2-stage cooling thermostat. This will increase the humidity removal up to 35% and provide a much more comfortable environment. This mode will also increase the supply temperature when in heating mode. When Balanced Climate mode is activated, it is employed in both heating and cooling modes.

NOTE: Units with mechanical dehumidification require an additional connection to be made when enabling Balanced Climate. Refer to dehumidification supplemental instructions for this step.

If the application is likely to require air conditioning operation below 60°F outdoor conditions, a low ambient control (LAC) kit must be installed. The LAC kit is equipped with an outdoor temperature switch that disables Balanced Climate mode when the outdoor temperature drops below 50°F. This prevents potential evaporator coil freeze up issues. The LAC kit also comes with an evaporator freeze protection thermostat that cuts out the compressor if the evaporator begins to freeze up.

If the unit is being installed with any ventilation package, a Bard LAC kit must be installed. Failure to utilize an LAC with any air conditioner can cause coil freeze up.

Balanced Climate can readily be applied to duct-free (supply and return air grille) applications. It may also be applied to ducted applications with **limited static** of 0.20" ESP (total including both supply and return statics). Consult Bard Application Engineering for details prior to implementation.

CAUTION: Balanced Climate is not a replacement for a dehumidification (hot gas reheat) unit for extreme applications, but rather an enhancement feature for limited climates and applications.

BARD C60HC1 & C42HC1

Sequence of Operation

Cooling Stage 1 – Circuit R-Y makes at thermostat pulling in compressor contactor, starting the compressor and outdoor motor. The G (indoor motor) circuit is automatically completed on any call for cooling operation or can be energized by manual fan switch on subbase for constant air circulation.

Cooling Stage 2 – Circuit R-Y1 makes at the thermostat, energizing the 2nd stage solenoid in the compressor. Default position is not energized. Compressor will run at low capacity until this solenoid is energized.

Heating Stage 1 – A 24V solenoid coil on reversing valve controls heating cycle operation. Two thermostat options, one allowing "Auto" changeover from cycle to cycle and the other constantly energizing solenoid coil during heating season and thus eliminating pressure equalization noise except during defrost, are to be used. On "Auto" option, a circuit is completed from R-B and R-Y on each heating "on" cycle, energizing reversing valve solenoid and pulling in compressor contactor starting compressor and outdoor motor. R-G also make, starting indoor blower motor. Heat pump heating cycle now in operation. The second option has no "Auto" changeover position, but instead energizes the reversing valve solenoid constantly whenever the system switch on subbase is placed in "Heat" position, the "B" terminal being constantly energized from R. A thermostat demand for Stage 1 heat completes R-Y circuit, pulling in compressor contactor and starting compressor and outdoor motor. R-G also make, starting indoor blower motor.

Heating Stage 2 – Circuit R-Y2 makes at the thermostat, energizing the 2nd stage solenoid in the compressor.

Pressure Service Ports

the typical Shrader type valves.

High and low pressure service ports are installed on all units so that the system operating pressures can be observed. Pressure tables 6A and 6B cover all models. It is imperative to match the correct pressure table to the unit by model number.

This unit employs high-flow Coremax valves instead of

WARNING! Do NOT use a Schrader valve core removal tool with these valves. Use of such a tool could result in eye injuries or refrigerant burns!

To change a Coremax valve without first removing the refrigerant, a special tool is required which can be obtained at www.fastestinc.com/en/SCCA07H. See the replacement parts manual for replacement core part numbers.

CARRIER 50VTC48L

FIGURE 308.2.2. OBSTRUCTED HIGH

>20" - 25"

FORWARD REACH

OPERATION

Sequence of Operation—When free cooling is not available, the compressor will be controlled by the thermostat. When free cooling is available, the outdoor-air damper is modulated by the Economizer control to provide a 50° to 55°F (10° to 12.8°C) supply-air temperature into the zone. As the supply-air temperature fluctuates above 55° (12.8°C) or below 50°F (10°C), the dampers will be modulated (open or close) to bring the supply-air temperature back within the set points. For Economizer operation, there must be a thermostat call for the fan (G). This will move the damper to its minimum position during the occupied mode.

NOTE: The DCV Max potentiometer must be closed (CCW)


when not using CO₂ sensor. Above 50°F (10°C) supply-air temperature, the dampers will modulate from 100% open to the minimum open position. From 50°F to 45°F (10° to 7.2°C) supply-air temperature, the dampers will maintain at the minimum open position. Below 45°F (7.2°C), the dampers will be completely shut. As the supply-air temperature rises, the dampers will come back open to the minimum open position once the supply-air temperature rises to 48°F (8.9°C). If power exhaust is installed, as the outdoor-air damper opens and closes, the power exhaust fans will be energized and deenergized. If fieldinstalled accessory CO₂ sensors are connected to the Economizer control, a demand controlled ventilation strategy will begin to operate. As the CO₂ level in the zone increases above the CO₂ set point, the minimum position of the damper will be increased proportionally. As the CO₂ level decreases because of the increase in fresh air, the outdoor-air damper will be proportionally closed. Damper position will follow the higher demand condition from DCV mode or free cooling mode. Damper movement from full closed to full open (or vice versa) will take between 1 1/2 and 2 1/2 minutes. If free cooling can be used as determined from the appropriate changeover command (dry bulb, enthalpy curve, or differential enthalpy), a call for cooling (Y1 closes at the thermostat) will cause the control to modulate the dampers open to maintain the supply air temperature set point at 50° to 55° F (10° to 12.8° C). As the supply air temperature drops below the set point range of 50° to 55° F (10° to 12.8°C), the control will modulate the outdoor-air dampers closed to maintain the proper supply-air temperature.

| | | | n #: 04-121369 ergy Report: 2023-07-26 XX x40' PC (Wood Frame Walls) krea: 960 ft ² | | | |
|---------------------------------------|------------------|------------------|---|-------------------------|----------------------------------|------------|
| Climate Zone | 14 (Palmdale) | | | | | |
| Azimuth (Front Orientation) | | Standard Design | Proposed Design | Margin | Margin % | Worst Case |
| | TDV-E | 366.40 | 297.14 | 69.26 | 18.9028% | |
| 30° | TDV-T SOURCE | 366.40 36.24 | 297.14 30.65 | 69.26 5.59 | 18.9028% 15.4249% | |
| | TDV-E | 358.72 | 295.30 | 63.42 | 17.6795% | ** |
| 75° | TDV-T SOURCE | 358.72 | 295.30 | 63.42 5.07 | 17.6795% | ** |
| | TDV-E | 35.63 363.47 | 30.56 296.43 | 67.04 | 14.2296% 18.4444% | |
| 120° | TDV-T | 363.47 | 296.43 | 67.04 | 18.4444% | |
| | SOURCE TDV-E | 36.01 366.46 | 30.64 297.42 | 5.37 69.04 | 14.9125% 18.8397% | |
| 165° | TDV-T | 366.46 | 297.42 | 69.04 | 18.8397% | |
| | SOURCE | 36.22 | 30.64 | 5.58 | 15.4059% | |
| 210° | TDV-E TDV-T | 366.40 366.40 | 297.14 297.14 | 69.26 69.26 | 18.9028% 18.9028% | |
| - | SOURCE | 36.24 | 30.65 | 5.59 | 15.4249% | |
| 255° | TDV-E TDV-T | 358.72 358.72 | 295.30 | 63.42 63.42 | 17.6795% 17.6795% | ** |
| 233 | SOURCE | 358.72 35.63 | 295.30 30.56 | 5.07 | 17.6795% 14.2296% | ** |
| | TDV-E | 363.47 | 296.44 | 67.03 | 18.4417% | |
| 300° | TDV-T SOURCE | 363.47 36.01 | 296.44 30.64 | 67.03 5.37 | 18.4417% 14.9125% | |
| | TDV-E | 366.46 | 297.42 | 69.04 | 18.8397% | |
| 345° | TDV-T | 366.46 | 297.42 | 69.04 | 18.8397% | |
| | SOURCE | 36.22 | 30.64 | 5.58 | 15.4059% | |
| Climate Zone 15 | 5 (Palm Springs) | | | | | |
| Azimuth | | Standard Design | Proposed Design | Margin | Margin % | Worst Case |
| ront Orientation) | TDV-E | 378.51 | 303.65 | 74.86 | 19.7775% | |
| 30° | TDV-T | 378.51 | 303.65 | 74.86 | 19.7775% | |
| | SOURCE | 33.26 | 26.66 | 6.60 | 19.8437% | ** |
| 75° | TDV-E TDV-T | 369.92 369.92 | 301.77 301.77 | 68.15 68.15 | 18.4229% 18.4229% | ** |
| | SOURCE | 32.57 | 26.55 | 6.02 | 18.4833% | ** |
| 120° | TDV-E TDV-T | 370.43 370.43 | 302.74 302.74 | 67.69 67.69 | 18.2734% 18.2734% | |
| - | SOURCE | 32.71 | 26.64 | 6.07 | 18.5570% | |
| 165° | TDV-E | 378.42 | 303.43 | 74.99 | 19.8166% | |
| | TDV-T SOURCE | 378.42 33.23 | 303.43 26.65 | 74.99 6.58 | 19.8166% 19.8014% | |
| | TDV-E | 378.51 | 303.65 | 74.86 | 19.7775% | |
| 210° | TDV-T | 378.51 | 303.65 | 74.86 | 19.7775% 19.8437% | |
| | SOURCE TDV-E | 33.26 369.92 | 26.66 301.77 | 6.60 68.15 | 19.8437% | ** |
| 255° | TDV-T | 369.92 | 301.77 | 68.15 | 18.4229% | ** |
| | SOURCE TDV-E | 32.57 370.43 | 26.55 302.74 | 6.02 67.69 | 18.4833% 18.2734% | ** |
| 300° | TDV-T | 370.43 | 302.74 | 67.69 | 18.2734% | |
| | SOURCE | 32.71 | 26.64 | 6.07 | 18.5570% | |
| 345° | TDV-E TDV-T | 378.42 378.42 | 303.43 303.43 | 74.99 74.99 | 19.8166% 19.8166% | |
| | SOURCE | 33.23 | 26.65 | 6.58 | 19.8014% | |
| Climate Zone 16 | 6 (Blue Canyon) | | | | | |
| Azimuth ont Orientation) | | Standard Design | Proposed Design | Margin | Margin % | Worst Case |
| | TDV-E | 307.24 | 278.52 | 28.72 | 9.3477% | ** |
| 30° | TDV-T | 307.24 | 278.52 | 28.72 | 9.3477% | ** |
| | SOURCE TDV-E | 54.83 341.77 | 41.05 272.69 | 13.78 69.08 | 25.1322% 20.2124% | ** |
| 75° | TDV-E | 341.77 | 272.69 | 69.08 | 20.2124% | |
| | SOURCE | 65.39 | 40.97 | 24.42 | 37.3452% | |
| 1360 | TDV-E | 307.35 | 273.40 | 33.95 | 11.0460% | |
| 120° | TDV-T SOURCE | 307.35 54.88 | 273.40 41.01 | 33.95 13.87 | 11.0460% 25.2733% | |
| | TDV-E | 309.02 | 273.26 | 35.76 | 11.5721% | |
| 165° | TDV-T | 309.02 | 273.26 | 35.76 | 11.5721% | |
| | SOURCE | 54.91 | 41.02 | 13.89 | 25.2959% | |
| 210° | TDV-E TDV-T | 307.24 307.24 | 273.52 273.52 | 33.72 33.72 | 10.9751% 10.9751% | |
| | SOURCE | 54.83 | 41.05 | 13.78 | 25.1322% | |
| | TDV-E | 341.77 | 272.69 | 69.08 | 20.2124% | |
| 255° | TDV-T SOURCE | 341.77 | 272.69 40.97 | 69.08 24.42 | 20.2124% 37.3452% | |
| li i | TDV-E | 65.39 307.35 | 273.40 | 33.95 | 37.3452% 11.0460% | |
| | TDV-T | 307.35 | 273.40 | 33.95 | 11.0460% | |
| 300° | | 54.88 | 41.01 | 13.87 | 25.2733% | |
| 300° | SOURCE | | | 25.76 | 11 57210/ | |
| | TDV-E | 309.02 | 273.26 273.26 | 35.76 35.76 | 11.5721% 11.5721% | |
| 300° 345° | | | 273.26 273.26 41.02 | 35.76 35.76 13.89 | 11.5721% 11.5721% 25.2959% | |

ROJECT SPECIFIC STATE AGENCY APPROVAL **IDENTIFICATION STAMP** DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: **REVIEWED FOR** SS 🗹 FLS 🗹 ACS 🗹 12/18/2024



PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF **R&S TAVARES ASSOCIATES, INC. DEVISED** SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE **EXPRESS WRITTEN CONSENT OF R&S** TAVARES ASSOCIATES, INC. ©



ORIGINAL PC STATE AGENCY APPROVAL APPROVED DIV. OF THE STATE ARCHITEC APP: 04-1230*5*9 PC SS / FLS / ACS / CG /

> Revision Schedule Description

> > PRE-CHECK (PC) DOCUMENT

Code: 2022 CBC A separate project application for construction is required

PROJECT TITLE PC 2022 CBC: 24' x 40' **EXPANDABLE TO** 120' x 40'

MISCELLANEOUS **NOTES & DETAILS**

22088 DRAWN BY Author CHECKED BY Checker

DATE

PROJECT NUMBER

M0.2

PROJECT:

24X40 (PC 04-121369) - Wall AC Climate Zone 14 Palmdale, CA

Project Designer: R & S Tavares Associates 11590 W. Bernardo Court, Suite 100

Report Prepared by:

San Diego, Ca. 92127

LAL B. SAHGAL LSA CONSULTING ENGINEERS 83, WINDSWEPT WAY MISSION VIEJO, CA 92692 (949) 830-4746

Job Number:

Date: 7/26/2023

The EnergyPro computer program has been used to perform the calculations summarized in this compliance report. This program has approval and is authorized by the California Energy Commission for use with both the Residential and Nonresidential 2022 Building Energy Efficiency Standards. This program developed by EnergySoft, LLC – www.energysoft.com.

| CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD | NRCC-PRF-E |
|---|--|
| Nonresidential Performance Compliance Method | (Page 2 of 17) |
| | |
| B. PROJECT SUMMARY | |
| Table B shows which building components are included in the performance calculation. If indicated as not includer permit application. | luded, the project must show compliance prescriptively if within the |
| Building Components Complying via Performance | Building Components Complying Prescriptively |
| | |

| В | uilding Comp | onents Complyin | Building Components Complying Pres | scriptively | | | | |
|---|--------------|-----------------|---|-------------|--------------|---|------------------------|--|
| Envelope (See Table G) Nonres Performance | | | Solar Thermal Water | | Performance | The following building components are ONLY eligible for prescriptive compliance and should be documented on the NRCC form listed if within the scope of the | | |
| Envelope (see Table G) | MultiFam | Not Included | Heating (See Table I3) | ⊠ | Not Included | permit application (i.e. compliance will not be shown of | | |
| Mechanical (See Table H) | Nonres | Performance | Covered Process: | | Performance | Indoor Lighting (Unconditioned) 140.6 & 170.2(e) | NRCC-LTI-E is required | |
| Mechanical (See Table 11) | MultiFam | Not Included | Commercial Kitchens (see Table J) | | Not Included | Outdoor Lighting 140.7 & 170.2(e) | NRCC-LTO-E is required | |
| Domestic Hot Water (See Table I) | Nonres | Not Included | Covered Process: Laboratory Exhaust (see Table J) | | Performance | Sign Lighting 140.8 & 170.2(e) | NRCC-LTS-E is required | |
| Table 1) | MultiFam | Not Included | | | Not Included | Building Components Complying with Mandatory Measure | | |
| Lighting (Indoor Conditioned, see Table K) | Nonres | Performance | Photovoltaics (see Table F) | | Performance | Electrical power systems, commissioning, solar escalator requirements are mandatory and sho on the NRCC form listed if applicable (i.e. com shown on the NRCC-PRF-E.) | uld be documented | |
| | MultiFam | Not Included | | × | Not Included | Electrical Power Distribution 110.11 | NRCC-ELC-E is required | |
| | | | Pattory (soo Table E) | | Performance | Commissioning 120.8 | NRCC-CXR-E is required | |
| | | | Battery (see Table F) | | Not Included | Solar and Battery 110.10 | NRCC-SAB-E is required | |

| CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance | Report Version: 2022.0.000 | Report Generated: 2023-07-25 10:52:04 |
|--|------------------------------|---|
| | Schema Version: rev 20220601 | Compliance ID: EnergyPro-4958-0723-0144 |

| CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD | NRCC-PRF-E |
|--|----------------|
| Nonresidential Performance Compliance Method | (Page 6 of 17) |
| | |

| COMPLIES ² | | | | | | | | |
|-----------------------------|--------------------------|--------------------------|---------------------------|--|--|--|--|--|
| Energy Component | Standard Design (SOURCE) | Proposed Design (SOURCE) | Compliance Margin (SOURCE | | | | | |
| Space Heating | 3.73 | 6.14 | -2.41 | | | | | |
| Space Cooling | 3.47 | 3.65 | -0.18 | | | | | |
| Indoor Fans | 14.94 | 8.15 | 6.79 | | | | | |
| Heat Rejection | 0 | 0 | 0 | | | | | |
| Pumps & Misc. | 0 | 0 | 0 | | | | | |
| Domestic Hot Water | 5.99 | 5.99 | 0 | | | | | |
| Indoor Lighting | 2.57 | 1.71 | 0.86 | | | | | |
| Flexibility | | | | | | | | |
| EFFICIENCY COMPLIANCE TOTAL | 30.7 | 25.64 | 5.06 (16.5%) | | | | | |
| Photovoltaics | | | | | | | | |
| Batteries | | | | | | | | |
| TOTAL COMPLIANCE | 30.7 | 25.64 | 5.06 (16.5%) | | | | | |

TABLE OF CONTENTS

20

NRCC-PRF-E

(Page 5 of 17)

NRCC-PRF-E

Cover Page Table of Contents Form NRCC/LMCC-PRF-E Certificate of Compliance HVAC System Heating and Cooling Loads Summary

| CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD | NRCC-PRF-E |
|--|----------------|
| Nonresidential Performance Compliance Method | (Page 3 of 17) |

| C1. COMPLIANCE SUMMARY | | | |
|---|-----------------------------|--|------------------------|
| | COMPLIES ³ | | |
| | Time Dependent | : Valuaton (TDV) | Source Energy Use |
| | Efficiency¹ (kBtu/ft² - yr) | Total ² (kBtu/ft ² - yr) | Total² (kBtu/ft² - yr) |
| Standard Design | 358.72 | 358.72 | 30.7 |
| Proposed Design | 295.31 | 295.31 | 25.64 |
| Compliance Margins | 63.41 | 63.41 | 5.06 |
| | Pass | Pass | Pass |
| Efficiency measures include improvements like a better building enve Compliance Totals include efficiency, photovoltaics and batteries Building complies when efficiency and total compliance margins are | | met load hour limits are not exceed | ed |

| CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance | Report Version: 2022.0.000 | Report Generated: 2023-07-25 10:52:04 |
|--|------------------------------|--|
| | Schema Version: rev 20220601 | Compliance ID: EnergyPro-4958-0723-014 |
| | | |

| C3. TDV ENERGY RESULTS FOR NON-REGULATED COMPONENTS ¹ | | | | | |
|--|-----------------------|-----------------------|-------------------------|--|--|
| Non-Regulated Energy Component | Standard Design (TDV) | Proposed Design (TDV) | Compliance Margin (TDV) | | |
| Receptacle | 67.93 | 67.93 | | | |
| Process | | | | | |
| Other Ltg | | | | | |
| Process Motors | | | | | |

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Nonresidential Performance Compliance Method

☐ This project is pursuing CalGreen Tier 1

| TOTAL (TOTAL COMPLIANCE + NON-REGULATED COMPONENTS) | 426.65 | 363.24 | 63.41 (14.9%) |
|--|--|--------|---|
| Notes: This table is not used for Energy Code Compliance. | | | |
| CA Building Energy Efficiency Standards - 2022 Nonresidential Compli | ance Report Version: 2022.0.0 Schema Version: rev 202 | · | rt Generated: 2023-07-25 10:52:04 nce ID: EnergyPro-4958-0723-0144 |

| C5. SOURCE ENERGY RESULTS FOR NON-REGULATED COMPONENTS ¹ | | | |
|---|--------------------------|--------------------------|---|
| Non-Regulated Energy Component | Standard Design (SOURCE) | Proposed Design (SOURCE) | Compliance Margin (SOURCE) ¹ |
| Receptacle | 4.92 | 4.92 | |
| Process | | | |
| Other Ltg | | | |
| Process Motors | | | |
| TOTAL (TOTAL COMPLIANCE + NON-REGULATED COMPONENTS) | 35.62 | 30.56 | 5.06 (14.2%) |

☐ This project is pursuing CalGreen Tier 2

| CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance | Report Version: 2022.0.000 | Report Generated: 2023-07-25 10:52 |
|--|------------------------------|---------------------------------------|
| | Schema Version: rev 20220601 | Compliance ID: EnergyPro-4958-0723-03 |

| Nonresidential Performance Compliance Method | | | (Page 1 of 1 |
|--|--------------------------------|----------------|--------------|
| Project Name: | 24X40 (PC 04-121369) - Wall AC | Date Prepared: | 2023-07- |

| A. G | eneral Information | | | | |
|------|---|--------------------------------|----|---|---------------------|
| 1 | Project Name | 24X40 (PC 04-121369) - Wall AC | | | |
| 2 | Run Title | Title 24 Analysis | | | |
| 3 | Project Location | Climate Zone 14 | | | |
| 4 | City | Palmdale | 5 | Standards Version | Compliance 2022 |
| 6 | Zip code | 99999 | 7 | Compliance Software (version) | EnergyPro 9.1 |
| 8 | Climate Zone | 14 | 9 | Building Orientation (deg) | 75 |
| 10 | Building Type(s) | Nonresidential | 11 | Weather File | PALMDALE_STYP20.epw |
| 12 | Project Scope | New complete scope | 13 | Number of Dwelling Units | 0 |
| 14 | Total Conditioned Floor Area in Scope (ft²) | 960 | 15 | Total # of hotel/motel rooms | 0 |
| 16 | Total Unconditioned Floor Area (ft²) | 0 | 17 | Fuel Type | Natural gas |
| 18 | Nonresidential Conditioned Floor Area | 960 | 19 | Total # of Stories (Habitable Above Grade) | 1 |
| 20 | Residential Conditioned Floor Area | 0 | | | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000

Report Generated: 2023-07-25 10:52:04 Compliance ID: EnergyPro-4958-0723-0144

| CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD | NRCC-PRF-E |
|--|----------------|
| Nonresidential Performance Compliance Method | (Page 4 of 17) |

| | COMPLIES ² | | | |
|-----------------------------|-----------------------|-----------------------|-------------------------|--|
| Energy Component | Standard Design (TDV) | Proposed Design (TDV) | Compliance Margin (TDV) | |
| Space Heating | 25.61 | 42 | -16.39 | |
| Space Cooling | 93.22 | 95.25 | -2.03 | |
| Indoor Fans | 152.65 | 81.72 | 70.93 | |
| Heat Rejection | 0 | 0 | 0 | |
| Pumps & Misc. | 0 | 0 | 0 | |
| Domestic Hot Water | 54.63 | 54.6 | 0.03 | |
| Indoor Lighting | 32.61 | 21.74 | 10.87 | |
| Flexibility | | | | |
| EFFICIENCY COMPLIANCE TOTAL | 358.72 | 295.31 | 63.41 (17.7%) | |
| Photovoltaics | | | | |
| Batteries | | | | |
| TOTAL COMPLIANCE | 358.72 | 295.31 | 63.41 (17.7%) | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220601

Report Generated: 2023-07-25 10:52:04 Compliance ID: EnergyPro-4958-0723-0144

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E Nonresidential Performance Compliance Method (Page 8 of 17)

| C7. ENERGY USE SUMMARY | | | | | | |
|------------------------|-------------------------------|-------------------------------|-----------------|--------------------------------|--------------------------------|------------------|
| Energy Component | Standard Design Site (MWh) | Proposed Design Site (MWh) | Margin (MWh) | Standard Design Site (MBtu) | Proposed Design Site (MBtu) | Margin (MBtu) |
| Space Heating | 0.8 | 1.3 | -0.5 | | | |
| Space Cooling | 2.3 | 2.3 | 0 | | | |
| Indoor Fans | 5.2 | 2.8 | 2.4 | | | |
| Heat Rejection | | | | | | |
| Pumps & Misc. | | | | | | |
| Domestic Hot Water | 2 | 2 | 0 | | | |
| Indoor Lighting | 1.2 | 0.8 | 0.4 | | | |
| Flexibility | | | | | | |
| EFFICIENCY TOTAL | 11.5 | 9.2 | 2.3 | 0 | 0 | 0 |
| Photovoltaics | | | | | | |
| Batteries | | | | | | |
| ENERGY USE SUBTOTAL | 11.5 | 9.2 | 2.3 | 0 | 0 | 0 |
| Receptacle | 2.5 | 2.5 | 0 | | | |
| Process | | | | | | |
| Other Ltg | | | | | | |
| Process Motors | | | | | | |
| ENERGY USE TOTAL | 14 | 11.7 | 2.3 | 0 | 0 | 0 |


Report Generated: 2023-07-25 10:52:04 CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220601 Compliance ID: EnergyPro-4958-0723-0144 PROJECT SPECIFIC STATE AGENCY APPROVAL IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗸 12/18/2024

DESIGN ♦ CONSULTING ♦ PROJECT MGT

11590 W BERNARDO COURT, SUITE 100

SAN DIEGO, CA 92127

PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE **EXPRESS WRITTEN CONSENT OF R&S** TAVARES ASSOCIATES, INC. ©



ORIGINAL PC STATE AGENCY APPROVAL APPROVED DIV. OF THE STATE ARCHITECT APP: 04-123059 PC

Revision Schedule Description

PRE-CHECK (PC) DOCUMENT

CODE: 2019 CBC

A separate project application for construction is required

PC 2022 CBC: 24' x 40' **EXPANDABLE TO** 120' x 40'

SHEET TITLE 24'x40' T24 CZ 14

PROJECT NUMBER 22088 CHECKED BY

06/15/2021

SHEET OF

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220601

Compliance ID: EnergyPro-4958-0723-0144

Report Generated: 2023-07-25 10:52:04

0:52:04 3-0144

| C8. ENERGY USE INTENSITY (EUI) | | | | | | | | | |
|--|---|---------------------------------|------------------------|-------------------|--|--|--|--|--|
| | Standard Design (kBtu/ft² / yr) | Proposed Design (kBtu/ft² / yr) | Margin (kBtu/ft² / yr) | Margin Percentage | | | | | |
| GROSS EUI ¹ | 49.76 | 41.58 | 8.18 | 16.44 | | | | | |
| NET EUI ¹ 49.76 41.58 8.18 16.44 | | | | | | | | | |
| ¹ Notes: Gross EUI is Energy Use To | ¹ Notes: Gross EUI is Energy Use Total (not including PV)/Total Building Area. Net EUI is Energy Use Total (including PV)/Total Building Area. | | | | | | | | |

D1. EXCEPTIONAL CONDITIONS

• The project uses the Simplified Geometry Performance Modeling Approach which is not capable of modeling daylighting controls and assumes the prescriptive Secondary Daylit Control requirements are met. PRESCRIPTIVE COMPLIANCE documentation (form NRCC-LTI-02-E) for the requirements of section 140.6(d) Automatic Daylighting Controls • The building does not include service water heating. Verify that service water heating is not required and is not included in the design.

• Project is claiming Exception 2 to Section 140.10(a): No PV system is required where the required PV system size is less than 4 kWdc.

| 01 02 03 04 | | | | | | |
|-------------------------------|---|--|--------------------------|--|--|--|
| Opaque Surfaces & Orientation | Total Gross Surface Area (ft ²) | Total Fenestration Area (ft ²) | Window to Wall Ratio (%) | | | |
| North-Facing ¹ | 240 | 32 | 13.33 | | | |
| East-Facing ² | 400 | 0 | 0 | | | |
| South-Facing ³ | 240 | 32 | 13.33 | | | |
| West-Facing ⁴ | 400 | 0 | 0 | | | |
| Total | 1280 | 64 | 5 | | | |
| Roof | 960 | 14 | 1.46 | | | |

¹North-Facing is oriented to within 45 degrees of true north, including 45 00'00" east of north (NE), but excluding 45 00'00" west of north (NW), ²East-Facing is oriented to within 45 degrees of true east, including 45 00'00" south of east (SE), but excluding 45 00'00" north of east (NE), 3South-Facing is oriented to within 45 degrees of true south, including 45 00'00" west of south (SW), but excluding 45 00'00" east of south (SE),

Power | Power Units |

 4 West-Facing is oriented to within 45 degrees of true west, including 45 00'00" north of west (NW), but excluding 45 00'00" south of west (SW),

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Report Generated: 2023-07-25 10:52:04

Schema Version: rev 20220601

| CERTIFICATE OF COM | CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRC | | | | | | | | | | | CC-PRF- |
|--|---|--|--|--|--|--|--|---|-------------------|-------|----------|---------|
| Nonresidential Performance Compliance Method | | | | | | | | | | (Page | 12 of 17 | |
| H3. NONRESIDENTIAL / COMMON USE AREA FAN SYSTEMS SUMMARY | | | | | | | | | | | | |
| 01 02 03 04 05 06 07 08 09 10 11 12 | | | | | | | | | 13 | | | |
| Posign QA Supply Fan | | | | | | | | R | eturn / Relief Fa | an | | |

Control

Fan Type

Constant Vol N/A N/A

CFM

Power

| AC-1 | 1 | 364.8 | 1,100 | | | | | |
|---|---|-------|-------|--|--|--|--|--|
| ¹ Status: N - New, A - Altered, E - Existing | | | | | | | | |

| H8. SYSTEM SPECIAL FEATURES | | | |
|-----------------------------|-------------------------------|--------------------------------------|---|
| 01 | 02 | 03 | 04 |
| System Name | Equipment Type | Interlocks per 140.4(n) ¹ | Other Special Features and Controls |
| AC-1 | Single Package VHP Air System | No | Zone(s) With CO2 Sensor Vent. Control Fixed DB |

Notes: This table includes controls related to the performance path only. For projects using the prescriptive path, mandatory and prescriptive controls requirements are documented on the NRCC-MCH-E. ¹ Yes = interlocks are provided, No = interlocks are not provided, NA means no operable openings.

H9. NONRESIDENTIAL / COMMON USE AREA & HOTEL/MOTEL VENTILATION

| , | | | | | | | | |
|---------------|---------------------------------------|---------------------------|---------------------------|-------------|-----------------------|---|--|--|
| 01 | 02 | 03 | 04 | 06 | 07 | | | |
| Zone Name | Ventilation Function | Mechanical # of People | Ventilation Supply OA CFM | Exhaust CFM | Conditioned Area (sf) | DCV or Occupant Sensor Controls, or Both | | |
| 1-First Floor | Education - Classrooms (ages 9-18) | 24 | 364.8 | 0 | 960 | DCV | | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220601

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Report Generated: 2023-07-25 10:52:04

Compliance ID: EnergyPro-4958-0723-0144

NRCC-PRF-E

Compliance ID: EnergyPro-4958-0723-0144

Power Units | Control

| Nonresidential Performance Compliance Method (Page 15 | | | | | | | | |
|---|--|--|--|--|--|--|--|--|
| L. DECLARATION OF REQUIRED CERTIFICATES OF INSTALLATION | | | | | | | | |
| Selections made by Documentation Author indicate which Certificates of Installation must be submitted for the features to be recognized for compliance. These documents must be retained and provided to the building inspector during construction and can be found online | | | | | | | | |
| Building Component | Form/Title | | | | | | | |
| Envelope | NRCI-ENV-01-E - Must be submitted for all buildings | | | | | | | |
| Envelope | NRCI-ENV-E - Envelope (for all buildings) | | | | | | | |
| Mechanical | NRCI-MCH-01-E - Must be submitted for all buildings | | | | | | | |
| Mechanical | NRCI-MCH-E - For all buildings with Mechanical Systems | | | | | | | |
| Indoor Lighting | NRCI-LTI-01-E - Must be submitted for all buildings | | | | | | | |
| Indoor Lighting | NRCI-LTI-E - Indoor Lighting (for all buildings) | | | | | | | |

| Indoor Lighting | NRCI-LTI-E - Indoor Lighting (for all buildings) | | | | | | | |
|--|---|--|--|--|--|--|--|--|
| | | | | | | | | |
| M. DECLARATION OF REQUIRED CERTIFICATES OF ACCEPTANCE | | | | | | | | |
| Selections made by Documentation Author indicate which Certificates of Acceptance must be submitted for the features to be recognized for compliance. These documents must be provided to the building inspector during construction and must be completed through an Acceptance Test Technician Certification Provider (ATTCP). | | | | | | | | |
| Building Component | Form/Title | | | | | | | |
| Envelope | NRCA-ENV-02-F - NRFC label verification for fenestration | | | | | | | |
| Indoor Lighting | Indoor Lighting NRCA-LTI-02-A - Occupancy Sensors and Automatic Time Switch Controls. | | | | | | | |

NRCA-MCH-02-A - Outdoor Air must be submitted for all newly installed HVAC units. Note: MCH-02-A can be performed in conjunction with Mechanical MCH-07-A Supply Fan VFD Acceptance (if applicable) since testing activities overlap Mechanical NRCA-MCH-05-A - Air Economizer Controls NRCA-MCH-06-A Demand Control Ventilation Systems must be submitted for all systems required to employ demand controlled ventilation Mechanical (refer to) can vary outside ventilation flow rates based on maintaining interior carbon dioxide (CO2) concentration setpoints.

N. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION

Selections made by Documentation Author indicate which Certificates of Verification must be submitted for the features to be recognized for compliance. These documents must be retained and provided to the building inspector during construction and can be found online There are no Certificates of Verification applicable to this project

Report Version: 2022.0.000 Report Generated: 2023-07-25 10:52:04 CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Schema Version: rev 20220601 Compliance ID: EnergyPro-4958-0723-0144 CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E **Nonresidential Performance Compliance Method** (Page 10 of 17)

| G4. NONRESIDEN | ITIAL AIR BARRIER | | | | | | | | | |
|-----------------------------------|-------------------|----------------------|---------|---------|----------|------------|----------|--------------------------------|--|--------|
| | | 01 | | | | | | | 02 | |
| | | Building Stor | y Name | | | | | | Air Barrier | |
| | | Com-Flo | or 1 | | | | | | No air barrier | |
| G5. OPAQUE SUR | RFACE ASSEMBLY S | UMMARY | | | | | | | | |
| 01 | 02 | 03 | 04 | 05 | C | 6 | 07 | 08 | 09 | 10 |
| Surface Name | Construction | Area (ft²) | Framing | Cavity | Continuo | us R-Value | Units | Value | Description of Assembly Layers | Status |
| Surface Name | Туре | Type Area (It) | Туре | R-Value | Interior | Exterior | Value | Description of Assembly Layers | Status | |
| R-19 Wood Framed Wall7 | Exterior Wall | 1,280 | Wood | 19 | N/A | N/A | U-factor | 0.0605 | Wood siding - 1/2 in. Vapor permeable felt - 1/8 in. Composite-1 Gypsum Board - 1/2 in. Softwood - 1.5 in. | N |
| R-19 Metal Floor Crawlspa14 | Exterior Floor | 960 | Metal | 19 | N/A | N/A | U-factor | 0.0588 | Vented Crawl Space Composite-2 Plywood - 1/2 in. Carpet - 3/4 in. | N |
| Standing Seam R-38 Metal16 | Roof | 960 | N/A | 36 | N/A | N/A | U-factor | 0.06 | Metal Standing Seam - 1/16 in. Composite-3 | N |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220601

Report Generated: 2023-07-25 10:52:04 Compliance ID: EnergyPro-4958-0723-0144

| CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E | | | | | | | | | | | |
|--|--------------|-----|---------|---------|--------|------|------------|-------|----------------|--------|-----|
| Nonresidential Performance Compliance Method (Page 13 of 17) | | | | | | | | | | | |
| H11. ZONAL SYSTEM AND TERMINAL UNIT SUMMARY | | | | | | | | | | | |
| 01 | 02 | 03 | 04 | 05 | 06 | 07 | 08 | 09 | 10 | 11 | 12 |
| Rated Capacity (kBtuh) Airflow (cfm) | | | | | | | | Fan | Fan | | |
| System ID | System Type | Qty | Heating | Cooling | Design | MIn. | Min. Ratio | Power | Power Units | Cycles | VSD |
| 1-First Floor-Trm | Uncontrolled | 1 | N/A | N/A | 1,100 | N/A | 0 | N/A | N/A | N/A | |
| K1. INDOOR CONDITIONED LIGHTING GENERAL INFO | | | | | | | | | | | |
| 01 | 02 | | 03 | | 04 | | | 05 | | 06 | |

| 01 | 02 | 03 | 04 | 05 | 06 | | |
|--|--|--------------------------|--------------------------|------------------------------------|------------------------------------|--|--|
| | | Installed Lighting Power | Lighting Control Credits | Additional (Custom) Allowance | | | |
| Occupancy Type ¹ | Conditioned Floor Area ² (ft ²) | (Watts) | (Watts) | Area Category Footnotes (Watts) | Area Category Footnotes (Watts) | | |
| lassroom, Lecture, or Training Vocational | 960 | 384 | 0 | 0 | 0 | | |
| Building Totals: | 960 | 384 | 0 | 0 | 0 | | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD

³Lighting information for existing spaces modeled is not included in this table

Schema Version: rev 20220601

Report Generated: 2023-07-25 10:52:04 Compliance ID: EnergyPro-4958-0723-0144

Report Generated: 2023-07-25 10:52:04

Compliance ID: EnergyPro-4958-0723-0144

Compliance ID: EnergyPro-4958-0723-0144

NRCC-PRF-E

| Nonre | sidential Performance Compliance Method | | (Page 16 of 17 | | |
|-------------------|---|--|--|--|--|
| Docume | ntation Author's Declaration Statement | | | | |
| 1. I cert | ify that this Certificate of Compliance documentation is acc | urate and complete. | | | |
| Docume | ntation Author Name: LAL B. SAHGAL | Documentation Author Signature: | | | |
| Compar | y: LSA CONSULTING ENGINEERS | Signature Date: | | | |
| Address | : 83, WINDSWEPT WAY | CEA/HERS Certification Identification | on (if applicable): M26885 | | |
| City/Sta | te/Zip: MISSION VIEJO, CA 92692 | Phone: (949) 830-4746 | | | |
| Respons | ible Person's Declaration statement | | | | |
| 1. 2. 3. 4. 5. 6. | the following under penalty of perjury, under the laws of the Information provided on this Certificate of Compliance I am eligible under Division 3 of the Business and Professio Compliance (responsible designer) The energy features and performance specifications, mater Certificate of Compliance conform to the requirements of The building design features or system design features ider compliance documents, worksheets, calculations, plans an I understand that a registered copy of this Certificate of Cothe enforcement agency for all applicable inspections, and I understand that a registered copy of this Certificate of Cooccupancy, and I will take the necessary steps to accomplis | is true and correct. Institute and correct. Institute and correct. Institute and correct. It is components, and manufactured devices for the builtitle 24, Part 1 and Part 6 of the California Code of Regulatified on this Certificate of Compliance are consistent we dispecifications submitted to the enforcement agency for mpliance shall be made available with the building perm I will take the necessary steps to accomplish this requirempliance is required to be included with the documental | ilding design or system design identified on this lations. with the information provided on other applicable or approval with this building permit application. nit(s) issued for the building, and made available to ement. | | |
| Respons | ible Designer Name: | Responsible Designer Signature: | | | |
| Compar | y: R & S Tavares Associates | | | | |
| Address | : 11590 W. Bernardo Court, Suite 100 | Date Signed: | | | |
| City/Sta | te/Zip: San Diego, Ca. 92127 | License #: | | | |
| Phone: | | Title: | Scope: | | |
| Respons | ible Designer Name: | Responsible Designer Signature: | · | | |
| Compar | y: R & S Tavares Associates | | | | |
| Address | : 11590 W. Bernardo Court, Suite 100 | Date Signed: | | | |
| City/Sta | te/Zip: San Diego, Ca. 92127 | License #: | License #: | | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220601

| CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE | NRCC-PRF-E | |
|--|------------------------------|-----------------|
| Nonresidential Performance Compliance Method | | (Page 17 of 17) |
| Responsible Designer Name: Lal Sahgal | Responsible Designer Signatu | re: |
| Company: LSA Consulting Engineers | | |
| Address: 83, Windswept Way | Date Signed: | |
| City/State/Zip: Mission Viejo, Ca. 92692 | License #: M26885 | |
| Phone: | Title: | Scope: |

Schema Version: rev 20220601

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E Nonresidential Performance Compliance Method (Page 11 of 17)

| 01 | 02 | 03 | 04 | 05 | 06 | 07 | 08 | 0: |
|-------------------------------|---|--------------------------------------|-----------------|---------------|---------------------|--------------|------------|------|
| Fenestration Assembly Name | Fenestration Type/ Product Type / Frame Type | Certification Method ¹ | Assembly Method | Area (ft²) | Overall U-factor | Overall SHGC | Overall VT | Stat |
| Sierra Pacific Windows | Vertical fenestration Operable window N/A | NFRC | Manufactured | 64 | 0.35 | 0.24 | 0.5 | N |
| Sola tube | Skylight Fixed window N/A | NFRC | Manufactured | 14 | 0.39 | 0.37 | 0.65 | 1 |

¹ Notes: Newly installed fenestration shall have a certified NFRC Label Certificate or use the CEC default tables found in Table 110.6-A and Table 110.6-B. Center of Glass (COG) values are for the glass-only, determined by the manufacturer, and are shown for ease of verification. Site-built fenestration values are calculated per Nonresidential Appendix NA6 and are used in the analysis. ² Status: N - New, A - Altered, E - Existing

| 01 | 02 | 03 | 04 | 05 | 06 | 07 | 08 | 09 | 10 | 11 | 12 |
|----------------|----------------------------------|-----|--|---------------------------------|--------------------|------------|--|--------------------|------------|-----------------------------------|---------------------|
| | | | Heating | | | | Cooling | | | | |
| Equipment Name | Equipment Type | Qty | Total Heating Output (kBtu/h) | Supp Heat Output (kBtu/h) | Efficiency Unit | Efficiency | Total Cooling Output (kBtu/h) | Efficiency Unit | Efficiency | Economizer Type (if Statupresent) | Status ¹ |
| AC-1 | Single Package VHP Air System | 1 | 34.37 | 13.65 | СОР | 3.3 | 34.56 | EER | 11 | Fixed DB | N |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance

Report Version: 2022.0.000 Schema Version: rev 20220601

Report Generated: 2023-07-25 10:52:04 Compliance ID: EnergyPro-4958-0723-0144


CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E (Page 14 of 17) **Nonresidential Performance Compliance Method K2. INDOOR CONDITIONED LIGHTING SCHEDULE** uminaire Schedule (includes all permanent installed lighting in conditioned space, and portable lighting over 0.3 w/f ${
m t}^2$ in offices) 06 01 **Complete Luminaire** Installed Watts (Conditioned) Description (i.e. 3-lamp Name or Item Tag fluorescent troffer, F32T8, Installed Watts one dimmable electronic 2x4 LED Panel According to 384 ¹If lighting power densities were used in the compliance model Building Departments will need to check prescriptive forms for Luminaire Schedule details.

| 3. INDOOR CONDIT | IONED LIGHTING CONTROL CREDIT | S | | | | | | |
|----------------------|---|-------------------------------------|-------------------------------------|-----------------------|------------------------|--------------------|-----------------------------------|---------------------------|
| ighting Control Cred | lits Schedule (includes all lighting co | ontrols installed in conditioned sp | pace for complianc | e credit per 140. | 6(a)2 and Table 1 | 40.6-A) | | |
| 01 | 02 | 03 | 04 | 05 | 06 | 07 | 08 | 09 |
| Area Description | Primary Function Area (must meet requirements of Table 140.6-A and 170.2-L) | Type of Lighting Control | Power Adjustment Factor (PAF) | Luminaire Item Tag | Watts per Luminaire | # of Luminaires | Lighting Controlled (Watts) | Control Credit (Watts) |
| S-1-First Floor | Classroom, Lecture, or Training Vocational | N/A | N/A | L-1 | 48 | 8 | 384 | 0 |
| | | | | | Lighting Control C | redits (Condition | ed) Total (Watts) | 0 |

| K4. INDOOR CONDITIONED LIGHTING MANDATORY LIGHTING CONTROL | |
|--|---|
| Building Level Controls | |
| 01 | 02 |
| Mandatory Demand Response 110.12(c) | Shut-Off Controls 130.1(c) & 160.5(b)4C |
| Required | Required |
| See NRCC-LTI-E for mandatory controls | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000

Report Generated: 2023-07-25 10:52:04



ROJECT SPECIFIC STATE AGENCY APPROVAC IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT APP: 02-122764 INC: **REVIEWED FOR** SS 🗹 FLS 🗹 ACS 🗹 12/18/2024




PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©

CLIENT 1651Juanita Street, San Jacinto, CA 92583 Voice (951) 943-1908 Fax (951)943-5768



Revision Schedule Description

PRE-CHECK (PC) DOCUMENT

CODE: 2019 CBC A separate project application for construction is required

PC 2022 CBC: 24' x 40' **EXPANDABLE TO** 120' x 40'

24'x40' T24 CZ 14 (WALL AC)

PROJECT NUMBER 22088 DRAWN BY rMc/SC CHECKED BY RH/RT DATE

SHEET OF

06/15/2021

PROJECT:

24X40 (PC 04-121369) - Wall AC Climate Zone 15 Palm Springs, CA

Project Designer:

R & S Tavares Associates 11590 W. Bernardo Court, Suite 100 San Diego, Ca. 92127

Report Prepared by:

LAL B. SAHGAL LSA CONSULTING ENGINEERS 83, WINDSWEPT WAY MISSION VIEJO, CA 92692 (949) 830-4746

Job Number:

Date: 7/26/2023

The EnergyPro computer program has been used to perform the calculations summarized in this compliance report. This program has approval and is authorized by the California Energy Commission for use with both the Residential and Nonresidential 2022 Building Energy Efficiency Standards. This program developed by EnergySoft, LLC – www.energysoft.com.

| CERTIFICATE OF COMPLIANC | E - NONRESID | DENTIAL PERFORI | MANCE COMPLIANCE MET | HOD | 1 | | NRCC-PRF-E |
|---|--------------|--------------------|---|-------------|--------------------|---|---------------------------------------|
| Nonresidential Performance | Compliance I | Method | | | | | (Page 2 of 17) |
| B. PROJECT SUMMARY | | | | | | | |
| Table B shows which building o | components a | re included in the | e performance calculation. <u>I</u> | f ina | licated as not inc | luded, the project must show compliance prescri | ptively if within the |
| В | uilding Comp | onents Complyir | ng via Performance | | | Building Components Complying Pre | scriptively |
| Envelope (See Table G) | Nonres | Performance | Solar Thermal Water | | Performance | The following building components are ONLY eligible for pand should be documented on the NRCC form listed if w | |
| Elivelope (see Table G) | MultiFam | Not Included | Heating (See Table I3) Not Included | | Not Included | permit application (i.e. compliance will not be shown | |
| Mechanical (See Table H) | Nonres | Performance | Covered Process: | | Performance | Indoor Lighting (Unconditioned) 140.6 & 170.2(e) | NRCC-LTI-E is required |
| Wechanical (See Table 11) | MultiFam | Not Included | Commercial Kitchens (see - Table J) | \boxtimes | Not Included | Outdoor Lighting 140.7 & 170.2(e) | NRCC-LTO-E is required |
| Domestic Hot Water (See Table I) | Nonres | Not Included | Covered Process: Laboratory Exhaust (see | | Performance | Sign Lighting 140.8 & 170.2(e) | NRCC-LTS-E is required |
| Table 1) | MultiFam | Not Included | Table J) | \boxtimes | Not Included | Building Components Complying with Mandatory Mea | |
| Lighting (Indoor Conditioned, see Table K) | Nonres | Performance | Photovoltaics (see Table F) | | Performance | Electrical power systems, commissioning, solar escalator requirements are mandatory and sho on the NRCC form listed if applicable (i.e. com shown on the NRCC-PRF-E.) | uld be documented pliance will not be |
| | MultiFam | Not Included | | \boxtimes | Not Included | Electrical Power Distribution 110.11 | NRCC-ELC-E is required |
| | | | | П | Performance | Commissioning 120.8 | NRCC-CXR-E is |

Not Included

Battery (see Table F)

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220601

Report Generated: 2023-07-25 10:57:22 Compliance ID: EnergyPro-4958-0723-0145

Solar and Battery 110.10

required

NRCC-SAB-E is

required

| CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD | NRCC-PRF-E |
|--|----------------|
| Nonresidential Performance Compliance Method | (Page 6 of 17) |

| | COMPLIES ² | | | |
|-----------------------------|--------------------------|--------------------------|----------------------------|--|
| Energy Component | Standard Design (SOURCE) | Proposed Design (SOURCE) | Compliance Margin (SOURCE) | |
| Space Heating | 0.73 | 1.33 | -0.6 | |
| Space Cooling | 7.45 | 7.45 | 0 | |
| Indoor Fans | 12.67 | 6.9 | 5.77 | |
| Heat Rejection | 0 | 0 | 0 | |
| Pumps & Misc. | 0 | 0 | 0 | |
| Domestic Hot Water | 4.23 | 4.23 | 0 | |
| Indoor Lighting | 2.57 | 1.71 | 0.86 | |
| Flexibility | | | | |
| EFFICIENCY COMPLIANCE TOTAL | 27.65 | 21.62 | 6.03 (21.8%) | |
| Photovoltaics | | | | |
| Batteries | | | | |
| TOTAL COMPLIANCE | 27.65 | 21.62 | 6.03 (21.8%) | |

TABLE OF CONTENTS

| Cover Page | 1 |
|--|----|
| Table of Contents Form NRCC/LMCC-PRF-E Certificate of Compliance | 2 |
| HVAC System Heating and Cooling Loads Summary | 20 |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

| Nonresidential Performance Compliance Method | | | (Page 3 of 17) |
|--|---|------------------------|--|
| | | | |
| C1. COMPLIANCE SUMMARY | | | |
| | COMPLIES ³ | | |
| | Time Dependent Valuaton (TDV) | | Source Energy Use |
| | Efficiency ¹ (kBtu/ft ² - yr) | Total² (kBtu/ft² - yr) | Total ² (kBtu/ft ² - yr) |

Standard Design 369.92 369.92 27.65 301.78 301.78 21.62 Proposed Design 68.14 6.03 **Compliance Margins** 68.14 1 Efficiency measures include improvements like a better building envelope and more efficient equipment Compliance Totals include efficiency, photovoltaics and batteries

³ Building complies when efficiency and total compliance margins are greater than or equal to zero and unmet load hour limits are not exceeded

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Schema Version: rev 20220601

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Report Generated: 2023-07-25 10:57:22 Compliance ID: EnergyPro-4958-0723-0145

NRCC-PRF-E

| CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD | NRCC-PRF-E |
|--|----------------|
| Nonresidential Performance Compliance Method | (Page 5 of 17) |
| | |

| C3. TDV ENERGY RESULTS FOR NON-REGULATED COMPONENTS ¹ | | _ | | |
|--|-----------------------|-----------------------|--------------------------------------|--|
| Non-Regulated Energy Component | Standard Design (TDV) | Proposed Design (TDV) | Compliance Margin (TDV) ¹ | |
| Receptacle | 66.69 | 66.69 | | |
| Process | | | | |
| Other Ltg | | | | |
| Process Motors | | | | |
| TOTAL (TOTAL COMPLIANCE + NON-REGULATED COMPONENTS) | 436.61 | 368.47 | 68.14 (15.6%) | |

¹ Notes: This table is not used for Energy Code Compliance. CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Report Generated: 2023-07-25 10:57:22 Schema Version: rev 20220601 Compliance ID: EnergyPro-4958-0723-0145

| CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD | NRCC-PRF-E |
|--|----------------|
| Nonresidential Performance Compliance Method | (Page 7 of 17) |

| Non-Regulated Energy Component | Standard Design (SOURCE) | Proposed Design (SOURCE) | Compliance Margin (SOURCE) ¹ |
|---|--------------------------|--------------------------|---|
| Receptacle | 4.92 | 4.92 | |
| Process | | | |
| Other Ltg | | | |
| Process Motors | | | |
| TOTAL (TOTAL COMPLIANCE + NON-REGULATED COMPONENTS) | 32.57 | 26.54 | 6.03 (18.5%) |
| Notes: This table is not used for Energy Code Compliance. | • | • | • |

☐ This project is pursuing CalGreen Tier 2

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Report Generated: 2023-07-25 10:57:22

| Nonresidential Performance Compliance Method | | | |
|--|------------------------------|----------------|----------------|
| | | | (Page 1 of 17) |
| Project Name: 24X | X40 (PC 04-121369) - Wall AC | Date Prepared: | 2023-07-25 |

| A. G | A. General Information | | | | | | |
|------|---|-------------------------------|---------------|---|-------------------------|--|--|
| 1 | Project Name | 4X40 (PC 04-121369) - Wall AC | | | | | |
| 2 | Run Title | Title 24 Analysis | e 24 Analysis | | | | |
| 3 | Project Location | Climate Zone 15 | | | | | |
| 4 | City | Palm Springs | 5 | Standards Version | Compliance 2022 | | |
| 6 | Zip code | 99999 | 7 | Compliance Software (version) | EnergyPro 9.1 | | |
| 8 | Climate Zone | 15 | 9 | Building Orientation (deg) | 75 | | |
| 10 | Building Type(s) | Nonresidential | 11 | Weather File | PALM-SPRINGS_STYP20.epw | | |
| 12 | Project Scope | New complete scope | 13 | Number of Dwelling Units | 0 | | |
| 14 | Total Conditioned Floor Area in Scope (ft²) | 960 | 15 | Total # of hotel/motel rooms | 0 | | |
| 16 | Total Unconditioned Floor Area (ft²) | 0 | 17 | Fuel Type | Natural gas | | |
| 18 | Nonresidential Conditioned Floor Area | 960 | 19 | Total # of Stories (Habitable Above Grade) | 1 | | |
| 20 | Residential Conditioned Floor Area | 0 | | | | | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance

Report Version: 2022.0.000 Schema Version: rev 20220601

Report Generated: 2023-07-25 10:57:22 Compliance ID: EnergyPro-4958-0723-0145

Report Generated: 2023-07-25 10:57:22

Compliance ID: EnergyPro-4958-0723-0145

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E (Page 4 of 17) Nonresidential Performance Compliance Method

| | COMPLIES ² | | | | |
|-----------------------------|-----------------------|-----------------------|-------------------------|--|--|
| Energy Component | Standard Design (TDV) | Proposed Design (TDV) | Compliance Margin (TDV) | | |
| Space Heating | 5.43 | 9.65 | -4.22 | | |
| Space Cooling | 152.4 | 156.74 | -4.34 | | |
| Indoor Fans | 140.88 | 74.91 | 65.97 | | |
| Heat Rejection | 0 | 0 | 0 | | |
| Pumps & Misc. | 0 | 0 | 0 | | |
| Domestic Hot Water | 38.99 | 39 | -0.01 | | |
| Indoor Lighting | 32.22 | 21.48 | 10.74 | | |
| Flexibility | | | | | |
| EFFICIENCY COMPLIANCE TOTAL | 369.92 | 301.78 | 68.14 (18.4%) | | |
| Photovoltaics | | | | | |
| Batteries | | | | | |
| TOTAL COMPLIANCE | 369.92 | 301.78 | 68.14 (18.4%) | | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220601

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E nresidential Performance Compliance Method (Page 8 of 17)

| C7. ENERGY USE SUMMARY | | | | | | |
|------------------------|-------------------------------|-------------------------------|-----------------|--------------------------------|--------------------------------|------------------|
| Energy Component | Standard Design Site (MWh) | Proposed Design Site (MWh) | Margin (MWh) | Standard Design Site (MBtu) | Proposed Design Site (MBtu) | Margin (MBtu) |
| Space Heating | 0.1 | 0.3 | -0.2 | | | |
| Space Cooling | 4.5 | 4.5 | 0 | | | |
| Indoor Fans | 4.8 | 2.5 | 2.3 | | | |
| Heat Rejection | | | | | | |
| Pumps & Misc. | | | | | | |
| Domestic Hot Water | 1.5 | 1.5 | 0 | | | |
| Indoor Lighting | 1.2 | 0.8 | 0.4 | | | |
| Flexibility | | | | | | |
| EFFICIENCY TOTAL | 12.1 | 9.6 | 2.5 | 0 | 0 | 0 |
| Photovoltaics | | | | | | |
| Batteries | | | | | | |
| ENERGY USE SUBTOTAL | 12.1 | 9.6 | 2.5 | 0 | 0 | 0 |
| Receptacle | 2.5 | 2.5 | 0 | | | |
| Process | | | | | | |
| Other Ltg | | | | | | |
| Process Motors | | | | | | |
| ENERGY USE TOTAL | 14.6 | 12.1 | 2.5 | 0 | 0 | 0 |

Report Version: 2022.0.000 Report Generated: 2023-07-25 10:57:22 CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Compliance ID: EnergyPro-4958-0723-0145 Schema Version: rev 20220601

ROJECT SPECIFIC STATE AGENCY APPROVAL IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 12/18/2024

DESIGN ♦ CONSULTING ♦ PROJECT MGT

11590 W. BERNARDO COURT, SUITE 100 SAN DIEGO, CA 92127 PHONE: (858) 444-3344 WWW.RSTAVARES.COM

PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©



ORIGINAL PC STATE AGENCY APPROVAL APPROVED DIV. OF THE STATE ARCHITECT APP: 04-123059 PC

> Revision Schedule Description

PROJECT TITLE PC 2022 CBC: 24' x 40' **EXPANDABLE TO** 120' x 40'

24'x40' T24 CZ 15

PROJECT NUMBER 22088 CHECKED BY

RH/RT 06/15/2021

SHEET NO.

SHEET OF

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220601

Report Generated: 2023-07-25 10:57:22 Compliance ID: EnergyPro-4958-0723-0145

☐ This project is pursuing CalGreen Tier 1

Schema Version: rev 20220601

Compliance ID: EnergyPro-4958-0723-0145

Return / Relief Fan Supply Fan CFM CFM Power | Power Units | Control Fan Type CFM Power Power Units | Control 1,100 0.5 BHP Constant Vol N/A N/A N/A 364.8 ^l Status: N - New, A - Altered, E - Existing H8. SYSTEM SPECIAL FEATURES System Name Equipment Type Interlocks per 140.4(n)¹ Other Special Features and Controls Zone(s) With CO2 Sensor Vent. Control AC-1 Single Package VHP Air System otes: This table includes controls related to the performance path only. For projects using the prescriptive path, mandatory and prescriptive controls requirements are documented on the NRCC-MCH-E. 1 Yes = interlocks are provided, No = interlocks are not provided, NA means no operable openings. H9. NONRESIDENTIAL / COMMON USE AREA & HOTEL/MOTEL VENTILATION 01 02 05 06 Zone Name Conditioned Area (sf) **Ventilation Function** # of People Supply OA CFM Exhaust CFN Education - Classro 1-First Floor (ages 9-18) CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Report Generated: 2023-07-25 10:57:22 Compliance ID: EnergyPro-4958-0723-0145 Schema Version: rev 20220601 CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD Nonresidential Performance Compliance Method L. DECLARATION OF REQUIRED CERTIFICATES OF INSTALLATION selections made by Documentation Author indicate which Certificates of Installation must be submitted for the features to be recognized for compliance. These documents must be retained nd provided to the building inspector during construction and can be found online Envelope NRCI-ENV-01-E - Must be submitted for all buildings NRCI-ENV-E - Envelope (for all buildings) Envelope NRCI-MCH-01-E - Must be submitted for all buildings Mechanical Mechanical NRCI-MCH-E - For all buildings with Mechanical Systems NRCI-LTI-01-E - Must be submitted for all buildings Indoor Lighting NRCI-LTI-E - Indoor Lighting (for all buildings) Indoor Lighting M. DECLARATION OF REQUIRED CERTIFICATES OF ACCEPTANCE Selections made by Documentation Author indicate which Certificates of Acceptance must be submitted for the features to be recognized for compliance. These documents must be provided to the building inspector during construction and must be completed through an Acceptance Test Technician Certification Provider (ATTCP) **Building Component** NRCA-ENV-02-F - NRFC label verification for fenestration Envelope NRCA-LTI-02-A - Occupancy Sensors and Automatic Time Switch Controls. Indoor Lighting NRCA-MCH-02-A - Outdoor Air must be submitted for all newly installed HVAC units. Note: MCH-02-A can be performed in conjunction with Mechanical MCH-07-A Supply Fan VFD Acceptance (if applicable) since testing activities overlap NRCA-MCH-05-A - Air Economizer Controls Mechanical NRCA-MCH-06-A Demand Control Ventilation Systems must be submitted for all systems required to employ demand controlled ventilatio (refer to) can vary outside ventilation flow rates based on maintaining interior carbon dioxide (CO2) concentration setpoints. N. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION ections made by Documentation Author indicate which Certificates of Verification must be submitted for the features to be recognized for compliance. These documents must be retained and provided to the building inspector during construction and can be found online There are no Certificates of Verification applicable to this project CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Report Generated: 2023-07-25 10:57:22 Schema Version: rev 20220601 Compliance ID: EnergyPro-4958-0723-0145

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Standard Design (kBtu/ft² / yr) Proposed Design (kBtu/ft² / yr)

 1 Notes: Gross EUI is Energy Use Total (not including PV)/Total Building Area. Net EUI is Energy Use Total (including PV)/Total Building Area.

• The building does not include service water heating. Verify that service water heating is not required and is not included in the design.

• Project is claiming Exception 2 to Section 140.10(a): No PV system is required where the required PV system size is less than 4 kWdc.

02

Total Gross Surface Area (ft²)

240

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD

¹North-Facing is oriented to within 45 degrees of true north, including 45 00'00" east of north (NE), but excluding 45 00'00" west of north (NW), ²East-Facing is oriented to within 45 degrees of true east, including 45 00'00" south of east (SE), but excluding 45 00'00" north of east (NE), 3 South-Facing is oriented to within 45 degrees of true south, including 45 00'00" west of south (SW), but excluding 45 00'00" east of south (SE), ⁴West-Facing is oriented to within 45 degrees of true west, including 45 00'00" north of west (NW), but excluding 45 00'00" south of west (SW),

43.01

• The project uses the Simplified Geometry Performance Modeling Approach which is not capable of modeling daylighting controls and assumes the prescriptive Secondary

Daylit Control requirements are met. PRESCRIPTIVE COMPLIANCE documentation (form NRCC-LTI-02-E) for the requirements of section 140.6(d) Automatic Daylighting Controls

Schema Version: rev 20220601

Nonresidential Performance Compliance Method

G1. ENVELOPE GENERAL INFORMATION (conditioned spaces only)

01

Opaque Surfaces & Orientation

North-Facing¹

East-Facing²

West-Facing

South-Facing³

Nonresidential Performance Compliance Method

H3. NONRESIDENTIAL / COMMON USE AREA FAN SYSTEMS SUMMAR

C8. ENERGY USE INTENSITY (EUI)

D1. EXCEPTIONAL CONDITIONS

GROSS EUI¹

NET EUI¹

NRCC-PRF-E

(Page 9 of 17)

Margin Percentage

17.11

17.11

04

Window to Wall Ratio (%)

13.33

13.33

Report Generated: 2023-07-25 10:57:22

NRCC-PRF-E

(Page 12 of 17)

07

DCV or Occupant Senso

DCV

NRCC-PRF-E

(Page 15 of 17)

Compliance ID: EnergyPro-4958-0723-0145

N/A

Margin (kBtu/ft² / vr)

8.88

03

Total Fenestration Area (ft²)

NRCC-PRF-E CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD (Page 10 of 17 Nonresidential Performance Compliance Method G4. NONRESIDENTIAL AIR BARRIER **Building Story Name** Air Barrier Com-Floor 1 No air barrier G5. OPAQUE SURFACE ASSEMBLY SUMMARY Continuous R-Value Construction raming Surface Nam Type R-Value ood siding - 1/2 in. apor permeable felt - 1/8 in. R-19 Wood xterior Wal 1,280 Wood N/A N/A U-factor 0.0605 Composite-1 Framed Wal Gypsum Board - 1/2 ir Softwood - 1.5 in. R-19 Metal Metal N/A N/A U-facto Floor Crawlspa14 arpet - 3/4 in. Metal Standing Seam - 1/16 in. Standing Seam Roof N/A N/A N/A R-38 Metal16 ¹ Status: N - New, A - Altered, E - Existing

Report Version: 2022.0.000

Schema Version: rev 20220601

Rated Capacity (kBtuh) Airflow (cfm) System ID Design 1-First Floor-Trm N/A 1,100 N/A 0 N/A N/A Uncontrolled 1 N/A K1. INDOOR CONDITIONED LIGHTING GENERAL INFO Additional (Custom) Allowance Installed Lighting Powe **Lighting Control Credits** Occupancy Type¹ **Area Category Footnotes Area Category Footnot** Classroom, Lecture, or Training Vocational **Building Totals:** See Table 140.6-C ²See NRCC-LTI--E for unconditioned spaces

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance

³Lighting information for existing spaces modeled is not included in this table

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance

esponsible Designer Name:

Company: R & S Tavares Associates

City/State/Zip: San Diego, Ca. 92127

Address: 11590 W. Bernardo Court, Suite 100

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance

Nonresidential Performance Compliance Method

H11. ZONAL SYSTEM AND TERMINAL UNIT SUMMARY

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E **Nonresidential Performance Compliance Method** (Page 16 of 17) **Documentation Author's Declaration Statement** 1. I certify that this Certificate of Compliance documentation is accurate and complete ocumentation Author Name: LAL B. SAHGAL ocumentation Author Signature: Company: LSA CONSULTING ENGINEERS Signature Date: ress: 83, WINDSWEPT WAY CEA/HERS Certification Identification (if applicable): M26885 City/State/Zip: MISSION VIEJO, CA 92692 Phone: (949) 830-4746 **Responsible Person's Declaration statement** I certify the following under penalty of perjury, under the laws of the State of California: The information provided on this Certificate of Compliance is true and correct. I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design or system design identified on this Certificate of Compliance (responsible designer) 3. The energy features and performance specifications, materials, components, and manufactured devices for the building design or system design identified on this Certificate of Compliance conform to the requirements of Title 24, Part 1 and Part 6 of the California Code of Regulations. 4. The building design features or system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations, plans and specifications submitted to the enforcement agency for approval with this building permit application. 5. I understand that a registered copy of this Certificate of Compliance shall be made available with the building permit(s) issued for the building, and made available to the enforcement agency for all applicable inspections, and I will take the necessary steps to accomplish this requirement. 6. I understand that a registered copy of this Certificate of Compliance is required to be included with the documentation the builder provides to the building owner at occupancy, and I will take the necessary steps to accomplish these requirements. Responsible Designer Signature: ompany: R & S Tavares Associates Address: 11590 W. Bernardo Court, Suite 100 Date Signed: City/State/Zip: San Diego, Ca. 92127 License #:

Responsible Designer Signature:

Date Signed:

License #:

Report Version: 2022.0.000

Schema Version: rev 20220601

Report Version: 2022.0.000

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E Nonresidential Performance Compliance Method (Page 17 of 17) Responsible Designer Name: Lal Sahgal sponsible Designer Signature ompany: LSA Consulting Engineers dress: 83. Windswept Way Date Signed: v/State/Zip: Mission Vieio, Ca. 92692 License #: M26885

Report Version: 2022.0.000

Schema Version: rev 20220601

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E (Page 11 of 17) Nonresidential Performance Compliance Method

G7A. FENESTRATION ASSEMBLY SUMMARY (NONRESIDENTIAL) Overall Fenestration Overall VT nestration Type/ Product Type / Frame Typ Overall SHG0 **Assembly Nam** Vertical fenestration Sierra Pacific Operable window Manufactured 0.35 0.24 Windows N/A Skylight NFRC 0.39 0.37 0.65 Sola tube Manufactured Fixed window Notes: Newly installed fenestration shall have a certified NFRC Label Certificate or use the CEC default tables found in Table 110.6-A and Table 110.6-B. Center of Glass (COG)

values are for the glass-only, determined by the manufacturer, and are shown for ease of verification. Site-built fenestration values are calculated per Nonresidential Appendix NA6 and are used in the analysis. Status: N - New, A - Altered, E - Existing

H1. DRY SYSTEM EQUIPMENT (FURNACES, AIR HANDLING UNITS, HEAT PUMPS, VRF, ECONOMIZERS ETC.) Total Type (if Heating Cooling Output Output (kBtu/h) (kBtu/h Single Package 13.65 COP Fixed DB VHP Air System

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220601

Status: N - New, A - Altered, E - Existing

Report Generated: 2023-07-25 10:57:22

Report Generated: 2023-07-25 10:57:22

Report Generated: 2023-07-25 10:57:22

Compliance ID: EnergyPro-4958-0723-0145

Report Generated: 2023-07-25 10:57:22

Compliance ID: EnergyPro-4958-0723-0145

Compliance ID: EnergyPro-4958-0723-0145

NRCC-PRF-E

(Page 13 of 17)

Compliance ID: EnergyPro-4958-0723-0145

Compliance ID: EnergyPro-4958-0723-0145 CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E

Nonresidential Performance Compliance Method (Page 14 of 17) K2. INDOOR CONDITIONED LIGHTING SCHEDULE uminaire Schedule (includes all permanent installed lighting in conditioned space, and portable lighting over 0.3 w/f ${
m t}^2$ in offices) 06 Complete Luminaire Installed Watts (Conditioned) Description (i.e. 3-lamp Name or Item Tag fluorescent troffer, F32T8, Installed Watts one dimmable electronic

If lighting power densities were used in the compliance model Building Departments will need to check prescriptive forms for Luminaire Schedule details. K3. INDOOR CONDITIONED LIGHTING CONTROL CREDITS Lighting Control Credits Schedule (includes all lighting controls installed in conditioned space for compliance credit per 140.6(a)2 and Table 140.6-A) **Primary Function Area (must** Power Lighting Controlled # of **Control Credit Area Description** meet requirements of Table Type of Lighting Contro Adjustment Item Tag (Watts) 140.6-A and 170.2-L) Factor (PAF) (Watts) S-1-First Floor N/A N/A Training Vocational

According to

Lighting Control Credits (Conditioned) Total (Watts) K4. INDOOR CONDITIONED LIGHTING MANDATORY LIGHTING CONTROL **Building Level Controls** Shut-Off Controls 130.1(c) & 160.5(b)4 See NRCC-LTI-E for mandatory controls


CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000


2x4 LED Panel

Report Generated: 2023-07-25 10:57:22

384

Report Generated: 2023-07-25 10:57:22








PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©

CLIENT 1651Juanita Street, San Jacinto, CA 92583 Voice (951) 943-1908 Fax (951)943-5768



Revision Schedule Description

PROJECT TITLE

PC 2022 CBC: 24' x 40' **EXPANDABLE TO** 120' x 40'

24'x40' T24 CZ 15

PROJECT NUMBER 22088 DRAWN BY rMc/CG CHECKED BY RH/RT

DATE 06/15/2021

SHFFT OF

24X40 (PC 04-121369) - Wall AC Climate Zone 16 Blue Canyon, CA

Project Designer:

R & S Tavares Associates 11590 W. Bernardo Court, Suite 100 San Diego, Ca. 92127

Report Prepared by:

LAL B. SAHGAL LSA CONSULTING ENGINEERS 83, WINDSWEPT WAY MISSION VIEJO, CA 92692 (949) 830-4746

Job Number:

Date: 7/26/2023

The EnergyPro computer program has been used to perform the calculations summarized in this compliance report. This program has approval and is authorized by the California Energy Commission for use with both the Residential and Nonresidential 2022 Building Energy Efficiency Standards. This program developed by EnergySoft, LLC – www.energysoft.com.

| CERTIFICATE OF COMPLIANC | E - NONRESID | DENTIAL PERFORI | MANCE COMPLIANCE METH | HOD |) | | NRCC-PRF- |
|---|--------------|---------------------|--|---------------|--------------------|--|---|
| Nonresidential Performance | Compliance I | Method | | | | | (Page 2 of 17 |
| B. PROJECT SUMMARY | | | | | | | |
| Table B shows which building o permit application. | components a | ire included in the | e performance calculation. I | f ina | licated as not inc | luded, the project must show compliance prescri | ptively if within th |
| В | uilding Comp | onents Complyir | ng via Performance | | | Building Components Complying Pre | scriptively |
| Envelope (See Table G) | Nonres | Performance | Solar Thermal Water | | Performance | The following building components are ONLY eligible for and should be documented on the NRCC form listed if w | |
| Elivelope (see Table G) | MultiFam | Not Included | Heating (See Table I3) | \boxtimes | Not Included | permit application (i.e. compliance will not be shown | |
| Machanical (See Table II) | Nonres | Performance | Covered Process: Commercial Kitchens (see | | Performance | Indoor Lighting (Unconditioned) 140.6 & 170.2(e) | NRCC-LTI-E is required |
| Mechanical (See Table H) | MultiFam | Not Included | Table J) | \boxtimes | Not Included | Outdoor Lighting 140.7 & 170.2(e) | NRCC-LTO-E is required |
| Domestic Hot Water (See Table I) | Nonres | Not Included | Covered Process: Laboratory Exhaust (see | | Performance | Sign Lighting 140.8 & 170.2(e) | NRCC-LTS-E is required |
| Table 1) | MultiFam | Not Included | Table J) | \boxtimes | Not Included | Building Components Complying with Man | datory Measures |
| Lighting (Indoor Conditioned, see Table K) | Nonres | Performance | Photovoltaics (see Table F) | | Performance | Electrical power systems, commissioning, solar escalator requirements are mandatory and sho on the NRCC form listed if applicable (i.e. comshown on the NRCC-PRF-E.) | ould be documente opliance will not be |
| | MultiFam | Not Included | | \boxtimes | Not Included | Electrical Power Distribution 110.11 | NRCC-ELC-E is required |
| | | • | | $\overline{}$ | | i | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Generated: 2023-07-26 13:02:48 Report Version: 2022.0.000 Compliance ID: EnergyPro-4958-0723-0170 Schema Version: rev 20220601

Battery (see Table F)

| CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD | NRCC-PRF-E | |
|--|----------------|--|
| Nonresidential Performance Compliance Method | (Page 6 of 17) | |

| | COMPLIES ² | | |
|-----------------------------|--------------------------|--------------------------|---|
| Energy Component | Standard Design (SOURCE) | Proposed Design (SOURCE) | Compliance Margin (SOURCE) ¹ |
| Space Heating | 16.26 | 11.75 | 4.51 |
| Space Cooling | 1.3 | 1.31 | -0.01 |
| Indoor Fans | 16.75 | 8.32 | 8.43 |
| Heat Rejection | 0 | 0 | 0 |
| Pumps & Misc. | 0 | 0 | 0 |
| Domestic Hot Water | 13.04 | 13.04 | 0 |
| Indoor Lighting | 2.57 | 1.71 | 0.86 |
| Flexibility | | | |
| EFFICIENCY COMPLIANCE TOTAL | 49.92 | 36.13 | 13.79 (27.6%) |
| Photovoltaics | | | |
| Batteries | | | |
| TOTAL COMPLIANCE | 49.92 | 36.13 | 13.79 (27.6%) |

TABLE OF CONTENTS

| Cover Page Table of Contents | 1 2 3 |
|--|-------------|
| Form NRCC/LMCC-PRF-E Certificate of Compliance HVAC System Heating and Cooling Loads Summary | 3 20 |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

| Nonresidential Performance Compliance Method | | | (Page 3 of 17) |
|--|-----------------------------|------------------------|------------------------|
| | | | |
| C1. COMPLIANCE SUMMARY | , | | |
| | COMPLIES ³ | | |
| | Time Dependen | t Valuaton (TDV) | Source Energy Use |
| | Efficiency¹ (kBtu/ft² - yr) | Total² (kBtu/ft² - yr) | Total² (kBtu/ft² - yr) |
| Standard Design | 307.23 | 307.23 | 49.92 |
| Proposed Design | 273.51 | 273.51 | 36.13 |
| Compliance Margins | 33.72 | 33.72 | 13.79 |

³ Building complies when efficiency and total compliance margins are greater than or equal to zero and unmet load hour limits are not exceeded

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD

¹ Efficiency measures include improvements like a better building envelope and more efficient equipment

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Nonresidential Performance Compliance Method

² Compliance Totals include efficiency, photovoltaics and batteries

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Report Generated: 2023-07-26 13:02:48 Compliance ID: EnergyPro-4958-0723-0170 Schema Version: rev 20220601

| C3. TDV ENERGY RESULTS FOR NON-REGULATED COMPONENTS ¹ | | | | |
|--|-----------------------|-----------------------|-------------------------|--|
| Non-Regulated Energy Component | Standard Design (TDV) | Proposed Design (TDV) | Compliance Margin (TDV) | |
| Receptacle | 63.66 | 63.66 | | |
| Process | | | | |
| Other Ltg | | | | |
| Process Motors | | | | |
| TOTAL (TOTAL COMPLIANCE + NON-REGULATED COMPONENTS) | 370.89 | 337.17 | 33.72 (9.1%) | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Report Generated: 2023-07-26 13:02:48 Schema Version: rev 20220601 Compliance ID: EnergyPro-4958-0723-0170

| CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD | NRCC-PRF-E |
|--|----------------|
| Nonresidential Performance Compliance Method | (Page 7 of 17) |

| Non-Regulated Energy Component | Standard Design (SOURCE) | Proposed Design (SOURCE) | Compliance Margin (SOURCE) ¹ | | | | |
|---|--------------------------|--------------------------|---|--|--|--|--|
| Receptacle | 4.92 | 4.92 | | | | | |
| Process | | | | | | | |
| Other Ltg | | | | | | | |
| Process Motors | | | | | | | |
| TOTAL (TOTAL COMPLIANCE + NON-REGULATED COMPONENTS) | 54.84 | 41.05 | 13.79 (25.1%) | | | | |
| ¹ Notes: This table is not used for Energy Code Compliance. | | | | | | | |
| | | | | | | | |
| C6. 'ABOVE CODE' QUALIFICATIONS | | | | | | | |
| ☐ This project is pursuing CalGreen Tier 1 ☐ This project is pursuing CalGreen Tier 2 | | | | | | | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E (Page 1 of 17) **Nonresidential Performance Compliance Method** 24X40 (PC 04-121369) - Wall AC | Date Prepared: 2023-07-26 **Project Name:**

| А. С | A. General Information | | | | | | | | |
|------|---|--------------------------------|---|---|------------------------|--|--|--|--|
| 1 | Project Name | 24X40 (PC 04-121369) - Wall AC | X40 (PC 04-121369) - Wall AC | | | | | | |
| 2 | Run Title | Title 24 Analysis | | | | | | | |
| 3 | Project Location | Climate Zone 16 | | | | | | | |
| 4 | City | Blue Canyon | ue Canyon 5 Standards Version Compliance 2022 | | | | | | |
| 6 | Zip code | 99999 | 7 | Compliance Software (version) | EnergyPro 9.1 | | | | |
| 8 | Climate Zone | 16 | 9 | Building Orientation (deg) | 30 | | | | |
| 10 | Building Type(s) | Nonresidential | 11 | Weather File | BLUE-CANYON_STYP20.epw | | | | |
| 12 | Project Scope | New complete scope | 13 | Number of Dwelling Units | 0 | | | | |
| 14 | Total Conditioned Floor Area in Scope (ft²) | 960 | 15 | Total # of hotel/motel rooms | 0 | | | | |
| 16 | Total Unconditioned Floor Area (ft²) | 0 | 17 | Fuel Type | Natural gas | | | | |
| 18 | Nonresidential Conditioned Floor Area | 960 | 19 | Total # of Stories (Habitable Above Grade) | 1 | | | | |
| 20 | Residential Conditioned Floor Area | 0 | | | | | | | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance

Report Version: 2022.0.000 Schema Version: rev 20220601

Report Generated: 2023-07-26 13:02:48 Compliance ID: EnergyPro-4958-0723-0170

| CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD | NRCC-PRF- |
|--|---------------|
| Nonresidential Performance Compliance Method | (Page 4 of 17 |

| COMPLIES ² | | | | | | | |
|-----------------------------|-----------------------|-----------------------|--------------------------------------|--|--|--|--|
| Energy Component | Standard Design (TDV) | Proposed Design (TDV) | Compliance Margin (TDV) ¹ | | | | |
| Space Heating | 51.5 | 114.86 | -63.36 | | | | |
| Space Cooling | 19.06 | 18.57 | 0.49 | | | | |
| Indoor Fans | 169.42 | 83.19 | 86.23 | | | | |
| Heat Rejection | 0 | 0 | 0 | | | | |
| Pumps & Misc. | 0 | 0 | 0 | | | | |
| Domestic Hot Water | 36.19 | 36.19 | 0 | | | | |
| Indoor Lighting | 31.06 | 20.7 | 10.36 | | | | |
| Flexibility | | | | | | | |
| EFFICIENCY COMPLIANCE TOTAL | 307.23 | 273.51 | 33.72 (11%) | | | | |
| Photovoltaics | | | | | | | |
| Batteries | | | | | | | |
| TOTAL COMPLIANCE | 307.23 | 273.51 | 33.72 (11%) | | | | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000

Schema Version: rev 20220601

Report Generated: 2023-07-26 13:02:48 Compliance ID: EnergyPro-4958-0723-0170

Report Generated: 2023-07-26 13:02:48

Compliance ID: EnergyPro-4958-0723-0170

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E Nonresidential Performance Compliance Method (Page 8 of 17)

| Energy Component | Standard Design Site (MWh) | Proposed Design Site (MWh) | Margin (MWh) | Standard Design Site (MBtu) | Proposed Design Site (MBtu) | Margin (MBtu) |
|---------------------|-------------------------------|-------------------------------|-----------------|--------------------------------|--------------------------------|------------------|
| Space Heating | 0.1 | 3 | -2.9 | 16.4 | | |
| Space Cooling | 0.8 | 0.7 | 0.1 | | | |
| Indoor Fans | 5.6 | 2.8 | 2.8 | | | |
| Heat Rejection | | | | | | |
| Pumps & Misc. | | | | | | |
| Domestic Hot Water | | | | 13.6 | 13.6 | 0 |
| Indoor Lighting | 1.2 | 0.8 | 0.4 | | | |
| Flexibility | | | | | | |
| EFFICIENCY TOTAL | 7.7 | 7.3 | 0.4 | 30 | 13.6 | 16.4 |
| Photovoltaics | | | | | | |
| Batteries | | | | | | |
| ENERGY USE SUBTOTAL | 7.7 | 7.3 | 0.4 | 30 | 13.6 | 16.4 |
| Receptacle | 2.5 | 2.5 | 0 | | | |
| Process | | | | | | |
| Other Ltg | | | | | | |
| Process Motors | | | | | | |
| ENERGY USE TOTAL | 10.2 | 9.8 | 0.4 | 30 | 13.6 | 16.4 |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220601 PROJECT SPECIFIC STATE AGENCY APPROVAL IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 12/18/2024

DESIGN ♦ CONSULTING ♦ PROJECT MGT 11590 W BERNARDO COURT, SUITE 100 SAN DIEGO, CA 92127

PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©



ORIGINAL PC STATE AGENCY APPROVAL APPROVED DIV. OF THE STATE ARCHITECT APP: 04-123059 PC

> Revision Schedule Description

PRE-CHECK (PC) DOCUMENT

CODE: 2019 CBC A separate project application for construction

is required

PC 2022 CBC: 24' x 40' **EXPANDABLE TO** 120' x 40'

24'x40' T24 CZ 16

PROJECT NUMBER 22088 Author CHECKED BY Checker

DATE 06/15/2021

SHEET OF

SHEET NO.

NRCC-CXR-E is required

NRCC-SAB-E is

required

Solar and Battery 110.10

NRCC-PRF-E

NRCC-PRF-E

(Page 5 of 17)

| Nonresidential Performance Com | npliance Method | | | (Page 9 of 17 | | | | |
|--------------------------------|---------------------------------|---------------------------------|------------------------|-------------------|--|--|--|--|
| | | | | | | | | |
| C8. ENERGY USE INTENSITY (EUI) | | | | | | | | |
| | Standard Design (kBtu/ft² / vr) | Proposed Design (kBtu/ft² / vr) | Margin (kBtu/ft² / vr) | Margin Percentage | | | | |

| CO. ENERGY OSE INVENSITY (EST) | | | | | | | | |
|---|---------------------------------|---------------------------------|------------------------|-------------------|--|--|--|--|
| | Standard Design (kBtu/ft² / yr) | Proposed Design (kBtu/ft² / yr) | Margin (kBtu/ft² / yr) | Margin Percentage | | | | |
| GROSS EUI ¹ | 67.5 | 49 | 18.5 | 27.41 | | | | |
| NET EUI ¹ 67.5 49 18.5 27.41 | | | | | | | | |
| ¹ Notes: Gross EUI is Energy Use Total (not including PV)/Total Building Area. Net EUI is Energy Use Total (including PV)/Total Building Area. | | | | | | | | |

D1. EXCEPTIONAL CONDITIONS

• The project uses the Simplified Geometry Performance Modeling Approach which is not capable of modeling daylighting controls and assumes the prescriptive Secondary Daylit Control requirements are met. PRESCRIPTIVE COMPLIANCE documentation (form NRCC-LTI-02-E) for the requirements of section 140.6(d) Automatic Daylighting Controls • The building does not include service water heating. Verify that service water heating is not required and is not included in the design.

• Project is claiming Exception 2 to Section 140.10(a): No PV system is required where the required PV system size is less than 4 kWdc.

| 01 | 02 | 03 | 04 |
|-------------------------------|---|--|--------------------------|
| Opaque Surfaces & Orientation | Total Gross Surface Area (ft ²) | Total Fenestration Area (ft ²) | Window to Wall Ratio (%) |
| North-Facing ¹ | 400 | 0 | 0 |
| East-Facing ² | 240 | 32 | 13.33 |
| South-Facing ³ | 400 | 0 | 0 |
| West-Facing ⁴ | 240 | 32 | 13.33 |
| Total | 1280 | 64 | 5 |
| Roof | 960 | 14 | 1.46 |

North-Facing is oriented to within 45 degrees of true north, including 45 00'00" east of north (NE), but excluding 45 00'00" west of north (NW), ²East-Facing is oriented to within 45 degrees of true east, including 45 00'00" south of east (SE), but excluding 45 00'00" north of east (NE), 3South-Facing is oriented to within 45 degrees of true south, including 45 00'00" west of south (SW), but excluding 45 00'00" east of south (SE), ⁴West-Facing is oriented to within 45 degrees of true west, including 45 00'00" north of west (NW), but excluding 45 00'00" south of west (SW),

Report Generated: 2023-07-26 13:02:48 CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000

| | Schema Version: rev 20220601 | Compliance ID: EnergyPro-4958-0723-0 |
|--|------------------------------|--------------------------------------|
| CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COM | NRCC-PRI | |
| Nonresidential Performance Compliance Method | | (Page 12 of |
| | | |

| H3. NONRESIDENTIAL / COMMON USE AREA FAN SYSTEMS SUMMARY | | | | | | | | | | | | |
|--|---------|----------------------|-----------|-------|-------------|--------------|----------|---------------------|-------|-------------|---------|---------------------|
| 01 | 02 | 03 | 04 | 05 | 06 | 07 | 08 | 09 | 10 | 11 | 12 | 13 |
| Name or Item Tag | I OTV I | Qty Design OA CFM | Design OA | | Supp | ly Fan | | Return / Relief Fan | | | | C+-+1 |
| Name or Item Tag | | | CFM | Power | Power Units | Control | Fan Type | CFM | Power | Power Units | Control | Status ¹ |
| AC-1 | 1 | 364.8 | 1,100 | 0.5 | ВНР | Constant Vol | N/A | N/A | N/A | N/A | N/A | N |

H8. SYSTEM SPECIAL FEATURES

¹ Status: N - New, A - Altered, E - Existing

| 01 | | 02 | 03 | 04 Other Special Features and Controls | | |
|--|--|----|--------------------------------------|--|--|--|
| | System Name Equipment Type | | Interlocks per 140.4(n) ¹ | | | |
| | AC-1 Single Package VHP Air System No Zone(s) With CO2 Sensor Vent. Co | | | | | |
| Notes: This table includes controls related to the performance path only. For projects using the prescriptive path, mandatory and prescriptive controls requirements ar NRCC-MCH-F | | | | | | |

H9. NONRESIDENTIAL / COMMON USE AREA & HOTEL/MOTEL VENTILATION

 1 Yes = interlocks are provided, No = interlocks are not provided, NA means no operable openings.

| | 01 | 02 | 03 | 04 | 05 | 06 | 07 | |
|---|---------------|---------------------------------------|-------------|---------------|-------------|---|-------------------|--|
| ſ | Zone Name | | | Ventilation | | Conditioned Area (sf) DCV or Occupant Sensor | | |
| L | | Ventilation Function | # of People | Supply OA CFM | Exhaust CFM | , | Controls, or Both | |
| ſ | 1-First Floor | Education - Classrooms (ages 9-18) | 24 | 364.8 | 0 | 960 | DCV | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220601

Report Generated: 2023-07-26 13:02:48 Compliance ID: EnergyPro-4958-0723-0170

| CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD | NRCC-PRF-E |
|--|-----------------|
| Nonresidential Performance Compliance Method | (Page 15 of 17) |
| | |
| L. DECLARATION OF REQUIRED CERTIFICATES OF INSTALLATION | |

| Building Component | Form/Title |
|---------------------------|--|
| Envelope | NRCI-ENV-01-E - Must be submitted for all buildings |
| Envelope | NRCI-ENV-E - Envelope (for all buildings) |
| Mechanical | NRCI-MCH-01-E - Must be submitted for all buildings |
| Mechanical | NRCI-MCH-E - For all buildings with Mechanical Systems |
| Indoor Lighting | NRCI-LTI-01-E - Must be submitted for all buildings |
| Indoor Lighting | NRCI-LTI-E - Indoor Lighting (for all buildings) |

| selections made by Documentation Author indicate which Certificates of Acceptance must be submitted for the features to be recognized for compliance. These documents must be provided to the building inspector during construction and must be completed through an Acceptance Test Technician Certification Provider (ATTCP). | | | | | | |
|--|---|--|--|--|--|--|
| Building Component | Form/Title | | | | | |
| Envelope | NRCA-ENV-02-F - NRFC label verification for fenestration | | | | | |
| Indoor Lighting | NRCA-LTI-02-A - Occupancy Sensors and Automatic Time Switch Controls. | | | | | |
| Mechanical | NRCA-MCH-02-A - Outdoor Air must be submitted for all newly installed HVAC units. Note: MCH-02-A can be performed in conjunction with MCH-07-A Supply Fan VFD Acceptance (if applicable) since testing activities overlap | | | | | |
| Mechanical | NRCA-MCH-05-A - Air Economizer Controls | | | | | |
| Machanical | NRCA-MCH-06-A Demand Control Ventilation Systems must be submitted for all systems required to employ demand controlled ventilation | | | | | |

N. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION

Selections made by Documentation Author indicate which Certificates of Verification must be submitted for the features to be recognized for compliance. These documents must be retained and provided to the building inspector during construction and can be found online There are no Certificates of Verification applicable to this project

(refer to) can vary outside ventilation flow rates based on maintaining interior carbon dioxide (CO2) concentration setpoints.

Report Generated: 2023-07-26 13:02:48 CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220601 Compliance ID: EnergyPro-4958-0723-0170 CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E (Page 10 of 17) Nonresidential Performance Compliance Method

| | NTIAL AIR BARRIER | | | | | | | | | | | | |
|-----------------------------------|-------------------|---------------|---------|---------|----------|------------|-------------|--------|--|---------------------|--|--|--|
| | | 01 | | | | | | | 02 | | | | |
| | | Building Stor | y Name | | | | Air Barrier | | | | | | |
| | | Com-Flo | or 1 | | | | | | No air barrier | | | | |
| G5. OPAQUE SUF | RFACE ASSEMBLY S | UMMARY | | | | | | | | | | | |
| 01 | 02 | 03 | 04 | 05 | 0 | 6 | 07 | 08 | 09 | 10 | | | |
| Surface Name | Construction | Area (ft²) | Framing | Cavity | Continuo | ıs R-Value | Units | Value | Description of Assembly Layers | Status ¹ | | | |
| Surface Name | Туре | Area (It) | Туре | R-Value | Interior | Exterior | Oilles | value | Description of Assembly Layers | Status | | | |
| R-19 Wood Framed Wall7 | Exterior Wall | 1,280 | Wood | 19 | N/A | N/A | U-factor | 0.0605 | Wood siding - 1/2 in. Vapor permeable felt - 1/8 in. Composite-1 Gypsum Board - 1/2 in. Softwood - 1.5 in. | N | | | |
| R-19 Metal Floor Crawlspa14 | Exterior Floor | 960 | Metal | 19 | N/A | N/A | U-factor | 0.0588 | Vented Crawl Space Composite-2 Plywood - 1/2 in. Carpet - 3/4 in. | N | | | |
| | Roof | 960 | N/A | 36 | N/A | N/A | U-factor | 0.06 | Metal Standing Seam - 1/16 in. | N | | | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Report Generated: 2023-07-26 13:02:48 Compliance ID: EnergyPro-4958-0723-0170 Schema Version: rev 20220601 CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E Nonresidential Performance Compliance Method (Page 13 of 17)

| | | | | | | | | | | (8 | , |
|---------------------------|------------------------|-----|--------------|---------------|--------|------|------------|-------|-------|--------|-----|
| | | | | | | | | | | | |
| H11. ZONAL SYSTEM AND TER | MINAL UNIT SUMMARY | | | | | | | | | | |
| 01 | 02 | 03 | 04 | 05 | 06 | 07 | 08 | 09 | 10 | 11 | 12 |
| | Rated Capacity (kBtuh) | | city (kBtuh) | Airflow (cfm) | | | Fan | | | | |
| System ID | System Type | Qty | Heating | Cooling | Design | MIn. | Min. Ratio | Power | Power | Cycles | VSD |

| K1. INDOOR CONDITIONED LIGHTING GENERAL INFO |
|--|
| KI. INDOOR CONDITIONED LIGHTING GENERAL INFO |

| 01 | 02 | 03 | 04 | 05 | 06 | |
|---|--|--------------------------|---|------------------------------------|------------------------------------|--|
| | | Installed Lighting Power | Lighting Control Credits | Additional (Custom) Allowance | | |
| Occupancy Type ¹ | Conditioned Floor Area ² (ft ²) | (Watts) | (Watts) Area Category Footnotes (Watts) | Area Category Footnotes Area Categ | Area Category Footnotes (Watts) | |
| Classroom, Lecture, or Training Vocational | 960 | 384 | 0 | 0 | 0 | |
| Building Totals: | 960 | 384 | 0 | 0 | 0 | |
| ¹ See Table 140.6-C | | | | | | |
| ² See NRCC-LTIE for uncondition | ned spaces | | | | | |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance

onsible Designer Name:

Company: R & S Tavares Associates

City/State/Zip: San Diego, Ca. 92127

Address: 11590 W. Bernardo Court, Suite 100

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD

³Lighting information for existing spaces modeled is not included in this table

Report Version: 2022.0.000

Report Generated: 2023-07-26 13:02:48 Compliance ID: EnergyPro-4958-0723-0170

NRCC-PRF-E

| Nonre | sidential Performance Compliance Method | (Page 16 of 17) |
|-----------|--|--|
| Docume | entation Author's Declaration Statement | |
| 1. I cert | tify that this Certificate of Compliance documentation is accurate and comple | te. |
| Docume | entation Author Name: LAL B. SAHGAL | Documentation Author Signature: |
| Compar | ny: LSA CONSULTING ENGINEERS | Signature Date: |
| Address | s: 83, WINDSWEPT WAY | CEA/HERS Certification Identification (if applicable): M26885 |
| City/Sta | ate/Zip: MISSION VIEJO, CA 92692 | Phone: (949) 830-4746 |
| | Compliance (responsible designer) The energy features and performance specifications, materials, components, Certificate of Compliance conform to the requirements of Title 24, Part 1 and The building design features or system design features identified on this Cert compliance documents, worksheets, calculations, plans and specifications su I understand that a registered copy of this Certificate of Compliance shall be the enforcement agency for all applicable inspections, and I will take the necessity. | responsibility for the building design or system design identified on this Certificate of and manufactured devices for the building design or system design identified on this Part 6 of the California Code of Regulations. ificate of Compliance are consistent with the information provided on other applicable bmitted to the enforcement agency for approval with this building permit application. made available with the building permit(s) issued for the building, and made available to essary steps to accomplish this requirement. |
| Respons | sible Designer Name: | Responsible Designer Signature: |
| Compar | ny: R & S Tavares Associates | |
| Address | s: 11590 W. Bernardo Court, Suite 100 | Date Signed: |
| City/Sta | ate/Zip: San Diego, Ca. 92127 | License #: |
| Dhanai | | Title: |

| CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance | Report Version: 2022.0.000 | Report Generated: 2023-07-26 13:02:48 |
|--|------------------------------|---|
| | Schema Version: rev 20220601 | Compliance ID: EnergyPro-4958-0723-0170 |

Date Signed:

License #:

esponsible Designer Signature:

| CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD Nonresidential Performance Compliance Method | | | | | | |
|--|-------------------|-------------------|--|--|--|---------------------------------------|
| | | | | | | Responsible Designer Name: Lal Sahgal |
| Company: LSA Consulting Engineers | | | | | | |
| Address: 83, Windswept Way | Date Signed: | Date Signed: | | | | |
| City/State/Zip: Mission Viejo, Ca. 92692 | License #: M26885 | License #: M26885 | | | | |
| Phone: | Title: | Scope: | | | | |

Report Version: 2022.0.000

Schema Version: rev 20220601

Report Generated: 2023-07-26 13:02:48 Compliance ID: EnergyPro-4958-0723-0170 CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E Nonresidential Performance Compliance Method (Page 11 of 17)

| 01 | 02 | 03 | 04 | 05 | 06 | 07 | 08 | 09 |
|-------------------------------|---|--------------------------------------|-----------------|----------------------------|---------------------|--------------|------------|---------------------|
| Fenestration Assembly Name | Fenestration Type/ Product Type / Frame Type | Certification Method ¹ | Assembly Method | Area (ft ²) | Overall U-factor | Overall SHGC | Overall VT | Status ² |
| Sierra Pacific Windows | Vertical fenestration Operable window N/A | NFRC | Manufactured | 64 | 0.35 | 0.24 | 0.5 | N |
| Sola tube | Skylight Fixed window N/A | NFRC | Manufactured | 14 | 0.39 | 0.37 | 0.65 | N |

values are for the glass-only, determined by the manufacturer, and are shown for ease of verification. Site-built fenestration values are calculated per Nonresidential Appendix NA6 and are used in the analysis. ² Status: N - New, A - Altered, E - Existing

| 01 | 02 | 03 | 04 | 05 | 06 | 07 | 08 | 09 | 10 | 11 | 12 |
|----------------|----------------------------------|-----|--|---------------------------------|--------------------|------------|--|--------------------|------------|------------------------------------|---------------------|
| | | | | Hea | ting | | | Cooling | | | |
| Equipment Name | Equipment Type | Qty | Total Heating Output (kBtu/h) | Supp Heat Output (kBtu/h) | Efficiency Unit | Efficiency | Total Cooling Output (kBtu/h) | Efficiency Unit | Efficiency | Economizer Type (if present) | Status ¹ |
| AC-1 | Single Package VHP Air System | 1 | 34.37 | 13.65 | СОР | 3.3 | 34.56 | EER | 11 | Fixed DB | N |

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance

Report Version: 2022.0.000 Schema Version: rev 20220601

Report Generated: 2023-07-26 13:02:48 Compliance ID: EnergyPro-4958-0723-0170

CERTIFICATE OF COMPLIANCE - NONRESIDENTIAL PERFORMANCE COMPLIANCE METHOD NRCC-PRF-E Nonresidential Performance Compliance Method (Page 14 of 17) K2. INDOOR CONDITIONED LIGHTING SCHEDULE

uminaire Schedule (includes all permanent installed lighting in conditioned space, and portable lighting over 0.3 w/f ${
m t}^2$ in offices) 01 **Complete Luminaire** Installed Watts (Conditioned) Description (i.e. 3-lamp Name or Item Tag fluorescent troffer, F32T8, **Total Number of Luminaires** Installed Watts one dimmable electronic 2x4 LED Panel According to ¹If lighting power densities were used in the compliance model Building Departments will need to check prescriptive forms for Luminaire Schedule details.

K3. INDOOR CONDITIONED LIGHTING CONTROL CREDITS Lighting Control Credits Schedule (includes all lighting controls installed in conditioned space for compliance credit per 140.6(a)2 and Table 140.6-A) Lighting Controlled **Primary Function Area (must** Power Control Credit # of Area Description meet requirements of Table Type of Lighting Control **Adjustment** Item Tag Luminaire (Watts) 140.6-A and 170.2-L) Factor (PAF) (Watts) S-1-First Floor N/A Training Vocational Lighting Control Credits (Conditioned) Total (Watts)

K4. INDOOR CONDITIONED LIGHTING MANDATORY LIGHTING CONTROL **Building Level Controls** Shut-Off Controls 130.1(c) & 160.5(b)40 See NRCC-LTI-E for mandatory controls

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000

79 / 60 °F 80 / 61 °F 48 / 46 °F

Cooling Coil

Supply Fan

1,100 cfm


Outside Air


365 cfm

75 / 60 °F

Report Generated: 2023-07-26 13:02:48

49 / 47 °F








PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©

1651Juanita Street, San Jacinto, CA 92583 Voice (951) 943-1908 Fax (951)943-5768



Revision Schedule Description

PRE-CHECK (PC) DOCUMENT

CODE: 2019 CBC A separate project application for construction

is required PC 2022 CBC: 24' x 40'

EXPANDABLE TO 120' x 40'

24'x40' T24 CZ 16 (WALL AC)

PROJECT NUMBER 22088 DRAWN BY Author CHECKED BY Checker DATE

06/15/2021

ENVELOPE MANDATORY MEASURES: NONRESIDENTIAL

120X40 (PC 04-116504) - Wall AC

DESCRIPTION

ENV-I

| | F CALIFORNIA Lestic Water | Heating 9 | System | | | | | C | ALIFORNIA ENERG | V COMMISSION | STATE OF CAL | LIFORNIA tic Water He | ating S | vstem | ١ |
|---|---|--|--|---|--|--|--|--|---|---|--|--|--|---|---------|
| | ICATE OF COMPLIA | | -, | | | | | | TEN ONIVIT EIVERO | NRCC-PLB-E | | E OF COMPLIANCE | | , | - |
| | | | | e for nonresidential occupancie ing the prescriptive path. For h | | | | | | I . | Project Na | me: 24X40 (PC 0 | 1-121369) | - Wall A | : |
| 110.1, | 110.3, 160.4 and | d 170.2(d), an | nd with requir | ements 180.1 for additions and | • | | .apaneres comp | mance is demonse | ratea with regainer | | | | | | - |
| | Name: 24X40 | (PC 04-121369 | 9) - Wall AC | Cli | Repor mate Zone 14 Date I | t Page: | | | | (Page 1 of 6) 9/7/2023 | | | | | |
| Floject | Audress. | | | Cili | mate zone 14 Date i | -repareu. | | | | 3/1/2023 | E. ADDIT | IONAL REMARK | | | - |
| | NERAL INFORM | | | | | | | | | | This table | includes remarks | nade by t | he pern | - 1i |
| 01 | | t Location (cit | • • | Palmdale ct all that apply): | 0 | 2 Clima | ate Zone | | 14 | | E DOME | CTIC LIOT MATER | FOLUDA | AFNIT | _ |
| | sroom | Types Within | Troject (selec | ct an that apply). | | | | | | | | STIC HOT WATER is used to demons | - | | _ |
| - Glass | | | | | | | | | | | | strated and with 1 | | | |
| B. PRO | OJECT SCOPE | | | | | | | | | | Equipmen | t Schedule: Wate | Heating | Efficien | C |
| | | | | ns that are within the scope of 0.2 for additions or alterations. | | | | | | | | 03 | | | |
| 170.2(d) and 141.0(a)/ 180.1, or 141.0(b)2N / 180.2 for additions or alterations. Solar water heating systems are documented on the NRCC-SAB compliance document. Combined hydronic water heating systems are documented on the NRCC-MCH compliance document. | | | | | | | | | | | System | A O Smith DEL- | LO Exc | eption t | |
| | | | 01 | I that and N | | 02 | | | 03 | | Name | | | 170.2 | -(|
| ⊠ Na | My pr ew system (DHW | - | ts of (check all | | Individual System | System Type ^{1,2} m (serving nonreside | ential snaces) | | stem Components Distribution | S | 07 | 08 | (| 09 | Ī |
| | stem Alteration | | <u> </u> | , | marviauai syste | fact Anie noureaine | ciai spaces) | ☐ Equipment | Distribution | Controls | Name or | Equipment Typ | el | ume | ₹; |
| ¹FOOTI | NOTES: Point of ι | use water hed | aters, or other | r non-central systems used to s | | • | red individual s | <u> </u> | | | Item Tag | Equipment Ty | (§ | gal) | |
| 1- | | | - | s and units in a multifamily res | | | | | | | A O Smith | Consumer Rate | 1 1 1 | 10 | |
| DHW | systems serving | | wennig units a | are considered "Central Systems | ы дог тиницатти у С | оссиринств | | | | | DEL-10 | Electric Storag TE: In systems >= 1 | | n with m | _ יי |
| | MPLIANCE RES | | | | | | | | | | average. | | | | _ |
| | | | | the compliance document is co ble indicated as not compliant | | r heating requiremer | nts. If this table | says "DOES NOT | COMPLY" or "COM | PLIES with | Water Hea | ating Equipment / | II Occupa | ncies | _ |
| Licepti | 01 | -, -, -, -, -, -, -, -, -, -, -, -, -, - | | 02 | , | 03 | | (| 04 | | | Yes | 1 | No | Δ |
| D | omestic Hot Wat | ter Equipmen | nt | Distribution Systems | | Controls | | Complian | nce Results | | 18 | | | | Ī |
| | Table | | | Table G | | Table H | | | | | 19 | | | - | |
| | Yes | | | Yes | | Yes | | CON | 1PLIES | | 20 | | | - | l |
| This ta | • | with unedita | | s because of selections made o | Generated Date | e/Time: | form. | | Documentation Softw | | 21 | | | | |
| This tan | ible is auto-filled ilding Energy Efficie | with unedital | ls - 2022 Nonres | s because of selections made on | Generated Date | e/Time: | form. | Compli Rep | ance ID: EnergyPro-4 ort Generated: 2023- | 1958-0923-0242 -09-07 12:06:05 | CA Buildin STATE OF CAL | g Energy Efficiency : | tandards - | · 2022 No | |
| CA Bui | ilding Energy Efficience | with unedital | ls - 2022 Nonres | | Generated Date | e/Time: : 2022.0.000 | form. | Compli Rep | ance ID: EnergyPro-4 | 958-0923-0242 -09-07 12:06:05 | CA Buildin STATE OF CAL Domest | ig Energy Efficiency : IFORNIA cic Water Hea | tandards - | · 2022 No | |
| CA Bui | ilding Energy Efficience CALIFORNIA estic Water I | with unedital | is - 2022 Nonres System | | Generated Date | e/Time: : 2022.0.000 n: rev 20220101 | form. | Compli Rep | ance ID: EnergyPro-4 ort Generated: 2023- | 1958-0923-0242 -09-07 12:06:05 | CA Buildin STATE OF CAL Domest CERTIFICATI | ig Energy Efficiency : IFORNIA CIC Water Hea E OF COMPLIANCE | tandards - | 2022 No | |
| CA Bui | ilding Energy Efficience CALIFORNIA estic Water I | with uneditar ency Standards Heating S | is - 2022 Nonres System | | Generated Date Report Version Schema Version Report | e/Time: : 2022.0.000 n: rev 20220101 | form. | Compli Rep | ance ID: EnergyPro-4 ort Generated: 2023- | 1958-0923-0242 -09-07 12:06:05 COMMISSION NRCC-PLB-E | CA Buildin STATE OF CAL Domest | Ig Energy Efficiency: IFORNIA LIC Water Hea | tandards - | 2022 No | |
| CA Bui | ilding Energy Efficience CALIFORNIA estic Water I | with uneditar ency Standards Heating S | is - 2022 Nonres System | | Generated Date Report Version Schema Version Report | e/Time: : 2022.0.000 n: rev 20220101 Page: | form. | Compli Rep | ance ID: EnergyPro-4 ort Generated: 2023- | 1958-0923-0242 -09-07 12:06:05 COMMISSION NRCC-PLB-E (Page 3 of 6) | CA Buildin STATE OF CAL Domest CERTIFICATI | ig Energy Efficiency : IFORNIA CIC Water Hea E OF COMPLIANCE | tandards - | 2022 No | |
| CA Bui | ilding Energy Efficience CALIFORNIA estic Water I CATE OF COMPLIAN Name: 24X40 (I | ency Standards Heating S NCE PC 04-121369) | is - 2022 Nonres System) - Wall AC | sidential Compliance | Generated Date Report Version Schema Version Report | e/Time: : 2022.0.000 n: rev 20220101 Page: | form. | Compli Rep | ance ID: EnergyPro-4 ort Generated: 2023- | 1958-0923-0242 -09-07 12:06:05 COMMISSION NRCC-PLB-E (Page 3 of 6) | CA Buildin STATE OF CAL Domest CERTIFICATI Project Nan | ig Energy Efficiency : IFORNIA CIC Water Hea E OF COMPLIANCE | ting Sy | vstem Wall AC | |
| CA Bui STATE OF C Dome CERTIFIC Project N | ilding Energy Efficience CALIFORNIA estic Water I CATE OF COMPLIAN Name: 24X40 (I | ency Standards Heating S NCE PC 04-121369) | is - 2022 Nonres System) - Wall AC | sidential Compliance | Generated Date Report Version Schema Version Report Date Pr | e/Time: : 2022.0.000 n: rev 20220101 Page: epared: | | Compli Repr CAI | ance ID: EnergyPro-4 ort Generated: 2023- LIFORNIA ENERGY | 1958-0923-0242 -09-07 12:06:05 COMMISSION NRCC-PLB-E (Page 3 of 6) 9/7/2023 | CA Buildin STATE OF CAL DOMEST CERTIFICATI Project Nam H. DOMES This table i | IFORNIA LIC WATER HEAD E OF COMPLIANCE THE THE STILL HOT WATER IS used to demonst | ting Sy -121369) - | vstem Wall AC | w |
| CA Bui STATE OF C Dome CERTIFIC Project N This tab | ilding Energy Efficience CALIFORNIA estic Water I CATE OF COMPLIAN Name: 24X40 (I) MESTIC HOT WA | ency Standards Heating S NCE PC 04-121369) ATER DISTRI | is - 2022 Nonres System) - Wall AC IBUTION SYS Inpliance for no | sidential Compliance | Generated Date Report Version Schema Version Report Date Pr | e/Time: : 2022.0.000 n: rev 20220101 Page: epared: | | Compli Repr CAI | ance ID: EnergyPro-4 ort Generated: 2023- LIFORNIA ENERGY | 1958-0923-0242 -09-07 12:06:05 COMMISSION NRCC-PLB-E (Page 3 of 6) 9/7/2023 | CA Buildin STATE OF CAL DOMEST CERTIFICATI Project Nam H. DOMES This table i | IFORNIA CIC Water Hea E OF COMPLIANCE ne: 24X40 (PC 04 | ting Sy -121369) - | vstem Wall AC | w |
| CA Bui STATE OF C Dome CERTIFIC Project N G. DON This tabe | ilding Energy Efficience CALIFORNIA estic Water I CATE OF COMPLIAN Name: 24X40 (I) MESTIC HOT WA | ency Standards Heating S NCE PC 04-121369) ATER DISTRII nonstrate comated with requirements with requirements of the company | System - Wall AC BUTION SYS Inpliance for neurirements 110 pancies | STEM Onresidential occupancies with 0.3(c), 160.4, 170.2(d). | Generated Date Report Version Schema Version Report Date Pr | e/Time: : 2022.0.000 n: rev 20220101 Page: epared: | 140.5. For mul | Compli Repr CAI | ance ID: EnergyPro-4 ort Generated: 2023- LIFORNIA ENERGY /motel occupancie | 1958-0923-0242 -09-07 12:06:05 COMMISSION NRCC-PLB-E (Page 3 of 6) 9/7/2023 | CA Buildin STATE OF CAL DOMEST CERTIFICATI Project Nam H. DOMES This table i | IFORNIA LIC WATER HEAD E OF COMPLIANCE THE THE STILL HOT WATER IS used to demonst | ting Sy -121369) - | vstem Wall AC | w 1 |
| CA Bui STATE OF C DOME CERTIFIC Project N G. DOM This tabic | ilding Energy Efficie CALIFORNIA estic Water I CATE OF COMPLIAN Name: 24X40 (I | ency Standards Heating S NCE PC 04-121369) ATER DISTRII constrate compated with required with required with required minus All Occup For systems Pipini | System - Wall AC BUTION SYS Inpliance for naturements 110 pancies serving dwell g that penetra | sidential Compliance STEM onresidential occupancies with | Generated Date Report Version Schema Version Report Date Pr distribution requir meet the minimur t be required to ha | e/Time: : 2022.0.000 n: rev 20220101 Page: epared: rements in 120.3 and m insulation requirents to pipe insulation fo | 140.5. For mul | Compli Rep CAI | ance ID: EnergyPro-4 ort Generated: 2023- LIFORNIA ENERGY /motel occupancie except: netration. Piping th | 1958-0923-0242 -09-07 12:06:05 COMMISSION NRCC-PLB-E (Page 3 of 6) 9/7/2023 | CA Buildin STATE OF CAL DOMEST CERTIFICATI Project Nam H. DOMES This table i | g Energy Efficiency: IFORNIA IC Water Hea E OF COMPLIANCE The: 24X40 (PC 04) STIC HOT WATER Is used to demonstated with requirem If the control of the | ting Sy -121369) - CONTRU | vstem Wall AC DLS boliance vs. 60.4(e) / | w 1 |
| CA Bui STATE OF C Dome CERTIFIC Project N This tabe | ilding Energy Efficie CALIFORNIA estic Water I CATE OF COMPLIAN Name: 24X40 (I | ency Standards Heating S NCE PC 04-121369) ATER DISTRII nonstrate com ated with required with required with required penel insula | System - Wall AC BUTION SYS Inpliance for not universents 110 pancies serving dwell g that penetrates metal fation shall about the serving shall | STEM Onresidential occupancies with 0.3(c), 160.4, 170.2(d). ling units, pipe insulation must ates framing members shall no framing shall use grommets, plut securely against all framing r | Generated Date Report Version Schema Version Report Date Pr distribution requir the required to haugs, wrapping or onembers | e/Time: : 2022.0.000 n: rev 20220101 Page: epared: rements in 120.3 and m insulation requirents pipe insulation fother insulating mater | 140.5. For mul nents in Table 1 r the distance of ial to assure th | Compli Report CAI | ance ID: EnergyPro-4 ort Generated: 2023- LIFORNIA ENERGY //motel occupancie) except: netration. Piping the lade with the metal | 1958-0923-0242 -09-07 12:06:05 COMMISSION NRCC-PLB-E (Page 3 of 6) 9/7/2023 | CA Buildin STATE OF CAL Domest CERTIFICATI Project Nan H. DOMES This table i | IFORNIA LIC WATER HEA E OF COMPLIANCE THE: 24X40 (PC 04) STIC HOT WATER Is used to demonsited with requirem. Yes | tandards - ting Sy -121369) - CONTRO rate compents in 16 | vstem Wall AC DLS boliance vs. 60.4(e) / | w 1 |
| CA Bui STATE OF C DOME CERTIFIC Project N G. DON This tab. complian Mandat | ilding Energy Efficie CALIFORNIA PESTIC Water I CATE OF COMPLIAN Name: 24X40 (I | ency Standards Heating S NCE PC 04-121369) ATER DISTRI constrate corrected with required with required peneinsula Piping peneinsula Piping Insula Piping Insula Piping Insula Piping Insula | System - Wall AC - W | STEM onresidential occupancies with 0.3(c), 160.4, 170.2(d). ling units, pipe insulation must ates framing members shall no raming shall use grommets, plut securely against all framing interior or exterior walls shall no in (QII) as specified in the Refuth a minimum of 1 inch of w | Report Version Schema Version Schema Version Report Date Pr distribution requir t be required to haus, wrapping or or or members not be required to lerence Residential | e/Time: : 2022.0.000 n: rev 20220101 Page: epared: rements in 120.3 and m insulation requirently pipe insulation for ther insulating mater have pipe insulation Appendix RA3.5. | 140.5. For mul nents in Table 1 r the distance of ial to assure th | tifamily and hotel 60.4-A (see blow) of the framing per at no contact is multirements are meritary and some contact is multiple contact in the contact is multiple contact in the contact is multiple contact in the contact in t | ance ID: EnergyPro-4 ort Generated: 2023: LIFORNIA ENERGY //motel occupancie Dexcept: Detration. Piping the lade with the metal t for compliance w | 1958-0923-0242 -09-07 12:06:05 COMMISSION NRCC-PLB-E (Page 3 of 6) 9/7/2023 | CA Buildin STATE OF CAL Domest CERTIFICATI Project Nan H. DOMES This table is demonstra | IFORNIA ICC Water Hea E OF COMPLIANCE The E 24X40 (PC 04) STIC HOT WATEF IS used to demonstated with requirem Yes | tandards - ting Sy -121369) - CONTRO rate compents in 16 No | vstem Wall AC DLS boliance vs. 60.4(e) / | w 1 |
| CA Bui STATE OF C DOME CERTIFIC Project N G. DON This tab. complian Mandat | ilding Energy Efficie CALIFORNIA PESTIC Water I CATE OF COMPLIAN Name: 24X40 (I) MESTIC HOT WA Die is used to dem unce is demonstratory Pipe Insulation | ency Standards Heating S NCE PC 04-121369) ATER DISTRII onstrate corrected with requirements of the peneric in sula Piping peneric in sula Piping in sula Piping have | System - Wall AC BUTION SYS Impliance for negurements 110 pancies serving dwell g that penetra etrates metal ation shall abugg installed in iation Installating surrounded pipe insulation | STEM onresidential occupancies with 0.3(c), 160.4, 170.2(d). ling units, pipe insulation must ates framing members shall no raming shall use grommets, plut securely against all framing interior or exterior walls shall no in (QII) as specified in the Refuth a minimum of 1 inch of w | Report Version Schema Version Schema Version Report Date Pr distribution require t be required to haugs, wrapping or or members iot be required to lerence Residential vall insulation, 2 in | e/Time: : 2022.0.000 n: rev 20220101 Page: epared: rements in 120.3 and m insulation requiren tive pipe insulation fo ther insulating mater have pipe insulation Appendix RA3.5. ches of crawlspace in | nents in Table 1 r the distance or rial to assure the | tifamily and hotel 60.4-A (see blow) of the framing per at no contact is multirements are menutes of attic insu | LIFORNIA ENERGY Whotel occupancie except: hetration. Piping the lade with the metal tor compliance will altion, shall not be alliation, shall not be | 1958-0923-0242 199-07 12:06:05 COMMISSION NRCC-PLB-E (Page 3 of 6) 9/7/2023 s, at at framing. ith Quality e required to | CA Buildin STATE OF CAL Domest CERTIFICATI Project Nan H. DOMES This table i demonstra 01 | IFORNIA CIC Water Hea E OF COMPLIANCE The compliance STIC HOT WATER Is used to demonstated with requirem Yes | tandards - ting Sy -121369) - CONTRO rate compents in 16 No | vstem Wall AC DLS boliance vs. 60.4(e) / | w 1 |
| CA Bui STATE OF C Dome CERTIFIC Project N G. DON This tab. complian Mandat | ilding Energy Efficie CALIFORNIA PESTIC Water I CATE OF COMPLIAN Name: 24X40 (I) MESTIC HOT WA Die is used to dem unce is demonstratory Pipe Insulation | ency Standards Heating S NCE PC 04-121369) ATER DISTRII constrate compared with required with required in sula Piping peneral Insula Piping Insula Pi | System - Wall AC - W | sidential Compliance STEM Onresidential occupancies with 0.3(c), 160.4, 170.2(d). Iing units, pipe insulation must ates framing members shall no raming shall use grommets, plut securely against all framing rinterior or exterior walls shall nion (QII) as specified in the Ref with a minimum of 1 inch of won. esidential spaces, pipe insulation minimum in piping, including supply and the and cold outlet piping, includit | Report Version Schema Version Schema Version Report Date Pr distribution requir t be required to haugs, wrapping or onembers out be required to lerence Residential all insulation, 2 in on for the following return piping of the | e/Time: : 2022.0.000 n: rev 20220101 Page: epared: ements in 120.3 and m insulation requirently pipe insulation for their insulating mater have pipe insulation in Appendix RA3.5. ches of crawlspace in gapplications is specific water heater | nents in Table 1 r the distance of the distance of the requirements in Table 1 records to assure the fall of the requirements in Table 1 if all of the requirements in the requirements in Table 1 if if it is a source of the requirements in Table 1 if it is a source of the requirements in Table 1 if it is a source of the requirements in Table 1 if it is a source of the requirements in Table 1 if it is a source of the requirements in Table 1 if it is a source of the requirements in Table 1 if it is a source of the requirements in Table 1 if it is a source of the requirements in Table 1 if it is a source of the requirements in Table 1 if it is a source of the requirements in Table 1 if it is a source of the requirements in Table 1 if it is a source of the requirements in Table 1 if it is a source of the requirements in Table 1 if it is a source of the requirements in Table 2 is a source of the requirements in Table 2 is a source of the requirements in Table 2 is a source of the requirements in Table 2 is a source of the requirements in Table 3 i | tifamily and hotel 60.4-A (see blow) of the framing per at no contact is multirements are meritaring the contact is multirements are meritaring the contact in the contact is multirements are meritaring the contact in the contact is multirements are meritaring the contact in the contact in the contact is multirements are meritaring the contact in th | A (see below) per | 1958-0923-0242 199-07 12:06:05 COMMISSION NRCC-PLB-E (Page 3 of 6) 9/7/2023 s, at at framing. ith Quality e required to | CA Buildin STATE OF CAL Domest CERTIFICATI Project Nam H. DOMES This table idemonstra 01 02 03 | g Energy Efficiency : IFORNIA CIC Water Hea E OF COMPLIANCE ne: 24X40 (PC 04) STIC HOT WATEF Is used to demonstated with requirem Yes \[\begin{array}{c ccccccccccccccccccccccccccccccccccc | tandards ting Sy | vstem Wall AC DLS boliance vs. 60.4(e) / | w 1 |
| CA Bui STATE OF C DOME CERTIFIC Project N G. DON This tabi complia. Mandat | ilding Energy Efficie CALIFORNIA PSTIC WATER I NAME: 24X40 (II WESTIC HOT WA Tole is used to demance is demonstratory Pipe Insulation | ency Standards Heating S NCE PC 04-121369) ATER DISTRII Honstrate com ated with required with required with required penel insula Piping Insula Piping have For systems Recirc The fi Pipes Insulation ship installed to be installed to be installed to the second penel insulation ship insulation ship installed to the second penel insulation ship insulation ship installed to the second penel insulation ship in | System - Wall AC - W | sidential Compliance STEM Conresidential occupancies with 0.3(c), 160.4, 170.2(d). Ing units, pipe insulation must ates framing members shall no raming shall use grommets, plut securely against all framing interior or exterior walls shall no inn (QII) as specified in the Reful with a minimum of 1 inch of won. Pesidential spaces, pipe insulation minimum of 1 inch of won. Pesidential spaces, pipe insulation minimum of 1 inch of won. Period outlet piping, including the suitable for outdoor service period in the suitable for outdoor | Report Version Schema Version Schema Version Report Date Pr Date Pr distribution requir t be required to haugs, wrapping or ormembers not be required to lerence Residential vall insulation, 2 in for the following return piping of the greturn piping of the gretur | e/Time: : 2022.0.000 n: rev 20220101 Page: epared: rements in 120.3 and m insulation requirently epipe insulation for their insulating mater have pipe insulation in Appendix RA3.5. ches of crawlspace in g applications is specie water heater the teach and heat trapted moisture, equipment moisture, equipment in the second control of the control of t | nents in Table 1 r the distance of the required to assure the distance of the required to the | tifamily and hotel 60.4-A (see blow) of the framing per at no contact is mulirements are menches of attic insulating storage sand wind. Insulating storage sand wind. Insulating storage sand wind. Insulating storage sand wind. | ance ID: EnergyPro-4 ort Generated: 2023- LIFORNIA ENERGY //motel occupancie except: netration. Piping the lade with the meta t for compliance we lalation, shall not be A (see below) per ystem ion exposed to we | 1958-0923-0242 -09-07 12:06:05 COMMISSION NRCC-PLB-E (Page 3 of 6) 9/7/2023 ss, at at framing. ith Quality e required to 120.3: | CA Buildin STATE OF CAL Domest CERTIFICATI Project Nam H. DOMES This table idemonstra 01 02 03 04 | ISTIC HOT WATER Is used to demonstated with requirem Yes | ting Sy -121369) - CONTRO rate compents in 16 | vstem Wall AC DLS boliance vs. 60.4(e) / | w 1 |
| CA Buil STATE OF C DOME CERTIFIC Project N G. DON This tab. complia. Mandat | ilding Energy Efficie CALIFORNIA PSTIC WATER I CATE OF COMPLIAN Name: 24X40 (I) MESTIC HOT WA Tole is used to dem tince is demonstratory Pipe Insulation | ency Standards Heating S NCE PC 04-121369) ATER DISTRII constrate compared with required with required insulation ship in the second secon | IS - 2022 Nonres System - Wall AC - Wall | sidential Compliance STEM Conresidential occupancies with 0.3(c), 160.4, 170.2(d). Ing units, pipe insulation must ates framing members shall no raming shall use grommets, plut securely against all framing rinterior or exterior walls shall nitor (QII) as specified in the Refunction (QII) as specified in the Refunction (QII) as including the piping, including supply and the piping, including the suitable for outdoor service per leeve. | Report Version Schema Version Schema Version Schema Version Date Property Date Propert | e/Time: : 2022.0.000 n: rev 20220101 Page: epared: rements in 120.3 and m insulation requirently epipe insulation for their insulating mater have pipe insulation in Appendix RA3.5. ches of crawlspace in g applications is specie water heater the teach and heat trapted moisture, equipment moisture, equipment in the second control of the control of t | nents in Table 1 r the distance of the comply assulation, or 4 in the comply of the complex of | tifamily and hotel 60.4-A (see blow) of the framing per at no contact is m uirements are me nches of attic insu- with Table 120.3- culating storage s and wind. Insulat le must be installe | ance ID: EnergyPro-4 ort Generated: 2023- LIFORNIA ENERGY //motel occupancie except: netration. Piping the lade with the meta t for compliance we lalation, shall not be A (see below) per ystem ion exposed to we | 1958-0923-0242 -09-07 12:06:05 COMMISSION NRCC-PLB-E (Page 3 of 6) 9/7/2023 ss, at at framing. ith Quality e required to 120.3: | CA Buildin STATE OF CAL Domest CERTIFICATI Project Nan H. DOME: This table idemonstra 01 02 03 04 05 | g Energy Efficiency: IFORNIA IIC Water Hea E OF COMPLIANCE The: 24X40 (PC 04) STIC HOT WATER Is used to demonstated with requirem Yes | tandards - ting Sy -121369) - CONTRI rate compents in 16 No | vstem Wall AC DLS boliance vs. 60.4(e) / | w 1 |
| CA Bui STATE OF C DOME CERTIFIC Project N G. DON This tab complian Mandat 13 | ilding Energy Efficie CALIFORNIA PSTIC WATER I CATE OF COMPLIAN Name: 24X40 (II MESTIC HOT WA Tole is used to demince is demonstrated by the complete of the | ency Standards Heating S NCE PC 04-121369) ATER DISTRII Constrate composed with required with required in All Occup For systems Piping Pi | System - Wall AC BUTION SYS Inpliance for manifements 110 pancies serving dwell go that penetrates metal for attion in shall about go installed in it attion in shall about go installed in go installed in it attion in serving nonrestruction in the state of the serving nonrestruction in the serving non | sidential Compliance STEM Onresidential occupancies with 0.3(c), 160.4, 170.2(d). Iing units, pipe insulation must ates framing members shall no raming shall use grommets, plut securely against all framing rinterior or exterior walls shall nion (QII) as specified in the Ref. with a minimum of 1 inch of won. esidential spaces, pipe insulation must and cold outlet piping, including supply and the analysis and cold outlet piping, including the suitable for outdoor service per leeve. TABLE 120.3-A | Report Version Schema Version Schema Version Report Date Pr distribution requin meet the minimur t be required to ha ugs, wrapping or o members not be required to le erence Residential vall insulation, 2 in- on for the following return piping of th ng between storage at due to sunlight, r 120.3(b) / 160.4(i) | e/Time: : 2022.0.000 n: rev 20220101 Page: epared: minsulation requirently pipe insulation for their insulating mater have pipe insulation in Appendix RA3.5. ches of crawlspace in grapplications is specime water heater the teach and heat trapemoisture, equipment in Pipe insulation but ULATION THICKNE | nents in Table 1 r the distance of the required for a nonrecire transition, or 4 in the required for a nonrecire transition of the required below graces. SS Nominal Pipe | tifamily and hotel 60.4-A (see blow) of the framing per at no contact is m uirements are me inches of attic insu- with Table 120.3- culating storage s and wind. Insulat le must be installed | ance ID: EnergyPro-4 ort Generated: 2023- LIFORNIA ENERGY /motel occupancie except: netration. Piping the lade with the metal at for compliance we lalation, shall not be lation, shall not be lation. A (see below) per light energy stem ion exposed to we led in a water proof | 1958-0923-0242 -09-07 12:06:05 COMMISSION NRCC-PLB-E (Page 3 of 6) 9/7/2023 ss, at al framing. ith Quality e required to 120.3: | CA Buildin STATE OF CAL DOMEST CERTIFICATI Project Nam H. DOMES This table idemonstra 01 02 03 04 05 | IFORNIA ICC Water Heat E OF COMPLIANCE The: 24X40 (PC 04) STIC HOT WATER IS used to demonstated with requirem Yes | tandards - ting Sy -121369) - CONTRO rate compents in 16 No | vstem Wall AC DLS boliance vs. 60.4(e) / | w 1 |
| CA Bui STATE OF C Dome CERTIFIC Project N This tab complian Mandat 13 | ilding Energy Efficie CALIFORNIA PSTIC WATER I CATE OF COMPLIAN Name: 24X40 (I) MESTIC HOT WA Tole is used to dem tince is demonstratory Pipe Insulation | ency Standards Heating S NCE PC 04-121369) ATER DISTRII Constrate compared with required with required in All Occup For systems Piping Piping Insula Piping Insula Piping Insula Piping Insula Piping Insula Piping Insulation shave For systems Recirr The fi Pipes Insulation shaled in on-crushab | IS - 2022 Nonres System - Wall AC - Wall | sidential Compliance STEM Conresidential occupancies with 0.3(c), 160.4, 170.2(d). Ing units, pipe insulation must ates framing members shall no raming shall use grommets, plut securely against all framing rinterior or exterior walls shall nitor (QII) as specified in the Refunction (QII) as specified in the Refunction (QII) as including the piping, including supply and the piping, including the suitable for outdoor service per leeve. | Report Version Schema Version Schema Version Schema Version Schema Version Date Property of the Property of th | e/Time: : 2022.0.000 n: rev 20220101 Page: epared: rements in 120.3 and m insulation requirently pipe insulation for their insulation for their insulation for their insulation in Appendix RA3.5. ches of crawlspace in gapplications is specified the water heater the tental and heat traper insulation but their insulation bu | nents in Table 1 r the distance of the comply assulation, or 4 in the comply of the complex of | tifamily and hotel 60.4-A (see blow) of the framing per at no contact is mulirements are menches of attic insulating storage stand wind. Insulating must be installed by the contact is mulirements. | ance ID: EnergyPro-4 ort Generated: 2023- LIFORNIA ENERGY //motel occupancie except: netration. Piping the lade with the meta t for compliance we lalation, shall not be A (see below) per ystem ion exposed to we | 1958-0923-0242 1958-0923-0242 1909-07 12:06:05 COMMISSION NRCC-PLB-E (Page 3 of 6) 9/7/2023 Ss, at al framing. ith Quality e required to 120.3: ather shall and ifamily & | CA Buildin STATE OF CAL Domest CERTIFICATI Project Nan H. DOME: This table idemonstra 01 02 03 04 05 | g Energy Efficiency: IFORNIA IIC Water Hea E OF COMPLIANCE The: 24X40 (PC 04) STIC HOT WATER Is used to demonstated with requirem Yes | tandards - ting Sy -121369) - CONTRI rate compents in 16 No | vstem Wall AC DLS boliance vs. 60.4(e) / | w 1 |

Generated Date/Time:

Selections have been made based on information provided in this document. If any selection have been changed by permit applicant, an explanation should be included in Table E. Additional Remarks. These documents must be provided to the building inspector during construction and can be found online

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance

I. DECLARATION OF REQUIRED CERTIFICATES OF INSTALLATION

J. DECLARATION OF REQUIRED CERTIFICATES OF ACCEPTANCE

K. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION

STATE OF CALIFORNIA

CERTIFICATE OF COMPLIANCE

Domestic Water Heating System

Project Name: 24X40 (PC 04-121369) - Wall A

NRCI-PLB-E - Must be submitted for all buildings

There are no forms required for this project.

There are no forms required for this project.

Report Version: 2022.0.000

| | N / 180.2 for additions or alterations. S | - I | | IDCC CAD | | | | | | | | | | | |
|--|--|---|---|--|--|--|---|-------------------------------------|---|--|--|--|--|--|---|
| ating systems are docum | | | ns are documented on the N | vксс-saв сотр | liance document. Combined | | | l | | | | Gas Service | | | |
| | ented on the NRCC-MCH compliance de | ocument. | | | | System Name | A O Smith DEL-10 | | n to 140.5(c)/ 0.2(d)3 | | | Water Heating System >= | Capacity-weighted Average Efficiency % | | |
| 01 | | C |)2 | | 03 | Name | | 1 | 0.2(u)3 | | | 1MMBtu/h ¹ | Average Efficiency % | | |
| My project consists of (ch | eck all that apply): | System | Type ^{1,2} | | System Components | 07 | 08 | 09 | | 10 | 11 | 12 | 13 | 14 | 15 |
| DHW system being instal | led for the first time) | Individual System (servir | ng nonresidential spaces) | □ Equipmen | t 🛮 Distribution 🔻 Controls | - 07 | 00 | 09 | Data dila sala | 1 | 11 | | 15 | 14 | 13 |
| ation (equipment, distribu | | | | | t Distribution Controls | Name or Item Tag | Equipment Type | Volume (gal) | Rated Input Capacity | Max GPM/ First Hour Rating | Rated Efficiency | Minimum Efficiency | Efficiency Unit | Designed Standby Loss | Maximum Standby Loss |
| - | r other non-central systems used to ser | | , are considered individual s | ystems. | | | | - " | (Btu/h) | (FHR) | · | Required | | | |
| - | rooms and units in a multifamily resid | | oinc. | | | A O Smith | | 10 | 5,120 | FHR >=75 | 0.95 | 0.93 | UEF | | |
| rving 2 or more awening | units are considered "Central Systems" | јог тинијатту оссиранс | les | | | DEL-10 | Electric Storage | | 1 | <u> </u> | | | - 4 | | |
| RESULTS | | | | | | average. | TE: In systems >= 1M | MBtu/h with | n muitiple unit | s, gas water neat | ers with input ca | pacity > 100,000 | Btu/n may meet 90% E | Et requirements via an input cap | acity-weighted |
| | t into the compliance document is com | nliant with water heating | a requirements. If this table | save "DOES NO | T COMPLY" or "COMPLIES with | | ating Equipment All | Occupancie | • | | | | | | |
| , , , , , | the table indicated as not compliant fo | , | grequirements. If this tubic | says DOLS NO | T CONTI ET OF CONTI ETES WITH | Water rice | | | Not | 1 | | | | | |
| 01 | 02 | 03 | | | 04 | | Yes | No | Applicable | | | | Requirement | | |
| t Water Equipment | Distribution Systems | Controls | | | | 18 | | | | Unfired storage | tank insulation s | hall have Interna | l + External >=R-16 OR | External >=R-3.5. Label required | l per 110.3(c)3 |
| Table F | Table G | Table H | | Compli | ance Results | 19 | | | | | | | | olar energy or recovered energy | • |
| Yes | Yes | Yes | | CC | OMPLIES | 20 | | | | | | | | BTUH or 2 kW has been specified | |
| L | | | Į. | | | | | _ | | | | | | ater heating system per 140.5(a) | • |
| CONDITIONS | | | | | | 21 | | | | _ | | | ay be an instantaneous | | |
| filled with uneditable con | nments because of selections made or o | data entered in tables thr | oughout the form. | | | | ' | <u> </u> | • | • | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | Generated Date/Time: | | | Documentation Software: EnergyPro | | | | | | Genera | ated Date/Time: | | Documentat | ion Software: EnergyPro |
| Efficiency Standards - 2022 | Nonresidential Compliance | Report Version: 2022.0.0 | 000 | Comp | pliance ID: EnergyPro-4958-0923-0242 | CA Buildin | ng Energy Efficiency Sta | ndards - 2022 | Nonresidential | Compliance | Report | : Version: 2022.0.00 | 00 | Compliance ID: Ene | rgyPro-4958-0923-0242 |
| | | Schema Version: rev 202 | 20101 | Re | eport Generated: 2023-09-07 12:06:05 | | , | | | • | | a Version: rev 2022 | | | ed: 2023-09-07 12:06:05 |
| ter Heating Systen | 2 | | | _ | | STATE OF CALL | | | | | | | | | |
| | | | | | CALIFORNIA ENERGY COMMISSION | Domest | tic Water Heati | ng Syste | m | | | | | CALIFORNIA E | NERGY COMMISSION |
| I PLIANCE X40 (PC 04-121369) - Wall <i>A</i> | | Report Page: | | | NRCC-PLB-E | | E OF COMPLIANCE | | | | | , | | | NRCC-PLB-E |
| 740 (PC 04-121309) - Wali P | | Date Prepared: | | | (Page 3 of 6) 9/7/2023 | Project Nam | me: 24X40 (PC 04-1 | 21369) - Wall | AC | | | Report Page: | | | (Page 4 of 6) |
| | | | | | 3,1,2223 | | | | | | | Date Prepared: | | | 9/7/2023 |
| | | | | | | | | | | | | | | | |
| T WATER DISTRIBUTIO | N SYSTEM | | | | | | STIC HOT WATER C | | | | 440.2 5 | 5 | | | Process to de- |
| demonstrate compliance | e for nonresidential occupancies with d | istribution requirements i | in 120.3 and 140.5. For mult | tifamily and ho | tel/motel occupancies, | This table i | is used to demonstra | te complian | | requirements in . | 110.3 for all occu | pancies. For mul | tifamily residential ana | I hotel/motel occupancies, comp | liance is also |
| demonstrate compliance onstrated with requireme | | istribution requirements | in 120.3 and 140.5. For mult | tifamily and hot | tel/motel occupancies, | This table i | is used to demonstra ated with requiremen | te compliand ts in 160.4(e |) / 170.2(d). | requirements in . | 110.3 for all occu | ipancies. For muli | • | I hotel/motel occupancies, comp | liance is also |
| o demonstrate compliance onstrated with requirements | e for nonresidential occupancies with d nts 110.3(c), 160.4, 170.2(d). | , | | <i>,</i> | | This table i | is used to demonstra ated with requiremen | te compliand ts in 160.4(e | | requirements in . | 110.3 for all occu | ipancies. For muli | tifamily residential and Requirement | I hotel/motel occupancies, comp | liance is also |
| o demonstrate compliance constrated with requirement sulation All Occupancies For systems serving • Piping that p | e for nonresidential occupancies with d nts 110.3(c), 160.4, 170.2(d). dwelling units, pipe insulation must m nenetrates framing members shall not l | eet the minimum insulat pe required to have pipe | ion requirements in Table 1 | 60.4-A (see blo | w) except: enetration. Piping that | This table i | is used to demonstra ated with requiremen | te compliand ts in 160.4(e | Not Applicable Co | onstruction docun | nents require ma | nufacturer certif | Requirement | ter-heating systems are equippe | |
| o demonstrate compliance constrated with requirement sulation All Occupancies For systems serving • Piping that penetrates representations | e for nonresidential occupancies with d nts 110.3(c), 160.4, 170.2(d). Idwelling units, pipe insulation must m inenetrates framing members shall not l netal framing shall use grommets, plug nall abut securely against all framing m | neet the minimum insulat be required to have pipe s, wrapping or other insu embers | ion requirements in Table 1 insulation for the distance o llating material to assure the | 60.4-A (see blo of the framing p at no contact is | w) except: enetration. Piping that made with the metal framing. | This table i demonstra | is used to demonstra ated with requiremen Yes | te compliand ts in 160.4(e | Not Applicable Cc | onstruction docun | nents require ma ols capable of adj ity > 167,000 BT(| nufacturer certifusting temperatu | Requirement ication that service wa | ter-heating systems are equippe | d with automatic |
| sulation All Occupancies For systems serving Piping that penetrates r Insulation sh Piping instal | e for nonresidential occupancies with d nts 110.3(c), 160.4, 170.2(d). dwelling units, pipe insulation must m penetrates framing members shall not l netal framing shall use grommets, plug | neet the minimum insulat be required to have pipe s, wrapping or other insu embers t be required to have pip | ion requirements in Table 1 insulation for the distance o ilating material to assure the e insulation if all of the requ | 60.4-A (see blo of the framing p at no contact is | w) except: enetration. Piping that made with the metal framing. | This table is demonstra | is used to demonstra ated with requiremen Yes | te compliand ts in 160.4(e No | Not Label Control of the Control of | onstruction docun mperature contro stems with capac umbing Code 613 | nents require ma ols capable of adj ity > 167,000 BTI .0. | nnufacturer certif usting temperatu UH equipped witl | Requirement ication that service wa ure settings per 110.3(a h outlet temperature c | ter-heating systems are equippe | d with automatic |
| o demonstrate compliance constrated with requirement sulation All Occupancies For systems serving Piping that penetrates repentrates repentrates rependent insulation sheet rependent insulation in | e for nonresidential occupancies with dents 110.3(c), 160.4, 170.2(d). I dwelling units, pipe insulation must menetrates framing members shall not lenetal framing shall use grommets, plugual abut securely against all framing meled in interior or exterior walls shall no | neet the minimum insulat be required to have pipe s, wrapping or other insu embers t be required to have pip ence Residential Append | ion requirements in Table 1 insulation for the distance of allating material to assure the einsulation if all of the requix RA3.5. | 60.4-A (see blo of the framing p at no contact is uirements are m | w) except: enetration. Piping that made with the metal framing. net for compliance with Quality | This table i demonstra | is used to demonstra ated with requiremen Yes | te compliand ts in 160.4(e | Not Applicable Cc te Sy Pli | onstruction docun mperature contro stems with capac umbing Code 613 | nents require ma ols capable of adj ity > 167,000 BTI .0. | nufacturer certif usting temperatu UH equipped witl | Requirement ication that service wa ure settings per 110.3(a h outlet temperature c e systems are capable o | ter-heating systems are equippe a). ontrols per 110.3(c)1 unless cove | d with automatic |
| For systems serving Piping that penetrates r Insulation SH Piping instal Insulation In Piping surrol Piping surrol Piping surrol Piping surrol Piping surrol Piping instal | e for nonresidential occupancies with dents 110.3(c), 160.4, 170.2(d). I dwelling units, pipe insulation must menetrates framing members shall not lenetal framing shall use grommets, pluguall abut securely against all framing medical interior or exterior walls shall no stallation (QII) as specified in the Referunded with a minimum of 1 inch of wasulation. | neet the minimum insulat be required to have pipe s, wrapping or other insu embers t be required to have pip ence Residential Append Il insulation, 2 inches of c | ion requirements in Table 1 insulation for the distance of allating material to assure the einsulation if all of the requix RA3.5. Trawlspace insulation, or 4 in all of the requirements and the einsulation if all of the requix RA3.5. | 60.4-A (see blo of the framing p at no contact is uirements are m nches of attic in | w) except: enetration. Piping that made with the metal framing. net for compliance with Quality sulation, shall not be required to | This table is demonstrated and the demonstrated and | is used to demonstra ated with requiremen Yes | te compliante ts in 160.4(e | | onstruction docum mperature control stems with capac umbing Code 613 ontrols for circulat 10.3(c)2 unless sor recirculation sys | nents require ma ols capable of adj ity > 167,000 BTI .0. cing pumps or ele systems serves he | nufacturer certif usting temperatu UH equipped witl ectrical heat trace ealthcare facility. | Requirement ication that service wa ure settings per 110.3(a h outlet temperature c e systems are capable c | ter-heating systems are equippe a). ontrols per 110.3(c)1 unless cove | d with automatic ered by California system per |
| For systems serving Piping instal Insulation In For systems serving Piping that penetrates r Insulation sh Piping instal Insulation In Piping surror have pipe in | e for nonresidential occupancies with dents 110.3(c), 160.4, 170.2(d). I dwelling units, pipe insulation must menetrates framing members shall not lenetal framing shall use grommets, pluguall abut securely against all framing medical interior or exterior walls shall no stallation (QII) as specified in the Referenced with a minimum of 1 inch of was sulation. | neet the minimum insulate per required to have pipe so, wrapping or other insulations to be required to have pipence Residential Append Il insulation, 2 inches of control for the following applica | ion requirements in Table 1 insulation for the distance of allating material to assure the einsulation if all of the requix RA3.5. Trawlspace insulation, or 4 in the time is specified to comply | 60.4-A (see blo of the framing p at no contact is uirements are m nches of attic in | w) except: enetration. Piping that made with the metal framing. net for compliance with Quality sulation, shall not be required to | This table is demonstra | is used to demonstra ated with requiremen Yes | te compliand ts in 160.4(e No | | onstruction documperature controls with capac umbing Code 613 ontrols for circulat 1.0.3(c)2 unless sor recirculation systiditions. | nents require ma ols capable of adj ity > 167,000 BTI .0. cing pumps or ele systems serves he stems serving mu | nufacturer certif usting temperatu UH equipped witl ectrical heat trace ealthcare facility. ultiple dwelling u | Requirement ication that service wa ure settings per 110.3(a h outlet temperature c e systems are capable c nits, design includes au | ter-heating systems are equippe a). ontrols per 110.3(c)1 unless cover of automatically turning off the s utomatic pump controls per 170. | d with automatic ered by California system per 2(d) or 180.1(b)3 for |
| For systems serving Piping instal Insulation In For systems serving Piping that penetrates r Insulation sh Piping instal Insulation In Piping surror have pipe in For systems serving Recirculating The first 8 ft | e for nonresidential occupancies with dents 110.3(c), 160.4, 170.2(d). I dwelling units, pipe insulation must menetal framing shall use grommets, pluguall abut securely against all framing medical interior or exterior walls shall no stallation (QII) as specified in the Referenced with a minimum of 1 inch of was sulation. In nonresidential spaces, pipe insulation g system piping, including supply and reformed that and cold outlet piping, including supply and reformed that and cold outlet piping, including | neet the minimum insulate required to have pipe s, wrapping or other insumbers to be required to have pipence Residential Append Il insulation, 2 inches of control for the following application piping of the water | ion requirements in Table 1 insulation for the distance of allating material to assure the einsulation if all of the requix RA3.5. crawlspace insulation, or 4 in tions is specified to comply heater | 60.4-A (see blo of the framing p at no contact is uirements are m nches of attic in with Table 120. | w) except: enetration. Piping that made with the metal framing. net for compliance with Quality sulation, shall not be required to 3-A (see below) per 120.3: | This table is demonstrated and the demonstrated and | is used to demonstra ated with requiremen Yes | te compliante ts in 160.4(e | Not | onstruction docum mperature control stems with capac umbing Code 613 ontrols for circulat 10.3(c)2 unless sor or recirculation systems. | nents require ma ols capable of adj ity > 167,000 BTI .0. cing pumps or ele systems serves he stems serving mu stems serving inc er 170.2(d). | unufacturer certif usting temperatu UH equipped witl ectrical heat trace ealthcare facility. ultiple dwelling und dividual dwelling | Requirement ication that service wa ure settings per 110.3(a h outlet temperature c e systems are capable c nits, design includes au units, design includes r | ter-heating systems are equippe a). ontrols per 110.3(c)1 unless cover of automatically turning off the solutionatic pump controls per 170. manual on/off controls as specifi | d with automatic ered by California system per 2(d) or 180.1(b)3 for ed in Reference |
| For systems serving Piping surror have pipe in For systems serving Piping that penetrates r Insulation sh Piping instal Insulation In Piping surror have pipe in For systems serving Recirculating The first 8 ft Pipes that a | e for nonresidential occupancies with dents 110.3(c), 160.4, 170.2(d). I dwelling units, pipe insulation must menetates framing members shall not lenetal framing shall use grommets, pluguall abut securely against all framing medical interior or exterior walls shall no stallation (QII) as specified in the Referunded with a minimum of 1 inch of wasulation. In nonresidential spaces, pipe insulation g system piping, including supply and refer to the system piping, including sexternally heated | neet the minimum insulate required to have pipe s, wrapping or other insumbers to be required to have pipence Residential Append Il insulation, 2 inches of control for the following application piping of the water go between storage tank a | ion requirements in Table 1 insulation for the distance of allating material to assure the einsulation if all of the requix RA3.5. crawlspace insulation, or 4 in tions is specified to comply heater and heat trap, for a nonrecire | 60.4-A (see blo of the framing p at no contact is uirements are m niches of attic in with Table 120. culating storage | w) except: enetration. Piping that made with the metal framing. net for compliance with Quality sulation, shall not be required to 3-A (see below) per 120.3: | This table is demonstrated and the demonstrated and | is used to demonstra ated with requiremen Yes | te compliante ts in 160.4(e | | onstruction docum mperature control stems with capac umbing Code 613 ontrols for circulat 10.3(c)2 unless so or recirculation system of recirculation system opendix RA4.4.9 pombustion air pos | nents require ma ols capable of adj ity > 167,000 BTI .0. cing pumps or ele systems serves he stems serving mu stems serving inc er 170.2(d). itive shut-off sha | unufacturer certifusting temperatu UH equipped with ectrical heat trace ealthcare facility. ultiple dwelling und dividual dwelling | Requirement ication that service was are settings per 110.3(as houtlet temperature of experiments, design includes auunits, design includes refer 160.4(3).on all newly | ter-heating systems are equippe a). ontrols per 110.3(c)1 unless cover of automatically turning off the solutionatic pump controls per 170. manual on/off controls as specifications as specifications. | d with automatic ered by California system per 2(d) or 180.1(b)3 for ed in Reference follows: |
| For systems serving Piping surrou have pipe in For systems serving Piping surrou have pipe in For systems serving Recirculating The first 8 ft Pips that a | e for nonresidential occupancies with dents 110.3(c), 160.4, 170.2(d). I dwelling units, pipe insulation must menetal framing shall use grommets, pluguall abut securely against all framing medical interior or exterior walls shall no stallation (QII) as specified in the Referenced with a minimum of 1 inch of was sulation. I nonresidential spaces, pipe insulation greystem piping, including supply and referenced of hot and cold outlet piping, including the externally heated protected from damage, including that | neet the minimum insulate required to have pipe s, wrapping or other insumbers to have pipe ence Residential Append II insulation, 2 inches of control for the following application piping of the water g between storage tank a due to sunlight, moisture | ion requirements in Table 1 insulation for the distance of allating material to assure the einsulation if all of the requix RA3.5. crawlspace insulation, or 4 in tions is specified to comply heater and heat trap, for a nonrecire, e, equipment maintenance, | 60.4-A (see blo of the framing p at no contact is uirements are m nches of attic in with Table 120. culating storage and wind. Insul | w) except: enetration. Piping that made with the metal framing. net for compliance with Quality sulation, shall not be required to 3-A (see below) per 120.3: e system ation exposed to weather shall | This table is demonstrated and the demonstrated and | is used to demonstra ated with requiremen Yes | te compliante ts in 160.4(e | | onstruction docum mperature control stems with capac umbing Code 613 ontrols for circulat 10.3(c)2 unless sor recirculation systems. For recirculation systems or recirculation systems of pendix RA4.4.9 por mbustion air pos Boilers with | nents require ma ols capable of adj ity > 167,000 BTI .0. cing pumps or ele systems serves he stems serving mu stems serving inc er 170.2(d). itive shut-off sha | unufacturer certifusting temperatu UH equipped with ectrical heat trace ealthcare facility. ultiple dwelling und dividual dwelling | Requirement ication that service was are settings per 110.3(as houtlet temperature of experiments, design includes auunits, design includes refer 160.4(3).on all newly | ter-heating systems are equippe a). ontrols per 110.3(c)1 unless cover of automatically turning off the solutionatic pump controls per 170. manual on/off controls as specifi | d with automatic ered by California system per 2(d) or 180.1(b)3 for ed in Reference follows: |
| For systems serving Piping surrou have pipe in For systems serving Piping surrou have pipe in For systems serving Recirculating The first 8 ft Pips that a | e for nonresidential occupancies with dents 110.3(c), 160.4, 170.2(d). Indwelling units, pipe insulation must menetrates framing members shall not lental framing shall use grommets, plugual abut securely against all framing med in interior or exterior walls shall no stallation (QII) as specified in the Referunded with a minimum of 1 inch of wasulation. In nonresidential spaces, pipe insulation as system piping, including supply and reference of hot and cold outlet piping, including the externally heated | neet the minimum insulate required to have pipe s, wrapping or other insumbers to have pipe ence Residential Append II insulation, 2 inches of control for the following application piping of the water g between storage tank a due to sunlight, moisture | ion requirements in Table 1 insulation for the distance of allating material to assure the einsulation if all of the requix RA3.5. crawlspace insulation, or 4 in tions is specified to comply heater and heat trap, for a nonrecire, e, equipment maintenance, | 60.4-A (see blo of the framing p at no contact is uirements are m nches of attic in with Table 120. culating storage and wind. Insul | w) except: enetration. Piping that made with the metal framing. net for compliance with Quality sulation, shall not be required to 3-A (see below) per 120.3: e system ation exposed to weather shall | O1 O2 O3 O4 O5 | is used to demonstra ted with requirement Yes | te compliance ts in 160.4(e | | onstruction docum mperature control stems with capac umbing Code 613 ontrols for circulat .10.3(c)2 unless sor recirculation systems. or recirculation systems opendix RA4.4.9 pombustion air pos Boilers with pressure | nents require ma ols capable of adj ity > 167,000 BTI .0. ting pumps or ele systems serves he stems serving mu stems serving inc er 170.2(d). itive shut-off sha input capacity >= | anufacturer certif usting temperatu UH equipped witl ectrical heat trace ealthcare facility. Ultiple dwelling und dividual dwelling und ill be provided pe = 2.5 MMBtu/h, in | Requirement ication that service was are settings per 110.3(a) in outlet temperature of exystems are capable of the capable of | ter-heating systems are equippe a). ontrols per 110.3(c)1 unless cover of automatically turning off the solutionatic pump controls per 170. manual on/off controls as specifications as specifications. | d with automatic ered by California system per 2(d) or 180.1(b)3 for ed in Reference follows: sitive vent static |
| For systems serving Piping survinave pipe in For systems serving Piping that penetrates r Insulation sh Piping instal Insulation in Piping surron have pipe in For systems serving Recirculating The first 8 ft Pipes that a | e for nonresidential occupancies with dents 110.3(c), 160.4, 170.2(d). Idwelling units, pipe insulation must menetrates framing members shall not lental framing shall use grommets, plughall abut securely against all framing med in interior or exterior walls shall no stallation (QII) as specified in the Referunded with a minimum of 1 inch of was usulation. In nonresidential spaces, pipe insulation system piping, including supply and refer to the and cold outlet piping, including externally heated protected from damage, including that cover suitable for outdoor service per 1 and or sleeve. | neet the minimum insulate required to have pipe s, wrapping or other insumbers to have pipe ence Residential Append II insulation, 2 inches of control for the following application piping of the water g between storage tank a due to sunlight, moisture | ion requirements in Table 1 insulation for the distance of allating material to assure the einsulation if all of the requix RA3.5. crawlspace insulation, or 4 in tions is specified to comply heater and heat trap, for a nonrecire, e, equipment maintenance, asulation buried below grad | 60.4-A (see blo of the framing p at no contact is uirements are m nches of attic in with Table 120. culating storage and wind. Insul | w) except: enetration. Piping that made with the metal framing. net for compliance with Quality sulation, shall not be required to 3-A (see below) per 120.3: e system ation exposed to weather shall | O1 O2 O3 O4 O5 | is used to demonstra ted with requirement Yes | te compliance ts in 160.4(e | | onstruction docum mperature control stems with capac umbing Code 613 ontrols for circulat 10.3(c)2 unless sor recirculation systems. For recirculation systems opendix RA4.4.9 por pombustion air pos Boilers with pressure Boilers wher | nents require ma ols capable of adj ity > 167,000 BTI .0. cing pumps or ele systems serves he stems serving mu stems serving inc er 170.2(d). itive shut-off sha input capacity >= | anufacturer certifusting temperatu UH equipped with ectrical heat trace ealthcare facility. Ultiple dwelling und dividual dwelling. Ill be provided pee = 2.5 MMBtu/h, in es two or more b | Requirement ication that service was are settings per 110.3(a) in outlet temperature of exystems are capable of the capable of | ter-heating systems are equippe a). ontrols per 110.3(c)1 unless cover of automatically turning off the sutomatic pump controls per 170. manual on/off controls as specifications as specifications and the specifical points are sesigned to operate with a nonpositioned input capacity per stack of | d with automatic ered by California system per 2(d) or 180.1(b)3 for ed in Reference follows: sitive vent static |
| For systems serving Piping survinave pipe in For systems serving Piping that penetrates r Insulation sh Piping instal Insulation in Piping surron have pipe in For systems serving Recirculating The first 8 ft Pipes that a | e for nonresidential occupancies with dents 110.3(c), 160.4, 170.2(d). I dwelling units, pipe insulation must menetrates framing members shall not lenetal framing shall use grommets, plughall abut securely against all framing meled in interior or exterior walls shall no stallation (QII) as specified in the Referunded with a minimum of 1 inch of wasulation. In onresidential spaces, pipe insulation graystem piping, including supply and refer to the control of the con | neet the minimum insulate required to have pipe s, wrapping or other insuembers to have pipe ence Residential Append II insulation, 2 inches of control for the following application piping of the water greater than the state of the water greater than the state of the water greater than the state of the | ion requirements in Table 1 insulation for the distance of allating material to assure the einsulation if all of the requix RA3.5. crawlspace insulation, or 4 in tions is specified to comply heater and heat trap, for a nonrecire, e, equipment maintenance, asulation buried below grad | 60.4-A (see blo of the framing p at no contact is uirements are m niches of attic in with Table 120. culating storage and wind. Insul | w) except: enetration. Piping that made with the metal framing. net for compliance with Quality sulation, shall not be required to 3-A (see below) per 120.3: e system ation exposed to weather shall | O1 O2 O3 O4 O5 | is used to demonstra ted with requirement Yes | te compliance ts in 160.4(e | | onstruction docummerature control stems with capac umbing Code 613 ontrols for circulat 10.3(c)2 unless s or recirculation sys diditions. or recirculation sys pendix RA4.4.9 p one boilers with pressure Boilers wher oller combustion a The fan mot | nents require ma ols capable of adj ity > 167,000 BTI .0. cing pumps or ele systems serves he stems serving mu stems serving inc er 170.2(d). itive shut-off sha input capacity >= e one stack serve air fans with mot or shall be driver | anufacturer certifusting temperatu UH equipped with ectrical heat trace ealthcare facility. ultiple dwelling und dividual dwelling und estwo or more boor >= 10 hp shall in by a variable spo | Requirement ication that service was use settings per 110.3(as houtlet temperature of esystems are capable of the following temperature of the following with a total combined one of the following the following temperature one of th | ter-heating systems are equippe a). ontrols per 110.3(c)1 unless cover of automatically turning off the substantial pump controls per 170. manual on/off controls as specifical installed commercial boilers as esigned to operate with a nonpositioned input capacity per stack of wing | d with automatic ered by California system per 2(d) or 180.1(b)3 for ed in Reference follows: sitive vent static 2.5 MMBtu/h. |
| For systems serving Piping surrol have pipe in For systems serving Piping instal Insulation In Piping surrol have pipe in For systems serving Recirculating The first 8 ft Pipes that al Insulation shall be positive installed with a connection of the service in t | e for nonresidential occupancies with dents 110.3(c), 160.4, 170.2(d). I dwelling units, pipe insulation must menetrates framing members shall not lenetal framing shall use grommets, pluguall abut securely against all framing meded in interior or exterior walls shall no stallation (QII) as specified in the Referunded with a minimum of 1 inch of was sulation. I nonresidential spaces, pipe insulation gystem piping, including supply and refer to the and cold outlet piping, including the externally heated protected from damage, including that cover suitable for outdoor service per 1 and or specific to the service of the surface of | neet the minimum insulate required to have pipe is, wrapping or other insulations, wrapping or other insulations, and it is required to have pipelence Residential Append II insulation, 2 inches of conforthe following applications piping of the water grown between storage tank and use to sunlight, moisture 1.20.3(b) / 160.4(f). Pipe in 1.20.3(b) / 160.4(f). Pipe in 1.20.3(b) / 160.4(f). | ion requirements in Table 1 insulation for the distance of allating material to assure the einsulation if all of the requix RA3.5. crawlspace insulation, or 4 intions is specified to comply heater and heat trap, for a nonrecirc e, equipment maintenance, assulation buried below grad N THICKNESS | 60.4-A (see bloof the framing pat no contact is uirements are maches of attic in with Table 120. Culating storage and wind. Insulate must be installed. | w) except: enetration. Piping that made with the metal framing. net for compliance with Quality sulation, shall not be required to 3-A (see below) per 120.3: e system ation exposed to weather shall | 01 02 03 04 05 06 | is used to demonstra ted with requirement Yes | te compliand ts in 160.4(e | | onstruction documperature control stems with capacumbing Code 613 ontrols for circulat 10.3(c)2 unless sor recirculation systems with capacumbing RA4.4.9 possible solutions. The far motion of | nents require maps capable of adjity > 167,000 BTI. O. cing pumps or elegystems serves he stems serving must be stems serving inches 170.2(d). It it is the stems serving inches 170.2(d). It is the stems serving inches 170.2(d). It is the stems serving inches 170.2(d). | anufacturer certifusting temperatu UH equipped with ectrical heat trace ealthcare facility. ultiple dwelling und dividual dwelling und estwo or more boor >= 10 hp shall in by a variable spo | Requirement ication that service was use settings per 110.3(as houtlet temperature of esystems are capable of the following temperature of the following with a total combined one of the following the following temperature one of th | ter-heating systems are equippe a). ontrols per 110.3(c)1 unless cover of automatically turning off the sutomatic pump controls per 170. manual on/off controls as specifications as specifications and the specifical points are sesigned to operate with a nonpositioned input capacity per stack of | d with automatic ered by California system per 2(d) or 180.1(b)3 for ed in Reference follows: sitive vent static 2.5 MMBtu/h. |
| For systems serving Piping instal Insulation short serving Professional insulation short serving Piping instal Insulation short serving Recirculating Recirculating Insulation short | e for nonresidential occupancies with dents 110.3(c), 160.4, 170.2(d). Indwelling units, pipe insulation must menetrates framing members shall not lental framing shall use grommets, plughall abut securely against all framing med in interior or exterior walls shall no stallation (QII) as specified in the Refer unded with a minimum of 1 inch of was unded with a minimum of 1 inch of was under with a minimum of 1 inch of was under the piping, including supply and refer to the stallation of the st | neet the minimum insulate required to have pipe is, wrapping or other insulations, wrapping or other insulations, and it is required to have pipelence Residential Append II insulation, 2 inches of conforthe following applications piping of the water grown between storage tank and use to sunlight, moisture 1.20.3(b) / 160.4(f). Pipe in 1.20.3(b) / 160.4(f). Pipe in 1.20.3(b) / 160.4(f). | cion requirements in Table 1 insulation for the distance of allating material to assure the einsulation if all of the requix RA3.5. crawlspace insulation, or 4 in tions is specified to comply heater and heat trap, for a nonrecire e, equipment maintenance, asulation buried below grad N THICKNESS Nominal Pipe 10 o < 1.5 to | 60.4-A (see blo of the framing p at no contact is uirements are m nches of attic in with Table 120. culating storage and wind. Insul le must be insta | w) except: enetration. Piping that made with the metal framing. net for compliance with Quality sulation, shall not be required to 3-A (see below) per 120.3: e system ation exposed to weather shall illed in a water proof and | 01 02 03 04 05 06 | is used to demonstra ted with requirement Yes | te compliand ts in 160.4(e | | onstruction documperature control stems with capac umbing Code 613 ontrols for circulat 10.3(c)2 unless s or recirculation syst iditions. or recirculation syst pendix RA4.4.9 p one boilers with pressure Boilers wher olier combustion a The fan mot design air vo | nents require maps capable of adjity > 167,000 BTI. O. cing pumps or elegystems serves hestems serving must be stems serving inches 170.2(d). It is the stems serving inches 170.2(d). | anufacturer certifusting temperatu UH equipped with ectrical heat trace ealthcare facility. Iltiple dwelling und dividual dwelling und estimate the provided pe = 2.5 MMBtu/h, in est two or more bor >= 10 hp shall h by a variable spontrols that limit | Requirement ication that service was use settings per 110.3(as houtlet temperature of experience) and the service was are capable of the following and the following with a total combined one of the following the fan motor demand | ter-heating systems are equippe a). ontrols per 110.3(c)1 unless cover of automatically turning off the substantial pump controls per 170. manual on/off controls as specifical installed commercial boilers as esigned to operate with a nonpositioned input capacity per stack of wing d to <=30% of the total design with the controls are equipped to the controls as specifically and the commercial boilers as esigned to operate with a nonpositioned input capacity per stack of wing d to <=30% of the total design with the controls are equipped as the controls are equippe | d with automatic ered by California system per 2(d) or 180.1(b)3 for ed in Reference follows: sitive vent static 2.5 MMBtu/h. eattage at 50% of the |
| For systems serving Piping surrol have pipe in For systems serving Piping instal Insulation In Piping surrol have pipe in For systems serving Recirculating The first 8 ft Pipes that a Insulation shall be positive in the same of the service in the | e for nonresidential occupancies with dents 110.3(c), 160.4, 170.2(d). I dwelling units, pipe insulation must menetrates framing members shall not lenetal framing shall use grommets, plughall abut securely against all framing meled in interior or exterior walls shall no stallation (QII) as specified in the Referunded with a minimum of 1 inch of wasulation. In onresidential spaces, pipe insulation greythm of hot and cold outlet piping, including the externally heated protected from damage, including that cover suitable for outdoor service per 1 and 10 per 10 per 11 per 11 per 11 per 12 per | peet the minimum insulate per required to have pipe s, wrapping or other insumbers to required to have pipe ence Residential Append II insulation, 2 inches of control for the following application piping of the water grows between storage tank a due to sunlight, moisture (20.3(b) / 160.4(f). Pipe in the following application of the water grows are the sunlight, moisture (20.3(b) / 160.4(f). Pipe in the following application of the water grows are the water | cion requirements in Table 1 insulation for the distance of ilating material to assure the e insulation if all of the requ ix RA3.5. crawlspace insulation, or 4 in tions is specified to comply heater nd heat trap, for a nonrecire e, equipment maintenance, nsulation buried below grad N THICKNESS Nominal Pipe I D < 1.5 Minimum Insula | 60.4-A (see blo of the framing p at no contact is uirements are m nches of attic in with Table 120. culating storage and wind. Insul le must be insta | w) except: enetration. Piping that made with the metal framing. net for compliance with Quality sulation, shall not be required to 3-A (see below) per 120.3: e system ation exposed to weather shall illed in a water proof and 1.5 to < 4 Multifamily & Hotel/Motel | 01 | is used to demonstra ted with requirement Yes | te compliante ts in 160.4(e | | onstruction documperature control stems with capac umbing Code 613 ontrols for circulat 10.3(c)2 unless s or recirculation systems diditions. or recirculation systems pendix RA4.4.9 p ombustion air pos Boilers with pressure Boilers when office combustion a The fan mot design air vo | nents require maps capable of adjity > 167,000 BTI. O. Ling pumps or electors serves he stems serving must be stems serving incomer 170.2(d). Litive shut-off shape input capacity >= e one stack serving in fans with motor shall be driver or shall include colume. Lers with an input capacity and the stack serving in the | anufacturer certifusting temperatu UH equipped with ectrical heat trace ealthcare facility. ultiple dwelling und dividual dwelling und libe provided pe = 2.5 MMBtu/h, in es two or more b or >= 10 hp shall in by a variable spinontrols that limit t capacity {d:gte/ | Requirement ication that service was are settings per 110.3(ath outlet temperature of the systems are capable of the following of the following and the fan motor demand | ter-heating systems are equippe a). ontrols per 110.3(c)1 unless cover of automatically turning off the substantial pump controls per 170. manual on/off controls as specifical installed commercial boilers as esigned to operate with a nonpositioned input capacity per stack of wing | d with automatic ered by California system per 2(d) or 180.1(b)3 for ed in Reference follows: sitive vent static 2.5 MMBtu/h. eattage at 50% of the efficiency < 90% shall |
| For systems serving Piping instal Insulation short serving Professional insulation short serving Piping instal Insulation short serving Recirculating Recirculating Insulation short | e for nonresidential occupancies with dents 110.3(c), 160.4, 170.2(d). I dwelling units, pipe insulation must menetrates framing members shall not lenetal framing shall use grommets, plughall abut securely against all framing meled in interior or exterior walls shall no stallation (QII) as specified in the Referunded with a minimum of 1 inch of wasulation. In onresidential spaces, pipe insulation greythm of hot and cold outlet piping, including the externally heated protected from damage, including that cover suitable for outdoor service per 1 and 10 per 10 per 11 per 11 per 11 per 12 per | neet the minimum insulate required to have pipe is, wrapping or other insulations, wrapping or other insulations, and it is required to have pipelence Residential Append II insulation, 2 inches of conforthe following applications piping of the water grown between storage tank and use to sunlight, moisture 1.20.3(b) / 160.4(f). Pipe in 1.20.3(b) / 160.4(f). Pipe in 1.20.3(b) / 160.4(f). | cion requirements in Table 1 insulation for the distance of ilating material to assure the e insulation if all of the requ ix RA3.5. crawlspace insulation, or 4 in tions is specified to comply heater nd heat trap, for a nonrecire e, equipment maintenance, nsulation buried below grad N THICKNESS Nominal Pipe I D < 1.5 Minimum Insula | 60.4-A (see blo of the framing p at no contact is uirements are m nches of attic in with Table 120. culating storage and wind. Insul le must be insta | w) except: enetration. Piping that made with the metal framing. net for compliance with Quality sulation, shall not be required to 3-A (see below) per 120.3: e system ation exposed to weather shall illed in a water proof and | 01 02 03 04 05 06 | is used to demonstra ted with requirement Yes | te compliand ts in 160.4(e | | onstruction documperature controls tems with capacimbing Code 613 ontrols for circulat 10.3(c)2 unless sor recirculation systems where the combustion air poses a Boilers where biller combustion air of the fan motodesign air votation in the combustion air posesure the fan motodesign air votation in the fan motodesign air votation | nents require maps capable of adjity > 167,000 BTI. .0. .ing pumps or electric serves have served in the serving must be served in the s | anufacturer certifusting temperatu UH equipped with ectrical heat trace ealthcare facility. ultiple dwelling und dividual dwelling und dividual dwelling und estwo or more be or >= 10 hp shall in by a variable sprontrols that limit to capacity (d:gte/ concentrations <= pect to firing rate | Requirement ication that service was are settings per 110.3(ath outlet temperature of experiments, design includes authorized to the following of the following the following the fan motor demand of SMMBtu/h and a steet 5% by volume on a dr | ter-heating systems are equippe a). ontrols per 110.3(c)1 unless cover of automatically turning off the sutomatic pump controls per 170. manual on/off controls as specific installed commercial boilers as esigned to operate with a nonpositioned input capacity per stack of wing did to <=30% of the total design was ady state full-load combustion elements. | d with automatic ered by California system per 2(d) or 180.1(b)3 for ed in Reference follows: sitive vent static 2.5 MMBtu/h. eattage at 50% of the efficiency < 90% shall 0%. Combustion air |

Documentation Software: EnergyPro

Compliance ID: EnergyPro-4958-0923-0242

CALIFORNIA ENERGY COMMISSION

(Page 5 of 6)

Report Generated: 2023-09-07 12:06:05

ADDITIONAL REMARKS his table includes remarks made by the permit applicant to the Authority Having Jurisdiction. DOMESTIC HOT WATER EQUIPMENT e demonstrated and with 141.0 / 180.1/180.2 for addition and alteration scopes. uipment Schedule: Water Heating Efficiency and Standby Loss Maximum Standby d Standby Loss Loss nts via an input capacity-weighted 3.5. Label required per 110.3(c)3 recovered energy per 110.3(c)5 has been specified per 110.3(c)6 system per 140.5(a)1. Water heating Documentation Software: EnergyPro Compliance ID: EnergyPro-4958-0923-0242 Report Generated: 2023-09-07 12:06:05 CALIFORNIA ENERGY COMMISSION occupancies, compliance is also ystems are equipped with automation 10.3(c)1 unless covered by California ally turning off the system per p controls per 170.2(d) or 180.1(b)3 fo controls as specified in Reference nmercial boilers as follows: erate with a nonpositive vent static

Mandatory Measures: The following notes (items) represent the Mandatory Measures for

Heat pumps with supplementary electric resistance heaters shall have controls:

- That prevent supplementary heater operation when the heating load can be met by the heat pump alone; and
- In which the cut-on temperature for compression heating is higher than the cut-on temperature for supplementary heating, and the cut-off temperature for compression heating is higher than the cut-off temperature for supplementary

Sec. 110.2 (b)

The minimum rate of outdoor air required per Section 120.1 (b) 2 shall be supplied to each space at all time the space is usually occupied.

Sec. 120.1 (c) 3

The Lesser of the minimum rate of outdoor air required by Sec. 120.1 (b) 2, or three complete air changes shall be supplied to the entire building during the one-hour period immediately before the building is normally occupied.

Sec. 120.1 (c) 2

Hotel/Motel Guest Room Thermostats shall have numeric temperature set points in degrees F; and set point stops accessible only to authorized personnel, to restrict overheating and over-cooling.

Sec. 120.2 (c)

All air distribution system ducts and plenums, including, but not limited to, building cavities, mechanical closets, air-handler boxes and support platforms used as ducts or plenums, shall be installed, sealed and insulated to meet the requirements of chapter 6 of the 2001 CMC. Supply-air and return-air ducts conveying heated or cooled air shall be insulated to a minimum installed level of R-8, unless ducts are in conditioned space.

The thermostatic controls for HVAC systems shall meet the following requirements as applicable:

- Each space conditioning zone shall be controlled by an individual thermostatic control that responds to temperature within the zone and meets the applicable requirements of Subsection (b).
- Each Thermostatic control required by Subsection (a) shall be capable of being set locally or remotely by adjustment or selection of sensors to control:
 - Comfort heating down to 55°F or lower.
 - 2) Comfort Cooling up to 85°F or higher
 - 3) Both heating and cooling, the thermostatic controls shall be capable of providing a temperature range or dead band of at least 5°F within which the supply of heating and cooling energy to the zone is shut off or reduced to a minimum.

Sec. 120.2 (a) & (b)

Outdoor air supply and exhaust equipment shall be installed with dampers that automatically close upon fan shutdown.

Sec. 120.2 (f)

2) Demand Control Ventilation Devices (CO2 sensors) shall be installed in accordance with Sec.

Sec. 120.1 (c) 4

3) Each space-conditioning system shall be installed with controls that comply with Items 1 and 2

- Are capable of automatically shutting off the system during periods of non-use
- An automatic time switch control device complying with Sec. 119(e), with an accessible manual override that allows operation of the system for up to
- An occupancy sensor; or
- A four-hour timer that can be manually operated.
- EXCEPTION: Mechanical systems serving retail stores and associated malls, restaurants, grocery stores, churches, and theaters equipped with 7day programmable timers.
- Automatically restart and temporarily operate the system as required to maintain: A setback heating thermostat set point, if the system provides mechanical
 - EXCEPTION: Area with the design winter outdoor temperature of greater
- A setup cooling thermostat set point, if the system provides mechanical
 - EXCEPTION: Area with the design summer outdoor temperature of less

EXCEPTION: Systems serving hotel/motel guest rooms, if they have a readily accessible manual shut-off switch.

Sec. 120.2 (e)

5) Service water heating systems and equipment shall meet the applicable requirements of the

Sec. 110.3 (b)

6) Service hot water systems with circulating pumps or with electrical heat trace systems shall be capable of automatically turning off the system. Sec. 110.3 (c) 2

7) Lavatories in public restrooms shall have controls that limit the water supply temperature to

Sec. 110.3 (c) 3

IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 12/18/2024

ROJECT SPECIFIC STATE AGENCY APPROVAC


DESIGN ♦ CONSULTING ♦ PROJECT MG 11590 W BERNARDO COURT, SUITE 100 SAN DIEGO, CA 92127

PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE **EXPRESS WRITTEN CONSENT OF R&S** TAVARES ASSOCIATES, INC. ©

CLIENT



ORIGINAL PC STATE AGENCY APPROVAL APPROVED DIV. OF THE STATE ARCHITECT APP: 04-123059 PC REVIEWED FOR SS D FLS D ACS Q CG D

Revision Schedule

Description

PRE-CHECK (PC) DOCUMENT

Code: 2022 CBC

A separate project application for construction is required PROJECT TITLE

PC 2022 CBC: 24' x 40' **EXPANDABLE TO** 120' x 40'

ENVELOPE AND NOTES

PROJECT NUMBER

22088

DRAWN BY rMc/CG

CHECKED BY RH/RT

DATE

SHEET NO.

SHEET OF

Generated Date/Time: CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220101

Documentation Software: EnergyPro Compliance ID: EnergyPro-4958-0923-0242 Report Generated: 2023-09-07 12:06:05

Lal Sahgal

LSA Consulting Engineers

3, Windswept Way

Mission Viejo Ca. 92692

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance

DOCUMENTATION AUTHOR'S DECLARATION STATEMENT

RESPONSIBLE PERSON'S DECLARATION STATEMENT

tify the following under penalty of perjury, under the laws of the State of California

The information provided on this Certificate of Compliance is true and correct

inspections. I understand that a completed signed copy of this Certificate of Compliance is required to the complete of the complete copy of the certificate of Compliance is required to the complete copy of the certificate of Compliance is required to the complete copy of the certificate of Compliance is required to the copy of the certificate of Compliance is required to the complete copy of the certificate of Compliance is required to the copy of the certificate of Compliance is required to the copy of the certificate of Compliance is required to the copy of the certificate of Compliance is required to the copy of the certificate of Compliance is required to the copy of the certificate of Compliance is required to the copy of the copy of

I certify that this Certificate of Compliance documentation is accurate and complete

Domestic Water Heating System

ect Name: 24X40 (PC 04-121369) - Wall AG

STATE OF CALIFORNIA

CERTIFICATE OF COMPLIANCE

nentation Author Name

LSA CONSULTING ENGINEERS

SION VIEJO CA 92692

B, WINDSWEPT WAY

LAL B. SAHGAL

Schema Version: rev 20220101

Generated Date/Time:

Report Version: 2022.0.000

Report Page:
Climate Zone 14 Date Prepared:

I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design or system design identified on this Certificate of Compliance (responsible designer)

The energy features and performance specifications, materials, components, and manufactured devices for the building design or system design identified on this Certificate of Compliance conform to the requiren The building design features or system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations

plans and specifications submitted to the enforcement agency for approval with this building permit application.

I will ensure that a completed signed copy of this Certificate of Compliance shall be made available with the building permit(s) issued for the building, and made available to the enforcement agency for all applicable

2023-09-07

Schema Version: rev 20220101

(949) 830-4746

Lal Sahgal

Lal Sahgal

Documentation Software: EnergyPro 4) The piping for all space conditioning and service water heating systems shall be insulated in Compliance ID: EnergyPro-4958-0923-0242 Report Generated: 2023-09-07 12:06:05

Compliance ID: EnergyPro-4958-0923-0242

Report Generated: 2023-09-07 12:06:05

CALIFORNIA ENERGY COMMISSION

NRCC-PLB-E

(Page 6 of 6) 9/7/2023


CALIFORNIA ENERGY COMMISSIO

(Page 2 of 6

accordance with TABLE 123-A.

Sec. 120.3

Appliance Efficiency Regulations as required by Sec. 110.1.



IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024





THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE **EXPRESS WRITTEN CONSENT OF R&S** TAVARES ASSOCIATES, INC. ©



ORIGINAL PC STATE AGENCY APPROVAL

APPROVED DIV. OF THE STATE ARCHITECT APP: 04-123059 PC REVIEWED FOR SS D FLS D ACS D CG D


Revision Schedule

PRE-CHECK (PC) DOCUMENT


A separate project application for construction is required

PC 2022 CBC: 24' x 40' **EXPANDABLE TO** 120' x 40'

> **CEILING PLAN** 36x40



ROJECT SPECIFIC STATE AGENCY APPROVAL



SIDEWALL

FOOTING

12" WIDE

(2) #5

CONT T&B

12" WIDE

(2) #5

CONT T&B

14" WIDE

(2) #5

CONT T&B

ENDWALL

FOOTING

14" WIDE

(3) #5 CONT

T&B

16" WIDE

(3) #5 CONT

T&B

16" WIDE

(3) #5 CONT

INTERIOR PAD

FOOTING

(3) #5 EW

3' - 4" SQ

(3) #5 EW

4' - 0" SQ

(4) #5 EW

PAD FOOTING @

SEPARATION

3' - 8" SQ


(4) #5 EW

4' - 2" SQ

(4) #5 EW

4' - 8" SQ

(4) #5 EW




- THE FOUNDATION DESIGN CONSIDERS AN ALLOWABLE SOIL BEARING PRESSURE OF 1,500 PSF FOR LOCATIONS THAT DO NOT REQUIRE A
- SOILS INVESTIGATION REPORT. DISTRICT SHALL BE RESPONSIBLE IN ISSUING AND CONTRACTING A SOILS INVESTIGATION THROUGH A QUALIFIED GEOTECHNICAL
- ENGINEER FOR LOCATIONS DEEMED QUALIFIED BY CBC 1803A.2. WELD PLATES SAHLL BE PLACED PER PLAN AT 21" MINIMUM FROM BUILDING CORNERS AND 14" MINIMUM FROM ADJACENT WELD PLATE. WELD PLATES WITHIN 21" FROM VENT SHALL REQUIRE
- TO THE VENT. SEE DETAIL 1/F2.23 FOUNDATION OVERALL CONSIDERS A 1/4" GAP AT EVERY MODLINE AND 6" SEISMIC SEPARATION GAP WHEN APPLICABLE.

REINFORCEMENT HAIRPINNED AROUND THE ANCHOR BOLT CLOSEST

- SIZE OF UNDER-FLOOR VENITIALATION CONSIDERS A RATIO OF 1:150 FOR THE TOTAL AREA OF OPENEINGS TO CRAWL SPACE AREA. CRAWL SPACE AREAS FITTED WITH A VAPOR BARIER IN ACCORDANCE WITH
- IBC, 1203.3.2 SHALL BE PERMITTED A RATIO ADJUSTMENT TO 1:1500. VENTILLATION OPENING SHALL BE COVERED WITH CORROSION RESITANT WIRE WITH THE LEAST DIMENSION NOT GREATER THAN 1/8".


| FOOTING SC | HEDULE (CON | CRETE FLOOF | R) | |
|---------------------------|--------------------------------|--------------------------------|-------------------------|-----------------------------|
| DESIGN FLOOR LIVE LOAD | SIDEWALL FOOTING | ENDWALL FOOTING | INTERIOR PAD FOOTING | PAD FOOTING @ SEPARATION |
| ☐ 50 + 15 PSF | 12" WIDE (2) #5 CONT T&B | 14" WIDE (3) #5.eONT | 3' - 2" SQ (3) #5 EW | 4' - 0" SQ (4) #5 EW |
| ☐ 100 PSF | 12" WIDE (2)#5 CONT T&B | 16" WIDE (3) #5 CONT T&B | 3' - 6" SQ (3) #5 EW | 4' - 6" SQ (4) #5 EW |
| ☐ 150 PSE | 14" WIDE (2) #5 CONT T&B | 16" WIDE (3) #5 CONT T&B | 4' - 2" SQ (4) #5 EW | 4' - 10" SQ (5) #5 EW |



| | V | VELD PLATE | SCHEDULE | |
|---------|------------------|------------|--------------|-----------|
| | | L6x4x3/8, | 16x3/8 SQ PL | |
| | | ≤ 100 PSF | 150 PSF | ≤ 150 PSF |
| EACH SI | DEWALL | 3 | 4 | - |
| EACH M | ODLINE | - | 2 | 2 |
| EACH | 24x40 | 5 | 7 | |
| END- | 36x40 | 6 | 7/10 | |
| WALL | 48x40 | 7 | 10/13 | |
| | 60x40 | 9 | 12 | |
| | 72x40 | 10 | 14 | |
| | 84x40 | 12 | 17— | |
| | 96x40 | 13 | 19- | |
| | 108x40 | 15 | 21 | |
| | 120x40 | 16 | 23 | |

PROJECT SPECIFIC STATE AGENCY APPROVAL IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 12/18/2024





THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE **EXPRESS WRITTEN CONSENT OF R&S** TAVARES ASSOCIATES, INC. ©

CLIENT



ORIGINAL PC STATE AGENCY APPROVAL APPROVED DIV. OF THE STATE ARCHITECT APP: 04-123059 PC REVIEWED FOR SS PLS PLACS CG P

> Revision Schedule Description

PRE-CHECK (PC) DOCUMENT


Code: 2022 CBC


A separate project application for construction is required PROJECT TITLE


PC 2022 CBC:24' x 40' **EXPANDABLE TO** 120' x 40'

> CONCRETE **FOUNDATION** PLAN

| | PROJECT NUM | BER |
|--|-------------|--------|
| | | 22088 |
| | DRAWN BY | rMc/SC |
| | CHECKED BY | JA/RT |
| | DATE | |







IN ACCORDANCE WITH CURRENT AISC SPECIFICATIONS AND STANDARDS. STEEL SHAPES SHALL COMFORM TO THE FOLLOWING STANDARD:

ALL OTHER:

STRUCTURAL HSS COLUMNS: ASTM A500 GRADE B STRUCTURAL W-SHAPES: ASTM A992 GRADE 50 TUBE STEEL: ASTM A500 GRADE A

FABRICATION, ERECTION, AND SHOP PAINTING SHALL BE IN ACCORDANCE WITH THE PROVISIONS OF THE AISC CODE OF STANDARD PRACTICE FOR STEEL BUILDING AND BRIDGES

HOLES IN STRUCTURAL STEEL SHALL NOT BE PERMITTED, UNLESS SPECIFIED IN THE STRUCTURAL DRAWINGS

ASTM A36

CONCRETE

ALL CONCRETE WORK, UNLESS MODIFIED BY CONTRACT DOCUMENTS, SHALL BE PERFORMED IN ACCORDANCE WITH CHAPTER 19A, CBC 2022 AND ACI 318-19.

TESTS AND INSPECTION SHALL BE PERFORMED BY A TESTING LABORATRY CONTRACTED BY THE DISTRICT.

MIX DESIGN SHALL BE SUBMITTED FOR QUALIFICATION AND PROVIDE A 28-DAY COMPRESSIVE STRENGTH F'C OF 3500 PSI, COMPOSED OF NORMAL WEIGHT TYPE I PORTALAND CEMENT IN CONFORMANCE WITH ASTM C150.

FORMWORK SHALL RESULT IN FINAL STRUCTURE THAT CONFORMS TO SHAPES, LINES, AND DIMENSIONS AS REQUIRED BY THE CONTRACT DOCUMENTS.

LOCATIONS OF VENTS AND OPENINGS FOR MECHANICAL AND ELECTRICAL USE SHALL BE VERIFIED BY ARCHITECT.

EMBEDMENT OF MATERIALS NOT HARMFULL TO CONCRETE AND WITHIN LIMITATIONS OF SECTION 20.6, ACI-318-19 SHALL BE PERMITTED. REFER TO OTHER DISCIPLINES FOR LOCATION OF CONDUIT, PIPES, FITTINGS, SLEEVES, ETC.

CONTINUOUS BATCH PLANT INSPECTION WAIVED PER CBC 1705A3.3. WHEN CONTINUOUS BATCH PLANT INSPECTION WAIVED, THE FOLLOWING PERIODIC INSPECTION SHALL BE REQUIRED:(INSPECTIONS PROVIDED BY DISTRICT)

QUALIFIED TECHNICIAN OF THE TESTING LABORATORY SHALL CHECK THE FIRST BATCH AT THE START OF

LICENSED WEIGHMASTER TO POSITIVELY IDENTIFY MATERIALS AS TO QUANTIFY AND CERTIFY TO EACH LOAD BY A BATCH TICKET.

BATCH TICKETS, INCLUDING MATERIAL QUANTITIES AND WEIGHTS SHALL ACCOMPANY THE LOAD, SHALL BE TRANSMITTED TO THE INSPECTOR OF RECORD BY A TRUCK DRIVER WITH THE LOAD IDENTIFIED THEREON. THE LOAD SHALL NOT BE PLACED WITHOUT A BATCH TICKET IDENTIFYING THE MIX. THE INSPECTOR WILL KEEP A DAILY RECORD OF PLACEMENTS, IDENTIFYING EACH TRUCK, ITS LOAD, AND TIME OF RECEIPT, AND APPROXIMATE LOCATION OF DEPOSIT IN THE STRUCTURE AND WILL TRANSMIT A COPY OF THE DAILY RECORD TO THE ENFORCEMENT AGENCY.

ANCHOR BOLTS, AND REINFORCING STEEL SHALL BE SECURELY TIED BEFORE CONCRETE IS POURED.

CONCRETE MIX

IN ADDITION TO THOSE REQUIREMENTS DICTATED BY THE PC DESIGN, THE CONCRETE MIX USED IN THE FOUNDATION ELEMENTS SHALL COMPLY WITH THE DURABILITY REQUIREMENTS OF AMERICAN CONCRETE INSTITUTE (ACI) 318 SECTION 19.3. THE PC DRAWINGS SHALL ACCOUNT FOR THE DEPENDENCY OF THESE DURABILITY REQUIREMEMNTS ON SITE-SPECIFIC CHARACTERISTICS.

A. WHEN THE PC DRAWINGS DO NOT REQUIRE A SITE-SPECIFIC GEOTECHNICAL REPORT THAT QUANTIFIES SULFATE CONTENT IN THE SOIL, THE PC DRAWINGS SHALL REQUIRE A CONCRETE MIX SHALL COMPLYING WITH ONE OF THE FOLLOWING PER ACI 318 TABLE 19.3.2.1. SEE THIS SHEET A.1 & A.2 FOR OPTIONS

B. MAXIMUM WATER/CEMENT RATION OF 0.45; MINIMUM COMPRESSIVE STRENGTH OF 4,500 POUNDS PER SQUARE INCH (PSI); TYPE V CEMENT PLUS POZZOLAN OR SLAG CEMENT COMPLYING WITH FOOTNOTE 7; AND PROHIBITION OF ADMIXTURES CONTAINING CALCIUM CHLORIDE

C. MAXIMUM WATER/CEMENT RATIO OF 0.40; MINIMUM COMPRESSIVE STRENGTH OF 5,000 PSI; TYPE V CEMENT COMPLYING WITH FOOTNOTE 8; AND PROHIBITION OF ADMIXTURES CONTAING CALCIUM CHLORIDE.

D. WHEN THE PC DRAWINGS REQUIRE A SITE-SPECIFIC GEOTECHNICAL REPORT THAT QUANTIFIES SULFATE CONTENT IN THE SOIL, THE PC DRAWINGS SHALL CLEARLY STATE THE EXPOSURE CLASS FOR EACH CATAGORY (I.E., F, S, W, AND C) OR COMBINATION THEREOF THE PC DESIGN IS APPROVED FOR. THE MAXIMUM WATER/CEMENT RATIO, MINIMUM COMPRESSIVE STRENGTH, CEMENTITOUS MATERIAL REQUIREMENTS, AND ADMIXTURE LIMITATIONS SHALL BE STATED ON THE PC DRAWINGS FOR EACH APPROVED CASE.

E. BOTH APPROACHES GIVEN SECTIONS 5.5.1 AND 5.5.2 ABOVE CAN BE INCLUDED ON THE PC DRAWINGS AS ALTERNATE OPTIONS IN ACCORDANCE WITH SECTION 1.4 ABOVE

F. CONCRETE EXPOSE TO THAW AND FREEZE CYCLES SHALL BE AIR ENTRAINED PER ACI 318 SECTION 19.3.3.1

STEEL REINFORCEMENT

DEFORMED BARS SHALL CONFORM TO ASTM A615.

fy= 60,000 PSI, FOR ALL BARS EXEPT FOR #3 BARS, fy= 40,000 PSI.

PROVIDE A MINIMUM CONCRETE COVER FOR REINFORCEMENT EMBEDDED IN: CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH = 3"

CONCRETE EXPOSED TO EARTH OR WEATHER FOR #5 BARS OR SMALLER = 1.5"

SPLICE LENGTHS SHALL BE A MINIMUM OF 48" FOR #5 BARS, AND 30" FOR #4 BARS UNLESS OTHERWISE SPECIFIED DRAWINGS.

ALL BOLTS AND ANCHOR BOLTS SHALL COMFORM TO ASTM A-307

BOLTS EXPOSED TO THE ELEMENTS SHALL BE GALVANIZED BY THE HOT-DIP OR MECHANICAL

WELDING

A. ALL WELDING SAHLL BE IN COMFORMANCE TO:

a. AWS D1.1, EXCEPT AS MODIFIED IN SECTION J2, AISC-360 FOR STEEL

AWS D1.3 FOR LIGHT GAUGE STEEL AWS D1.4 FOR REINFORCING STEEL

ELECTRODE CLASSIFICATION:

a. E70XX FOR STEEL AND CONCRETE STEEL REINFORCEMENT

SHOP AND FIELD WELDING SHALL BE PERFORMED BY AWS CERTIFIED WELDERS

E60XX FOR LIGHT GAUGE STEEL

WELDS SHALL BE CAPABLE OF PRODUCING THE FOLLOWING V-NOTCH TOUGHNESS AS DETERMINED BY APPROPRIATE AWS A5 CLASSIFICATION TEST METHOD OR MANUFACTURER

LATERAL FORCE RESISTING SYSTEM (LFRS) = 20 FT-LB AT 0 DEGREE F

COMPLETE JOINT PENETRATION GROOVE WELD = 20 FT-LB AT 40 DEGREE F

PERIODIC INSPECTION OF FILLET WELDS LESS THAN OR EQUAL TO 5/16", FLOOR AND ROOF DECK WELDS.

b. CONTINUOUS INSPECTION FOR OTHER WELDS.

NONDESTRUCTIVE TESTING (NDT):

a. ULTRASONIC TESTING SHALL BE PERFORMED ON 100 PERCENT OF CJP GROOVE WELDS IN MATERIALS 5/16" OR THICK OR GREATER. ULTRASONIC TESTING NOT REQUIRED FOR MATERIALS LESS THAN 5/16" THICK. TESTING FREQUENCY MAY BE REDUCED TO 25%, PROVIDED PROVISIONS SET FORTH IN SECTION N5.5e, AISC-360 IS MET.

MAGNETIC PARTICLE TESTING SHALL BE PERFORMED ON 25 PERCENT OF ALL BEAM-TO-COLUMN CJP GROOVE WELDS. TESTING FREQUENCY MAY BE REDUCED TO 10%, PROVIDED PROVISIONS SET FORTH IN J6.2g, AISC-341 IS MET.

FOUNDATIONS

GEOTECHNICAL INVESTIGATION SHALL BE CONDUCTED IN ACCORDANCE WITH SECTION 1803A.1 THROUGH 1803A.8 BY GEOTECHNICAL ENGINEER CONTRACTED BY THE DISTRICT. ALLOWABLE FOUNDATION AND LATERAL SOIL PRESSURE VALUES MAY BE DETERMINED FROM TALBLE 1806A.2, WHERE GEOTECHNINCAL REPORTS IS NOT REQUIRED PER SECT 1803A.2. A MAXIMUM ALLOWABLE SOIL PRESSURE OF 1000 PSF AND 1500 PSF SHALLBE PERMITTED FOR TEMPORARY W AND PERMANENT CONCRETE FOUNDATIONS RESPECTIVELY IN ACCORDANCE WITH SECTION 4.6, IR 16-1

A PREVIIOUS REPORT FOR A SPECIFIC SITE MAY BE RESUBMITTED. THE ALLOWABLE FOUNDATIONA AND LATERAL SOIL PRESSURE VALUES ARE ALLOWED A 33% INCREASE FOR SHORT TERM WIND AND SEIMIC LOADS.

THE DISTRCT SHALL BE RESPONSIBLE FOR EXCAVATION, BACKFILL, SETTING ELEVATIONS, CRANING AND RIGGING. PROVIDE SHIMS TO LEVEL BUILDING WITHIN 1/2" TOLERANCE.

COLD-FORMED STEEL:

ALL WORK SHALL, UNLESS MODIFIED BY THE CONCTRACT DOCUMENTS, SHALL BE PERFORMED IN ACCORDANCE WITH CURRENT AISI SPECIFICATIONS AND STANDARDS.

MATERIAL SPECIFICATION:

ASTM A-1011/A, GRADE 33 FOR MATERIALS THICKNESS 0.120 OR LESS UNLESS OTHERWISE NOTI

ASTM A-1003, GRADE 33 TYPE H FOR LIGHT GUAGE STUDS AND TRACKS SHAPES SHALL BE DIMENSIONED TO SSMA SPECIFICATIONS.

C. SCREWS EXPOSED TO THE ELEMENTS SHALL BE GALVANIZED

STEEL DECK

MINIMUM THICKNESS PERMITTED FOR FLOOR STEEL DECKS IS 20GA. PER DSA IR 16-1, 1.2.1, MINIMUM THICKNESS OF NON-STRUCTURAL STEEL ROOF DECKING IS 26GA. STANDING SEAM ROOF PANELS ARE GRADE 40 SHEET STEEL WITH ALUMINUM ZINC COATING CONFORMING TO ASTM A792 AND AZ55.

CHANGES AFFECTING STRUCTURAL PORTION OF THE APPROVED PC SHALL NEED DSA APPROVAL AND SHALL BE CLASSIFIED AS CCD CATEFORY A.

ALL FRAMING LUMBER SHALL BE GRADE MARKED BY AN APPROVED GRADING AGENCY

SHEATHING:

EACH SHEET SHALL BE GRADE MARKED BY THE AMERICAN PLYWOOD ASSOCIATION IN ACCORDANCE WITH THE PROCEDURES AND QUALIFICATIONS SET FORTH BY PS 1-19.

SUB FLOOR: 1 1/8" T&G UNBLOCKED PLYWOOD, SHALL PROVIDE A SMOOTH AND UNIFORM SURFACE

CAPABLE OF ACCEPTING CARPET FINISH PLYWOOD ROOF DECK OPTION: APA RATED 3/4" T&G OSB OR EQUIVALENT RATED SHEATHING

EXTERIOR WALL SIDING: STANDARD: 5/8" DURATEMP OR 5/8" SMART PANEL

OPTION: 5/8" MOD

OPTION: 1/2" OSB OR CDX PLYWOOD FOR PLASTER/STUCCO FINISH

OPTION: 1/2" OSB OR CDX PLYWOOD FOR HARDIE BOARD (LAP SIDING) FINISH

EXTERIOR WALL SIDING ATTACHMENT:

COPPER PER CBC 2304.10.1.1

FASTENERS USED FOR THE ATTACHMENT OF EXTERIOR WALL COVERINGS SHALL BE HOT-DIPPED GALVANIZED, MECHANICALLY DEPOSITED ZINC-COATED, STAINLESS, SILICON BRONZE OR COPPER PER CBC SECTION 2304.10.1.1

FASTEN TO WOOD FRAMING WITH 8D BOX NAILS @ 6" E.N., 12" F.N. FASTEN TO LIGHT GAGE METAL FRAMING WITH #8 WAFER HEAD STSMS @ 6" E.N., 12" F.N. FASTEN TO STRUCTURAL STEEL WITH #12 STSMS OR 0.145 DIAM SHOT PINS @ 12" O.C.

TREATED WOOD:

ALL WOOD LOCATED WITHIN 6" OF EXPOSED EARTH SHALL BE "PRESERVATIVE TREATED" OR SHALL BE "NATURALLY DURABLE" MATERIAL IN ACCORDANCE WITH CBC SECTION 2304.12.1.2.

ALL ROUGH LUMBER SHALL BE DF #2 OR BETTER. ALL POWER DRIVEN FASTENERS SHALL BE HILTI FASTENERS ICC# ESR-1663, AND RAMSET POWER

DRIVEN FASTENERS (ICC # ESR-1799), OR SIMPSON POWER DRIVEN FASTENERS ICC #ESR-2138, OR OTHER EQUIVALENT PRODUCTS WITH ICC REPORTS AND APPROVED BY DSA. FASTENERS, INCLUDING NUTS AND WASHERS, IN CONTACT WITH PRESERVATIVE-TREATED WOOD SHALL BE OF HOT-DIPPED ZINC-COATED GALVANIZED STEEL, STAINLESS STEEL, SILICON BRONZE OR

ROOF DIAPHRAGM:

3/4" T&G RATED SHEATHING UNBLOCKED DIAPHRAGM, EXPOSURE 1, 48/24 SPAN RATING FASTEN AT METAL SUPPORTS W/ #10 x 1 1/4" SELF-TAPPING PHILLIPS FLAT-HEAD ZINC

COATED TEKS SCREWS @ 6" BN/CON. EDGE, 6" EN, AND 12" O.C. FN. PROVIDE A MINIMUM OF 3/8" EDGE DISTANCE FOR FASTENERS TO PLYWOOD EDGE PER CBC SECTION 2306.2.

NOTE: ALL PANEL EDGES SHALL BE ATTACHED TO FRAMING MEMBERS OR BLOCKING. WHERE USED AS BLOCKING, FLAT STRAPPING SHALL BE A MINIMUM THICKNESS OF 33MILS WITH A MINIMUM WIDTH OF 1.5 INCHES AND SHALL BE EITHER INSTALLED BELOW SHEATHING. FOR OTHER THAN STEEL SHEATHING, THE SCREWS SHALL BE INSTALLED THROUGH THE SHEATHING TO THE BLOCKING.

FLOOR DIAPHRAGM:

1 1/8" PLYWOOD UNBLOCKED DIAPHRAGM - STURD-I-FLOOR T&G RATED SHEATHING, EXTERIOR, 48" oc SPAN RATING FASTEN AT METAL SUPPORTS W/ #10 - 24 x 2" SELF-TAPPING PHILLIPS FLAT-HEAD ZINC COATED TEKS @ 6" O.C. BN/CON. EDGE, 6" O.C. EN, 12" FN. PROVIDE A MINIMUM OF 3/8" EDGE DISTANCE FOR FASTENERS TO PLYWOOD EDGE PER CBC SECTION 2306.2

NOTE: ALL PANEL EDGES SHALL BE ATTACHED TO FRAMING MEMBERS OR BLOCKING. WHERE USED AS BLOCKING. FLAT STRAPPING SHALL BE A MINIMUM THICKNESS OF 33MILS WITH A MINIMUM WIDTH OF 1.5 INCHS AND SHALL BE BELOW SHEATHING. FOR OTHER THAN STEEL SHEATHING, THE SCREWS SHALL BE FITHER INSTALLED INSTALLED THROUGH THE SHEATHING TO THE BLOCKING.

CONCRETE FLOOR DATA: LIGHTWEIGHT CONCRETE FLOOR STRENGTH: 3500 PSI

TYPE: I OR II DESINTY: 110 PCF - MAX

DIMENSION LUMBER ATTACHMENT TO STEEL FRAMING:

2 x STUDS AT CORNER STEEL COLUMNS (NAILING STUD) USE: #10 - 24 x 2 1/2" LG. SELF-DRILLING SELF-TAPPING PHILLIPS FLAT-HEAD WITH WASHER ZINC COATED TEK SCREWS AT 24" OC.

NAILING NOTES:

ALL NAILS SHALL BE COMMON UNLESS OTHERWISE NOTED

MACHINE APPLIED 16d FASTENERS SHALL HAVE AN EMBEDMENT OF NOT LESS THAN 1 1/2" INTO THE SECOND MEMBER, AND SHALL NOT BE LESS THAN 3" IN OVERALL LENGTH.

NAILS SHALL BE ACCEPTABLE FOR HAND NAILING, PROVIDED THE REQUIREMENT EMBEDMENT IS MAINTAINEI

CONNECTIONS AND FASTENERS:

ALL CONNECTIONS AND FASTENERS IN DRAWINGS CAN BE SUBSTITUTED BY AN EQUIVALENT PRODUCT PROVIDING REPORTS ARE SUBMITTED TO AND APPROVED BY DSA. **CONNECTIONS LAG SCREWS:**

LAG SCREWS SHALL BE INSTALLED WITH WASHER AND TURNED BY WRENCH, OVER-TORQUING SHALL BE AVOIDED. PRE-DRILLED CLEARANCE AND LEAD HOLE SHALL BE REQUIRED AS DESCRIBED BELOW:

THE CLEARANCE HOLE FOR THE UNTHREADED PORTION OR THE SHANK SHALL HAVE SAME DEPTH AND DIAMETER.

THE LEAD HOLE FOR THE THREADED PORTION OF THE SHANK SHALL HAVE SAME DEPTH AND 65% TO 85% OF SHANK DIAMETER FOR LUMBER WITH SPECIFC GRAVITY OF, G > 0.6 60% TO 75% OF SHANK DIAMETER FOR LUMBER WITH SPECIFC GRAVITY OF, 0.5 < G ≤ 0.6 40% TO 70% OF SHANK DIAMETER FOR LUMBER WITH SPECIFC GRAVITY OF, G ≤ 0.5

LEAD OR CLEARANCE HOLES SHALL NOT BE REQUIRED FOR 3/8" DIAMETER OR SMALLER LAG SCREWS.

NAILING SCHEDULE: (ALL NAILS SHALL BE COMMON OR BOX NAILS, GALVANIZED WHERE EXPOSED) PER CBC TABLE 2304.10.2

| | CONNECTION | C | OMMO | N FASTENERS | ВС | X NA | IL FASTENERS | LOCATION |
|-----|-----------------------------|-----|-------|--------------|-------|-------|--------------|---------------------------------|
| | | QTY | SIZE | SPACING O.C. | QTY | SIZE | SPACING O.C. | |
| 1. | JOIST TO SILL OR GIRDER | 3- | - 8d | | 3- | 10d | | TOENAIL |
| 2. | BRIDGING TO JOIST | 2- | - 8d | | 2- | 10d | | TOENAIL EA. END |
| | 1X6 OR LESS SUBFLOOR TO | | | | | | | |
| 3. | EA. JOIST | 2. | - 8d | | 2- | 10d | | FACE NAIL |
| | WIDER THAN 1X6 SUBFLOOR | _ | | | _ | | | |
| 1 | TO EA. JOIST | 3 | - 8d | | 3_ | 10d | | FACE NAIL |
| | 2" SUBFLOOR TO JOIST | _ | - 16d | | _ | N/A | N/A | BLIND & FACE NAIL |
| Э. | SOLE PLT. TO JOIST OR BLK'G | ۷. | - 16a | | IN/A | IN/A | IN/A | BLIND & FACE NAIL |
| _ | | | 40.1 | 0.401 | | 40.1 | 0.40" | EAGE NAIL |
| ъ. | TO EA. JOIST | | 16d | @ 16" | | 16d | @ 12" | FACE NAIL |
| | | | | | | | | |
| | SOLE PLT. TO JOIST OR BLK'G | | | | | | | |
| | @ BRACED WALL PANEL | 3- | - 16d | @ 16" | 3- | 16d | @ 16" | TYP. FACE NAIL |
| 7. | TOP PLT. TO STUD | 2- | - 16d | | 3- | 10d | | END NAIL |
| 8. | STUD TO SOLE PLT. | 2- | - 16d | | 3- | 10d | | END NAIL |
| | OR | 4- | - 8d | | 4- | 10d | | TOENAIL |
| 9. | DOUBLE STUDS | | 16d | @ 24" | | 10d | @ 16" | FACE NAIL |
| | DOUBLE TOP PLT. | | 16d | @ 16" | | 10d | @ 12" | TYP. FACE NAIL |
| | DOUBLE TOP PLT. | 8- | - 16d | MIN. U.N.O. | 12- | 10d | 0 | 24" MIN LAP SPLICE |
| | BLKG. BTW. JOIST OR | Ŭ | | | | | | |
| 11 | RAFTERS TO TOP PLT. | 3 | - 8d | | 3 | 10d | | TOENAIL |
| | RIM JOIST TO TOP PLT. | J. | 8d | @ 6" | 3- | | @ 6" | TOENAIL |
| 12. | | | ou | @ 6" | | 10d | @ 6" | TOENAIL |
| | TOP PLT., LAPS & | _ | 40.1 | | | 40.1 | | EAGE NAII |
| | INTERSECTIONS | 2- | - 16d | | 3- | 10d | | FACE NAIL |
| | CONT. HDR. 2 PIECES | | 16d | @ 16" | | | | ALONG EDGE |
| | CLG. JOIST TO PLT. | 3- | - 8d | | 3- | 10d | | EA. JOIST, TOENAIL |
| 16. | CONT. HDR. TO STUD | 4- | - 8d | | 4- | 10d | | TOENAIL |
| | CLG. JOIST LAP OVER | | | | | | | |
| 17. | PARTITIONS | 3- | - 16d | | 4- | 10d | | FACE NAIL |
| | CLG. JOIST PARALLEL TO | | | | | | | |
| 18. | RAFTERS | 3. | - 16d | | SEE . | TABLE | 2308.7.3.1 | FACE NAIL |
| | RAFTER TO PLT. | | - 8d | | | 16d | | TOENAIL ^c |
| 19. | 1" DIA. BRACE TO EZ. STUD & | ١ . | ou | | 3- | 100 | | TOLIVAIL |
| 20 | | _ | 04 | | _ | 104 | | EACE NAIL |
| | PLT. | _ | - 8d | | _ | 10d | | FACE NAIL |
| 21. | 1X8 SHT'G. TO EA. BRG. | 3. | - 8d | | 3- | 10d | | FACE NAIL |
| | WIDER THAN 1X8 SHT'G TO | l . | | | ١. | | | |
| | BRG. | 3- | - 8d | | 3- | 10d | | FACE NAIL |
| 23. | BUILT-UP CORNER STUDS | | 16d | @ 24" | | | | FACE NAIL |
| | | | | | | | | FACE NAIL @ TOP & BTM. STAGR. |
| 24. | BUILT-UP GIRDERS & BEAMS | | 20d | @ 32" | | 10d | @ 24" | ON OPP. SIDES |
| | | l | | | | | | |
| | | 2- | - 20d | | N/A | N/A | N/A | FACE NAIL @ ENDS & @ EA. SPLICE |
| 25. | 2" PLANKS | | - 16d | | N/A | | N/A | @ EA. BRG. |
| | COLLAR TIE TO RAFTER | | - 10d | | | 10d | | FACE NAIL |
| | JACK RAFTER TO HIP | | - 10d | | | 16d | | TOENAIL |
| | ROOF RAFTER TO 2X RIDGE | | - 16d | | | 10d | | END NAIL |
| | JOIST TO BAND JOIST | | - 16d | | | 10d | | END NAIL |
| | | | | | | | NI/A | |
| 3U. | 4X BLOCKING TO STUDS | ı | - A34 | | N/A | | N/A | FACE NAIL |
| | OR | 4- | - 8d | | 4- | 10d | | TOENAIL |

A.) NAILS SPACED AT 6 INCHES AT INTERMEDIATE SUPPORTS WHERE SPANS ARE 48 INCHES OR MORE. FOR NAILING OF WOOD STRUCTURAL PANEL AND ARTICLEBOARD DIAPGHRAMS AND SHEAR WALLS, REFER TO SECTION 2305 NAILS. FOR WALL SHEATHING ARE PERMITTED TO BE COMMON, BOX OR CASING. B.) SPACING SHALL BE 6 INCHES ON CENTER ON THE EDGES AND 12 INCHES ON CENTER AT INTERMEDIATE SUPPORTS FOR NONSTRUCTURAL APPLICATIONS. PANEL SUPPORTS AT 16 INCHES (20 INCHES IF STRENGTH AXIS IN THE LONG DIRECTION OF THE PANEL, UNLESS OTHERWISE MARKED C.) WHERE A RAFTER IS FASTENED TO AN ADJACENT PARALLEL CEILING JOIST IN ACCORDANCE WITH THIS SCHEDULE AND THE CEILING JOIST IS FASTENED TO THE TOP PLATE IN ACCORDANCE WITH THIS SCHEDULE, THE NUMBER OF TOENAILS IN THE RAFTER SHALL BE PERMITTED TO BE REDUCED BY ONE NAIL

D.) RSRS-01 IS A ROOF SHEATHING RING SHANK NAIL MEETING THE SPECIFICATIONS IN ASTM F1667

DECIMAL AND GAUGE CHARTS

60d, 40d

30d

20d

16d

12d, 10d

8d

6d

PENNY GAUGE

8

10

11

0.2242

0.2092

0.1943

0.1793

0.1644

0.1495

0.1345

0.1196


| FRACTION | DECIMAL |
|----------|---------|
| 1/32 | 0.03125 |
| 1/16 | 0.0625 |
| 3/32 | 0.09375 |
| 1/8 | 0.125 |
| 5/32 | 0.15625 |
| 3/16 | 0.1875 |
| 7/32 | 0.21875 |
| 1/4 | 0.25 |
| 9/32 | 0.28125 |
| 5/16 | 0.3125 |
| 11/32 | 0.34375 |
| 3/8 | 0.375 |
| 13/32 | 0.40625 |
| 7/16 | 0.4375 |
| 15/32 | 0.46875 |
| 1/2 | 0.5 |
| 17/32 | 0.53125 |
| 9/16 | 0.5625 |
| 19/32 | 0.59375 |
| 5/8 | 0.625 |
| 21/32 | 0.65625 |
| 11/16 | 0.6875 |
| 23/32 | 0.71875 |
| 3/4 | 0.75 |
| 25/32 | 0.78125 |
| 13/16 | 0.8125 |
| 27/32 | 0.84375 |
| 7/8 | 0.875 |
| 29/32 | 0.90625 |
| 15/16 | 0.9375 |
| 31/32 | 0.96875 |

IDENTIFICATION STAMP DIV. OF THE STATE ARCHITEC APP: 02-122764 INC: **REVIEWED FOR** SS 🗹 FLS 🗹 ACS 🗹 12/18/2024

ROJECT SPECIFIC STATE AGENCY APPROVAL

DESIGN ♦ CONSULTING ♦ PROJECT 11777 BERNARDO PLAZA COURT, SUITE SAN DIEGO, CA 92128

PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©



APPROVED DIV. OF THE STATE ARCHITEC APP: 04-123059 PC REVIEWED FOR SS 🗹 🗹 S 🗹 ACS 🖳 CG 🗹

> Revision Schedule Description

> > PRE-CHECK (PC) DOCUMENT

Code: 2022 CBC A separate project application for construction is required

PC 2022 CBC: 24' x 60' **EXPANDABLE TO**

STRUCTURAL GEN NOTES

PROJECT NUMBER 22088 DRAWN BY


CHECKED BY DATE


SHEET OF


rMc/SM


JA/RT

STRUCTURAL NOTES











* SIZE OF WELD (S) = THICKNESS OF 2 1 1/2" = 1'-0" ROOF BRACING STRAP @ ENDWALL THINER MATERIAL STRAP PER PLAN, INSTALLED TAUT ON TO TRUSS TOP CHORD (NO SLACK) SW TRUSS TOP CHORD JOIST REQ'D @ TRUSS BRACING LOCATIONS PER PLAN, TYP. (3) SIDES 16 GA STRAP *(S) 12" TOT. TO ROOF BM, (3) SIDES 14 GA STRAP *(S) 10" TOT. TO ROOF BM, TYP





5 1 1/2" = 1'-0" STRAP SPLICE DETAIL (ROOF)

* SIZE OF WELD (S) = THICKNESS OF THINER MATERIAL

IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT

APP: 02-122764 INC:

REVIEWED FOR
SS FLS ACS D


DATE: 12/18/2024

DESIGN OF CONSULTING OF PROJECT MG*

11590 W BERNARDO COURT, SUITE 100

SAN DIEGO, CA 92127

......



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©

CLIENT



APPROVED
DIV. OF THE STATE ARCHITECT
APP: 04-123059 PC
REVIEWED FOR
SS PLS ACS CG D
DATE: 02/20/2024

Revision Schedule

Description Date

PRE-CHECK (PC) ALTERNATE DOCUMENT
CODE: 2019 CBC

A separate project application for construction is required

PC 2022 CBC:24' x 40' EXPANDABLE TO 120' x 40'

MONO SLOPE
ROOF FRM'G PLAN
CROSS-STRAP
OPT.

PROJECT NUMBER

22088

DRAWN BY

MJM


CHECKED BY


RH/rMc


DATE


06/07/2021


\$3.0.3











PROJECT SPECIFIC STATE AGENCY APPROVAL IDENTIFICATION STAMP DIV. OF THE STATE ARCHITECT APP: 02-122764 INC: REVIEWED FOR SS 🗹 FLS 🗹 ACS 🗹 DATE: 12/18/2024





THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE **EXPRESS WRITTEN CONSENT OF R&S** TAVARES ASSOCIATES, INC. ©



ORIGINAL PC STATE AGENCY APPROVAL



Revision Schedule

Code: 2022 CBC

A separate project application for construction is required

PC 2022 CBC:24' x 40' EXPANDABLE TO 120' x 40'

SHEET TITLE
TYP FRAMING

22088 rMc/SC

| | | | | 2x4 Interio | r Wall Openi | ng Schedule | | | | | |
|--------|-------|----------|--------|-------------|--------------|-------------|------|--------|-------------|------|--|
| COL | OPN'G | | HDR | | | SILL | | FULL I | HEIGHT KING | STUD | |
| HEIGHT | SIZE | | | | | | | | | | |
| | | Lumber | Number | Туре | Lumber | Number | Туре | Lumber | Number | Туре | |
| 9FT | 3070 | HF / SYP | 1 | #2 | - | - | - | HF | 2 | #2 | |
| | | DF / SYP | 1 | #2 | - | - | - | DF | 2 | #2 | |
| | 4070 | HF / SYP | 1 | #2 | - | - | - | HF | 2 | #2 | |
| | | DF / SYP | 1 | #2 | - | - | - | DF | 2 | #2 | |
| | 6040 | HF/SYP | 2 | #2 | DF | 2 | #2 | HF | 2 | #2 | |
| | | DF / SYP | 2 | #2 | DF | 2 | #2 | DF | 2 | #2 | |
| | 8040 | HF / SYP | 3 | #2 | HF | 3 | #2 | HF | 2 | #2 | |
| | | DF / SYP | 3 | #2 | DF | 3 | #2 | DF | 2 | #2 | |
| 10FT | 3070 | HF / SYP | 1 | #2 | - | - | - | HF | 2 | #2 | |
| | | DF / SYP | 1 | #2 | - | - | - | DF | 2 | #2 | |
| | 4070 | HF/SYP | 1 | #2 | - | - | | HF | 2 | #2 | |
| | | DF / SYP | 1 | #2 | - | | - | DF | 2 | #2 | |
| | 6040 | HF / SYP | 2 | #2 | HF | 2 | #2 | HF | 2 | #2 | |
| | | DF / SYP | 2 | #2 | DF | 2 | #2 | DF | 2 | #2 | |
| | 8040 | HF/SYP | 3 | #2 | HF | 3 | #2 | HF | 2 | #2 | |
| | | DF / SYP | 3 | #2 | DF | 3 | #2 | DF | 2 | #2 | |

| 10 | | HF | 1 | #2 | 16" O.C. | - | | - | - |
|------------|--------|--------|--------------|------------|-------------|--------|--------------|-------------|---------|
| | | DF | 1 | #2 | 16" O.C. | - | - | - | - |
| 9 | | HF | 1 | #2 | 16" O.C. | - | - | - | - |
| | | Lumber | Number | Туре | Spacing | Lumber | Number | Type | Spacing |
| COL HEIGHT | - | | Typical I | Location | | • | 4ft From Bui | lding Corne | r |
| | | | 2x4 Interior | Wall Frami | ng Schedule | | | | |
| , | | | | | | | | | |
| | DF/SYP | 3 | #2 | DF | 3 | #2 | DF | 2 | #2 |
| 8040 | HF7SYP | 3 | #2 | HF | 3 | #2 | HF~ | | #2 |

| COL HEIGHT | OPN'G SIZE | | HDR | | | SILL | | FULL HEIGHT KING STUD | | |
|---------------|---------------|----------|--------|------|--------|--------|------|-----------------------|--------|------|
| HEIGHT | SIZL | Lumber | Number | Туре | Lumber | Number | Туре | Lumber | Number | Туре |
| 9FT | 3070 | HF / SYP | 1 | #2 | HF | 1 | #2 | HF | 1 | #2 |
| | | DF / SYP | 1 | #2 | DF | 1 | #2 | DF | 1 | #2 |
| | 4070 | HF / SYP | 1 | #2 | HF | 1 | #2 | HF | 1 | #2 |
| | | DF / SYP | 1 | #2 | DF | 1 | #2 | DF | 1 | #2 |
| | 6040 | HF / SYP | 1 | #2 | HF | 1 | #2 | HF | 1 | #2 |
| | | DF / SYP | 1 | #2 | DF | 1 | #2 | DF | 1 | #2 |
| | 8040 | HF / SYP | 1 | #2 | HF | 1 | #2 | HF | 2 | #2 |
| | | DF / SYP | 1 | #2 | DF | 1 | #2 | DF | 2 | #2 |
| 10FT | 3070 | HF / SYP | 1 | #2 | HF | 1 | #2 | HF | 1 | #2 |
| | | DF / SYP | 1 | #2 | DF | 1 | #2 | DF | 1 | #2 |
| | 4070 | HF/SYP | 1 | #2 | HF | 1 | #2 | HF | 1 | #2 |
| | | DF / SYP | 1 | #2 | DF | 1 | #2 | DF | 1 | #2 |
| | 6040 | HF / SYP | 1 | #2 | HF | 11 | #2 | HF | 2 | #2 |
| | | DF / SYP | 1 | #2 | DF | 1 | #2 | DF | 2 | #2 |
| | 8040 | HF/SYP | 1 | #2 | HF | 1 | #2 | HF | 2 | #2 |
| | | | 1 | #2 | DF | 1 | #2 | DF | 2 | #2 |

| | 2x6 Exte | erior Wall Fr | aming Sche | dule (SHTH'G | FINISH) | | | | | |
|------------|----------|---------------|------------|--------------|---------|--------------|------------------------|----------|--|--|
| COL HEIGHT | | Typical | Location | | | 4ft From Bui | t From Building Corner | | | |
| | Lumber | Number | Туре | Spacing | Lumber | Number | Туре | Spacing | | |
| 9 | HF | 1 | #2 | 16" O.C. | HF | 1 | #2 | 16" O.C. | | |
| | DF | 1 | #2 | 16" O.C. | DF | 1 | #2 | 16" O.C. | | |
| 10 | HF | 1 | #2 | 16" O.C. | HF | 1 | #2 | 16" O.C. | | |
| | DF | 1 | #2 | 16" O.C. | DF | 1 | #2 | 16" O.C. | | |

| 2x6 Exterior Wall Framing Schedule (PLASTER FINISH) | | | | | | | | |
|---|------------------|--------|------|----------|--------------------------|--------|------|----------|
| COL HEIGHT | Typical Location | | | | 4ft From Building Corner | | | |
| | Lumber | Number | Туре | Spacing | Lumber | Number | Type | Spacing |
| 9 | HF | 1 | #2 | 16" O.C. | HF | 1 | #2 | 16" O.C. |
| | DF | 1 | #2 | 16" O.C. | DF | 1 | #2 | 16" O.C. |
| 10 | HF | 1 | #2 | 16" O.C. | HE | 1 | #2 | 16" O.C. |
| | DF | 1 | #2 | 16" O.C. | DF | 11 | #2 | 16" O.C. |

2x6 Exterior Wall Opening Schedule (PLASTER FINISH)

HF

DF

1

Lumber Number

Type

#2

#2

#2

#2

#2

#2

#2

#2

#2

#2

#2

#2

Lumber

HF

DF

DF

DF

DF

Type

#2

#2

#2

#2

#2

#2

#2

#2

#2

#2

#2

#2

#2

OPN'G

4070

6040

8040

3070

4070

6040

8040

Lumber

DF

HF

DF

HF

DF

HF

DF

HF

HF

Number

1

HEIGHT

9FT

10FT

FULL HEIGHT KING STUD

Number

Type

#2

#2

#2

#2

#2

#2

#2

#2

#2


#2

#2

#2


#2

NOTE: SEE DETAIL 1 ON SHEETS A2.1 - A2.6






PROFESSIONAL STAMP



THE PLANS, IDEAS & DESIGNS SHOWN ON THESE DRAWINGS ARE THE PROPERTY OF R&S TAVARES ASSOCIATES, INC. DEVISED SOLELY FOR THIS CONTRACT. THESE PLANS SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE FOR WHICH THEY WERE NOT INTENDED WITHOUT THE EXPRESS WRITTEN CONSENT OF R&S TAVARES ASSOCIATES, INC. ©

CLIENT





Revision Schedule

Description

PRE-CHECK (PC) DOCUMENT

Code: 2022 CBC

A separate project application for construction is required

PROJECT TITLE

PC 2022 CBC:24' x 40' EXPANDABLE TO 120' x 40'

SHEET TITLE

FRAMING SCHEDULES

PROJECT NUMBER
22088

rMc/SC

CHECKED BY

JA/RT

TE

S4.5

SHEET OF

001 1.53.06 AM

